



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

www.courts.ca.gov/tcfmac.htm
tcfmac@jud.ca.gov

TRIAL COURT FACILITY MODIFICATION ADVISORY COMMITTEE

OPEN MEETING WITH NO CLOSED SESSION AGENDA

Open to the Public Unless Indicated as Closed (Cal. Rules of Court, rule 10.75(c)(1))

OPEN PORTION OF THIS MEETING IS BEING RECORDED

Date: July 17, 2015
Time: 10:00 AM – 4:00 PM
Location: Sacramento/Teleconference for Public Access
Public Call-in Number: 1-877-820-7831 Listen Only Code: 4502468

Meeting materials for open portions of the meeting will be posted on the advisory body web page on the California Courts website at least three business days before the meeting. Agenda items are numbered for identification purposes only and will not necessarily be considered in the indicated order.

I. OPEN MEETING (CAL. RULES OF COURT, RULE 10.75(C)(1))

Call to Order and Roll Call 10:00 AM

Approval of Minutes

Approve minutes of the May 22, 2015 Trial Court Facility Modification Advisory Committee meeting.

II. ACTION ITEMS (ITEMS 1 – 10)

Action Item 1 – (Action Required) – List A – Emergency Facility Modification Funding (Priority 1)

Summary: Ratify emergency facility modifications from List A.

Action Requested: Staff recommends 49 projects for a total of \$1,116,044 to be paid from funds previously encumbered for emergency funding.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Action Item 2 – (Action Required) – List B – Facility Modifications Less than \$50K (Priority 2)

Summary: Ratify facility modifications less than \$50K from List B.

Action Requested: Staff recommends 166 projects for a total of \$1,322,178 to be paid from funds previously encumbered for facility modifications less than \$50K.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Action Item 3 – (Action Required) – List C – Cost Increases Over \$50K

Summary: Ratify facility modifications requiring cost increases over \$50K from List C.

Action Requested: Staff recommends three projects for a total cost increase to the Facility Modification Program Budget of \$604,788.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Action Item 4 – (Action Required) – List D – Facility Modifications Over \$50K

Summary: Review recommended facility modifications over \$50K from List D.

Action Requested: Staff recommends 23 projects for a total cost to the Facility Modification Program Budget of \$4,502,970.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Action Item 5 – (Action Required) – List F – Court-Funded Facilities Requests (Facility Modifications)

Summary: Review Court-Funded Facilities Requests (Facility Modifications) from List F.

Action Requested: Staff recommends executing projects on List F – Court-Funded Facilities Requests (Facility Modifications).

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Discussion Item 1 – List E – Funded Facility Modifications On Hold

Summary: Review facility modifications that have been funded by the committee, but are on hold for various reasons.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Discussion Item 2 – Update on Solano Hall of Justice Retaining Wall Project

Summary: Discuss facility modification (FM-0040733) at Solano Hall of Justice that has been on hold for over three years.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Action Item 6 – (Action Required) – Five Year Infrastructure Plan – Deferred Maintenance Request Log

Summary: Review and discuss the Judicial Council Five Year Infrastructure Plan – Deferred Maintenance Request Log that is provided to Department of Finance on an annual basis.

Action Requested: Review and approve this report for submittal to the Judicial Council, with a recommendation to submit to DOF in September 2015.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Action Item 7 – (Action Required) – FY 2015-2016 Budget Plans

Summary: Review and discuss finalized FY 2015-2016 budget plans. Proposed budget previously presented at May 22, 2015 meeting.

Action Requested: Approve FY 2015-2016 budget.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager and Ms. Angela Guzman, Financial Manager

Action Item 8 – (Action Required) – Quarterly Activity Report, Quarter 4 of Fiscal Year 2014-2015

Summary: Review and discuss the *Trial Court Facility Modification Advisory Committee Activity Report for Quarter 4, Fiscal Year 2014-2015*.

Action Requested: Provide input and additions to draft document and approve release to E&P upon revision.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

Action Item 9 – (Action Required) – Policy on Art Acquisition for Court Facilities

Summary: Review and discuss *Judicial Council Policy on Art Acquisition for Court Facilities*.

Action Requested: Approve policy for adoption by Judicial Council.

Presenter: Mr. Curt Soderlund, Chief Administrative Officer and Ms. Debora Morrison, Senior Attorney, Legal Services

Action Item 10 – (Action Required) – Budget Change Proposals for FY 2016-2017

Summary: Review and discuss proposed Budget Change Proposals for FY 2016-2017

1. *Operations and Maintenance, Facility Modifications, and New Construction – General Fund*, Mr. Patrick McGrath, Facilities Operations Manager
2. *Trial Court Security System Maintenance, Replacement and Improvements – General Fund*, Mr. Edward Ellestad, Senior Security Coordinator and Mr. Brad Boulais, Senior Project Manager
3. *Trial Court Facilities-Risk Management Program – General Fund*, Mr. Jim Mullen, Senior Facilities Risk Manager and Ms. Angela Guzman, Financial Manager
4. *Los Angeles Superior Court - Antelope Valley Juvenile Court Facility Modifications – General Fund*, Ms. Angela Guzman, Financial Manager and Mr. Brad Boulais, Senior Project Manager
5. *Green Pilot Projects – Cap and Trade*, Ms. Laura Sainz, Environmental Compliance and Sustainability Manager

Action Requested: Approve BCPs to move forward to August Judicial Council meeting.

III. DISCUSSION ITEMS (ITEMS 3-5; SEE ITEMS 1-2 ABOVE)

Discussion Item 3 – Seismic Study Presentation

Summary: Discuss seismic studies performed on courthouse facilities and the possibility for a Budget Change Proposal for further seismic efforts.

Presenter: Mr. Jim Mullen, Senior Facilities Risk Manager and Mr. Jerry Pfab, Senior Manager, Facilities Management Unit

Discussion Item 4 – Update on Status of Santa Barbara Area Court Improvement

Summary: Discuss Santa Barbara Superior Court’s transition of juvenile proceedings to the Jury Assembly Building.

Presenter: Ms. Eunice Calvert-Banks, Manager, Real Estate Unit, and Ms. Angela Guzman, Financial Manager

Discussion Item 5 – Update on Status of *Trial Court Methodology for Prioritizing and Ranking Facility Modifications*

Summary: Discuss status of *Trial Court Methodology for Prioritizing and Ranking Facility Modifications* document, previously reviewed by the committee on April 13, 2015.

Presenter: Mr. Patrick McGrath, Facilities Operations Manager

IV. INFORMATION ONLY ITEMS (ITEMS 1-2)

Information Item 1 – Budget Change Proposal for Alameda Courthouse Project

Summary: Informational Budget Change Proposal for Funds Transfer to Complete Funding Plan for the Alameda Courthouse Project.

Information Item 2 – Report on Budget Reconciliation

Summary: Informational report on FY 15-16 budget reconciliation and spending plan, as well as completed and canceled facility modifications during the reporting period.

V. ADJOURNMENT

Adjourn Meeting



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

www.courts.ca.gov/tcfmac.htm
tcfmac@jud.ca.gov

TRIAL COURT FACILITY MODIFICATION ADVISORY COMMITTEE

MINUTES OF OPEN MEETING WITH CLOSED SESSION

May 22, 2015
10:00 a.m. – 4:00 p.m.
In-Person Meeting

Advisory Body Members Present: Hon. David Edwin Power, Chair, Hon. William F. Highberger, Vice-Chair, Hon. Donald Cole Byrd, Hon. James L. Stoelker, Hon. Vanessa W. Vallarta, Mr. Michael M. Roddy, Ms. Jeanine D. Tucker, and Ms. Linda Romero Soles

Advisory Body Members Absent: Ms. Christina M. Volkens

Others Present: Hon. Huey Cotton, Hon. Gregory Dohi, Hon. James Herman, Mr. Darrel Parker, Mr. Curt Soderlund, Mr. Burt Hirschfeld, Mr. Gerald Pfab, Mr. Patrick McGrath, Ms. M.R. Gafill Malloy, Mr. Nick Turner, Mr. Kenneth Kachold, Ms. Angela Guzman, Ms. Laura Sainz, Mr. Brad Boulais, Mr. Edward Ellestad, Mr. Dennis Duncan, Mr. Ernest Ballesteros, and Ms. Hilda Iorga

OPEN MEETING

Call to Order and Roll Call

The chair called the meeting to order at 10:00 a.m. and took roll call.

Approval of Minutes

The advisory body reviewed and approved the minutes of the April 13, 2015 Trial Court Facility Modification Advisory Committee meeting.

PUBLIC WRITTEN COMMENT

One public comment was received from Santa Barbara Superior Court.

ACTION ITEMS (ITEMS 1-11)

Action Item 1 – (Action Required) – List A – Emergency Facility Modification Funding (Priority 1)

Summary: Ratify emergency facility modifications from List A.

Action: *Reviewed and ratified 27 projects for a total of \$483,169 to be paid from funds previously encumbered for emergency funding.*

Action Item 2 – (Action Required) - List B – Facility Modifications Less than \$50K (Priority 2)

Summary: Ratify facility modifications less than \$50K from List B.

Action: Reviewed and ratified 99 projects for a total of \$865,006 to be paid from funds previously encumbered for facility modifications less than \$50K.

Action Item 3 – (Action Required) - List C – Cost Increases Over \$50K

Summary: Ratify facility modifications requiring cost increases over \$50K from List C.

Action: Reviewed and ratified four projects for a total cost increase to the Facility Modification Program Budget of \$253,093.

Action Item 4 – (Action Required) - List D – Facility Modifications Over \$50K

Summary: Review recommended facility modifications over \$50K projects from List D.

Action: Reviewed 12 projects for a total cost to the Facility Modification Program Budget of \$2,077,589.

Action Item 5 – (Action Required) – Project Funding Consideration – Santa Barbara Superior Court

Summary: Consideration of project to construct three attorney/client rooms required to facilitate the move of Santa Barbara Superior Court juvenile proceedings to the Jury Assembly Building

Action: The committee reviewed the project as part of List D and approved the project for funding. The committee requested staff to report back in July on the plan to release all financial and legal responsibility of the vacated and closed Juvenile modular building.

Action Item 6 – (Action Required) – Project Funding Consideration – Larson Justice Center

Summary: Consideration of project to create 80 additional parking stalls on perimeter landscaping.

Action: The committee reviewed the project and deemed that the project remain an unfunded Priority 3 FM until such time as the committee is presented with significant information necessitating the project's execution.

Action Item 7 – (Action Required) – Energy Conservation Project – Gordon Schaber Courthouse

Summary: Consideration of a lighting energy conservation project at Gordon Schaber Courthouse.

Action: The committee reviewed and approved the project, which will encompass the changing of T8 lamps to LED lamps. With rebate incentives, the project has a return on investment of 13 months.

Action Item 8 – (Action Required) – Water Conservation Policy

Summary: Judicial Council staff has developed a Water Conservation Policy in response to California's ongoing drought.

Action: The committee reviewed and approved the policy, contingent upon water leak language being revised as per the Facilities Policy Working Group, to move forward to the Judicial Council for adoption.

Action Item 9 – (Action Required) – Quarterly Activity Report, Quarter 3 of Fiscal Year 2014-2015

Summary: Review and approval of the *Trial Court Facility Modification Advisory Committee Activity Report for Quarter 3, Fiscal Year 2014-2015.*

Action: The committee reviewed and approved the draft report to move forward to the Judicial Council.

Action Item 10 – (Action Required) – FY 2016-2017 Budget Change Proposal

Summary: Review and discuss Budget Change Proposal priorities for FY 2016-2017.

Action: The committee reviewed and discussed the proposed Budget Change Proposals for FY 2016-2017. The committee approved staff recommendations for the budget as well as “Option 2” asking for \$12M in additional funding, with the addition of a fourth BCP for security funding. The committee directed staff to report on potential seismic study costs at the July 2015 meeting.

Action Item 11 – (Action Required) – FY 2015-2016 Budget Plans

Summary: Review and discuss FY 2015-2016 budget plans, including potential planned work.

Action: The committee reviewed and approved the proposed O&M and FM budgets for FY 2015-2016. The budgets will be submitted to the July 2015 Judicial Council meeting for approval.

DISCUSSION ITEMS (ITEM 1)

Discussion Item 1

Summary: Reviewed List E – *Funded Facility Modifications On Hold*. These are FMs that the committee has previously approved, but that are on hold pending county shared cost approval, project manager assignment, or other reasons. This list will be provided at every meeting going forward.

INFORMATION ONLY ITEMS (ITEMS 1-2)

Information Item 1

Summary: The committee reviewed List G – *Closed Facility Modifications*. This list is provided on an annual basis, or as requested by the committee.

Information Item 2

Summary: The committee reviewed List H – *Canceled Facility Modifications*. This list is provided on an annual basis, or as requested by the committee.

ADJOURNMENT

There being no further open meeting business, the meeting was adjourned at 12:28 p.m.

Approved by the advisory body on_____.



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

**Action Item 1 – (Action Required) - List A – Emergency
Facility Modification Funding (Priority 1)**

Summary:

List A – Emergency Facility Modification Funding (Priority 1)

Total Project Count:	49
Total Potential FM Budget Share of Cost:	\$1,116,044

Supporting Documentation:

- List A - Emergency Facility Modifications (Priority 1)

Action Requested:

Ratify Judicial Council Staff preliminary decision for execution approval of List A – Emergency Facility Modifications (Priority 1).

This page intentionally left blank



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
1	FM-0054913	Mendocino	County Courthouse	23-A1	1	HVAC - Replace Vacuum Return System - Replace failed vacuum return system, 2 make up water pumps, 2 vacuum pumps, 1 water tank and related parts including replacing insulations on system.	\$ 130,727	\$ 88,398	In Work	67.62
2	FM-0054929	Los Angeles	Alhambra Courthouse	19-11	1	Exterior - Replace 30 windows 1st flr North side of building, glass panes approx. 3ft.W x 12ft.H. Pickup glass, remove vandalized glass panes. Windows were covered with boards to prevent safety issue. 30 windows on 1st flr were vandalized; window panes were hit with rocks, concrete trash can, and with the fists of the vandal.	\$ 55,000	\$ 47,300	Complete	86
3	FM-0054932	Los Angeles	Stanley Mosk Courthouse	19-K1	1	HVAC - Installed (3) 40 amp circuits, new breaker, 300' of cable, conduit, plug, hardware; and (1) 20 amp circuit, conduit, plug, hardware, new breaker and 100' of cable. Installed (3) rented 5 ton 208/230 volt units and wire into newly installed circuits, and installed (4) rented 1 ton 120 volt units. Room 426 was too warm, due to high temperatures outside and existing cooling system was unable to keep pace. Spot coolers were installed to provide supplemental cooling.	\$ 55,004	\$ 55,004	Complete	100
4	FM-0054947	Los Angeles	Downey Courthouse	19-AM1	1	Elevators, Escalators, & Hoists - Install new power supply. Elevator #1 is not working due to a malfunctioning pulse starter and needs a new power supply in order to operate properly.	\$ 11,537	\$ 9,656	Complete	83.7
5	FM-0054965	Los Angeles	Van Nuys Courthouse West	19-AX2	1	Exterior Shell - Replace motor operator to Sally Port to Main Lock Up. Motor has shorted/failed and is not operative. No direct impact to Court because there is an entrance and exit sally port gate, buses are using one side to enter/exit.	\$ 10,153	\$ 8,171	In Work	80.48
6	FM-0054966	Los Angeles	Pasadena Courthouse	19-J1	1	Exterior - Replace one 4ft x 4ft window pane. Removed vandalized window pane, clean up / removal of glass shards, and boarded up window. One window was vandalized on the 1st floor North side of the building. The window pane was kicked into the building and shattered.	\$ 10,000	\$ 6,935	In Work	69.35
7	FM-0054968	Los Angeles	Van Nuys Courthouse East	19-AX1	1	Plumbing - Replace failed (1) 12" x 3/8" nipple and (1) 3/8" angle stop. remediate water damage with potential ACM for 200 sqft combined area. Conference Room women's restroom angle stop to sink failed and was leaking at approx. 2.0 gallons a minute of potable cold water. The only shut off for this water supply is located 15' above the ceiling. Water did not penetrate to the floors below.	\$ 30,000	\$ 30,000	Complete	100
8	FM-0054970	Lake	Lakeport Court Facility	17-A3	1	HVAC - failed wiring - Replace power feed wiring in new flex conduit from the ground floor electrical room/Contactor to the 4th floor AHU, approx 150 lin feet of conduit and wiring. Failed wiring in existing conduit was not able to be traced through county space.	\$ 5,000	\$ 5,000	Complete	100
9	FM-0054993	Solano	Solano Justice Building	48-B1	1	Earthquake damage response - HVAC - Provide eight (8) temporary "Move and Cool" units to accommodate the courts needs while the County's Central Plant is put back on line. The County has agreed to reimburse the JCC 100% of the cost. The Costs have been entered into the County's FEMA claim.	\$ 25,045	\$ 25,045	In Work	100
10	FM-0054994	Los Angeles	Airport Courthouse	19-AU1	1	Exterior Shell - Restore operations to Employee Pass through Security Entrance Door in Employee Parking Structure. Door hardware/Push Bar/Locking Mechanism is not working and needs to be replaced.	\$ 4,874	\$ 3,761	In Work	77.17
11	FM-0054995	Los Angeles	El Monte Courthouse	19-O1	1	Exterior Shell - Replace damaged operator motor on automatic exit door. The automatic exit door in the buildings NW corner is not currently operating in automatic mode & must be manually operated; the door was forced open and now it will not lock properly which is a security concern.	\$ 10,000	\$ 5,812	In Work	58.12
12	FM-0054996	Los Angeles	Van Nuys Courthouse West	19-AX2	1	Plumbing - Replace failed domestic water pipe and remediate water damage adjacent to 2nd floor traffic window #1, replace wet ceiling tiles Domestic water pipe in 3rd floor adjacent to public restrooms is leaking down to 2nd floor Traffic Window #1 (Secured Area).	\$ 30,000	\$ 30,000	Complete	100
13	FM-0054997	Los Angeles	Compton Courthouse	19-AG1	1	Plumbing - Water leak from a clogged floor drain on the 2nd flr inside the Cafeteria. Black water penetrated to the 1st floor secured hallway between Rm 100 and Traffic Court Rm. Set up 4'x7'x10' splash guard and scaffolding due to 30 ft ceiling. Replace two P-traps and approx. 20ft of cast iron drain pipe, extracted approx. 40 sf of black water.	\$ 40,122	\$ 26,533	Complete	66.13



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCF MAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
14	FM-0055020	Placer	South Placer Justice Center	31-H1	1	HVAC - Install an Automated Logic Direct Digital Control (ALC-DDC) system and components for AHU #5. 1.) Install two (2) new M-module to control AHU-5. 2.) Engineering and programming. 3.) Commission new module operation by Airco Automation technical services personnel - The Control module for AHU-5 has failed putt the AHU out of service.	\$ 9,971	\$ 9,971	In Work	100
15	FM-0055025	Los Angeles	Metropolitan Courthouse	19-T1	1	Plumbing - Water leak due to cracked storm drain line, penetrated from 9th flr to 8th flr server room. Replaced 20ft of 4in cast iron pipe & (20) 1x1 ceiling tiles. Water extraction & Disinfected/cleaned 480sq ft of carpet. Conducted Bacteria, Moisture, environmental testing, remediation & Containment set up.	\$ 35,165	\$ 33,245	In Work	94.54
16	FM-0055037	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Replace 10LF of 3/4" of failed domestic water pipe in ceiling of 18th floor. Perform remediation for lobby area(25sf), replace twenty (20) damaged ceiling tiles, domestic water pipe in the ceiling of the 18th floor adjacent to room 115 is leaking into the 18th floor public lobby causing damage to ceiling tiles & high moisture levels in the lobby.	\$ 30,000	\$ 20,637	In Work	68.79
17	FM-0055038	Los Angeles	Van Nuys Courthouse West	19-AX2	1	Plumbing - Replace 6" of failed copper piping. Leak on 6" copper main domestic line in ceiling above sheriff's locker room; remediate leak damaged 2ft x 2ft hard lid ceiling and water dame below. No impact to court operations.	\$ 30,056	\$ 30,056	In Work	100
18	FM-0055039	San Diego	East County Regional Center	37-11	1	Elevators, Escalators, & Hoists - Replaced control board. Elevator #5 was not leveling, doors were not opening. Elevator #5 had a bad board that needed replacing.	\$ 3,938	\$ 2,666	Complete	67.71
19	FM-0055040	Los Angeles	Van Nuys Courthouse East	19-AX1	1	Vandalism - Replace (1) 4' x 10' broken window in the 2nd floor public hallway. There is currently a 4' x 10' window that is cracked & has a small hole in it, the window needs to be replaced to further damage.	\$ 10,000	\$ 8,974	In Work	89.74
20	FM-0055042	Alameda	Hayward Hall of Justice	01-D1	1	HVAC - Renovate chiller dual-pumping system. Catastrophic system failure requires a temporary chilling unit during pump renovation work.	\$ 104,325	\$ 92,119	In Work	88.3
21	FM-0055055	Los Angeles	Inglewood Courthouse	19-F1	1	Plumbing - Remediate water damage in ACM environment including replacement of 400 sq/ft of damaged ceiling tiles. There is a water leak coming from the first floor janitorial closet caused by a hose bib that was not properly shut off & the hose end not in a drain; Cost reimbursement being sought from the court.	\$ 32,159	\$ 23,978	In Work	74.56
22	FM-0055059	Los Angeles	Norwalk Courthouse	19-AK1	1	Plumbing - Flood Restoration to approximately within 5,000 SF within an ACM environment in first floor elevator lobby, child care center, janitorial closet, & in-custody area; dry leak affected areas in basement elevator pits, elevator lobby, document storage room, & IT storage area. There is a flood caused by an overflowing mop sink that was left unattended and flooded multiple areas on the 1st floor & in the basement causing water damage to multiple items. Cost reimbursement being sought from the court.	\$ 100,000	\$ 85,030	Complete	85.03
23	FM-0055060	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Remediation, set up 10'x10'x12' containment, dry area, clean up and disinfect, environmental testing. Replace 2" copper domestic water line, fittings and 2 ball valves. Install (4) 5'x5'x3/4" ceiling panels. Replace 11 Water closet kits and 7 Urinal kits. Disposal of 5CF ACM Debris. Domestic cold water line in ceiling failed and leaked onto carpet, causing moisture in ceiling and floor. After piping restored water supply was recharged, 18 flush valves stuck open requiring replacement.	\$ 30,000	\$ 20,637	In Work	68.79
24	FM-0055062	Contra Costa	Concord-Mt. Diablo District	07-D1	1	Plumbing - Plumbing Leak Restoration - Remove 130 Sq Ft of drywall; replace 2 feet of 3/4 inch pipe; Wipe down 12 2x4s Isolate area with plastic and remove moisture using one de-humidifier and one air scrubber; test for mold; replace drywall; re-test for mold; remove containment – Broken pipe in wall caused water damage.	\$ 10,000	\$ 10,000	In Work	100



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
25	FM-0055082	Los Angeles	Inglewood Juvenile Court	19-E1	1	Roof - Set up containment (10x10) & drying equipment in Department 242 chambers, Renovate roof penetrations (25 sq.ft.), sand and paint all penetrations in ceiling and walls to match existing (9sq.ft). There is rain water leaking through the roof into department 242 chambers causing water damage to the ceiling and walls; roof area and ceiling need to be patched to prevent further water damage.	\$ 5,540	\$ 4,475	Complete	80.78
26	FM-0055086	Los Angeles	Van Nuys Courthouse East	19-AX1	1	Plumbing - Replace 2 drain line and floor sink, extract black water 250SF, clean carpets, extract gray water 250SF, replace four 2x2 ceiling tiles. 2nd flr kitchen - snake drain, extract gray water 320SF (x2). Water leaking on the 1st flr from ceiling; water coming from 2" cast iron drain line from the 2nd flr kitchen. Work in an ACM environment.	\$ 30,000	\$ 26,922	In Work	89.74
27	FM-0055089	Los Angeles	Hall of Records-County Records Center	19-AV3	1	COUNTY MANAGED - Plumbing - Replace failed 5" coupling on a fire sprinkler line.	\$ 4,500	\$ 4,185	In Work	93
28	FM-0055090	Los Angeles	Stanley Mosk Courthouse	19-K1	1	Plumbing - Replace deteriorated section of 3" cast iron drain pipe. A section of a 3" cast iron drain pipe in the 3rd floor is deteriorated and leaking water on an area of dirt 20 ft. x 40 ft. The leak affected area is adjacent to the building's foundation and the pipe needs to be replaced.	\$ 15,000	\$ 15,000	In Work	100
29	FM-0055091	Los Angeles	Chatsworth Courthouse	19-AY1	1	HVAC - Damaged Chiller Tube - Identify the leaking chiller tube and install a machined brass plug. The cracked tube on evaporator for Chiller #2 needed to be plugged to prevent any mixture of refrigerant and water, and avoid any further damage. During a Level VIII PM found a water and refrigerant mixture in the evaporator on Chiller #2.	\$ 10,001	\$ 8,381	In Work	83.8
30	FM-0055093	Los Angeles	Stanley Mosk Courthouse	19-K1	1	Plumbing - Water remediation, set-up containment in room 246, environmental testing. Replace 2ft of 3/4 inch copper piping and fittings, replaced 5 ceiling tiles. Men's Jury Restroom in Room 730 had a pin hole leak in the hot water piping to the sink causing water to travel to Room 426. This work was completed as a P1 emergency due to water leaking into the Family Law Services Resources Center Room 426.	\$ 5,795	\$ 5,636	Complete	97.26
31	FM-0055101	Los Angeles	Van Nuys Courthouse West	19-AX2	1	Plumbing - Remediate water damage in an ACM environment due to clogged drain line. Replace approx. (4) ceiling tiles and remove black water from carpet are. Restore operation to drain & drain pipe. There is a clogged drain in the fan room P-111 on the penthouse level that has caused the flood & water has leaked through the ceiling of room 1007 on the 10th floor causing water damage to ceiling tiles & high moisture levels on the carpet.	\$ 30,000	\$ 24,144	In Work	80.48
32	FM-0055115	Los Angeles	Downey Courthouse	19-AM1	1	Elevators, Escalators, & Hoists - Replace bad 2V1 & 2 relays on elevator #4 & returned to service. Custody elevator #4 is stuck at the basement level with the doors closed & is not responding; relays need to be replaced to prevent this from happening in the future & possibly causing an entrapment.	\$ 4,220	\$ 3,532	In Work	83.7
33	FM-0055118	Los Angeles	Pasadena Courthouse	19-J1	1	Plumbing - Close off both restrooms & extract water from floor, unclog sinks, set up containment & drying equipment, perform environmental testing, dry and wipe down restrooms, perform final wipe down & remove containments after clearance. There is a clogged sink in the 4th floor women's public restroom caused by a person blocking the sink & leaving water running; water is leaking down to the 3rd floor men's public restroom causing health and safety hazards in both areas.	\$ 17,360	\$ 12,039	In Work	69.35
34	FM-0055123	Los Angeles	Norwalk Courthouse	19-AK1	1	Exterior Shell - Replace a damaged operator motor of an automatic exit door. An automatic exit door in the building's east side is not currently operating in automatic mode and must be manually operated. The door was forced open and now it will not lock properly which is a safety and security issue.	\$ 10,000	\$ 10,000	In Work	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification
Emergency and Priority 1 (List A)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
35	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Replace failed cast iron piping and remediate water damage. Replace approx. (4) 1' x 1' ceiling tiles, replace approx. 8' of 3" cast iron pipe and (1) 90 degree elbow in 3" drain line. A 3" cast iron drain line located in the ceiling between the 5th & 6th floors is damaged causing water to leak down into 5th floor Rm 5-305; there is water damage to ceiling tiles & moisture on floors & walls.	\$ 30,125	\$ 30,125	In Work	100
36	Los Angeles	Pasadena Courthouse	19-J1	1	Elevators, Escalators, & Hoists - Replaced resistor in brake circuit for Elevator #2. Replaced door timer relay for Elevator #1. Elevators 1 and 2 returned to service. Elevators 1 and 2 were down and not responding.	\$ 2,615	\$ 1,814	Complete	69.35
37	Fresno	B.F. Sisk Federal Courthouse	10-O1	1	Security - Elevator Cameras for elevators 1, 2 and 3 went down due to a failed encoder. Remove existing encoder and replace with a new encoder.	\$ 4,826	\$ 4,826	In Work	100
38	Los Angeles	San Pedro Courthouse	19-Z1	1	Elevator- Replace defective solid state starter on Elevator #1. Elevator was non-functioning and stuck between the 1st & 2nd floors with the doors closed.	\$ 4,720	\$ 4,491	Complete	95.15
39	Los Angeles	Pomona Courthouse South	19-W1	1	Elevators, Escalators, & Hoists - Replace (1) seismic detector & (1) backup battery on judge's elevator #6. Judge's elevator #6 is stuck on the first floor with the doors open & will not move until backup battery and seismic detector are replaced.	\$ 3,010	\$ 2,743	In Work	91.14
40	Humboldt	Humboldt County Courthouse	12-A1	1	HVAC - Water leak into evidence room from county hot water loop. Stop water flow from vent, remediate the water in the evidence room and surrounding restroom. Test for Mold, Lead and ACM. Contain and remediate using correct protocols. Dry out damaged evidence.	\$ 49,000	\$ 16,346	In Work	33.36
41	Los Angeles	Van Nuys Courthouse West	19-AX2	1	Plumbing - Replace failed seal in 4" toilet drain and remediate water damage within an ACM environment. Replace damaged seal and 18" section of 4" drain line. There is currently water leaking into the basement sump pump room from the main lock up on the first floor caused by a damaged seal in a 4" toilet drain line.	\$ 30,000	\$ 24,144	In Work	80.48
42	Los Angeles	Van Nuys Courthouse East	19-AX1	1	HVAC - Replace failed evaporator pan and mitigate associated water damage due to pan failure. Remove water from carpet. 7th Floor Air Handler Room, evaporator pan has failed and water leaked out and through wall into the Judges Chambers. 8ft x 15ft of carpet in chambers is wet. Water has leaked down to the 6th floor Air Handler room.	\$ 40,000	\$ 40,000	In Work	100
43	Los Angeles	Compton Courthouse	19-AG1	1	Plumbing - A water supply line in the wall, that supplies water to the toilet in the 5th floor lock up holding cell leaked water. Water penetrated the fire proofing and leaked down to the 4th floor and in a private hallway by room 406. Restore water supply line to toilet and build back. Remediation required for ACM environment.	\$ 31,056	\$ 31,056	In Work	100
44	Los Angeles	Stanley Mosk Courthouse	19-K1	1	Plumbing - Replace failed 4" cast iron drain line & 1" copper water supply line, restore wall access holes. There is currently water leaking from the 5th floor ceiling near room #501 & the women's restroom secured hallway which has affected approx. 12 sq. ft. of ceiling tiles and the floor; the leak is due to a cracked 4" black cast iron waste line & 1" copper domestic water supply line.	\$ 30,165	\$ 30,165	In Work	100
45	Los Angeles	Compton Courthouse	19-AG1	1	Plumbing - Remediate water damage in ACM environment including approx. 10 sq. ft. of ceiling tiles, 30 sq. ft. of desk & cubicle areas, & 10 sq. ft. of carpet. There is a water leak coming from a janitorial closet on the 5th floor, leaking down a pipe chase to the 3rd floor causing moisture on ceiling, desk & cubicle area D13, & carpet in room 301.	\$ 35,000	\$ 35,000	In Work	100
46	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Remediate water damage in ACM environment including approx. (10) 1' x 1' ceiling tiles, & an 8' x 10' affected area in wall on 11th floor. There is a water leak originating from an overflowing urinal in the 12th floor men's employee restroom leaking down to the 11th floor secure hallway near Dept. 114 courtroom causing moisture in ceiling tiles and walls.	\$ 30,000	\$ 30,000	In Work	100



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
47	FM-0055172	Los Angeles	Compton Courthouse	19-AG1	1	Plumbing - Water leak caused by a failed 6in sewage stack & 2in drain line within pipe chase; 3 sections affected on 3rd & 4th flrs. Remove/replace 3ft x 10ft section of gypsum/plaster wall to enact repairs. Replace 10ft of 6in cast iron pipe & 20ft of 2in Cast iron pipe. Set-up (2) containments, approx 980sf. Drying equipment, Conduct 2x day moisture readings, remediation, disinfect/bacterial cleaning due to black water contamination and perform ACM/Environmental testing.	\$ 29,860	\$ 29,860	In Work	100
48	FM-0055188	Los Angeles	Inglewood Courthouse	19-F1	1	Plumbing - Renovate roofing penetration to prevent future damage. Water penetrated via conduit penetrating the roof. Remediation water damage in ACM environment and replace affected ceiling tiles, stop leak and restore piping. Water is leaking from the 6th floor ceiling into rooms 600B & 609. 10sq of ceiling tiles and 10sq of carpet has been affected in rooms 600B & 609. Files in room 600B have been affected by the water leak. Fireproofing is wet and will be remediated.	\$ 30,125	\$ 22,461	In Work	74.56
49	FM-0055199	Los Angeles	Compton Courthouse	19-AG1	1	Plumbing - Replace failed cast iron piping in ceiling area. Remediate water damage in an ACM environment in affected areas approx. 10 sq. ft. of 1' x 1' ceiling tiles & 5-10 sq. ft. of carpet in room 856, and replace damaged drain line. A cast iron drain line located in the ceiling between the 8th & 9th floors is damaged causing water to leak down into 8th floor Rm. 856 public defender's office; there is water damage to ceiling tiles & moisture on floors & walls.	\$ 29,895	\$ 19,770	In Work	66.13
							\$1,325,889	\$1,116,044		



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

**Action Item 2 – (Action Required) - List B – Facility
Modifications Less than \$50K (Priority 2)**

Summary:

List B – Facility Modifications Less than \$50K (Priority 2)

Total Project Count:	166
Total Potential FM Budget Share of Cost:	\$1,322,178

Supporting Documentation:

- List B – Facility Modifications Less than \$50K (Priority 2)

Action Requested:

Ratify Judicial Council Staff preliminary decision for execution approval of List B – Facility Modifications Less than \$50K (Priority 2).

This page intentionally left blank



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
1	FM-0052337	Napa	Juvenile Court	28-C1	2	HVAC - Replace approx. 20' of damaged round duct work and failed sheet metal duct seam sealant system.	\$ 22,137	\$ 22,137	Unfunded	100
2	FM-0054912	Orange	Central Justice Center	30-A1	2	Elevator - Replace hydraulic tank unit assembly on elevator #8 with one new dry pump unit to include new motor, tank, Maxton valve, silencer, oil level gauge, rubber mounting pads, hydraulic fluid, isolation coupling and low oil switch. The 35 year old hydraulic tank unit assembly is leaking from one of the seams due to expansion and contraction during normal operation.	\$ 49,954	\$ 45,543	In Work	91.17
3	FM-0054918	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	2	Elevators - Replace defective (18) elevator controller cooling fans, (2) per unit. The controller cooling fans have broken or are malfunctioning; without cooling fans the controllers could overheat and cause elevator break down & possible entrapment.	\$ 4,952	\$ 3,466	In Work	69.99
4	FM-0054919	Santa Clara	Morgan Hill Courthouse	43-N1	2	HVAC - Replace failed (1) new B3920 Controller and test. AHU #1 Andover controller causing warning 34 buss communication error. Similar issue occurred to AHU #2 and #5 controller failed.	\$ 3,784	\$ 3,784	Complete	100
5	FM-0054921	San Diego	Juvenile Court	37-E1	2	HVAC - Remove and replace supply fan 20hp VSD; remove and replace return fan 7.5hp VSD. VSDs to include electronic bypass. Lubricate and verify operation of the economizer and exhaust dampers. Unit starts and stops, speed controls are non-operational and do not communicate with BAS.	\$ 13,380	\$ 13,380	Complete	100
6	FM-0054922	San Diego	Juvenile Court	37-E1	2	HVAC - Remove and replace supply fan 15hp VSD; remove and replace return fan 3hp VSD. VSDs to include electronic bypass. Lubricate and verify operation of the economizer and exhaust dampers. Unit starts and stops, speed controls are non-operational and do not communicate with BAS.	\$ 12,169	\$ 12,169	In Work	100
7	FM-0054923	Los Angeles	Burbank Courthouse	19-G1	2	Elevators - Renovate failed alarm bell and install code complaint emergency battery lowering device on elevator unit. Elevator #2 is not currently compliant and needs upgrades to existing system in order to complete preliminary work order requirement.	\$ 4,656	\$ 4,226	Complete	90.76
8	FM-0054924	Orange	Central Justice Center	30-A1	2	HVAC - Replace failed shaft and VFD to the 2nd floor AHU-15 supply fan affecting courtrooms and chambers. Project will be completed after hours.	\$ 7,526	\$ 6,861	In Work	91.17
9	FM-0054928	Orange	North Justice Center	30-C1	2	Interior Finishes Emergency Exit Corridor - Remove dead-end corridor and the closets created to restore the proper exit corridor and in-custody passage, per the local Fire Authority and a preliminary notice, on the 3rd floor, phase III of the courthouse. The project includes the removal and replacement of 2 doors with appropriate door systems with panic hardware, micro-switch kits, exit delay timer control boxes, siren alerts and integration into existing fire alarm, abate existing flooring.	\$ 45,000	\$ 45,000	Unfunded	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
10	FM-0054931	San Bernardino	Big Bear Courthouse	36-11	2	COUNTY MANAGED - Exterior Shell - Reseal the concrete exterior of the building approx. 10,900SF. Existing sealant and lower paint layers are cracking and exposing the block. Work is necessary to prevent water intrusion in the rainy season. Scope includes seal cracks and renovate wall penetrations.	\$ 8,504	\$ 8,504	In Work	100
11	FM-0054933	Orange	Central Justice Center	30-A1	2	Plumbing - Replace 2 Variable Frequency Drives and one motor to the domestic pumps supplying water to the building.	\$ 21,607	\$ 19,513	Unfunded	90.31
12	FM-0054934	San Diego	County Courthouse	37-A1	2	Electrical - Replace approx. 200 lights and replace approx. 12 ballasts. Courtroom lights are too dim and need replacement. Lamps in area contain ACM and required ACM containment set up and proper procedure to be followed.	\$ 10,629	\$ 8,229	In Work	77.42
13	FM-0054935	Los Angeles	Santa Monica Courthouse	19-AP1	2	Electrical - Remove all existing non-compliant exit signs in stairwell, install new wiring & exit signs in proper locations that are clearly visible. The existing emergency exit signs in the North East stairwell are currently code non-compliant & do not illuminate. Install 6 Lithonia 20 LED Emergency/Exit units, 100 of Conduit, 300 wiring, 10 new junction.	\$ 7,174	\$ 5,631	Unfunded	78.49
14	FM-0054936	Los Angeles	Alhambra Courthouse	19-11	2	HVAC - Provide & install (1) new 2" Eclipse butterfly valve & (1) new linkage arm in place of existing FGR valve. Boiler #3 is unable to pass AQMD testing and tune up can not be performed due to a seized butterfly valve; boiler is not in compliance with SCAQMD standards.	\$ 5,223	\$ 4,492	In Work	86
15	FM-0054937	Los Angeles	Norwalk Courthouse	19-AK1	2	HVAC - Remove & replace (2) 3" domestic water OS&Y valves in basement. The 3" isolation valves for the fire protection water are currently unable to be closed due to excessive rust and corrosion on the valve assembly; renovation work is required to bring the system to compliance & allow for proper flushing & drainage.	\$ 4,724	\$ 4,017	In Work	85.03
16	FM-0054938	San Mateo	Municipal Court Building - Northern Branch	41-C1	2	Exterior - Remove low and overhanging tree branches due to local vandalism; Remove 7 dead trees - Several trees have broken and overhanging branches causing safety issues at the parking areas.	\$ 13,387	\$ 11,139	In Work	83.21
17	FM-0054939	Los Angeles	Inglewood Courthouse	19-F1	2	Fire Protection - Replace (1) defective smoke detector on 7th floor, (1) defective water flow switch on 4th floor, and modify tamper switch in basement. There are currently defective components in the fire alarm system that were found during annual testing & need to be replaced to restore the system to proper operation.	\$ 3,026	\$ 2,256	Complete	74.56
18	FM-0054940	Placer	South Placer Justice Center	31-H1	2	Plumbing - Flush valves vandalized - Install automatic flush valves at each urinal and select W.C.s to avoid flood possibility and improve water conservation.	\$ 3,500	\$ 3,500	In Work	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
19	Fresno	Fresno County Courthouse.	10-A1	2	Interior Finishes - Demo existing split and cracked vinyl floor covering in the two employee staff restrooms on the 1st floor at the back of the Jury Assembly Room and install new vinyl flooring approx 200 sq. ft. - Existing flooring conditions present health and safety hazard with water intrusion under the vinyl flooring, lifting it up, creating trip hazards, and causing more splits and cracks. Repairs are not practical and duct tape has been put down as a temporary, not truly effective, measure until new flooring can be installed.	\$ 4,849	\$ 4,849	In Work	100
20	Los Angeles	Stanley Mosk Courthouse	19-K1	2	Interior Finishes - Replace existing damaged doors & hardware with new steel fire rated doors, surface mount panic hardware & closers. Current hallway fire doors leading to the 3rd floor are damaged beyond repair & missing hardware which are both fire & safety hazards.	\$ 5,305	\$ 5,160	Unfunded	97.26
21	Los Angeles	Norwalk Courthouse	19-AK1	2	Vandalism - Grind, sand and polish stainless steel elevator panels & install new plexi glass panels in elevators. Graffiti has been engraved into multiple stainless steel and plexi glass panels inside public elevators 1-4 which could create a safety issue.	\$ 15,421	\$ 13,112	Awaiting Shared Cost Approval	85.03
22	San Diego	Juvenile Court	37-E1	2	Holding Cell - Tie into existing hot water above the women's locker room. Run a 1/2 copper water line from the locker room to the holding cells and connect to the existing toilet/lavatory combo units in the holding cells to provide hot water. Install insulation on new water service. Work needed due to discrepancies found during the San Diego County IMQ Title 15 Health Inspections - FY2015. Holding cell are required to have hot water and the holding cells failed the requirement for hot water.	\$ 6,372	\$ 6,372	In Work	100
23	Los Angeles	Downey Courthouse	19-AM1	2	Fire Protection - Replace (10) corroded sprinkler heads in loading dock entrance, Replace (17) corroded sprinkler heads and (17) escutcheons in North Hallway, 1st floor, and Replace (18) corroded sprinkler heads and (18) escutcheons in South Hallways and offices, 2nd floor. work is require by code.	\$ 4,086	\$ 3,420	Complete	83.7
24	Los Angeles	San Fernando Courthouse	19-AC1	2	Elevators, Escalators, & Hoists - Elevator Generator Refurbishment on four elevators: Judge's 1, Judge's 2, Passenger 1 and Jail 2. Replace generator bearings on the AC and DC end of each unit. Elevator cabs not leveling properly on the floor causing tripping hazard, generator bearings need to be replaced.	\$ 49,910	\$ 41,630	Unfunded	83.41
25	Napa	Criminal Court Building	28-A1	2	Plumbing - Holding Cells - Remove combo unit sink/toilets (9); clear/replace supply lines; replace seals; re-install units - supply line clogs due to electrolysis corrosion.	\$ 4,991	\$ 4,991	In Work	100
26	Santa Clara	Morgan Hill Courthouse	43-N1	2	Interior Finishes - Replace failed surface continuous hinge (2ea), cover plate (6ea) - existing hinges cannot be located - and (1) door closure.	\$ 3,889	\$ 3,889	In Work	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
27	Fresno	Clovis Court	10-G1	2	Pest Control - Tarp the building and fumigate for drywood termites per state regulations. Prepare site for fumigation and disconnect/reconnect utilities as required. A termite inspection was conducted and the resulting Wood Destroying Pests and Organisms Report showed visible problems of drywood termites with fumigation.	\$ 7,645	\$ 7,645	In Work	100
28	Los Angeles	Pomona Courthouse South	19-W1	2	Elevators, Escalators, & Hoists - Replace SCR-PRI board and door operator linkage bearings. The SCR-PRI board has stopped working and the elevator will not run without a working SCR-PRI board. Also the bearings are worn out due to age and need to be replaced for smooth operation and to prevent breakdowns.	\$ 3,801	\$ 3,464	In Work	91.14
29	Santa Clara	Morgan Hill Courthouse	43-N1	2	Fire Protection- Fire Life Safety - Continuous Ground Fault on Fire Panel - Replace 1 each failed Notifier LEM module - Remove and replace existing with new (1 ea) Notifier LEM-320 Loop Expander module.	\$ 3,493	\$ 3,493	In Work	100
30	San Diego	Hall of Justice	37-A2	2	COUNTY MANAGED - Electrical - Install manual bypass switch to Court IT quadrant, Room 456. Currently, the entire wing of this building is configured in a way that shuts lights off after 6:00PM and on weekends. Court IT and their sub-contractors are required to work after hours to support court operations and do require sufficient lighting other than the current utilization of desk, floor lamps and moderate emergency lighting in corridor that has presented a safety concern.	\$ 3,105	\$ 3,105	In Work	100
31	Los Angeles	Beverly Hills Courthouse	19-AQ1	2	HVAC - Replace (2) 6" failed lug style isolation butterfly valves with new using new bolt kits. The (2) condenser chilled water valves on chiller #2 are not working properly; the valves are not stopping the water flow, which is necessary for system isolation during repairs or parts replacement.	\$ 4,871	\$ 3,873	In Work	79.52
32	Los Angeles	Michael D. Antonovich Antelope Valley Courthouse	19-AZ1	2	HVAC - Install (1) new 20hp motor, install (1) new J8 coupling, & install required shims to properly align new motor. The P-2B chilled water pump motor had bad bearings, a bad coupling, and is not operating properly & making loud noises.	\$ 3,655	\$ 2,687	In Work	73.51
33	Los Angeles	Michael D. Antonovich Antelope Valley Courthouse	19-AZ1	2	HVAC - Remove existing bearings, install new bearings, re-assemble motor to pump, & install required shims to properly align motor. The P-3B condenser water pump is currently making loud noises, vibrating, & not functioning properly; this pump is currently the only back up to the main pump & needs to be put back into service as soon as possible.	\$ 3,641	\$ 2,676	In Work	73.51



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
34	Alameda	Fremont Hall of Justice	01-H1	2	Security - Sally Port Gate - Replace failed curtain - Remove existing door and operator - Remove guide rails - Remove existing curtain - Install 1 each new gate and operator assembly - Return to normal service.	\$ 20,350	\$ 20,350	In Work	100
35	Los Angeles	Chatsworth Courthouse	19-AY1	2	HVAC - Remove & replace (2) 6" butterfly isolation valves using new hardware & replace (1) defective pressure regulating valve. Chiller #2 cannot currently be tested or analyzed due to the isolation valves not functioning properly; isolation valves stop water from getting to the chiller temporarily so tests, maintenance, modifications, etc. can be performed.	\$ 4,745	\$ 3,976	In Work	83.8
36	Napa	Historical Courthouse	28-B1	2	Electrical- Remove (1) electrical whip and modify to electrical outlet in the civil area. Modify (3) electrical outlets in the law library and connect electrical whips for modular furniture. Install (1) new electrical location in public space to accommodate modular furniture and connect electrical whip. Space reconfiguration required due to post earthquake court relocations.	\$ 2,356	\$ 2,356	In Work	100
37	Orange	West Justice Center	30-D1	2	Interior Finishes - Acoustic ceiling tiles in the Basement Sergeant's office are falling off creating a safety concern. Remove all ceiling tiles and mastic, patch drywall, float and re-finish ceiling.	\$ 3,055	\$ 2,770	In Work	90.68
38	Santa Clara	Downtown Superior Court	43-B1	2	Electrical - Replace failed 1 each connection of automatic transfer switch (43-B1 ATS01) to generator start signal - Court Impact, a loss of power to internal mains of 43-B1 will not initiate a start signal to the generator - Install hard wire connection from the ATS to the Generator - Run new 300 feet of control cabling from B1 ATS to the B2 ATS and terminate - Program ATS and test.	\$ 6,577	\$ 6,577	In Work	100
39	Los Angeles	Inglewood Courthouse	19-F1	2	HVAC - Remove end bell, replace (6) motor terminals, re-attach end bell & attach starter to new motor terminal connections. Chiller #2 is currently leaking refrigerant and is low on oil, if modifications are not performed chiller could shut down on low oil pressure which could possibly affect court operations.	\$ 14,670	\$ 10,938	In Work	74.56
40	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	2	HVAC - Drain condenser water system, remove supply & return chiller condenser shut off valves, install new supply and return valves with new couplings, refill & test system. Chiller #2 currently has isolation valves for the condenser water system that do not close and need to be replaced so that the flow of water can be stopped and PM can be performed.	\$ 9,470	\$ 6,628	In Work	69.99



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
41	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	2	HVAC - Drain condenser water system, remove supply & return chiller condenser shut off valves, install new supply and return valves with new couplings, refill & test system. Chiller #1 currently has isolation valves for the condenser water system that do not close and need to be replaced so that the flow of water can be stopped and PM can be performed.	\$ 9,470	\$ 6,628	In Work	69.99
42	Santa Barbara	Santa Maria Courts Building G	42-F5	2	Elevators, Escalators, & Hoists - Judges' Elevator 3 - Restore Battery Lowering Device to function as outlined by DIR circular Letter E-01-03. DIR requirement to comply with circular Letter E-01-03; Batteries and device to be replaced for full compliancy.	\$ 5,701	\$ 5,701	Complete	100
43	Santa Barbara	Santa Maria Courts Building G	42-F5	2	Elevators, Escalators, & Hoists - Passenger Elevator 1 - Restore Battery Lowering Device to function as outlined by DIR circular Letter E-01-03. DIR requirement to comply with circular Letter E-01-03; Batteries and device to be replaced for full compliancy.	\$ 5,701	\$ 5,501	Complete	96.49
44	Santa Barbara	Santa Maria Courts Building G	42-F5	2	Elevators, Escalators, & Hoists - Custody Elevator 2 - Restore Battery Lowering Device to function as outlined by DIR circular Letter E-01-03. DIR requirement to comply with circular Letter E-01-03; Batteries and device to be replaced for full compliancy.	\$ 5,701	\$ 5,701	Complete	100
45	Santa Barbara	Santa Maria Courts Building C + D	42-F1	2	Elevators, Escalators, & Hoists - Passenger Elevator 1 - Restore Battery Lowering Device to function as outlined by DIR circular Letter E-01-03. DIR requirement to comply with circular Letter E-01-03; Batteries and device to be replaced for full compliancy.	\$ 5,701	\$ 3,118	Complete	54.7
46	Los Angeles	Pasadena Courthouse	19-J1	2	Elevators, Escalators, & Hoists - Remove broken obsolete brake lever arm, install (1) newly manufactured brake lever arm, test elevator for proper operation & return to service. The brake lever arm on elevator #3 is currently broken and the car is out of service; brake lever arm will need to be replaced in order to put the elevator back in service.	\$ 4,638	\$ 3,216	Complete	69.35
47	San Bernardino	Barstow Courthouse	36-J1	2	HVAC - Replace leaking discharge isolation valves and pressure relief valves on all 3 refrigerant circuits. Pressurize all 3 circuits with Nitrogen and perform leak check. Evacuate circuits to industry standards and charge circuits with refrigerant to design. This work is necessary as circuit 1 has lost a significant amount of its charge and has been locked-out leaving the chiller operating at 66% capacity. Deficiencies found during Level VIII PM SWO 2462621.	\$ 10,706	\$ 8,343	In Work	77.93



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
48	FM-0054991	Los Angeles	Parking Structure Lot 59- Whittier Admin CTR	19-AO2	2	Vandalism - Paint over all graffiti on exterior walls and stairwells throughout parking structure. There is currently graffiti spray painted and written on multiple walls and stairways throughout the parking structure which can be seen by anyone in the area and may contain inappropriate words and images.	\$ 4,316	\$ 3,730	In Work	86.43
49	FM-0054992	Los Angeles	Inglewood Courthouse	19-F1	2	Elevator - Replace defective selector sheave in Elevator #5. The sheave provides information as to the location of the elevator within the hoist way. Work must be completed to ensure proper elevator performance.	\$ 9,814	\$ 7,317	In Work	74.56
50	FM-0055002	Los Angeles	Stanley Mosk Courthouse	19-K1	2	Escalator - Coil and Brake - Remove and replace the coil and break to one escalator, work requires special rigging and the removal of the motor and gear box to access the break and coil. Currently the escalator has been taken out of service and work must be completed to bring it back to working conditions.	\$ 17,010	\$ 16,544	Unfunded	97.26
51	FM-0055003	San Diego	East County Regional Center	37-I1	2	Plumbing - Water remediation, environmental testing, disinfect, carpet water extraction - approx. 150 sq.ft., carpet cleaning. Replace 4" drain pipe. Replace 5 wet ceiling tiles, build back and replace drywall in children's hallway, men's public restroom and utility closet that was removed to access leak. Install access panel in men's public restroom. Broken 4" drain line on 1st flr next to law library caused flooding on ground flr Pre Trial Services, and 1st flr children's waiting room.	\$ 3,739	\$ 2,532	In Work	67.71
52	FM-0055004	Lake	Lakeport Court Facility	17-A3	2	COUNTRY MANAGED - Pest Control - Seal all openings in exterior of building per county inspections to keep bats out of court and common area spaces, approx. 3200 lin ft of sealing using a 120 ft boom lift.	\$ 4,443	\$ 4,443	Complete	100
53	FM-0055005	Los Angeles	Airport Courthouse	19-AU1	2	HVAC - Remove, rebuild, & re-install sand filter pump. The sand filter pump impeller is currently locked up & the motor will not spin; sand filter needs to be rebuilt in order to operate properly.	\$ 2,634	\$ 2,033	In Work	77.17
54	FM-0055006	Los Angeles	Metropolitan Courthouse	19-T1	2	HVAC - Replace 16 (8 each) air inlet louvers on cooling towers 1 & 2 to achieve maximum air flow and efficiency. Currently the air inlet louvers are past their life expectancy and in bad condition causing poor air flow into the cooling tower making it inefficient (Poor Heat Transfer).	\$ 4,989	\$ 4,717	In Work	94.54
55	FM-0055007	Los Angeles	Beverly Hills Courthouse	19-AQ1	2	Exterior Shell - Install new 16'L Miller safety edges & new photo eyes on Gates 1 & 2. The current safety edges on the judges' roll up gates are not functioning properly during gate operation which is a safety hazard.	\$ 4,475	\$ 3,559	Complete	79.52



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
56	FM-0055008	Los Angeles	Inglewood Courthouse	19-F1	2	Fire Protection - Install approx. (50) LED Retrofit Kits on exit signs so they will stay illuminated at all times. Approx. (50) exit signs throughout the facility currently contain step down transformers that burn out due to power surges & fluctuations leaving exit signs not illuminated properly; Fire Marshall deficiency report states all exit signs must be internally illuminated at all times.	\$ 3,847	\$ 2,868	In Work	74.56
57	FM-0055010	Los Angeles	Metropolitan Courthouse	19-T1	2	Plumbing - Replace approx. 6LF of 6" carbon steel spool pipe with new 6" stainless steel spool pipe. The 6" domestic water pipe that runs between the backflow preventer & city water meter is damaged & leaking which could lead to flooding in the parking structure and would affect court operations.	\$ 5,145	\$ 4,864	In Work	94.54
58	FM-0055011	Los Angeles	Chatsworth Courthouse	19-AY1	2	Plumbing - Replace (24) water hammer arresters & install (24) ball valves for future isolation: (6) 1" arresters & valves, (16) 3/4" arresters & valves, (2) 1-1/2" arresters & valves. Current water hammer arresters in multiple locations in the basement & on the first floor are defective & are not absorbing water pressure surges the way they should which could lead to broken pipes and floods if not replaced.	\$ 6,850	\$ 5,740	Complete	83.8
59	FM-0055012	Los Angeles	Michael D. Antonovich Antelope Valley Courthouse	19-AZ1	2	HVAC - Shut down power to sub panel, remove existing 480v breaker that pertains to P3-C condenser pump & replace per manufacturer specifications. The current electrical breaker for condenser pump #6 will not reset; the pump is currently locked out which means there is no back up if main pump fails.	\$ 5,297	\$ 3,894	In Work	73.51
60	FM-0055013	Placer	South Placer Justice Center	31-H1	2	Access control system has failed due to lack of programming and monitoring - Re-program door locks to manage access control between public and judicial corridors, monitor access to IT and secure areas with available key fobs. Retrieve keys to prevent un-authorized access. Provide training and software to manage lock control and monitoring.	\$ 3,500	\$ 3,500	In Work	100
61	FM-0055014	Los Angeles	Pasadena Courthouse	19-J1	2	Plumbing - Replace approx. 10' of 3" cast iron pipe & fitting; install 2' sq. access panel in ceiling of storage room; install approx. (20) 12" x 12" new ceiling tiles; clean & disinfect leak affected areas, perform final environmental testing. A 3" main cast iron drain pipe located under the 2nd floor deputy locker room & in the ceiling of the 1st floor storage room clogged & cracked, leaking into first floor storage room causing moisture issues on walls & ceiling.	\$ 9,167	\$ 6,357	Complete	69.35
62	FM-0055015	San Diego	Juvenile Court	37-E1	2	Plumbing - Replace two 2" Belimo valves and actuator. Due to wear and tear valves and actuator are no longer working properly, are beyond their life expectancy and require replacement.	\$ 3,706	\$ 2,765	In Work	74.62



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
63	Los Angeles	Compton Courthouse	19-AG1	2	Plumbing - Remove existing submersible pump & install (1) new pump, (1) new 4" gate valve, and re-connect to existing piping with new fittings. Current submersible pump is failing and needs to be replaced in order to pump water out of the pit; if pump is not replaced an overflow and flood could occur causing a health and safety hazard.	\$ 10,705	\$ 7,079	In Work	66.13
64	San Diego	South County Regional Center	37-H1	2	COUNTY MANAGED - Electrical - Replace failed electrical circuit components affecting Court & Law Library.	\$ 5,623	\$ 5,623	In Work	100
65	Merced	New Downtown Merced Courthouse	24-A8	2	Electrical - Install new fuel pump and new fuel gauge - Fuel pump has started leaking diesel through drain port, fuel gauge has been repaired prior and is stuck again. Unit requires replacement.	\$ 6,389	\$ 6,389	In Work	100
66	Los Angeles	Airport Courthouse	19-AU1	2	Plumbing - Re-program boilers to operate in master/slave configuration, replace pressure relief valves & thermometers, and return to proper operation. Domestic hot water boilers 1 & 2 are currently malfunctioning and not coming on line which leaves multiple areas in the building without hot water.	\$ 3,052	\$ 2,355	In Work	77.17
67	Los Angeles	Metropolitan Courthouse	19-T1	2	Plumbing - Replace one 5hp pump motor and re-build one existing submersible pump. Currently the submersible pump is not functioning and the work must be completed to ensure proper coverage of the parking structure so it does not flood.	\$ 14,751	\$ 13,946	In Work	94.54
68	Santa Barbara	Santa Maria Clerks Building	42-F7	2	Fire Protection - Replaced undersized Backflow Device\Backflow Preventer - BFP 04 with 2" model. Undersized BFP installed by County during construction causing audible noise intrusion in interior of Clerk's office.	\$ 2,580	\$ 2,580	Complete	100
69	San Diego	East County Regional Center	37-I1	2	Plumbing - Post flood Water remediation, extract standing water, carpet shampoo, disinfect and dehumidification. Pre-trial services and Children's Hallway had standing water. Water needed to be extracted, carpets need to be shampooed, disinfected and tested for bacteria.	\$ 9,940	\$ 9,940	In Work	100
70	Santa Barbara	Lompoc Municipal Court	42-D1	2	HVAC - Replace inoperable Split System. Split system no longer functioning as designed for unit servicing IT room. Existing unit will need to be removed from roof and replaced with new.	\$ 4,992	\$ 1,761	Complete	35.27
71	San Bernardino	Rancho Cucamonga Courthouse	36-F1	2	HVAC - Replace a 3" isolation valve on the discharge line of Chiller #2. This work is necessary due to deficiencies found during the Level VIII PM 2476373. Project will include after-hours work and temporary cooling to facilitate chilled shut down.	\$ 5,218	\$ 3,968	In Work	76.05
72	Los Angeles	Airport Courthouse	19-AU1	2	Electrical - Replace approx. (75) emergency exit lights & ballasts. During annual emergency lighting test it was found that multiple lights were out and need to be replaced in order to bring the system to compliance.	\$ 11,345	\$ 8,755	In Work	77.17



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
73	Santa Barbara	Santa Barbara Figueroa Division	42-B1	2	Electrical - Replace faulty lighting control panel. Existing lighting control panel no longer functioning as designed causing intermittent lighting failures in Holding and Detention cells.	\$ 4,510	\$ 4,510	Complete	100
74	Santa Barbara	Santa Maria Courts Building G	42-F5	2	HVAC - Replace inoperable exhaust fan - exhaust fan 1 motor and bearings no longer functioning as designed and must be replaced. Existing unit will need to be removed from roof and replaced with new.	\$ 3,030	\$ 2,924	In Work	96.49
75	San Diego	County Courthouse	37-A1	2	HVAC - Post flood water remediation in ACM environment. Replaced damaged ceiling tiles and cove base in interior space caused by initial P1. Remediate water damage in affected areas in basement, chambers, office space, holding cells and mezzanine lounge.	\$ 16,091	\$ 12,458	In Work	77.42
76	Los Angeles	Metropolitan Courthouse	19-T1	2	Security - Install (3) new Glenn Johnson 904 overhead stops on 3 sets of double doors. The main entry doors are currently getting slammed open by the public which is damaging the bottom arms on the doors; this is causing the doors to not close properly which is a safety & security concern.	\$ 2,918	\$ 2,759	In Work	94.54
77	San Mateo	Central Branch	41-B1	2	Electrical - Replace existing non positional exterior light fixtures (6) on north and south sides of the building with bright LED lights - reduced usage facility shows an increased level of vandalism and site damage. Work needed to mitigate future potential damage.	\$ 6,090	\$ 6,090	In Work	100
78	San Bernardino	Rancho Cucamonga Courthouse	36-F1	2	HVAC - Replace a 3" isolation valve on the discharge line of Chiller #1. This work is necessary due to deficiencies found during the Level VIII PM 2462599. Project will include after hours work and temporary cooling to facilitate chilled shut down.	\$ 5,466	\$ 4,157	In Work	76.05
79	Los Angeles	Alhambra Courthouse	19-I1	2	Interior Finishes - Furnish & install (1) new stained door in Judge's chambers. The Judges chambers in Department 4 is currently missing a door and the Judge has requested that a new door be installed which will prevent any future health & security concerns.	\$ 4,459	\$ 3,835	In Work	86
80	Los Angeles	Alhambra Courthouse	19-I1	2	Plumbing - Install new 3hp submersible cutter pump with new cast iron flanged discharge elbow. The sewer ejection pump is currently leaking which indicates that the column shaft bearings are severely worn and the discharge pipe is severely corroded.	\$ 11,159	\$ 9,597	In Work	86
81	Los Angeles	Airport Courthouse	19-AU1	2	Roof - Re-coat Existing Radius Roof Section - Remove loose roofing granules and coat the roof with four coats of Elastomeric Cool Roof product to prevent leakage in the rain. Cool roof coating should extend the life of the roof another ten years.	\$ 47,943	\$ 36,998	Unfunded	77.17



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCF MAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST	
82	FM-0055063	Sacramento	Carol Miller Justice Center	34-D1	2	Plumbing - Remediation, environmental testing, dry leak affect area, restore 6" copper piping. Leak on 6" copper main domestic line in ceiling above sheriff's locker room; leak damaged 2ft x 2ft hard lid ceiling. No impact to court operations.	\$ 2,671	\$ 2,671	In Work	100
83	FM-0055064	Los Angeles	Compton Courthouse	19-AG1	2	HVAC - Replace the chilled water condenser end bells, clean blocked tube entrance thoroughly, install end-bells & piping using new gaskets & seals; Move pump motor & replace coupling insert, install motor & align to pump, then return to operation. Currently one of chiller #2 condenser water tubes is clogged & beyond repair, chilled water pump & condenser water pump couplings need to be replaced to prevent premature failure of pumps & motors.	\$ 4,654	\$ 3,078	In Work	66.13
84	FM-0055065	Los Angeles	Compton Courthouse	19-AG1	2	Vandalism - Remove etched/scratched graffiti from multiple doors & partition walls, then re-seal all areas where removal has been performed. The 1st, 4th, & 9th floor men's public restrooms have been vandalized by graffiti into doors & partition walls which is a safety hazard for the public.	\$ 4,492	\$ 2,971	In Work	66.13
85	FM-0055066	Contra Costa	Wakefield Taylor Courthouse	07-A2	2	Grounds and Parking Lot - Remove concrete stepping stones and tree roots from 20 foot path going from the judges' parking lot to the court entry; Dig down 4 inches; Lay a rock base; Install 3 x 20x 4 concrete sidewalk; Work to be done off hours. There have been numerous reports of tripping. Last Monday, a judge tripped and hit her head.	\$ 6,749	\$ 6,749	Complete	100
86	FM-0055067	Riverside	Southwest Justice Center	33-M1	2	HVAC - AHU #3 - Remove and replace the chilled water valve of air handler #3. The valve is leaking chilled water on to the roof of the building and can no longer be repaired. The replacement work will need to be done on a Saturday on overtime, due to the chilled water having to be shut off to system #3; this unit supplies cooling to some of the courtrooms and judges' chambers within the building.	\$ 10,157	\$ 10,157	In Work	100
87	FM-0055068	Los Angeles	Chatsworth Courthouse	19-AY1	2	Plumbing - Replace (1) existing valve with new Wilkins/Zurn 2.5" ZW-209 pressure reducing valve, & replace (1) wye strainer with new Wilkins/Zurn 4" FSC epoxy coated flanged wye strainer; including all necessary connections, gaskets, bolt kits & flanges. The current pressure reducer valve and wye strainer are old and rusted causing them to not work properly; water is leaking & if water continues to leak it could cause flooding & possibly stop water supply to the building.	\$ 6,196	\$ 5,192	In Work	83.8
88	FM-0055069	Orange	West Justice Center	30-D1	2	HVAC - Replace all filter driers, add loop guard agent on chiller #2 to prevent equipment failure and consequent loss of cooling to the building. The project will include after-hours execution, restart sequence test, removal of any build-up scale/debris, and chemical tube treatment to ensure proper operation of replaced components.	\$ 4,500	\$ 4,081	In Work	90.68



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
89	FM-0055070	Orange	West Justice Center	30-D1	2	HVAC - Replace all filter driers, add loop guard agent on chiller #1 to prevent equipment failure and consequent loss of cooling to the building. The project will include after-hours execution, restart sequence test, removal of any build-up scale/debris, and chemical tube treatment to ensure proper operation of replaced components.	\$ 4,174	\$ 3,785	In Work	90.68
90	FM-0055071	Los Angeles	Van Nuys Courthouse East	19-AX1	2	HVAC - Replace (30) burner gaskets, (1) spark igniter with required cable, (2) inducer draft motors, (1) exhaust blower so boiler will operate properly. RBI Boiler #4 is not currently providing hot water to the 4-stage HVAC system; the boiler has been out of service for some time and needs to be upgraded in order to operate again.	\$ 4,463	\$ 4,005	In Work	89.74
91	FM-0055072	Los Angeles	Long Beach Courthouse	19-Y1	2	Elevators, Escalators, & Hoists - Install new electronic door edge on elevator #4 to sense the presence of an obstruction in the door opening using infrared beams. Current mechanical safety edge on elevator #4 is not working properly and is a major safety concern as elevator doors could potentially close on someone. Unit is the only building elevator with access to the Mezzanine level. Decommissioning the unit is not an option at this time.	\$ 2,407	\$ 1,819	In Work	75.59
92	FM-0055073	Imperial	Imperial County Courthouse	13-A1	2	HVAC - Replace failed condenser system on AC unit that was found inoperable with a leak causing the IT room to shut down due to overheating. This is the only AC unit supplying critical system in the IT room. Replacement of the condensing system will ensure cooling to the IT Room.	\$ 2,616	\$ 2,616	Complete	100
93	FM-0055074	San Diego	Hall of Justice	37-A2	2	HVAC - Replace pump motor and mechanical seal for the VFD back up motor. VFD back up motor and pump has failed and must be replaced. Unit is not being supplied with chilled water from booster pumps and is relying on secondary mechanical chilled water system. Room 372.	\$ 5,257	\$ 2,115	In Work	40.24
94	FM-0055075	San Diego	North County Regional Center - Vista Center	37-F2	2	HVAC - Replace pump motor and mechanical seal for the VFD back up motor. VFD back up motor and pump has failed and must be replaced. Unit is not being supplied with chilled water from booster pumps and is relying on secondary mechanical chilled water system. Affects employee women's restroom/interpreter hallway.	\$ 3,605	\$ 3,605	Complete	100
95	FM-0055078	San Diego	County Courthouse	37-A1	2	Elevators, Escalators, & Hoists - Minor renovations for Escalators 1-2 up, 2-3 up and 3-2 down. Work required per DIR notice to comply. Work to include replacement of damaged steps, replacement of failed hardware generating non-compliant oil leaks, restore electrical component for motor junction boxes to original design.	\$ 17,448	\$ 13,508	Complete	77.42



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
96	San Diego	County Courthouse	37-A1	2	Holding Cell - Replace Air control valve assembly that controls the faucets in holding cell & replace poly tubing. The faucet in cell #2 is constantly running water and not working properly. This needs to be addressed to preclude risk of flooding and a waste of water resources.	\$ 2,795	\$ 2,795	In Work	100
97	San Diego	South County Regional Center	37-H1	2	Fire Protection - Replace five Fire Door Release Devices. Fire flies above five fire doors are broken or defective. This presents a safety issue during a fire, due to not functioning properly.	\$ 4,833	\$ 1,458	In Work	30.16
98	Merced	New Downtown Merced Courthouse	24-A8	2	Electrical - Add grounding in hub rooms (total of 4) to protect IT equipment. Racks were added but not grounded.	\$ 3,076	\$ 3,076	In Work	100
99	San Diego	East County Regional Center	37-I1	2	Electrical - 9th Floor: AH20 motor wires not spliced properly and will be corrected. Penthouse: Replace 2 Fuse Clamps/3 fuses. 8th Floor: Move circuit/replace breaker. 7th, 4th and 1st Floors, G Level, Outside Electrical Room: Replace breakers. 5th Floor: Replace breakers #4, #8. Ground Floor: Replace rusted panel parts. G level: Remove wiring, re-strip connects. Chiller Room: Replace contactor. Modifications needed based on Infrared Report on Electrical Panels and devices located throughout Courthouse. High heat in scan shows high risk of failure.	\$ 48,418	\$ 48,418	In Work	100
100	Lake	South Civic Center	17-B1	2	Plumbing - Clear clogged line - Line jet all of the main lines from cleanouts (2) as directed by building engineer's camera and record the main lines from the courthouse to the connection with the main sewer.	\$ 6,316	\$ 6,316	In Work	100
101	Mendocino	County Courthouse	23-A1	2	Electrical (Safety) - Replace damaged, non-operational light system - Current system has failed. 1.) Provide and install 2 new LED light fixtures with slip fitter mounting at the top of the entry stairs to the court house building. 2) The new fixtures will be mounted on Atlas wall brackets extending 18" from the wall for directional lighting. 3) The junction box/gutter and roughly 50lf of conduit will be mounted on the surface of the tile and will be painted green/turquoise in color to match the existing.	\$ 5,439	\$ 3,678	In Work	67.62
102	San Diego	North County Regional Center - Vista Center	37-F2	2	Plumbing - First Floor Secured Hallway - Replaced (2) three-piece cold water ball valves. Cold water valve in ceiling was deteriorated and leaking requiring replacement. Scope of work included isolation and draining of water for valve replacement, then refilled and checked for leaks after installation of new valves.	\$ 3,359	\$ 3,359	Complete	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
103	FM-0055097	Fresno	Fresno County Courthouse.	10-A1	2	Fire Protection - Install additional sprinkler heads in 7th floor air handler room, 3rd floor old server room and above the electrical switch gear in the B-2 mechanical room. Install smoke gaskets at the double door entrance at the B-2 garage level. Install (5) photo luminescent "EXIT" signs and (2) photo luminescent directional signs and remove and reinstall 12" x 12" ceiling tile for installation of backing at five locations. Correction items per 2014 Fresno Fire Inspection.	\$ 19,840	\$ 19,840	In Work	100
104	FM-0055098	Los Angeles	Burbank Courthouse	19-G1	2	Roof - Install (1) new 3' x 7' steel stiffened 16g fire rated door with continuous full surface hinge. The roof access door is currently decomposing and splintering due to weather and elements and has become a safety hazard to anyone who operates it.	\$ 2,783	\$ 2,526	In Work	90.76
105	FM-0055099	Orange	Central Justice Center, Civil Complex Center	30-A3	2	Fire Protection - To remove and replace 20 LED battery backup exit signs in place of existing powered exit signs, supply and install 15 battery backup exit signs in place of self-illuminating exit signs, run power from closet emergency light or exit sign. Work required due to system failure and in compliance with per Cal-fire correction notice 0130-11.	\$ 9,636	\$ 9,636	In Work	100
106	FM-0055102	Orange	Harbor Justice Center-Newport Beach Facility	30-E1	2	HVAC - Remove and Replace Degraded Insulation on Chilled Water Pipes. Exposed chilled water pipes will sweat and drip during warm weather.	\$ 9,967	\$ 8,404	In Work	84.32
107	FM-0055103	Los Angeles	Michael D. Antonovich Antelope Valley Courthouse	19-AZ1	2	HVAC - Replace inlet vanes and orifice cylinder in order to restore suction diffuser on condenser water pump #6. The current suction diffuser has fallen apart and is not operating properly which could lead to future damage to the condenser water pump; installation of new suction diffuser will help prevent down time and costly repairs in the future.	\$ 2,545	\$ 1,871	In Work	73.51
108	FM-0055104	Lake	South Civic Center	17-B1	2	Exterior Shell - Install one (1) Hamilton 145BD secured drop box with lock into exterior wood wall at the front of the building due to court closures and hours reductions. Reposition and anchor existing exterior bench.	\$ 4,249	\$ 4,249	In Work	100
109	FM-0055105	Santa Barbara	Santa Maria Courts Building G	42-F5	2	HVAC - Replace inoperable exhaust fans 11 & 16. Exhaust fans 11 & 16 motors and bearings no longer functioning as designed and must be replaced. Existing units will need to be removed from roof.	\$ 4,674	\$ 4,510	In Work	96.49
110	FM-0055106	Santa Barbara	Santa Maria Courts Building C + D	42-F1	2	Plumbing - Replaced leaking domestic hot water line, adjacent valve and fittings; build back and finish work. Visible signs of water intrusion above drywall ceiling in gallery at East entrance.	\$ 10,984	\$ 6,008	Complete	54.7



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
111	Los Angeles	Alhambra Courthouse	19-11	2	Vandalism - Perform etch/scratch removal on interior of (3) windows & install approx. 458 sq. ft. of anti-graffiti film on interior of (68) windows. The windows on the third floor North elevation do not currently have any type of protection from vandalism; a few windows have been vandalized, all windows need protection from future vandalism.	\$ 4,245	\$ 3,651	In Work	86
112	Kern	Bakersfield Superior Court	15-A1	2	HVAC - Replace inoperable motor on AHU22. Frame is no longer available for unit and needs to be replaced with similar model with adjustable mounting.	\$ 3,278	\$ 2,053	In Work	62.64
113	Santa Clara	Morgan Hill Courthouse	43-N1	2	HVAC - Chiller #2 is failing due to refrigerant leaks - Replace (2) failed filter dryers including housing and gaskets, (1) isolation ball valve on hot gas bypass, (1) 2-1/1 90 degree copper elbow on discharge line. The court is impacted due to insufficient cooling capacity.	\$ 12,688	\$ 12,688	In Work	100
114	Los Angeles	Van Nuys Courthouse West	19-AX2	2	HVAC - Restore and torque medium voltage starter air switches, medium voltage starter system, & medium voltage switch gear. The medium voltage system is not currently functioning properly.	\$ 5,572	\$ 4,484	In Work	80.48
115	San Diego	County Courthouse	37-A1	2	Electrical - Replace 200 out of 200 lights and replace 12 ballasts. Replacement lights are Florescent Lamps (GE F32T8/SPP41/ECO 200 LAMPS) Courtroom is too dim and lights need replacing, area contains ACM and proper procedures to be followed.	\$ 7,935	\$ 7,935	In Work	100
116	San Diego	South County Regional Center	37-H1	2	Interior Finishes - Dept. 9 - Remove 5 existing sound wall panels and install new fixation system to back of panels to prevent delaminating from walls, restore material on edges of panels and reinstall in courtroom. Sound panels are falling off walls, fabric on panels is detaching. Panels are contacting patrons/staff and is a safety issue.	\$ 12,459	\$ 12,459	In Work	100
117	Kern	Bakersfield Juvenile Center	15-C1	2	Fire Protection - Replace leaking couplings (33 total) for dry stand pipe. Couplings in East, West and Center stairwells are leaking and must be replaced.	\$ 8,427	\$ 5,626	In Work	66.76
118	Santa Clara	Downtown Superior Court	43-B1	2	Exterior finishes - Water intrusion is occurring from the 4th floor window area Department 9 - Court impact - Judge is afraid water damage will occur to documents. Remove failed window sealant at window area, clean, prime, and install new sealant.	\$ 5,454	\$ 5,454	In Work	100
119	San Diego	Hall of Justice	37-A2	2	Electrical - Replace failing electrical circuit components. Provide dedicated (4) 20-amp, 120-volt dedicated circuits and outlets at South wall and (3) 20-amp, 120-volt circuits at South office/bullpen area and kitchen. Existing circuits are frequently shorting out causing disruption; work is necessary to accommodate increase in court business.	\$ 5,578	\$ 5,578	In Work	100



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
120	FM-0055119	Los Angeles	Beverly Hills Courthouse	19-AQ1	2	HVAC - ACM remediation, set up separation barrier at entrance to Air Handler Room. Remove 30 linear ft of TSI piping insulation. Replace 30' of 2" deteriorated Black Steel piping with 30' of 2" copper type L piping, replace 40' of deteriorated 3" Black Steel piping with 40' of 3" copper type L piping, replace fittings, pneumatic control valve, actuator, and the remediated insulation with non-ACM materials. Piping and pneumatic valve are corroded, leaking on HW supply piping and need replacing.	\$ 23,653	\$ 18,809	Unfunded	79.52
121	FM-0055120	Los Angeles	Norwalk Courthouse	19-AK1	2	Electrical - Remove and dispose of existing tank and contaminated piping. Install 60' of W' Welded Black Steel piping for Supply Lines and 60' of 1" Welded Black Steel Return Lines. Install one 25 gallon Double Walled Day Tank with pump, motor, and control module and install one 25 gallon Double Walled Day Tank with pump, motor for backup. Connect tanks with piping, electrical connections and purge system. Piping lines are leaking and tank is beyond its life expectancy and requires replacement.	\$ 32,174	\$ 27,358	Unfunded	85.03
122	FM-0055121	Los Angeles	Alhambra Courthouse	19-11	2	Vandalism - Install approx. 2,716 sq. ft. of anti-graffiti film on interior & exterior of approx. (118) windows. The windows on the first floor North elevation do not currently have any type of protection from vandalism; all windows need protection from future vandalism on both the inside and the outside.	\$ 18,676	\$ 16,061	Awaiting Shared Cost Approval	86
123	FM-0055125	Orange	Harbor Justice Center-Newport Beach Facility	30-E1	2	HVAC - Air Handler Units - Remove and replace the rusted and leaking drain pans on 3 Air Handler Units.	\$ 4,955	\$ 4,178	In Work	84.32
124	FM-0055126	Napa	Criminal Court Building	28-A1	2	Exterior Shell - Repair window system to eliminate and prevent leakage - Leaking is allowing rainwater to infiltrate building. Clean/Prime building joint at windows; Remove old or deteriorated sealant and seal with polyurethane sealant; Barricade lift utilization area while protecting floor with plywood; and cleanup after project completion.	\$ 6,749	\$ 6,749	In Work	100
125	FM-0055127	Los Angeles	Alhambra Courthouse	19-11	2	Vandalism - Replace approx. (10) 1/4" bronze tempered glass windows & add anti-graffiti film to interior & exterior of new windows. There are currently (10) windows on the first floor south elevation that have been vandalized by graffiti etched & scratched into the glass as well as BB gun holes which can negatively affect the strength & integrity of the glass causing a safety hazard.	\$ 11,600	\$ 9,976	In Work	86



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
126	FM-0055128	Los Angeles	Compton Courthouse	19-AG1	2	Vandalism - Replace approx. 528 sq. ft. of anti-graffiti film on 44 windows and replace approx. (36) laser engraved ADA & Fire signs. Multiple windows and custom signs in public areas have been vandalized by graffiti being etched and scratched into them and need to be replaced to help prevent future vandalism and safety hazards.	\$ 5,304	\$ 3,508	In Work	66.13
127	FM-0055129	Napa	Criminal Court Building	28-A1	2	Elevators - Replace one (1) Oil Scavenger Pump with a new pump - Current pump is not operating correctly and is causing a low oil condition.	\$ 3,625	\$ 3,625	In Work	100
128	FM-0055130	Contra Costa	Arnason Justice Center	07-E3	2	HVAC - Replace return fan #2 motor - Motor has failed causing pressure issues in the building which keep the doors from closing. This creates a security issue.	\$ 4,142	\$ 4,142	In Work	100
129	FM-0055131	Los Angeles	Alhambra Courthouse	19-I1	2	Vandalism - Perform etch/scratch removal on exterior of (6) windows. Install approx. 1,245 sq. ft. on (89) south windows, approx. 1,112 sq. ft. of anti-graffiti film on (98) north 2nd floor windows, and approx. 1,412 sq. ft. of anti-graffiti film on interior of (110) north 4th floor windows. The windows do not currently have any type of protection from vandalism; a few windows have been vandalized, all windows need protection from future vandalism.	\$ 23,761	\$ 20,434	In Work	86
130	FM-0055134	Los Angeles	Van Nuys Courthouse East	19-AX1	2	HVAC - Replace (26) burners, (30) gaskets, & (1) spark igniter with required cable so boiler will operate properly. RBI Boiler #3 is not currently providing hot water to the 4-stage HVAC system; the boiler has been out of service for some time and needs to be upgraded in order to operate again. Ref. PM SWO# 2535481.	\$ 5,339	\$ 4,791	In Work	89.74
131	FM-0055137	Los Angeles	Van Nuys Courthouse West	19-AX2	2	HVAC - Replace Purge Unit and Braze piping connections. Chiller #2 is non-operational due to faulty Purge Unit. (Chillers supply both East & West building). Purge unit needs to be replaced as it is causing the chiller to shut down. Deficiencies found during Level VIII PM SWO 2462632.	\$ 7,729	\$ 6,220	In Work	80.48
132	FM-0055138	Los Angeles	Norwalk Courthouse	19-AK1	2	Interior Finishes - Set up containment and negative air machines, build scuffle with plywood on top for protection of all equipment, replace approx. 252 sq. ft. of plaster ceiling and paint to match existing. The ceiling inside the MCR room is heavily cracked and damaged; debris could potentially fall from the ceiling and damage electronic communication and network equipment which would impact the court's computer network and possibly cause a shut down.	\$ 14,635	\$ 12,444	In Work	85.03
133	FM-0055139	Napa	Historical Courthouse	28-B1	2	Fire Protection - Remove and replace four (4) deficient sprinkler heads. Heads failed the Level IV PM due to having paint on them.	\$ 3,144	\$ 3,144	In Work	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
134	FM-0055140	Santa Clara	Old Courthouse	43-B2	2	HVAC - Restore existing Trane Chiller to original capacity - Identify refrigerant leaks on compressor suction, discharge, oil, and motor terminal gaskets and restore. Descale and brush condenser tubes and recharge chiller with existing refrigerant - Multiple leaks on Trane Chiller are causing chiller failure.	\$ 12,484	\$ 12,484	In Work	100
135	FM-0055141	Sonoma	Hall of Justice	49-A1	2	HVAC - Remove failed CHW coils/condensate drain pan and install new CHW coils and drain pan.	\$ 12,322	\$ 12,322	In Work	100
136	FM-0055142	Los Angeles	Pomona Courthouse South	19-W1	2	HVAC - Install (1) new 30HP ABB VFD with bypass and reconnect wiring. The variable frequency drive (VFD) that regulates the supply fan is overheating and shutting down; the VFD regulates supply fan motor speeds so it does not run on high at all times, which saves energy and extends equipment life.	\$ 7,528	\$ 6,861	In Work	91.14
137	FM-0055144	Los Angeles	Downey Courthouse	19-AM1	2	HVAC - Cooling Tower #1 Replace Fan Blade and Motor Assembly. Remove protective screen located on top of cooling tower and reinstall after fan blade/motor assembly replacement. Replace shaft, fan bushing, fan blade assembly, driver sheave and bushing, driven sheave and bushing, vibration switch and bad wiring, Power-band belt. Perform full balance on fan blade assembly after installation is completed. Deficiencies found during Level 8 PM SWO 2462135. Fan blade/motor assembly require replacement.	\$ 27,029	\$ 22,623	Unfunded	83.7
138	FM-0055149	Los Angeles	Van Nuys Courthouse West	19-AX2	2	HVAC - Replace (1) damaged pneumatic valve and actuator on air handler #3. The chilled water supply pneumatic valve on air handler #3 currently has a leak and needs to be replaced so the air handler can operate properly.	\$ 3,315	\$ 2,668	In Work	80.48
139	FM-0055150	Lake	Lakeport Court Facility	17-A3	2	COUNTY MANAGED - Parking Lot - Replace/Resurface due to water issues at foundation wall - Replace approx. 2000 sq ft. of Sub x 10" thick, 5500 sq ft. 8" base rock and 1" of base rock rolled and compacted then 4512 sq ft. tack coat with petro mat the 2' of asphalt, including removal of 6671 sq ft.; strip and curbs to meet ADA code.	\$ 19,239	\$ 19,239	In Work	100
140	FM-0055151	Los Angeles	Pomona Courthouse South	19-W1	2	Elevators, Escalators, & Hoists - Replace worn out door hanger rollers on 3 floors, pick up rollers on 3 floors, separator on 1 floor, and zone lock assembly. The elevator hall doors on floors 1, 3, & 4 are currently out of adjustment and are operating with very old and worn out parts, which is a safety hazard for all elevator passengers.	\$ 5,257	\$ 4,791	In Work	91.14
141	FM-0055162	Los Angeles	Van Nuys Courthouse West	19-AX2	2	Elevators, Escalators, & Hoists - Install (1) new motor contactor in elevator control panel. Elevator #4 is currently out of service due to a faulty motor contactor which could cause the elevator to stop between floors or cause entrapments; a new m-contactor needs to be installed so the elevator can be put safely back into service.	\$ 4,225	\$ 3,400	In Work	80.48



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
142	FM-0055163	Fresno	Fresno County Courthouse.	10-A1	2	Holding Cells - Remove existing glass in the two holding cell interview rooms and install 1-50 x 44 and 1-60 x 44 3/4" OA clear laminated impact security glass with speak hole and satin anodized cover plate. Remove any remaining wall phones on each side of the interview rooms and cover all exposed wall boxes with stainless steel covers attached with security screws. The phones in the interview rooms are currently and have regularly been broken/pulled out of the wall.	\$ 5,043	\$ 5,043	In Work	100
143	FM-0055164	Los Angeles	Airport Courthouse	19-AU1	2	HVAC - Chiller#1- Rebuild failed isolation block. Replace oil regulator and flange gaskets, refrigerant only O-ring, rod spindle, plug pipe, screw spring plunger, purge liquid line isolation valve, and two 3/8 copper elbows. Install new Trane Control Keypad Control Panel Assembly.	\$ 24,407	\$ 18,835	Unfunded	77.17
144	FM-0055166	Stanislaus	Turlock Superior Court	50-D1	2	Grounds and Parking Lot - Replace broken parking lot fixtures to vandal proof to match other existing. Install steel grate covering rock drainage to prevent rock from being removed, and replace glass on soffit lighting to plexi-glass to prevent breakage. Rocks in drainage pits used to break lamp fixtures and glass creating safety issues.	\$ 8,930	\$ 8,930	In Work	100
145	FM-0055168	Los Angeles	Metropolitan Courthouse	19-T1	2	Vandalism - Sand/Prep bathroom walls and partition walls for painting and painting to remove writing on walls and etching into partition walls and sinks, which is causing a safety concern due to gang related issues.	\$ 4,967	\$ 4,696	In Work	94.54
146	FM-0055169	Contra Costa	Arnason Justice Center	07-E3	2	Exterior shell - Install rivet nuts to all hinge screws on frame side, remove threshold/cover, remove left glass door and shave bottom - Remove threshold, back fill closer cavity, and reinstall the threshold on right glass door - Doors are dragging on threshold and need to be realigned.	\$ 3,369	\$ 3,369	In Work	100
147	FM-0055173	Los Angeles	Van Nuys Courthouse West	19-AX2	2	HVAC - Replace flow switch, 3/8" solenoid valve & multiple fasteners, then charge unit with R-22 refrigerant & return to operation. The package unit that supplies the microwave room is not operating properly & causing temperatures to rise; if temperatures get too high there could be damage caused to equipment and monitors in the room as well as health & safety hazards.	\$ 3,150	\$ 2,535	In Work	80.48
148	FM-0055174	Siskiyou	Dorris	47-B1	2	Grounds and Parking Lot - Replace approximately 140LF of perimeter fence - Existing fence came down during a storm, condition of fence makes it un-repairable therefore replacement fence required - Without fence in place members of the public have unfettered access to unsecured areas of the court building and grounds.	\$ 11,052	\$ 11,052	In Work	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
149	FM-0055175	Los Angeles	Alhambra Courthouse	19-11	2	Electrical - Remove faulty day tank fuel pump & motor, install new day tank fuel pump with motor, connect all controls, prime fuel system, & run equipment to ensure proper operation. The day tank diesel pump is currently leaking fuel during operation; fuel pump & motor are not operating properly and need to be replaced to avoid possible fire & safety hazards and to comply with fire life safety & AQMD standards.	\$ 2,704	\$ 2,325	In Work	86
150	FM-0055176	Los Angeles	Van Nuys Courthouse East	19-AX1	2	HVAC - Remove existing failed booster pump assembly - Provide & install new direct replacement PACO bare shaft pump, align & secure new pump with existing components. Chilled water booster pump #1 has encountered a catastrophic failure which destroyed the pump housing and caused approx. 7,000 gallons of water to drain from the system. Pump needs to be replaced immediately as the entire building is currently running on a back up pump & if it fails there will be no chilled water for the entire HVAC system.	\$ 15,379	\$ 13,801	In Work	89.74
151	FM-0055177	Los Angeles	Chatsworth Courthouse	19-AY1	2	HVAC - Remove belts, motor sheave & bearing housings; replace old bearings with new; reassemble motor, sheave, belt, and check for proper operation. The return fan motor for air handlers #2 & #3 is currently making excessive noise and is not operating properly; motor bearings need to be replaced to prevent seizing of the motor which would negatively affect building cooling.	\$ 3,473	\$ 2,910	In Work	83.8
152	FM-0055179	Orange	Harbor Justice Center-Newport Beach Facility	30-E1	2	Plumbing - Flood clean up after toilet failed, flooding a hallway and an office.	\$ 8,000	\$ 8,000	In Work	100
153	FM-0055180	Orange	Harbor Justice Center-Newport Beach Facility	30-E1	2	Plumbing - Replace broken cold water shut-off valve for women's locker room. No cold water to showers or toilets.	\$ 4,500	\$ 4,500	In Work	100
154	FM-0055181	San Diego	East County Regional Center	37-11	2	HVAC - Replace leaky economizer mounting flange gaskets, motor terminal plate gaskets, motor cooling pipe gaskets, and seals. Chiller #1 is currently locked out due to refrigerant leaks and needs to be in working order to keep the building cool on the hottest summer days.	\$ 9,698	\$ 9,698	In Work	100
155	FM-0055182	Stanislaus	Modesto Main Courthouse	50-A1	2	HVAC - Failed Chiller Valve Assembly -Rebuild failed valve assembly.	\$ 3,311	\$ 3,311	In Work	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FMs Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
156	FM-0055187	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	2	HVAC - Remove steam condensate piping in ceiling and through deck, remove waterproofing and concrete from around 2" pipe. Replace leaking 2" piping, extend piping out so if this happens again, it doesn't melt the waterproofing and start leaking below. Waterproof trough area where 10" relief line and 2" steam vent line penetrate slab under Temple St. bridge walkway. Fabricate/galvanize grates to cover existing hole. Piping has deteriorated and was leaking.	\$ 20,000	\$ 13,758	In Work	68.79
157	FM-0055189	Los Angeles	Bellflower Courthouse	19-AL1	2	Electrical - The cranking controller on the emergency generator is damaged beyond repair & the generator will not turn off; controller needs to be replaced in order to restore the generator back to normal working conditions. Remove faulty generator controller & panel, install new Basler 20/20 Level 1 Controller, new Basler Voltage Regulator, new sending units, & new Basler remote enunciator; connect all wiring and run generator to ensure proper operation.	\$ 13,758	\$ 10,723	In Work	77.94
158	FM-0055190	Napa	Criminal Court Building	28-A1	2	Doors - Reinstall one (1) motor assembly, one (1) drive chain and install one (1) new idler shaft - Door will not open with button function or with key.	\$ 6,873	\$ 6,873	In Work	100
159	FM-0055191	Los Angeles	Van Nuys Courthouse West	19-AX2	2	Fire Protection - Replace (4) tamper switches, (1) water flow switch, (10) water gauges; replace 2" corroded pipe in basement, restore 2" angle drain valve, replace (27) escutcheons, (3) sprinkler heads, missing signs; install missing wrenches for sprinkler heads, & (1) missing sprinkler head guard, per Annual Standpipe Inspection. The annual standpipe inspection has failed due to faulty switches, valves, gauges etc. & multiple devices need to be replaced to avoid fire & safety hazards.	\$ 9,417	\$ 7,579	In Work	80.48
160	FM-0055192	Los Angeles	Van Nuys Courthouse East	19-AX1	2	Vandalism - Sand, prep, & refinish approx. 1,100 LF of wood handrails in public hallways using low VOC polyurethane wood finish & preservative with natural wood finish color. The wood handrails thought the public hallways on floors 2 through 7 have been vandalized by graffiti & have inappropriate and profane writing/markings which is a safety issue for the court.	\$ 4,370	\$ 3,922	In Work	89.74
161	FM-0055193	Fresno	JJC Delinquency Court	10-P1	2	Security - Provide 2 ea. new Pelco CM9770-VCC video input cards; one to replace an existing card that has failed, and one to have as a spare as replacement parts are hard to obtain. Verify proper operation of video surveillance system - Failed video input card caused attached 32 cameras in holding areas and elevators to go dark.	\$ 8,873	\$ 8,873	In Work	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification

FM's Less Than \$50K (List B)

4/29/2015 to 6/26/2015

Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % of COST
162	FM-0055194	Los Angeles	Van Nuys Courthouse West	19-AX2	2	Electrical - Remove approx. (70) existing mercury vapor light bulbs & ballasts; modify existing wiring and conduit to be directly wired to bulb sockets & install (70) new self ballasted CFL bulbs with socket extensions. Mercury vapor lights out & the ballasts for the existing fixture are no longer manufactured; Public hallway is dark in several areas which is a tripping hazard; new configuration 80% more energy efficient.	\$ 7,860	\$ 6,326	In Work	80.48
163	FM-0055195	El Dorado	Main St. Courthouse	09-A1	2	HVAC - Removing 30 HP compressor and replacing with a rebuilt compressor of same model and size on Chiller located outside the building - Chiller compressor crank seized and non-operable.	\$ 18,730	\$ 18,730	In Work	100
164	FM-0055196	Los Angeles	Pomona Courthouse South	19-W1	2	Electrical - Remove & replace (70) Red LED exit signs, (60) Bug eye LED emergency lights, & (30) NICAD 4.8V batteries. Emergency lighting & exit signs throughout the building are not currently functioning properly and need to be replaced in order to bring the fire life safety system to code & prevent future safety hazards.	\$ 12,722	\$ 11,595	In Work	91.14
165	FM-0055197	Los Angeles	Pomona Courthouse South	19-W1	2	Elevators, Escalators, & Hoists - Replace (1) faulty SCR control board with new. Public elevator #5 is currently stopping intermittently and the controls need to be rebooted in order to restart the car; the SCR board needs to be replaced immediately in order to return the elevator to service & avoid future safety hazards.	\$ 5,543	\$ 5,052	In Work	91.14
166	FM-0055198	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	2	Plumbing - Drain hot water loop & replace (4) 8" actuators on hot water pump shut off valves. The hot water shut off valves to the comfort heating are currently broken and will not stop the flow of water into the hot water loop which could cause safety issues during emergencies.	\$ 7,102	\$ 4,885	In Work	68.79
							\$ 1,504,455	\$ 1,322,178		



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

**Action Item 3 – (Action Required) - List C – Cost Increases
Over \$50K**

Summary:

List C – Cost Increases Over \$50K

Total Project Count:	3
Total Potential FM Budget Share of Cost:	\$604,788

Supporting Documentation:

- List C – Cost Increases Over \$50K

Action Requested:

Approve Judicial Council Staff recommendation to execute projects on List C – Cost Increases Over \$50K.

This page intentionally left blank



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF TCFMAC FUNDED COST	CURRENT COST ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF CURRENT COST ESTIMATE	NOTES	FACILITY MODIFICATION PROGRAM COST INCREASE	JOB STATUS	FACILITY MODIFICATION PROGRAM BUDGET % OF COST
1 FM-0030727	Los Angeles	Compton Courthouse	19-AG1	2	Elevators, renovate (11), upgrade elevators, controls are problematic and prone to frequent failures.	\$ 2,974,988	\$ 1,967,360	\$ 3,483,599	\$ 2,366,347	This project was previously funded in FY 2011-2012. Due to fund reversion in June 2015 and additional scope required by the State Fire Marshal to bring the elevator systems up to code, the project requires a total of \$508,611 of additional funding. The State's share of this funding is \$398,987. Shared cost is allocated based on the common and exclusive use per elevator system.	\$ 398,987	In Work	74.85
2 FM-0050342	Los Angeles	Metropolitan Courthouse	19-T1	2	Exterior Shell - Walk Up Teller Windows - Install four (4) new Walk-up windows and required casework, demolition, framing and electrical. Additional teller windows required due to increased court traffic due to court closures in the area.	\$ 210,000	\$ 210,000	\$ 138,836	\$ 138,836	This project was previously funded in FY 2012-2013 for \$210,000, however, only \$24,021.09 for initial design work was expended and the rest reverted due to project execution delays. Project bid received for execution phase is \$162,857, less the amount that was previously spent, this creates a need of \$138,836 to be funded from FY 2015-2016 for project completion. Current requested value to refund is \$138,836.	\$ 138,836	In Work	100.00
3 FM-0054226	Los Angeles	Pasadena Courthouse	19-J1	1	Plumbing - Water remediation, Containments set up: Courtroom G 6ftx10ftx15ft, 3rd flr restroom 4ftx8ftx15ft, 2nd flr restroom 6ftx9ftx 9ft, and 2nd flr hallway 3 containments 6ftx9ftx20ft, 8ftx9ftx12ft, and 4ftx8ftx16ft. Dry leak affected areas, ACM testing and clearance, water pumped off roof, and build back. Roof Rain Water Leaks: 6th Flr Dept. G, 3rd Flr Men's RR, 2nd Flr Men's Public RR and Public Hallway.	\$ 13,961	\$ 9,682	\$ 110,522	\$ 76,647	Cost escalation due to additional remediation efforts.	\$ 66,965	Complete	69.35
											\$ 604,788		



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

**Action Item 4 – (Action Required) - List D – Facility
Modifications Over \$50K**

Summary:

List D – Facility Modifications Over \$50K

Total Project Count:	23
Total Potential FM Budget Share of Cost:	\$4,502,970

Supporting Documentation:

- List D – Facility Modifications Over \$50K

Action Requested:

Approve Judicial Council Staff recommendation to execute projects on List D – Facility Modifications Over \$50K.

This page intentionally left blank



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

DRAFT

Trial Court Facility Modification
FMs Greater Than \$50K (List D)
6/1/2005 to 6/26/2015
Meeting Date 7/17/2015

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST
1	FM-0055054	Butte	Butte County Courthouse	04-A1	2	HVAC - Remove and replace air handler AC1 located on the '96 expansion roof. The air handler has reached the end of its life cycle. The frame and bottom of the unit are rusting through.	\$ 333,000	\$ 333,000	\$ 333,000	35	100
2	FM-0055184	Stanislaus	Modesto Main Courthouse	50-A1	2	Roof - Renovate the existing roof by applying approximately 23,825 sf of a silicone product over existing roof. Project will require minimal disturbance to the existing roof surface which contains ACMs, and will provide an additional 10 year warranty. Extends the roof life due to failures.	\$ 125,000	\$ 125,000	\$ 458,000	35	100
3	FM-0055185	Stanislaus	Hall of Records	50-A2	2	Roof - Renovate the existing roof by applying approximately 15,205 sf of a silicone product over existing roof. Project will require minimal disturbance to the existing roof surface which contains ACMs, and will provide an additional 10 year warranty. Extend the roof life due to failures.	\$ 80,000	\$ 62,256	\$ 520,256	35	77.82
4	FM-0052979	Los Angeles	Burbank Courthouse	19-G1	2	Roof - Original Gable Roof Section - Remove approximately 12,500 sf of existing rolled roofing over a pre-existing roof. Work will include new plywood roof sheathing, Dens Deck material, insulation board and a new SBS roof system with Cool Roof coating. Two pieces of abandoned mechanical equipment will also be removed from the roof and the penetrations will be capped. The existing gable roof membrane is failing and requires immediate replacement.	\$ 303,983	\$ 275,895	\$ 796,151	40	90.76
5	FM-0056506	Sacramento	Juvenile Courthouse	34-C2	2	HVAC - Temperature uncontrollable and overheating. Current system cannot control overtemp condition and IT equipment can be damaged. Install new N+1 computer cooling system to match engineering recommendation. Disconnect and remove existing failed system.	\$ 270,000	\$ 270,000	\$ 1,066,151	40	100
6	FM-0054816	Stanislaus	Hall of Records	50-A2	2	Elevator Restoration/Modernization: Frequent elevator failures require elevator restoration. Obsolete equipment requires modernization: Elevator equipment will include installing a new drive motor controller, new machine, new drive motor, new governor, new hoist way wiring, and new traveling cable. A new fire alarm system will be installed to allow Firefighter's Service as well as fire alarm devices required by code and tied into the existing panel for the in-custody elevator. The machine room will be updated with new door hardware to meet code and a HVAC system to maintain equipment operating temperature.	\$ 268,320	\$ 208,807	\$ 1,274,958	45	77.82
7	FM-0054950	Fresno	Fresno County Courthouse	10-A1	2	Fire Protection - Install approximately 3,531 lf of photoluminescent egress path markings, (1,020) stair markers, (82) aluminum stair nosings, and (39) "Exit" path signs throughout North, South, and Center stairwells per Fresno Fire requirements. Install fire-resistant material where missing on ceiling structural members in the chiller room on the B-2 level per Fresno Fire requirements. To correct deficiencies noted on the 2014 Fresno Fire Inspection Report.	\$ 51,377	\$ 49,070	\$ 1,324,028	45	95.51
8	FM-0055049	Fresno	Firebaugh Court	10-K1	2	Plumbing - Remove all piping from the sump well up to within 12" of the concrete walls above ground. Remove existing control panels and pumps. Install new piping, two (2) new 4", 7.5 hp, 475 gpm sump pumps, and new alternating pump controls The original system is failing and not pumping the sewage properly. Rusted-out piping within the sump well and through the pumps is leaking and will lead to complete failure. The pumps and controls are obsolete and will need to be changed with the piping.	\$ 51,500	\$ 29,880	\$ 1,353,908	50	58.02
9	FM-0055145	Los Angeles	Alfred J. McCourtney Juvenile Center	19-AE1	2	County Managed - HVAC - Failing VAV Controllers - Remove and replace all existing VAV controllers. Replace all existing network wiring. Provide labor and materials to add a supervisory controller and network wiring for remote system access. Provide labor and materials to replace the systems controller and sensors for AHU #1 and #2. Provide labor and materials to install all parts and programming.	\$ 130,643	\$ 130,643	\$ 1,484,551	50	100



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST
10	Los Angeles	Alhambra Courthouse	19-11	2	Vandalism - Remove and replace (37) 36" X 140" X 1/4" Bronze Tempered glass and window gaskets on the second and third floor. Provide City permits to replace glass window and shut down street. Mobilize (1) 34' Engine powered Articulating Boom lift for two days. Provide traffic control for streets and pedestrians for 2 days. Mark area with traffic cones and caution tape for safety. Glass panes have graffiti etched/carved deep into the glass, altering the glass integrity and posing a safety hazard.	\$ 110,300	\$ 94,858	\$ 1,579,409	50	86
11	Los Angeles	Inglewood Courthouse	19-F1	2	Fire - Replace two (2) fire pumps and single-walled day tank. Pumps are not compliant with SCAQMD emission standards. Day tank is not compliant with Title 40. Work is required to prevent notice to comply from the State Fire Marshal and CUPA.	\$ 232,521	\$ 173,368	\$ 1,752,777	55	74.56
12	Solano	Hall of Justice	48-A1	2	Plumbing - Remove and replace (13) CW Faucets, (9) HW Faucets, (16) Pneumatic Pushbutton Assemblies, (3) 1/2" Ball Valves, (3) 3/4" Ball Valves, (4) 1" Ball Valves, (3) 1 1/2" Ball Valves, (3) 2" Ball Valves, (2) 1/2" Angle Stops; Re-route 16' of 1" pipe; Work to be done off-hours. Integrated plumbing fixtures in the holding cells have failed or are leaking. Water supply has been turned off to four of the holding cells. Repair parts are obsolete.	\$ 71,598	\$ 71,598	\$ 1,824,375	60	100
13	Los Angeles	Stanley Mosk Courthouse	19-K1	2	Electrical - Remove two (2) existing day tanks and install one (1) Simplex 50 gallon day tank with pumps, piping, fittings and switches for #1/#2 emergency generators. Install 80' of 3/4" welded black steel piping for supply lines and 80' of 1" welded black steel return line. Existing units are deteriorated and beyond their life expectancy, could cause fuel spillage and prevent generators from providing emergency power during a power outage and require replacement.	\$ 51,338	\$ 49,931	\$ 1,874,306	60	97.26
14	Los Angeles	El Monte Courthouse	19-O1	2	HVAC - ACM testing. Replace (9) butterfly isolation valves, (2) check valves, (2) flange strainers on condenser valves. Set up 10'x20' containment, abate pipe insulation, install new 2" insulation 100LF. Replace (9) butterfly isolation valves (2) flange strainers on Chilled Water Valves. Replace (6) 8" and (1) 6" butterfly isolation valve (4) 0-160 psi pressure gauges on Cooling Tower. Chemically clean Chillers 1 & 2.	\$ 126,770	\$ 73,679	\$ 1,947,985	60	58.12
15	Los Angeles	Airport Courthouse	19-AU1	2	Interior Finish - Remove and replace 2,975 Square Feet of Epoxy Flooring in the holding area in the basement. The floor epoxy has failed and broken pieces can be used as a weapon. In addition, it has caused a health and safety issue.	\$ 83,926	\$ 64,766	\$ 2,012,750	65	77.17
16	Fresno	B.F. Sisk Federal Courthouse	10-O1	2	Exterior Windows - Replace - All windows are single pane and are original to the 1964 construction. Many are warped and ill fitting. Potential energy savings and rebates for this project.	\$ 1,500,000	\$ 1,500,000	\$ 3,512,750	65	100
17	Orange	North Justice Center	30-C1	2	HVAC - Phase 1 - Design - Cooling Towers - Demo, remove, replace, and relocate two 250+ ton (20hp ea.) cooling towers. The cooling towers require relocation due to current unsafe work conditions and replacement due to age and failing components. The rooftop location has a rusting and failing blower wheel shaft that could break at any moment and cannot be replaced or maintained due to lack of fall protection; relocation will allow preventive maintenance to be performed in a safe and efficient manner.	\$ 258,000	\$ 233,000	\$ 3,745,750	65	90.31
18	Los Angeles	Alfred J. McCourtney Juvenile Center	19-AE1	2	County Managed - Elevator - Elevator Modernization - Install a smartrise system controller with a battery lowering and emergency power future capability. Install new hall and car fixtures. Install new submersible power unit with an oil cooler. Install new GAL solid state car and hall equipment package. Install stainless door, entrance skins for the car and hall. Install an elevator recall only smoke detection system. Install a new jack assembly, buffer springs and hydraulic line.	\$ 310,725	\$ 214,556	\$ 3,960,306	70	69.05



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST
19	Los Angeles	Compton Courthouse	19-AG1	2	Plumbing - Phase I Design FM - SPCC Containment Plan: Install Berm System around Day Tanks and Double Walled piping system and gutter for secondary containment. Replace Tank Monitor system. Need to install Berm System to isolate Basement Vault, diesel supply/return lines to isolate any leaking fuel, keep water from intruding into area and mixing with spilled fuel. Existing supply and return lines have no secondary containment for piping. Existing Tank Monitoring System needs to be upgraded, due to age it cannot be replaced.	\$ 53,000	\$ 35,049	\$ 3,995,355	75	66.13
20	Los Angeles	Clara Shortridge Foltz	19-L1	2	SPCC - Secondary Containment - Provide secondary containment for generator pumps, aboveground storage tank, and elevator hydraulic tanks.	\$ 60,000	\$ 41,274	\$ 4,036,629	75	68.79
21	Alameda	Fremont Hall of Justice	01-H1	2	SPCC - Secondary Containment - Phase 1 FM-Design - Provide secondary containment for generator, aboveground storage tank, and elevator hydraulic tanks.	\$ 128,374	\$ 101,929	\$ 4,138,558	75	79.4
22	Alameda	Hayward Hall of Justice	01-D1	2	SPCC - Secondary Containment - Phase 1 FM-Design - Provide secondary containment for generator, aboveground storage tank, and elevator hydraulic tanks.	\$ 109,065	\$ 96,304	\$ 4,234,862	75	88.3
23	Orange	West Justice Center	30-D1	2	HVAC - The Condenser coils and fan motors as well as the compressors and their motors on Chiller #3 are showing extreme wear and deterioration. Replace chiller with a new Trane Stealth Chiller. Work to include: removal and disposal of existing chiller, provide seismic isolation for new chiller, lengthen concrete pad if necessary, install and commission new Trane chiller. Protective coating on coils, insulation on new pipe, testing, and training.	\$ 295,663	\$ 268,107	\$ 4,502,970	77	90.68
24	Los Angeles	Metropolitan Courthouse	19-T1	3	Electrical - Replace a total of 98 exterior Mercury Vapor, High Pressure Sodium, and Fluorescent Light fixtures with high efficient LED fixtures. Building exterior lighting fixtures/poles have broken lenses, sockets, bulbs making the area dark at night, safety issue. Parts are no longer available due to fixtures being outdated.	\$ 84,027	\$ 79,439	\$ 4,582,409	35	94.54
25	Los Angeles	Santa Monica Courthouse	19-AP1	3	Roof - Remove and replace 53,000 sf of existing roof with new SBS roof system, currently the existing roof system is failing and leaks are increasing, work will replace the roof at three building sections at various levels. New building metal and curbs will be replaced as needed.	\$ 1,114,341	\$ 874,646	\$ 5,457,055	35	78.49
26	Nevada	Joseph Center	29-B1	3	Security - Transaction casework and layout - Install a glass enclosure on top of the existing 27 foot long transaction counter, including replacement of adjacent half door with full length door. To include modification of counter to allow for an ADA window and four additional transaction windows and barrier between the public and staff / money drawer. Current counter and layout cited in a security evaluation and through court audit.	\$ 25,800	\$ 25,800	\$ 5,482,855	45	100
27	Los Angeles	Torrance Courthouse	19-C1	3	Interior Finishes - Replacement of the Cafeteria area T-Bar Ceiling. This includes ceiling grid replacement with tiles, new light fixtures, extended existing HVAC ducting with new 2' x 2' lay-in. Replace (2) new switches, (3) P.A. speakers, (2) Exits signs. Work will be done after hours not to impact facility operations. Ceiling tiles are damaged and deteriorated beyond their life expectancy, several are stained or discolored. Ceiling tiles and T-bars require replacement.	\$ 63,423	\$ 53,998	\$ 5,536,853	45	85.14
28	Butte	Butte County Courthouse	04-A1	3	Security - The single in-custody holding cell located in the older section of the courthouse is substandard for current criminal cases. The project goal is to accommodate larger number of simultaneous in-custody classifications and increase overall holding capacity. This project addresses the deficiency by remodeling to add 3 holding cells.	\$ 288,960	\$ 288,960	\$ 5,825,813	50	100
29	Solano	Hall of Justice	48-A1	3	Security - Interior Finishes - Secure transaction counter - Install approximately 100 lineal feet of barrier wall and public transaction counter with twelve (12) 4 wide forced entry resistant laminated glass transaction windows, to ensure the safety of the family law clerks. There have been numerous security incidents involving disgruntled public customers including punching, spitting and verbal altercations.	\$ 260,145	\$ 260,145	\$ 6,085,958	50	100



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST	
30	FM-0053022	Riverside	Larson Justice Center	33-C1	3	Grounds and Parking Lot - East Parking Lot - Create and install 80 parking stalls out of perimeter landscape around the current lot. The recent closure of the County lot behind the courthouse, closure of the Court Annex/County building next door and its parking lot, and the building of a County Law building next door have created a serious parking issue in the immediate area of the Larson Justice Center resulting in a 200+ parking stall loss. Customers are currently parking on the landscape.	\$ 485,040	\$ 391,961	\$ 6,477,919	50	80.81
31	FM-0051642	Amador	New Amador County Courthouse	03-C1	3	Safety and security - Remove the 4 existing exterior windows on the east exterior wall of the building and replace them with 4 new dark tinted ballistic resistant units - The existing window glazing does not provide any ballistic resistant protection.	\$ 23,622	\$ 23,622	\$ 6,501,541	50	100
32	FM-0054411	Placer	Juvenile Hall	31-B3	3	COUNTY MANAGED - HVAC - Boiler is failing and requires replacement FY 2015.	\$ 30,960	\$ 30,960	\$ 6,532,501	50	100
33	FM-0054960	Solano	Hall of Justice	48-A1	3	Roof - Replace roof - Phase II of existing/funded Phase I FM#50740.	\$ 1,341,198	\$ 976,660	\$ 7,509,161	55	72.82
34	FM-0050684	Santa Clara	Old Courthouse	43-B2	3	Energy Efficiency Retrofit Project - Install occupancy sensors for lighting control in core restrooms on floors 1-3 - EEM 5.	\$ 16,727	\$ 16,727	\$ 7,525,888	55	100
35	FM-0052949	Los Angeles	Alhambra Courthouse	19-I1	3	Plumbing - Remove and replace 7 recessed wall drinking fountains and 1 surface mount ADA drinking fountain. Eight drinking fountains in the public areas of the courthouse are deteriorated and are not operational.	\$ 37,098	\$ 31,904	\$ 7,557,793	55	86
36	FM-0052950	Los Angeles	Chatsworth Courthouse	19-AY1	3	Plumbing - Remove and replace 8 high-low recessed drinking fountains and 3 ADA wall hung drinking fountains. Drinking fountains in the public areas of the courthouse are not operational.	\$ 60,063	\$ 50,333	\$ 7,608,126	55	83.8
37	FM-0053460	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	3	Roof - Overlay existing roof with new PVC roof system / Due to roof currently being in poor to fair condition, recommended overlay of existing roof will bring it to good condition. The Square Footage for this roof overlay is approx. 43,000.	\$ 596,413	\$ 417,429	\$ 8,025,555	55	69.99
38	FM-0053476	San Joaquin	Manteca Branch Court	39-C1	3	Energy Efficiency - Lighting - Replace a total of 305 light fixtures throughout the facility. Remove: (19) T12 light fixtures, (73) Compact Fluorescents, (201) T8 Light Fixtures, (2) Incandescent Light Fixtures and (10) Metal Halide Light Fixtures. All fixture will be replaced with LED fixture.	\$ 69,115	\$ 69,115	\$ 8,094,670	55	100
39	FM-0053492	San Joaquin	Lodi Branch - Dept. 2	39-D2	3	Energy Efficiency - Lighting - Replace a total of 141 light fixtures throughout the facility. Remove: (16) Compact Fluorescents, (109) T8 Light Fixtures, and (12) Incandescent Light Fixtures. All fixtures will be replaced with LED fixture.	\$ 35,955	\$ 35,955	\$ 8,130,625	55	100
40	FM-0054905	Los Angeles	Torrance Courthouse	19-C1	3	Grounds and Parking Lot - Repair asphalt, Slurry coat and restripe parking lot (285,000sq).	\$ 265,000	\$ 225,621	\$ 8,356,246	55	85.14
41	FM-0052775	San Francisco	Civic Center Courthouse	38-A1	3	Exterior Walls - Prepare and apply anti-graffiti coating to all exterior walls from grade to 10ft high (approx. 6700sqft) - janitorial efforts are having minimal results, time consuming and causing public hazard at sidewalks.	\$ 62,248	\$ 62,248	\$ 8,418,494	58	100
42	FM-0034097	San Bernardino	Barstow Courthouse	36-J1	3	Parking Lot - Saw cut and demo approximately 28,000 SF, 4 inch depth, of asphalt at lower level employee parking lot that is JCC managed and resurface with approximately 28,000 SF, 4 inch thick asphalt w/ 6 inch base, install 59 parking bumpers and re-stripe. Slurry seal new asphalt. Currently the asphalt in the parking lot has numerous cracks, pot holes, and uneven areas that pose a tripping hazard.	\$ 237,360	\$ 237,360	\$ 8,655,854	60	100



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST
43	Orange	Harbor Justice Center-Newport Beach Facility	30-E1	3	HVAC-Central Plant-Replace building chiller room components for proper control of chiller with Distech EC-BOS controls and webserver (non-proprietary), program sequence of operation and modify existing condenser water pipe with two Belimo water valves with actuators; increasing efficiency and to mitigate concerns over potential tower failures/boards. Existing boards and controllers are obsolete; failure will result in large, costly project. Install 4 VFDs to 4 existing water pumps.	\$ 210,000	\$ 177,072	\$ 8,832,926	60	84.32
44	Solano	Hall of Justice	48-A1	3	Interior Finishes - Flooring remove and replace tile flooring to eliminate tripping hazards. Tile is obsolete and we are unable to match current tile. The mastic contains ACMs and the project includes testing, abatement, and monitoring of ACMs.	\$ 21,205	\$ 15,441	\$ 8,848,367	60	72.82
45	Madera	Sierra Courthouse	20-D1	3	Security - Install fencing for sheriff and staff secured parking - reduce potential custody escapes or attacks - provide safety for court staff and patrons.	\$ 167,594	\$ 113,964	\$ 8,962,331	60	68
46	San Diego	Kearny Mesa Traffic Court	37-C1	3	Grounds and Parking Lot - Slurry coat, re-stripe the parking lot and paint the curbs as required. The striping is fading to where directional arrows and lane markings are, making it difficult for people to see.	\$ 18,771	\$ 18,771	\$ 8,981,102	60	100
47	Santa Barbara	Santa Maria Courts Building G	42-F5	3	Roof Access - Replace Roof Access Window with Door/Landing/Handrailing - Safety Hazard.	\$ 28,896	\$ 27,882	\$ 9,008,984	60	96.49
48	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	3	Grounds and Parking Lot - Replace waterproof membrane, sprinklers, and landscaping in planter on the exterior of the Courthouse near County Council Chambers. Due to years of deterioration the waterproofing membrane in the planter leaks through when there is excessive water present. This was the cause of a serious leak into the County Council Chambers in January 2014.	\$ 52,588	\$ 36,806	\$ 9,045,791	60	69.99
49	Los Angeles	Torrance Courthouse	19-C1	3	Interior Finishes - Perform environmental testing, remove & replace approx. 950 sq. ft. of ceiling tiles & t bar, remove & replace approx. 610 sq. ft. of floor tiles, replace (1) new porcelain sink, and (1) new Mars air curtain inside back door. The first	\$ 24,755	\$ 21,076	\$ 9,066,867	65	85.14
50	Orange	Central Justice Center	30-A1	3	Exterior Equipment - The roof tie-down fixtures have deteriorated and are no longer approved for use by OSHA.	\$ 219,083	\$ 199,738	\$ 9,266,605	65	91.17
51	Glenn	Historic Courthouse	11-A1	3	HVAC - Two (2) Carrier Split Systems - Install two (2) Carrier or equivalent split systems to provide air to the Judge's Office and CEO's Office - SAFETY, ENERGY.	\$ 22,825	\$ 22,825	\$ 9,289,430	65	100
52	Kern	Shafter/Wasco Courts Bldg.	15-E1	3	Security - Enhance parking by adding Judges Secure Parking and Access to the Courthouse - Branch suffers from lack of secure parking.	\$ 76,230	\$ 76,230	\$ 9,365,660	65	100
53	Santa Clara	Morgan Hill Courthouse	43-N1	3	Energy Efficiency Project - Retrofit Exterior Parking Lot Lighting from 250w Metal Halide to 150w LED lamps.	\$ 63,508	\$ 63,508	\$ 9,429,168	65	100
54	Los Angeles	San Fernando Courthouse	19-AC1	3	Roof - Remove and replace existing roofs on main deck, 2nd and 3rd floor Northeast decks as well as machine room roofs at the main roof (approximately 38,000) with a SBS roof System, the condition of these three sections of roof currently are in poor to fair condition. Roof metal will be replaced as needed.	\$ 807,176	\$ 673,266	\$ 10,102,433	65	83.41
55	Los Angeles	Glendale Courthouse	19-H1	3	Grounds- Replace concrete employee patio (1,000sf). Concrete patio is cracked and not level in several areas. In addition, of section of the patio is missing concrete. Health and Safety risk to employees, that could trip and fall.	\$ 16,000	\$ 14,486	\$ 10,116,920	65	90.54
56	Contra Costa	Wakefield Taylor Courthouse	07-A2	3	HVAC - BAS to HVAC - Expand BAS functionality to all HVAC equipment and points - Some critical equipment is not connected to BAS and existing BAS is not functioning properly creating temperature control issues throughout the building.	\$ 189,857	\$ 189,857	\$ 10,306,777	65	100
57	Contra Costa	George D. Carroll Courthouse	07-F1	3	HVAC - BAS to HVAC - Expand BAS functionality to all HVAC equipment and points - Some critical equipment is not connected to BAS creating temperature control issues throughout the building.	\$ 237,783	\$ 178,313	\$ 10,485,090	65	74.99



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST
58	FM-0055154	Lassen	New Susanville Courthouse	18-C1	3	HVAC BAS - Upgrade the building automated system (BAS) to allow full function control of all HVAC equipment throughout the building. The upgrade will allow full control access the maintenance shop desktop computer and by remote access via the internet. This remote courthouse experiences harsh climate and frequent equipment outages. Full functioning control access through the BAS is critical to maintain court operations.	\$ 61,650	\$ 61,650	\$ 10,546,740	67	100
59	FM-0049852	Butte	Butte County Courthouse	04-A1	3	Fence/Security - Install 990 linear feet of 9' gauge chain link fencing at 7' high. Install one 4' wide by 7' high swing gate on the West side of the fence line. - Security issues.	\$ 35,015	\$ 35,015	\$ 10,581,755	68	100
60	FM-0051535	Los Angeles	West Covina Courthouse	19-X1	3	Elevator (Wheelchair lift) - Units 1 - 3, Replace defective parts, make adjustments, service and return to safe operation. Currently units operate with the door open which is unsafe to the public. This work is also needed to comply with ADA access requirements.	\$ 28,184	\$ 23,396	\$ 10,605,151	68	83.01
61	FM-0053551	Solano	Solano Justice Building	48-B1	3	EARTHQUAKE - Repair cracks and aesthetic damage created by earthquake throughout building in secured hallways, courtrooms 101-104, and jury courtyard scaffolding is required. Epoxy injection at concrete wall, 35 lin ft. and approx 650 sq ft of drywall and stucco repairs. Paint and patch cracks to match existing.	\$ 20,099	\$ 20,099	\$ 10,625,250	69	100
62	FM-0049235	Santa Clara	Hall of Justice (East)	43-A1	3	Plumbing - Floor drains (8 ea) - Roof mechanical room - Remove existing roof mechanical room drains - Install new drains and reseal flooring - Drains are plugged and not draining creating potential flooding.	\$ 24,840	\$ 24,840	\$ 10,650,090	70	100
63	FM-0051115	Santa Clara	Downtown Superior Court	43-B1	3	Energy Efficiency measure - Install 1 new Variable Frequency Drive (VFD) on the existing chilled water pump, install a deferential pressure sensor (DP) and re-program the BAS to modulate the chilled water flow- this will reduce energy consumption-expected pay back is 19.6 years.	\$ 58,896	\$ 58,896	\$ 10,708,986	70	100
64	FM-0051344	Mendocino	County Courthouse	23-A1	3	Energy Efficiency Project - Electrical Lighting - Change Light bulbs, install photocell and sensors - Swap 234 T12 Bulb and ballast to T8 install 3 occupancy sensors, install 3 photo cells.	\$ 66,703	\$ 45,105	\$ 10,754,090	70	67.62
65	FM-0051519	Contra Costa	George D. Carroll Courthouse	07-F1	3	Energy Efficiency Project - Electrical - Install new lighting control system; Install 66 new occupancy sensors; Retrofit 36 four lamp light fixtures to 2 lamp fixtures; Engineering and design - Energy savings \$14,000.00 per year.	\$ 222,699	\$ 167,002	\$ 10,921,092	70	74.99
66	FM-0051527	San Luis Obispo	Courthouse Annex	40-A1	3	Interior Finishes - Replace existing worn and defective seating with new auditorium style fixed seating - 16 standard seats and 2 ADA seats. Work is needed to maintain acceptable courtroom seating.	\$ 22,941	\$ 22,941	\$ 10,944,033	70	100
67	FM-0052782	Merced	New Downtown Merced Courthouse	24-A8	3	Security - Expand the vestibule and add a covered staging area - Remove the existing store front and provide a separate storefront in the new location, level the existing alcove concrete to expand the new interior security vestibule, construct a new 1,800 SF covered walkway and staging area, this will require a single 400 SF tilt concrete panel, sixteen (16) column footings, two (2) new 3'6" power activated storefront doors, transparent roof panels at the covered walkway and staging areas, two new cameras at the staging area and approximately 800 SF of flooring and t-bar ceiling at the lobby and vestibule. This work is required to alleviate security issues at the main entry due to inadequate circulation.	\$ 704,856	\$ 704,856	\$ 11,648,889	70	100
68	FM-0052829	Kings	Avenal Court	16-C1	3	Exterior Shell - Remove, replace, or restore approximately 80 lf of 2 1/2" x 11" bottom ledger, 48 lf of 2" x 6" fascia and trim, and 96 lf of 1" x 12" fascia; remove small section of existing white gutter and install 25 lf gutter and 1 down spout to match as close to exterior brown color; caulk and patch trim areas as required to receive paint; paint all exterior brown color only - Existing wood fascia and trim is cracking, splitting, and deteriorating due to fungus and weather damage.	\$ 22,167	\$ 12,859	\$ 11,661,748	70	58.01
69	FM-0053002	Los Angeles	Monrovia Training Center	19-N1	3	Roof - Remove and replace existing roof system at areas eleven different areas 20,000 amount of SF / Due to the poor condition of these areas, recommended removal and replacement of existing systems will bring entire building roof to good condition.	\$ 286,937	\$ 201,688	\$ 11,863,436	70	70.29



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST
70	Los Angeles	Alhambra Courthouse	19-I1	3	Roof - Remove and replace existing roof with new SBS roof system - Remove and replace approximately 31,800sf of built up roof currently being in poor condition. Work will include new building metal, vents and walk pads as needed.	\$ 699,821	\$ 601,846	\$ 12,465,282	70	86
71	Los Angeles	Glendale Courthouse	19-H1	3	Roof - Overlay 38,000 sq. ft. of existing roof system with new PVC membrane overlay / Due to roof decks currently being in poor to fair condition, remaining service life is less than 5 years. The recommended overlay of all existing roofs will bring the building to good condition. The multi-level, multi-sectioned roof area totals approximately 34,000 square feet.	\$ 468,115	\$ 423,831	\$ 12,889,114	70	90.54
72	Los Angeles	Torrance Courthouse	19-C1	3	Roof - Remove and replace 40,000 square feet of the existing main deck and lower deck sections with new SBS roof system / Due to roof decks currently being in poor to fair condition, remaining service life is less than 5 years. Work to include new building metal, vent jacks and equipment curbs as needed.	\$ 845,633	\$ 719,972	\$ 13,609,086	70	85.14
73	Los Angeles	Airport Courthouse	19-AU1	3	Roof - Upper Roof and Heli-Stop - Remove and replace approximately 16,000sf of SBS roof system and bead blast and re-coat approximately 3,400sf at the Heli-stop. The SBS roof system and Heli-Stop will be coated with an Elastomeric cool roofing material.	\$ 428,022	\$ 330,262	\$ 13,939,348	70	77.16
74	Los Angeles	Pomona Courthouse South	19-W1	3	Roof - Remove and replace existing roof with new SBS roof system at main deck (23,220 sq. ft.), lower north deck (2,838 sq. ft.), and lower south deck (2,838 sq. ft.). The roofs are currently in poor to fair condition at best. Roofing metal will be replaced as needed.	\$ 682,895	\$ 622,391	\$ 14,561,738	70	91.14
75	Los Angeles	S. Bay Municipal Traffic Court Trailer	19-C4	3	Roof - Overlay existing roof with new PVC roof system / Due to roof system currently being in poor to fair condition, remaining service life is less than 5 years. The recommended overlay of existing roof system will bring the building to good condition. The roof area totals approximately 4,000 square feet.	\$ 47,678	\$ 40,593	\$ 14,602,331	70	85.14
76	Los Angeles	Pomona Courthouse North	19-W2	3	HVAC - Replace all the faulty components on DX System - Compressor #1, AHU01, Compressor #2, AHU02 and the Condenser Fan Units. Recharge the DX System with 148 lbs recovered refrigerant and an additional 400 lbs of new R-22 refrigerant. DX System was not cooling and reported non-operational, several leaks were found. P1 SWO 1383325 was opened to recover refrigerant and charged system with 125lbs of nitrogen.	\$ 39,402	\$ 37,924	\$ 14,640,256	70	96.25
77	Orange	West Justice Center	30-D1	3	HVAC - Fall Protection - Design, build and install a custom service platform w/catwalk to access the top of the cooling tower during routine & predictive maintenance. Provide access ladder w/safety cage and gate to access elevated walkway. Add fall protection where necessary to provide safe access and to comply with OSHA regulations.	\$ 70,878	\$ 64,272	\$ 14,704,528	74	90.68
78	Contra Costa	Bray Courts	07-A3	3	Interior Finishes - Earthquake Restoration of cracks and aesthetic damages to approx 7100 sq ft of the interior building.	\$ 46,812	\$ 40,034	\$ 14,744,561	75	85.52
79	Alameda	George E. McDonald Hall of Justice	01-F1	3	Interior - Paint Walls and Doors - Wall paper has delaminated from the walls, Restore walls to a paintable condition, Paint Walls 1st and 2nd floor public area (17,800 SQ FT) - Paint Doors (22 EA) both sides.	\$ 21,910	\$ 19,281	\$ 14,763,842	75	88
80	Los Angeles	West Los Angeles Courthouse	19-AR1	3	Roof - Remove and replace 20,000 sq. ft. of existing main upper deck and two lower deck roofs with new PVC roof system / Due to roof currently being in poor to fair condition at best, recommended removal and replacement of existing main deck and lower decks will bring the entire system to good condition.	\$ 407,434	\$ 407,434	\$ 15,171,276	75	100
81	Contra Costa	George D. Carroll Courthouse	07-F1	3	Door Locks - Re-key all locking doors - Replace all lock barrels, create a new master key numbering system so that all cylinders are on the same system, consistency needed for master lock door access.	\$ 40,000	\$ 29,996	\$ 15,201,272	80	74.99



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST	
82	FM-0043866	Amador	New Amador County Courthouse	03-C1	3	Electrical - LED Lighting - Convert 14 parking lot and 34 building exterior and public walkway lamps to energy saving LED fixtures - Energy Savings.	\$ 68,500	\$ 68,500	\$ 15,269,772	80	100
83	FM-0052844	Ventura	Juvenile Courthouse	56-F1	3	COUNTY MANAGED - Interior Finishes - Replace All Interior Door Hardware Failing - Low Quality/Failing - County Managed Recommended by County/MP - Bldg was built in 2005. Per County, "Hardware is of low quality, failing and is no longer being made.	\$ 73,204	\$ 73,204	\$ 15,342,976	80	100
84	FM-0053004	Los Angeles	Van Nuys Courthouse West	19-AX2	3	Roof - Remove and replace existing roof with new SBS roof system - Work to include replacing approximately 25,000sf of failing built up roof, two roof drains, re-coat the Heli-Stop and replace building metal as needed.	\$ 585,070	\$ 470,864	\$ 15,813,840	80	80.48
85	FM-0053549	Los Angeles	Downey Courthouse	19-AM1	3	Roof - Remove and replace existing main deck, lower east deck and lower west deck (approximately 34,000 sf) with a SBS type roof system - Due to main and lower decks currently being in poor condition at best, recommended removal and replacement of existing systems will bring building roof to good condition.	\$ 742,028	\$ 621,077	\$ 16,434,918	80	83.7
86	FM-0024505	Solano	Hall of Justice	48-A1	3	Interior Finishes (Safety Issue) - Mechanical Room Floor - Remove elevated concrete pads (320 SQ FT) re-pour concrete to level floor (320 SQ FT) to level floor and eliminate tripping hazard. Concrete ramp - install ramp (20 LF) to allow safe removal and installation of mechanical equipment.	\$ 15,968	\$ 11,628	\$ 16,446,546	80	72.82
87	FM-0025086	Merced	Old Court	24-A1	3	HVAC - BAS, Installation for integration with BAS at New Merced - Needed for proper system operation.	\$ 82,136	\$ 82,136	\$ 16,528,682	85	100
88	FM-0052843	Ventura	East County Courthouse	56-B1	3	ENERGY EFFICENCY - COUNTY MANAGED - Electrical - Interior Lighting Retrofit.	\$ 129,518	\$ 129,518	\$ 16,658,200	85	100
89	FM-0052970	Los Angeles	Whittier Courthouse	19-AO1	3	Roof / Remove and replace existing one story section of roof with new and overlay 5 story section of roof with torch applied system / Due to both sections of roof currently being in poor to fair condition, recommended overlay of 5 story section and replacement of 1 story section of existing roof will bring entire roof system to good condition.	\$ 458,640	\$ 396,403	\$ 17,054,602	85	86.43
90	FM-0052981	Los Angeles	East Los Angeles Courthouse	19-V1	3	Roof - Remove and replace existing roof with new PVC roof system / Due to roof currently being in poor to fair condition at best, recommended removal and replacement of existing roof will bring it to good condition.	\$ 615,485	\$ 478,355	\$ 17,532,957	85	77.72
91	FM-0022145	Santa Clara	Santa Clara Courthouse	43-G1	3	Elevator - Refurbish elevator and controls and install Vista Monitoring System to enhance reportability - This is the only elevator in the building.	\$ 115,545	\$ 115,545	\$ 17,648,502	90	100
92	FM-0025793	Butte	Butte County Courthouse	04-A1	3	Grounds - Parking lot renovation - Lot in poor condition, project includes slurry seal parking lot,(166,000 square feet) to include curb prep, and restriping parking lot to include handicap parking area	\$ 108,529	\$ 108,529	\$ 17,757,031	90	100
93	FM-0041050	Los Angeles	Bellflower Courthouse	19-AL1	3	Exterior Shell- Grind, sand and refinish rusted and damaged handrails on 2nd through 4th Floor exterior balconies. Court Administrator concerned about condition. Paint flaking and sharp edges are a problem.	\$ 40,752	\$ 40,752	\$ 17,797,783	90	100
94	FM-0051373	Alameda	Wiley W. Manuel Courthouse	01-B3	3	Energy Efficiency project - HVAC - Install VFD's - install (2) VFD for EF 1&2.	\$ 176,372	\$ 147,800	\$ 17,945,583	90	83.8
95	FM-0051473	Alameda	George E. McDonald Hall of Justice	01-F1	3	Energy Efficiency Project - HVAC - Restore Economizer Dampers and Actuators, install VFD (4) - Restore Damper and Actuators (5), install 2 VFD to Supply and Return Fan on unit #1, install 2 VFD to Primary Chilled Water Pumps.	\$ 86,530	\$ 86,530	\$ 18,032,113	90	100
96	FM-0051791	Sacramento	Gordon Schaber Sacramento Superior Court	34-A1	3	Plumbing - To abate and remove two (2) abandoned boilers and associated plumbing and equipment - Boilers have been decommissioned and abandoned in place and are occupying valuable space.	\$ 100,104	\$ 100,104	\$ 18,132,217	90	100



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM BUDGET SHARE OF PRELIMINARY ESTIMATE	CUMULATIVE TOTAL OF FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	TOTAL SCORE RANK	FACILITY MODIFICATION PROGRAM % OF COST
97	FM-0054462	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	3	Elevator - Elevator Renovation - Complete renovation of fourteen (14) geared traction elevators. Work will include but not be limited to, car frames and platforms, buffers and safeties, hoistway entrance frames, doors and pit equipment, new AC gearless machines, micro-processor control systems, regenerative VVVF AC drives, fly ball governors, current code required wiring, interior and lobby control panels, car and hall door panels with new doors, counterweights and (see addtl description).	\$ 4,741,771	\$ 3,318,766	\$ 21,450,983	90	69.99
98	FM-0022429	Placer	South Placer Justice Center	31-H1	3	Fire System - Replace fire suppression system in Court IT from wet pipe to dry pipe. There is no back up Servers in this Court. If this equipment were lost, the Court could not function. Code compliance.	\$ 40,000	\$ 40,000	\$ 21,490,983	90	100
99	FM-0034443	San Mateo	Traffic/Small Claims Annex	41-A2	3	Exterior of Building - Paint exterior of building (2 floors) Power wash, Prepare and Patch, Caulk - Due to Concrete Spalling, Expansion Joint Deterioration, Faded Paint.	\$ 46,766	\$ 46,766	\$ 21,537,749	90	100
100	FM-0044066	Orange	Betty Lou Lamoreaux Justice Center	30-B1	3	Exterior - Safety-Security - Members of the public are exposed to the elements while standing in long lines prior to entering the facility through weapons screening. This project will provide an awning to reduce exposure. The lines are very long which causes discomfort for the public during inclement and hot weather. The court architect developed a proposal consisting of free standing steel tube columns, metal bracing-ribbing, and a canvas barrel-shaped cover.	\$ 59,584	\$ 47,637	\$ 21,585,386	95	79.95
101	FM-0052978	Los Angeles	Parking Structure Lot 59- Whittier Admin CTR	19-AO2	3	Grounds and Parking Lot - To provide and install new safety enclosures throughout the garages existing openings. Such opening as: the side facing walls, the decorative open spaces, the areas between each support columns and each opening for the first 2 floors. This project will also include the installation of a new rolling safety gate (with card reader), electrical installation to the panel and low voltage (for new gate motor) and approx. 550 LF of new welded iron fencing and mesh.	\$ 153,654	\$ 132,803	\$ 21,718,189	95	86.43
102	FM-0028372	Solano	Hall of Justice	48-A1	3	Fencing - 30K sf, Install secured fencing with card reader access for judges parking lot for security from the public - Contingency Only.	\$ 146,751	\$ 146,751	\$ 21,864,940	100	100
103	FM-0031636	Sacramento	Carol Miller Justice Center	34-D1	3	Grounds and Parking - Parking lot lighting - Retrofit the existing parking lot lighting from high pressure sodium lighting to new more efficient LED lighting. Remove and replace total of 13 light poles with two fixtures per pole. Better Energy Efficiency.	\$ 31,759	\$ 31,044	\$ 21,895,985	100	97.75
104	FM-0040539	Orange	Central Justice Center	30-A1	3	HVAC - Replace Air Handling units for improved control-efficiency - The air handlers are beyond their replacement life cycle.	\$ 1,728,012	\$ 1,728,012	\$ 23,623,997	105	100
105	FM-0052830	Ventura	Hall of Justice	56-A1	3	COUNTY MANAGED - Electrical - 4160 Volt Breaker Upgrade. Replace 36yr old Breakers to improve reliability of e-system.	\$ 91,073	\$ 91,073	\$ 23,715,070	110	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

**Action Item 5 – (Action Required) – List F – Court-Funded
Facilities Requests (Facility Modifications)**

Summary:

Review Court-Funded Facilities Requests (Facility Modifications) from List F.

- Fresno Superior Court requests one (1) facility modification totaling \$20,460

Supporting Documentation:

- List F – Court-Funded Facilities Requests (Facility Modifications)

Action Requested:

Staff recommends one Court-Funded Facilities Request for review and approval.

This page intentionally left blank



ITEM #	CFR NUMBER	COUNTY	BUILDING ID	FACILITY NAME	LEASE, LICENSE, OR FM	REQUEST TYPE	CFR DESCRIPTION	CFR TERM	FUND SOURCE	CURRENT YEAR COSTS FY 14-15 (Includes existing costs prior to CFR term)	BUDGET YEAR COSTS	TOTAL CFR COMMITMENT (CFR Term)	REVIEW NOTES - Real Estate and Facilities Management, Capital Program, and Finance
1	10-CFR012	Fresno	10-A1	Fresno County Courthouse	Facility Modification	One-Time	Install redundant gas fire suppression cylinder to meet code requirements for Court's primary server room. The facility is currently not compliant with SFM & FFD requirements for fire suppression in this room. The installation would bring the building/server room into compliance and would provide fire protection, thereby reducing the possibility for catastrophic damage.	One- Time	TCTF	\$ 20,460	\$ -	\$ 20,460	Pending



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Discussion Item 1

Summary:

Review and discuss List E – *Funded Facility Modifications On Hold*

Total Project – Count:	22
Total FM Budget Share:	\$8,239,881

Supporting Documentation:

- List E – *Funded Facility Modifications On Hold*

This page intentionally left blank



	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM SHARE OF COST	FACILITY MODIFICATION PROGRAM BUDGET % OF COST	SHARED COST APPROVED?	PM ASSIGNED?	OTHER HOLD REASON?	COMMENTS
1	FM-0017040	Los Angeles	Compton Courthouse	19-AG1	2	Fire - Phase 1 - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$ 818,000	\$ 540,943	66.13%	Yes	No		
2	FM-0028322	Orange	Central Justice Center	30-A1	2	Fire - Phase 1 - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$ 913,973	\$ 833,269	91.17%	Yes	No		
3	FM-0031644	Santa Barbara	Santa Maria Courts Complex	42-F	2	Site - Parking lot safety issues - Remove and replace existing campus parking lot areas where sink holes have developed, compaction around under ground pipes is failing and asphalt deterioration has created trip hazards. Recompact, Repave & Restripe to comply with ADA standards; Sinkhole/Surface Damage. Approximate area of renovation is 82,300 S.F. which includes general parking as well as secured parking areas.	\$ 480,000	\$ 355,968	74.16%	No	Yes		Shared Cost for design phase approved.
4	FM-0040733	Solano	Hall of Justice	48-A1	2	Construct 1,070 lf of retaining wall, 525 lf of earthen berms, 575 lf of access ramps; install drainage pipe and 2 pumps to extract water trapped within the prevention area. \$1.7M was spent in 2005 for flood damage and \$146K was spent in FY 10/11 on flood prevention measures. Emergency exiting must be sealed during flood conditions.	\$ 1,531,000	\$ 1,114,874	72.82%	No	Yes		Shared Cost for design phase approved. Design effort is in work.
5	FM-0049125	Mendocino	County Courthouse	23-A1	2	HVAC - Fan coils (3 ea) - Remove and replace three (3) corroded and leaking fan coils. Scope of work will require asbestos abatement.	\$ 106,864	\$ 72,261	67.62%	No	Yes	County declined Shared Cost	Approved but Unfunded
6	FM-0051702	Mendocino	County Courthouse	23-A1	2	HVAC - Replace Two (2) Failing Chillers - Remove and replace two (2) 40 year old 35 - ton chillers that are failing and beyond repair. Install new controllers with BAC-net interface, includes electrical and piping, insulation as required. Replace four (4) Chilled Water Coils - The four (4) custom sized Chilled Water Coils are failing and beyond repair and in need of replacement, ACM abatement included. Three (3) coils in mechanical room and one (1) coil on 3rd floor.	\$ 720,968	\$ 487,519	67.62%	No	Yes	County declined Shared Cost	Approved but Unfunded
7	FM-0052151	Orange	Betty Lou Lamoreaux Justice Center	30-B1	3	Energy Efficiency - FM related to Energy Conservation Project 30B1_01242014HV1- HVAC - Chiller #2 - Replace existing Chiller # 2 with energy efficient Multistack chiller. Replacing the existing chiller with an energy efficient chiller will result in a cost savings and payback within 5 years. The project includes Engineering, Demolition/Installation, piping, electrical, controls, startup and commissioning, refrigerant monitoring system.	\$ 595,242	\$ 475,896	79.95%	Yes	No		
8	FM-0052243	Los Angeles	Alhambra Courthouse	19-11	3	Energy Efficiency Project -1911_02282013LV1 - Lighting and controls upgrade - Retrofit (1,533) F32T8 fluorescent fixtures with new 28-watt lamps and new ballast, (249) 3-lamp and 4-lamp fluorescent fixtures with new reflector, 28-watt lamps and new ballast, and (1) 2x2 fluorescent fixtures with new reflector, 17-watt lamps and new ballast. Install two (2) Vending Miser sensors to control vending machines. Replace 32 Exterior HID fixtures on the with new lower wattage LED fixtures.	\$ 222,058	\$ 190,970	86.00%	Yes	No		
9	FM-0052807	Los Angeles	Stanley Mosk Courthouse	19-K1	2	Fire Protection - Replace 1,811 sprinkler heads throughout facility that are more than 50 yrs old and found deficient and/or painted over during latest inspection. Sprinkler heads have failed U/L testing.	\$ 215,621	\$ 209,713	97.26%	Yes	No		
10	FM-0052909	San Bernardino	Barstow Courthouse	36-J1	2	Roof - Remove and Replace Roof - Remove and ACM abate approximately 26,000 SF of existing roof material and replace it with approximately 26,000 SF of new 20 year warranty, Title 24 compliant, roof system. Scope includes providing a 3rd party Hygienist to monitor the abatement, removing damaged seal around building, replacing counter flashing and pipe / vent flashing at various locations, and other work as per SOW.	\$ 580,000	\$ 451,994	77.93%	Yes	No		
11	FM-0052980	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	2	Roof - Remove and replace existing roof (62,550 SF) with new PVC roof system at the Main Deck, Penthouse decks (4) and lower eyebrow deck. Roofing system condition reports recommends replacement to mitigate leaks and imminent failure in a large percentage of the overall roofing system. New roof drains required for change in roofing systems.	\$ 1,503,360	\$ 1,034,161	68.79%	Yes	No		



FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	TCFMAC FUNDED COST	FACILITY MODIFICATION PROGRAM SHARE OF COST	FACILITY MODIFICATION PROGRAM BUDGET % OF COST	SHARED COST APPROVED?	PM ASSIGNED?	OTHER HOLD REASON?	COMMENTS
12	FM-0052982	Los Angeles	Metropolitan Courthouse	19-T1	2	Roof - Remove and replace existing main deck, penthouse & stairwell deck roofs (27,000 SF) with new 3 ply roof systems. Roofing system is failing. Work includes new flashings and reglet metal where needed, metal etching and repainting of the deteriorating standing seam metal roof (2,535 SF) and cleaning and resetting roof drains and caps.	\$ 634,160	\$ 599,535	94.54%	Yes	No	
13	FM-0053006	Los Angeles	Bellflower Courthouse	19-AL1	2	Roof - Remove and replace existing roof with new PVC roof system - Due to roof currently being in poor condition, recommended removal and replacement of existing roof will bring entire system to good condition.	\$ 667,498	\$ 520,248	77.94%	Yes	No	
14	FM-0053008	Los Angeles	Compton Courthouse	19-AG1	2	Roof - Remove and replace the upper roof, main roof deck and stand alone restroom roofs (approximately 34,000 SF) with a 3 ply roofing system, roofing system is failing. Work includes new flashings, and reglet metal where needed.	\$ 747,216	\$ 494,134	66.13%	Yes	No	
15	FM-0054074	San Mateo	Municipal Court Building - Northern Branch	41-C1	2	HVAC - Replace Ten (10) failed hot water reheat coils, associated valves and piping at New Wing side - Active and temporarily remediated leaks at (7) coils; (3) additional coils clogged and inactive.	\$ 88,703	\$ 73,810	83.21%	No	Yes	
16	FM-0054311	Los Angeles	Pomona Courthouse South	19-W1	2	HVAC - Replace (1) hot water coil and (2) chilled water coils, Drain Pan and install new Spring Isolators. ACM testing and remediation. AHU leaking water onto 4th floor Mechanical Room.	\$ 110,893	\$ 101,068	91.14%	Yes	No	
17	FM-0054490	Los Angeles	Alhambra Courthouse	19-11	2	Fire Protection - Replace 4" Pre-Action Fire Valve assembly (UL listed). Ensure that a secondary form of Fire Watch is set into place during replacement operations. Connect to 120 volt power supply for Fire valve assembly and connect Pre-Action valve to fire panel. Correct deficiency from State Fire Marshal Report; Replace pre-action system with one that is UL listed and approved to fire department safety standards.	\$ 86,170	\$ 74,106	86.00%	Yes	No	
18	FM-0054640	Los Angeles	Metropolitan Courthouse	19-T1	2	Fire Protection - Replace Fire doors, add panic hardware, magnetic hold open, and smoke detectors with relay modules and tie into the fire alarm system to close upon activation. Fire Marshall corrections for the Fire Rated doors located on Level A, B, and C.	\$ 76,882	\$ 72,684	94.54%	Yes	No	
19	FM-0054851	San Diego	Juvenile Court	37-E1	2	Fire Protection - Fire Safety Corrections Notice - Correct items #2, #3, & #5. Remove two (2) floor stops impeding proper operation of fire doors. Install 82 Lever Action Latch sets on doors in 1st & 2nd floors and 39 sets on doors located in 2nd floor DA Office. Install missing Smoke Seal Gaskets and Door Sweeps on 114 doors in various locations and on 10 doors in 2nd floor DA Office. Install six (6) combination security locks in specified locations. Install 22 missing Occupancy Load signs. (Ref FM ID 0054645).	\$ 105,693	\$ 78,868	74.62%	No	Yes	
20	FM-0054726	Stanislaus	Modesto Main Courthouse	50-A1	2	HVAC - To replace failing Baltimore Aircoil Cooling Tower CTW01 (OM00003271) located in the east penthouse - The shell of Cooling Tower CTW01 has severe corrosion damage. There are several locations on the tower that have rusted through leaving too many holes to effectively repair. The base of the tower is also severely corroded and must be replaced.	\$ 280,000	\$ 217,896	77.82%	No	Yes	
21	FM-0054882	Los Angeles	Metropolitan Courthouse	19-T1	2	HVAC - Heating Hot Water & Chilled Water Copper pipes between Main isolation & Control valves on floors 3, 5 & 8 are corroding, leaking and deteriorating. Existing isolation valves are non-functional and the building must be drained prior to replacement. Remove/replace 300ft of copper piping, install 12 Isolation Valves, six (6) Control Valves, 12 Balancing Valves, 12 Temperature Gauges & 12 Pressure Gauges.	\$ 183,490	\$ 173,471	94.54%	Yes	No	
22	FM-0054904	San Diego	East County Regional Center	37-11	2	Plumbing - Replace existing domestic booster pump system with new Grundfos Domestic Water Booster Pump Package. Existing booster pump system has only two operational pumps with one pump currently inoperable due to failed controller. Existing pump system has experienced frequent failures and needs to be replaced as it is critical in providing domestic water to the upper floors.	\$ 98,201	\$ 66,492	67.71%	No	Yes	
						\$ 10,765,992	\$ 8,239,881					



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Discussion Item 2

Summary:

Update on status of Solano Hall of Justice Retaining Wall Project (FM-0040733)

Supporting Documentation:

- Project report
- Slides

This page intentionally left blank

Discussion Item 2 Solano Hall of Justice Flood Protection Project

- FM-0040733
- Phase 1 Study &
Design Approved
- \$319,759



- Phase 2 in Planning- \$1M+
- Current Status – Phase 1 Design pending County Board of Sup for additional funding approval.

Fairfield Justice Campus Flood Protection




- Overview
- Past Events
- Affected Jurisdictions
- Project Definition
- Next Steps
- Questions & Answers

Overview

- Over the past 3 decades, region had local flooding incidences
- Created by region's geographic location and inadequate storm water infrastructure
- Limited water holding capacities are compounded by storm surges which increase impact to region
- Greatest impact during high-tide conditions combined with westerly storm winds

Site Area



Past Storm Events

- 6 significant storm events that have impacted region
- Shut down of County and Court's operations
- Loss of use as well & costs to repair damage
- County emergency response facilities and infrastructure compromised/incapacitated

2005 Event

*County of Solano – Sheriff's Building
Fairfield, California*



1. South hallway drywall removed.



2. Typical office drywall removal.

*County of Solano – Hall of Justice Building
Fairfield, California*



4. Courtroom 103, wood base removed at jury Wall.



5. Overall view of hallway behind courtrooms.

Study Summary

RECOMMENDATION SUMMARY - SOLANO COUNTY JUSTICE CAMPUS

Attachment 2

WINZLER & KELLY - 2009

LOCAL IMPROVEMENTS

- DETENTION PONDS
- PUMP STATION UPGRADES
- DRAINAGE UPGRADES
- NET POSITIVE TO COMMUNITY

JACOBS - 2011




HOJ BUILDING ONLY

- 5-6' WALLS
- NEW STAIRS AND LANDINGS
- NEW RAMPS
- NET NEGATIVE TO NEIGHBORS

LIONAKIS - 2014

PROTECTION OF JUSTICE CAMPUS

- FLOOD WALLS
- UNDERGROUND DETENTION
- NEW PUMPS
- NO NET EFFECT TO NEIGHBORS



RELATIVE STUDY OPTION COST MODELS							
Author	Year	Option	Description	Goal	Operations	Orig. Est.	2016 Dollars
W&K	2009	Alternative 1	New Detention Ponds and New Washington Street Pump Station	Eliminate Ponding	Improved	\$10.1 M	\$12.2 M
		Alternative 2	New Detention Ponds and County Pump Station Upgrade	Eliminate Ponding	Improved	\$8.8 M	\$10.7 M
		Alternative 3	Storm Drain Boxes Upgrade and New Washington Pump Station	Reduce Ponding	Improved	\$17.7 M	\$21.5 M
		Alternative 4	Storm Drain Boxes Upgrade and County Pump Station Upgrade	Reduce Ponding	Improved	\$16.4 M	\$19.9 M
Jacobs	2011	HQJ Wall	5.5' wall and berm around HQJ	Protect HQJ	Reduced	\$1.5 M	\$1.9 M
Lionakis	2014	15 Year Wall	Wall of varying height - equal retention volume	Protect Campus	Improved	\$14.2 - 15.1 M	\$14.2 - 15.1 M
		25 Year Wall	Wall of varying height - equal retention volume	Protect Campus	Improved	\$17.6 - 18.1 M	\$17.6 - 19.1 M

Affected Jurisdictions/Agencies

- Judicial Council of California,
- City of Fairfield,
- City of Suisun City
- Solano County
- Armijo High School
- Union Pacific Railway

Actions to date

- Initiated study and development of potential plan
- Focus group developed to review funding options
- Inter-agency responsibilities identified
- Short and long term options developed

Project Definition

- Phase 1 – Walls and Berms
 - \$4 - \$5 million estimated total project cost
 - Can begin design immediately
 - 18 -24 month total project delivery
 - Project focused on Fairfield Justice Campus
 - Stakeholders: Solano County, Judicial Council of California
 - Benefits to Solano County Residents using Judicial Campus Functions

Walls & Berms



CONCEPTUAL RENDERING OF HOJ ENTRANCE

Project Definition

- Phase 2 – Onsite/Offsite Detention
 - Onsite – Detention facility to hold storm surge waters
 - \$9 - \$10 million estimated total project cost
 - Could begin entitlements immediately
 - 24 – 28 month total project delivery
 - Benefits to Solano County Residents using Judicial Campus Functions as well local property owners adjacent to site
 - Offsite – Park/Field Detention Basin
 - \$2 - \$2.5 million estimated total project cost
 - Creation of 15 acre-foot storm water storage basin that could function as recreational soccer fields
 - Would require cross jurisdictional support and environmental entitlements as well project study and design
 - 24 – 36 months



Onsite Detention

15 Year Protection:

Protection Area: 440,000 Square Feet
Detention Area: 100,000 Square Feet
Water Storage: 875,556 Cubic Feet / 20.1 Acre Feet (underground)
Max Depth: 11'-4" (total water table)



INSTALLATION IMAGES



PEDESTRIAN TRAFFIC



VEHICULAR TRAFFIC

WALL HEIGHT & STORAGE CAPACITY STUDY - PRECAST VOLUME AND PROTECTION AREA

LIONAKIS

Actions Taken:

- Confirmed limited short term funding available
- Storm channels and culverts maintenance/cleanings completed by both City of Fairfield and City of Suisun City
- Requested Union Pacific to review/address maintenance
- Developing survey map of canal heights
- Develop monitoring strategy for new buoy sensors in San Pedro bay
- Finalizing scope for Phase 1 design targeting:
 - Court building
 - Central Plant

Next Steps (Phase I)

- July 2015 - Negotiate design and construction document scope
- August 2015 - Board of Supervisors to approve design task order
- September 2015 - Judicial Council executes task order
- Lionakis schedule as follows
 - September /October 2015 - Due diligence & CEQA
 - November 2015/February 2016 - Design
 - March/May 2016 - Construction drawing and permitting
- June 2016 – County BoS & JCC funding discussion/approval
- June/July 2016 - County managed bid and contract award
- August 2016 - Construction commences

This page intentionally left blank



JUDICIAL COUNCIL OF CALIFORNIA

455 Golden Gate Avenue · San Francisco, California 94102-3688

www.courts.ca.gov

REPORT TO THE TRIAL COURT FACILITY MODIFICATION ADVISORY COMMITTEE

For meeting on: July 17, 2015

Title	Agenda Item Type
Fairfield Justice Campus, Flood Protection Project	Discussion
From	Date of Report
Lisa Hinton, Project Manager	July 10, 2015
	Contact
	Lisa Hinton 916-263-2508
	Patrick McGrath 916-643-8051

Executive Summary

Over the past three decades the region, specifically the Solano County, Fairfield Justice Campus, which includes the Hall of Justice, have been subject to impacts from local flooding incidents. Impacts are a direct result from the region's geographic location and inadequate storm water infrastructure. The limited water holding capacities are compounded by storm surges which increase the impact to the Justice Campus. The greatest impact is to the Hall of Justice Courthouse.

Solano County retains title to the Hall of Justice and has a 27.18% of shared cost. As such, in 2009 Solano County conducted the first of three studies to improve the flooding impacts. This initial study looked at the Justice Campus and beyond and required support by multiple jurisdictions. The study was vast in scope, and included detention ponds, pump station upgrades and drainage improvements. This recommendation was not supported by the multiple jurisdictions and was deemed cost prohibitive.

The second study, facilitated by the Judicial Council in 2011, focused on the protection of the Hall of Justice via walls, ramps and landings. The estimate for improvements was more palatable at \$1.5M and the Trial Court Facilities Modification Working Group funded the project in fiscal year 2011-2012. Given that Solano County retains title to the building, Solano County was engaged shortly after funding approval.

Given Solano County's shared cost and vested interest in the Hall of Justice, a third study was conducted; a joint effort co-managed by Solano County and the Judicial Council. The results of this study are a multi-phased project extending to multiple jurisdictions. The proposed approach while aggressive provided for a holistic approach to contain water and provided a "No harm to other's solution" by capturing runoff from county, court, and city locations. While beneficial to all parties, further investigation determined that this approach was both cost prohibitive.

A study group combining state, county, and city stakeholders to better evaluate the challenges, financial resources available, and both city and county growth plans. The group developed some immediate measures and actions that while not a solution will eliminate some contributing factors and lessen the risk of flooding. At this time, the group has developed a two-pronged approach. Phase one eliminates risk to the most critical building and infrastructure components. Phase two will address those components at a lesser degree of risk and provides a better long term resolution.

The first phase of the project focuses on the Hall of Justice and Solano County Central Plant; protecting the facilities via a combination of walls and berms that, during an storm event, won't negatively impact adjacent properties. Previous fund commitments by the Judicial Council as well as Solano County funds will be used to implement this first phase of the project.

A later second phase, protecting the campus as a whole will be developed once phase one is underway. This later phase of the project engages the following stakeholders: Army Corps of Engineers, City of Fairfield, City of Suisun, Union Pacific Railway, Armijo High School and Solano County. The second phase is more complex and consists of both on and offsite detention. This phase will be a much longer term effort given the large number of stakeholders and the potential costs associated with this phase.



The long-term strategy is illustrated below, which proposes an onsite detention area to capture flood water.

15 Year Protection:

Protection Area: **440,000 Square Feet**
 Detention Area: **100,000 Square Feet**
 Water Storage: **875,556 Cubic Feet / 20.1 Acre Feet (underground)**
 Max Depth: **11'-4"** (below water table)



INSTALLATION IMAGES



PEDESTRIAN TRAFFIC VEHICULAR TRAFFIC

WALL HEIGHT & STORAGE CAPACITY STUDY - PRECAST VOLUME AND PROTECTION AREA





JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Action Item 6 – (Action Required) – Five Year Infrastructure Plan – Deferred Maintenance Request Log

Summary:

Review and discuss the Judicial Council Five Year Infrastructure Plan – Deferred Maintenance Request Log that is provided to Department of Finance on an annual basis.

Supporting Documentation:

- Report with request log

Action Requested:

Review and approve this report for submittal to the Judicial Council, with a recommendation to submit to DOF in September 2015.

This page intentionally left blank

Action Item 6
Five Year Infrastructure Plan –
Deferred Maintenance Request Log

- DOF first required Deferred Maintenance Report in FY 14-15
- To be included in COBCP process
- Building Name, ROM, Prioritization
- Current List – 2,856
- Total Value – \$2,122,563,000
- JCC Share of Cost – \$1,658,515,000

Action Item 6
Five Year Infrastructure Plan –
Deferred Maintenance Request Log

- **Prioritization Methodology**
 - Removed vacant & buildings scheduled for surplus
 - System Hierarchy – TCFMAC, TCPJAC, CEAC
 - Facility Condition Index
- **Approval Process**
 - TCFMAC – Deferred List
 - CFAC – Approved COBCP Document
 - Judicial Council – BCP Process



JUDICIAL COUNCIL OF CALIFORNIA

455 Golden Gate Avenue · San Francisco, California 94102-3688

www.courts.ca.gov

REPORT TO THE TRIAL COURT FACILITY MODIFICATION ADVISORY COMMITTEE

For business meeting on: July 17, 2015

Title	Agenda Item Type
Five-Year Infrastructure Plan – Deferred Maintenance Report Fiscal Year 2015-2016	Review
Rules, Forms, Standards, or Statutes Affected	Effective Date
None	Date of Report
Recommended by	Contact
Pat McGrath, Facility Operations Manager Real Estate and Facilities Management	Pat McGrath 2860 Gateway Oaks Drive, Suite 400 Sacramento, CA 95833-4336 916-643-8051 (O) 916-468-2475 (C)

Executive Summary

The state Department of Finance (DOF) has requested the Judicial Council submit a prioritized list of deferred maintenance needs in early September 2015. This list will be the basis for a high-level statement of the Judicial Branch's needs in the 2016 California's Five-Year Infrastructure Plan that is annually published by the Executive Branch¹ and potentially the basis for a future funding request.

To comply with DOF's request, staff of the Facilities Management Unit of Real Estate and Facilities Management has prepared the attached Deferred Maintenance List (the list). For active facilities the list presents a total of 2856 deferred maintenance needs with an estimated rough

¹ The 2015 Plan is here: <http://www.ebudget.ca.gov/2015-Infrastructure-Plan.pdf>

order of magnitude value of \$2.1 billion, of which the Judicial Branch responsible share is \$1.7 billion.

The branch portfolio contains another 835 deferred maintenance projects with a total potential value of \$388 million which are not included on the list. While identified in previous years, this work is not targeted for planning or execution due to their facility classification as an inactive facility or one targeted for disposal.

Methodology

Classification of Projects:

The portfolio of the Judicial Branch is in a state of flux. The Capital Construction program, historical decreases to court operational funding, and court operational changes, create two distinct classifications of facilities.

The first classification is court facilities that are fully active and operational and will continued to be used by the courts for the foreseeable future. The majority of these facilities have a significant amount of deferred maintenance, and as funding is identified, infrastructure systems in these facilities will be targeted for renewal.

The second category is composed of facilities that:

- a) Are closed for public access but are intended to be reoccupied once court operational funding is restored;
- b) Are scheduled for replacement by a Capital Construction project that is now in design or site acquisition;
- c) Are closed for public access and have a signed disposition agreement; or
- d) Are closed for public access and have a draft agreement containing all negotiated business terms, subject only to approval by the Office of Legal Services, the Judicial Council and, within a reasonable timeframe, the counterpart review and approval authorities of the other party to that agreement;.
- e) Are scheduled for replacement by a Capital project that is now in construction and meet either condition (c) or (d) above.

Other than to address, prevent or mitigate a threat to health, safety, property damage, potential liability, or pursuant to contractual agreement, there is no foreseeable need to act on deferred maintenance for facilities assigned to the second category. Therefore, deferred maintenance needs of these facilities are not included on the attached list.

Prioritization:

DOF requested that this list be targeted by priority. As such, the Trial Court Facilities Modification Advisory Committee (TCFMAC), in conjunction with input from the Trial Court Presiding Judges Advisory Committee and the Court Executive Advisory Committee, developed a prioritized list of building systems that Judicial Council staff should use to support this requirement. Additionally, the TCFMAC directed that the building Facility

Condition Index is to be used to target those facilities in need of planned improvements the most.

Taken together these methods target infrastructure renewal in those active facilities for the most critical systems in the building which are in the worst condition.

The vast majority of the systems identified within this report are considered a classification of Priority 5—Beyond Rated Life, But Serviceable. Current budget limitations primarily restrict the branch to funding Priority 1—Immediately or Potentially Critical and Priority 2—Necessary, But Not Yet Critical projects. These projects are identified and funded over the course of the fiscal year as systems fail or deteriorate to the point of imminent failure.

Infrastructure and System Exclusion:

Local area network and phone infrastructure systems are removed from this report. While there may be significant deferred maintenance present within these systems, renovations for these systems are not maintained, funded and managed by the staff of the Judicial Council. These systems are directly managed and controlled locally by the Superior Courts throughout the state.

Shared Cost:

Many court facilities throughout the state share equity ownership between the state and counties. This results in a proportional share of system renewal costs being allocated to the state and county respectively. Upon execution of the various deferred projects the actual value of the county and state share may vary from this report due to rounding functions within the data set.

Previous Committee Action

The TCFMAC approved the FY 2014–2015 Deferred Maintenance Request Log for release to DOF on November 3, 2014.

Recommendation

Staff recommends that the TCFMAC review and approve this report for submittal to the Judicial Council, with a recommendation to submit to DOF in September 2015.

Page Intentionally Left Blank

Deferred						
LINE #	County	Facility Name	Project System Targeted for Renewal	Project Rough Order of Magnitude	Judicial Branch Share of Cost	County Share of Cost
1	El Dorado	Johnson Bldg.	B30 Roofing	\$ 96,000	\$ 96,000	\$ -
2	Alameda	Hayward Hall of Justice	B30 Roofing	\$ 710,000	\$ 627,000	\$ 83,000
3	Los Angeles	Airport Courthouse	B30 Roofing	\$ 719,000	\$ 555,000	\$ 164,000
4	Riverside	Family Law Court	B30 Roofing	\$ 53,000	\$ 53,000	\$ -
5	Solano	Hall of Justice	B30 Roofing	\$ 1,624,000	\$ 1,183,000	\$ 441,000
6	Los Angeles	Santa Monica Courthouse	B30 Roofing	\$ 1,866,000	\$ 1,464,000	\$ 401,000
7	Los Angeles	Downey Courthouse	B30 Roofing	\$ 1,202,000	\$ 1,006,000	\$ 196,000
8	Santa Barbara	Santa Maria Courts, Bldg G	B30 Roofing	\$ 264,000	\$ 255,000	\$ 9,000
9	Riverside	Riverside Juvenile Justice Trailers	B30 Roofing	\$ 24,000	\$ 24,000	\$ -
10	Riverside	Riverside Juvenile Justice Trailers	B30 Roofing	\$ 19,000	\$ 19,000	\$ -
11	San Bernardino	San Bernardino Courthouse	B30 Roofing	\$ 165,000	\$ 157,000	\$ 7,000
12	Santa Barbara	Santa Maria Courts Bldgs C + D	B30 Roofing	\$ 577,000	\$ 577,000	\$ -
13	Santa Barbara	Santa Maria Courts, Bldg F	B30 Roofing	\$ 11,000	\$ 11,000	\$ -
14	San Bernardino	Rancho Cucamonga Courthouse	B30 Roofing	\$ 84,000	\$ 64,000	\$ 20,000
15	Riverside	Riverside Juvenile Court	B30 Roofing	\$ 500,000	\$ 247,000	\$ 253,000
16	Solano	Solano Justice Building	B30 Roofing	\$ 43,000	\$ 33,000	\$ 10,000
17	Alameda	Wiley W. Manuel Courthouse	B30 Roofing	\$ 338,000	\$ 283,000	\$ 55,000
18	Butte	Butte County Courthouse	B30 Roofing	\$ 713,000	\$ 713,000	\$ -
19	Contra Costa	Wakefield Taylor Courthouse	B30 Roofing	\$ 206,000	\$ 206,000	\$ -
20	Contra Costa	Bray Courts	B30 Roofing	\$ 750,000	\$ 641,000	\$ 109,000
21	Contra Costa	Jail Annex	B30 Roofing	\$ 178,000	\$ 11,000	\$ 168,000
22	Del Norte	Del Norte County Superior Court	B30 Roofing	\$ 31,000	\$ 19,000	\$ 12,000
23	Humboldt	Humboldt County Courthouse (Eureka)	B30 Roofing	\$ 418,000	\$ 139,000	\$ 279,000
24	Imperial	Imperial County Courthouse	B30 Roofing	\$ 465,000	\$ 465,000	\$ -
25	Kern	Bakersfield Superior Court	B30 Roofing	\$ 844,000	\$ 529,000	\$ 315,000
26	Kern	Bakersfield Justice Bldg.	B30 Roofing	\$ 381,000	\$ 195,000	\$ 186,000
27	Kern	Bakersfield Juvenile Center	B30 Roofing	\$ 178,000	\$ 119,000	\$ 59,000
28	Kern	Delano/North Kern Court	B30 Roofing	\$ 180,000	\$ 145,000	\$ 35,000
29	Kern	Shafter/Wasco Courts Bldg.	B30 Roofing	\$ 226,000	\$ 203,000	\$ 23,000
30	Kern	Taft Courts Bldg.	B30 Roofing	\$ 75,000	\$ 75,000	\$ -
31	Kern	Arvin/ Lamont Branch	B30 Roofing	\$ 393,000	\$ 240,000	\$ 154,000
32	Kings	Avenal Court	B30 Roofing	\$ 22,000	\$ 13,000	\$ 9,000
33	Kings	Corcoran Court	B30 Roofing	\$ 51,000	\$ 45,000	\$ 6,000
34	Los Angeles	San Fernando Courthouse	B30 Roofing	\$ 1,312,000	\$ 1,094,000	\$ 218,000
35	Los Angeles	Alfred J. McCartney Juvenile Justice	B30 Roofing	\$ 639,000	\$ 441,000	\$ 198,000
36	Los Angeles	Sylmar Juvenile Court	B30 Roofing	\$ 151,000	\$ 52,000	\$ 99,000
37	Los Angeles	Compton Courthouse	B30 Roofing	\$ 451,000	\$ 298,000	\$ 153,000
38	Los Angeles	Norwalk Courthouse	B30 Roofing	\$ 448,000	\$ 381,000	\$ 67,000
39	Los Angeles	Bellflower Courthouse	B30 Roofing	\$ 441,000	\$ 343,000	\$ 97,000
40	Los Angeles	Beverly Hills Courthouse	B30 Roofing	\$ 303,000	\$ 241,000	\$ 62,000
41	Los Angeles	Hall of Records	B30 Roofing	\$ 54,000	\$ 6,000	\$ 48,000
42	Los Angeles	Van Nuys Courthouse West	B30 Roofing	\$ 1,063,000	\$ 855,000	\$ 207,000
43	Los Angeles	Chatsworth Courthouse	B30 Roofing	\$ 1,031,000	\$ 864,000	\$ 167,000
44	Los Angeles	Inglewood Courthouse	B30 Roofing	\$ 318,000	\$ 237,000	\$ 81,000
45	Los Angeles	Burbank Courthouse	B30 Roofing	\$ 803,000	\$ 729,000	\$ 74,000
46	Los Angeles	Alhambra Courthouse	B30 Roofing	\$ 1,114,000	\$ 958,000	\$ 156,000
47	Los Angeles	Pasadena Courthouse	B30 Roofing	\$ 398,000	\$ 276,000	\$ 122,000
48	Los Angeles	Clara Shortridge Foltz Criminal Justice	B30 Roofing	\$ 2,261,000	\$ 1,555,000	\$ 706,000
49	Los Angeles	Monrovia Training Center	B30 Roofing	\$ 316,000	\$ 222,000	\$ 94,000
50	Los Angeles	Mental Health Court	B30 Roofing	\$ 328,000	\$ 234,000	\$ 94,000
51	Los Angeles	Edmund D. Edelman Children's Court	B30 Roofing	\$ 1,099,000	\$ 769,000	\$ 330,000
52	Los Angeles	Metropolitan Courthouse	B30 Roofing	\$ 352,000	\$ 332,000	\$ 19,000
53	Los Angeles	Central Arraignment Courts	B30 Roofing	\$ 660,000	\$ 596,000	\$ 64,000
54	Los Angeles	East Los Angeles Courthouse	B30 Roofing	\$ 991,000	\$ 770,000	\$ 221,000
55	Los Angeles	Pomona Courthouse South	B30 Roofing	\$ 690,000	\$ 629,000	\$ 61,000
56	Los Angeles	West Covina Courthouse	B30 Roofing	\$ 1,546,000	\$ 1,283,000	\$ 263,000
57	Madera	Sierra Courthouse	B30 Roofing	\$ 61,000	\$ 41,000	\$ 19,000
58	Merced	Old Court	B30 Roofing	\$ 165,000	\$ 165,000	\$ -
59	Mono	New Mammoth Lakes Courthouse	B30 Roofing	\$ 97,000	\$ 97,000	\$ -
60	Napa	Criminal Court Building	B30 Roofing	\$ 232,000	\$ 232,000	\$ -
61	Nevada	Nevada City Courthouse Annex	B30 Roofing	\$ 328,000	\$ 140,000	\$ 188,000
62	Orange	Civil Complex Center ("CXC")	B30 Roofing	\$ 153,000	\$ 153,000	\$ -
63	Orange	Betty Lou Lamoreaux Justice Center	B30 Roofing	\$ 261,000	\$ 209,000	\$ 52,000
64	Orange	North Justice Center	B30 Roofing	\$ 592,000	\$ 534,000	\$ 57,000
65	Placer	Historic Courthouse	B30 Roofing	\$ 71,000	\$ 55,000	\$ 16,000
66	Sacramento	Gordon Schaber Sacramento Superior	B30 Roofing	\$ 674,000	\$ 674,000	\$ -
67	San Diego	Hall of Justice	B30 Roofing	\$ 147,000	\$ 59,000	\$ 88,000
68	San Diego	Juvenile Court	B30 Roofing	\$ 411,000	\$ 307,000	\$ 104,000
69	San Diego	Department 9 Trailer	B30 Roofing	\$ 23,000	\$ 23,000	\$ -
70	San Diego	Department 10 Trailer	B30 Roofing	\$ 23,000	\$ 23,000	\$ -
71	San Diego	North County Regional Center - North	B30 Roofing	\$ 1,831,000	\$ 1,831,000	\$ -
72	San Diego	East County Regional Center	B30 Roofing	\$ 1,671,000	\$ 1,131,000	\$ 539,000
73	Santa Clara	Hall of Justice (East)	B30 Roofing	\$ 353,000	\$ 353,000	\$ -

74	Santa Clara	Hall of Justice (West)	B30 Roofing	\$ 282,000	\$ 282,000	\$ -
75	Santa Clara	Downtown Superior Court	B30 Roofing	\$ 18,000	\$ 18,000	\$ -
76	Santa Clara	Historic Courthouse	B30 Roofing	\$ 237,000	\$ 237,000	\$ -
77	Santa Cruz	Jury Assembly Room	B30 Roofing	\$ 28,000	\$ 28,000	\$ -
78	Tulare	Visalia Superior Court	B30 Roofing	\$ 612,000	\$ 198,000	\$ 414,000
79	Ventura	Hall of Justice	B30 Roofing	\$ 1,199,000	\$ 837,000	\$ 361,000
80	Ventura	East County Courthouse	B30 Roofing	\$ 532,000	\$ 328,000	\$ 203,000
81	Los Angeles	Glendale Courthouse	B30 Roofing	\$ 825,000	\$ 747,000	\$ 78,000
82	Riverside	Hall of Justice	B30 Roofing	\$ 35,000	\$ 35,000	\$ -
83	San Luis Obispo	Courthouse Annex	B30 Roofing	\$ 684,000	\$ 340,000	\$ 344,000
84	Riverside	Blythe Courthouse - Superior Court	B30 Roofing	\$ 163,000	\$ 163,000	\$ -
85	Riverside	Larson Justice Center	B30 Roofing	\$ 1,371,000	\$ 1,108,000	\$ 263,000
86	Santa Barbara	Santa Maria Juvenile Court (new)	B30 Roofing	\$ 9,000	\$ 6,000	\$ 3,000
87	San Francisco	Civic Center Courthouse	B30 Roofing	\$ 399,000	\$ 399,000	\$ -
88	Santa Barbara	Santa Maria Courts Bldgs C + D	D1010 Elevators & Lifts	\$ 234,000	\$ 234,000	\$ -
89	San Bernardino	Barstow Courthouse	D1010 Elevators & Lifts	\$ 96,000	\$ 75,000	\$ 21,000
90	Riverside	Corona	D1010 Elevators & Lifts	\$ 103,000	\$ 55,000	\$ 47,000
91	Solano	Hall of Justice	D1010 Elevators & Lifts	\$ 574,000	\$ 418,000	\$ 156,000
92	San Bernardino	Rancho Cucamonga Courthouse	D1010 Elevators & Lifts	\$ 475,000	\$ 361,000	\$ 114,000
93	Solano	Solano Justice Building	D1010 Elevators & Lifts	\$ 95,000	\$ 72,000	\$ 23,000
94	Alameda	Wiley W. Manuel Courthouse	D1010 Elevators & Lifts	\$ 1,114,000	\$ 934,000	\$ 180,000
95	Alameda	Hayward Hall of Justice	D1010 Elevators & Lifts	\$ 1,010,000	\$ 892,000	\$ 118,000
96	Alameda	Hayward Hall of Justice	D1090 Other Conveying Systems	\$ 56,000	\$ 50,000	\$ 7,000
97	Alameda	Fremont Hall of Justice	D1010 Elevators & Lifts	\$ 798,000	\$ 634,000	\$ 164,000
98	Contra Costa	Wakefield Taylor Courthouse	D1010 Elevators & Lifts	\$ 485,000	\$ 485,000	\$ -
99	Contra Costa	Danville District Courthouse	D1010 Elevators & Lifts	\$ 96,000	\$ 96,000	\$ -
100	Contra Costa	George D. Carroll Courthouse	D1010 Elevators & Lifts	\$ 307,000	\$ 231,000	\$ 77,000
101	El Dorado	Johnson Bldg.	D1010 Elevators & Lifts	\$ 93,000	\$ 93,000	\$ -
102	Fresno	Fresno County Courthouse	D1010 Elevators & Lifts	\$ 1,305,000	\$ 1,251,000	\$ 53,000
103	Fresno	B.F. Sisk Federal Courthouse	D1010 Elevators & Lifts	\$ 577,000	\$ 577,000	\$ -
104	Humboldt	Humboldt County Courthouse (Eureka)	D1010 Elevators & Lifts	\$ 196,000	\$ 66,000	\$ 131,000
105	Kern	Bakersfield Superior Court	D1010 Elevators & Lifts	\$ 862,000	\$ 540,000	\$ 322,000
106	Kern	Bakersfield Justice Bldg.	D1010 Elevators & Lifts	\$ 829,000	\$ 423,000	\$ 405,000
107	Los Angeles	San Fernando Courthouse	D1010 Elevators & Lifts	\$ 50,000	\$ 42,000	\$ 8,000
108	Los Angeles	Santa Clarita Courthouse	D1010 Elevators & Lifts	\$ 11,000	\$ 10,000	\$ 1,000
109	Los Angeles	Alfred J. McCourtney Juvenile Justice	D1010 Elevators & Lifts	\$ 400,000	\$ 277,000	\$ 124,000
110	Los Angeles	Compton Courthouse	D1010 Elevators & Lifts	\$ 4,868,000	\$ 3,219,000	\$ 1,649,000
111	Los Angeles	Bellflower Courthouse	D1010 Elevators & Lifts	\$ 64,000	\$ 50,000	\$ 14,000
112	Los Angeles	Downey Courthouse	D1010 Elevators & Lifts	\$ 167,000	\$ 140,000	\$ 27,000
113	Los Angeles	Beverly Hills Courthouse	D1010 Elevators & Lifts	\$ 978,000	\$ 777,000	\$ 200,000
114	Los Angeles	Hall of Records	D1010 Elevators & Lifts	\$ 152,000	\$ 16,000	\$ 136,000
115	Los Angeles	Van Nuys Courthouse East	D1010 Elevators & Lifts	\$ 2,389,000	\$ 2,143,000	\$ 245,000
116	Los Angeles	Van Nuys Courthouse West	D1010 Elevators & Lifts	\$ 255,000	\$ 205,000	\$ 50,000
117	Los Angeles	Torrance Courthouse	D1010 Elevators & Lifts	\$ 1,461,000	\$ 1,321,000	\$ 140,000
118	Los Angeles	Inglewood Juvenile Court	D1010 Elevators & Lifts	\$ 89,000	\$ 72,000	\$ 17,000
119	Los Angeles	Inglewood Courthouse	D1010 Elevators & Lifts	\$ 2,510,000	\$ 1,872,000	\$ 639,000
120	Los Angeles	Burbank Courthouse	D1010 Elevators & Lifts	\$ 131,000	\$ 119,000	\$ 12,000
121	Los Angeles	Glendale Courthouse	D1010 Elevators & Lifts	\$ 94,000	\$ 85,000	\$ 9,000
122	Los Angeles	Alhambra Courthouse	D1010 Elevators & Lifts	\$ 1,069,000	\$ 919,000	\$ 150,000
123	Los Angeles	Pasadena Courthouse	D1010 Elevators & Lifts	\$ 677,000	\$ 470,000	\$ 208,000
124	Los Angeles	Stanley Mosk Courthouse	D1010 Elevators & Lifts	\$ 1,957,000	\$ 1,903,000	\$ 54,000
125	Los Angeles	Stanley Mosk Courthouse	D1020 Escalators & Moving Walks	\$ 10,600,000	\$ 10,300,000	\$ 300,000
126	Los Angeles	El Monte Courthouse	D1010 Elevators & Lifts	\$ 922,000	\$ 536,000	\$ 386,000
127	Los Angeles	Edmund D. Edelman Children's Court	D1010 Elevators & Lifts	\$ 4,758,000	\$ 3,330,000	\$ 1,428,000
128	Los Angeles	Metropolitan Courthouse	D1010 Elevators & Lifts	\$ 82,000	\$ 78,000	\$ 4,000
129	Los Angeles	Central Arraignment Courts	D1010 Elevators & Lifts	\$ 590,000	\$ 533,000	\$ 58,000
130	Los Angeles	Pomona Courthouse South	D1010 Elevators & Lifts	\$ 64,000	\$ 58,000	\$ 6,000
131	Los Angeles	West Covina Courthouse	D1010 Elevators & Lifts	\$ 216,000	\$ 179,000	\$ 37,000
132	Nevada	Nevada City Courthouse	D1010 Elevators & Lifts	\$ 230,000	\$ 151,000	\$ 79,000
133	Orange	Betty Lou Lamoreaux Justice Center	D1010 Elevators & Lifts	\$ 30,000	\$ 24,000	\$ 6,000
134	Orange	North Justice Center	D1010 Elevators & Lifts	\$ 612,000	\$ 553,000	\$ 59,000
135	Placer	Historic Courthouse	D1010 Elevators & Lifts	\$ 94,000	\$ 72,000	\$ 22,000
136	San Diego	Kearny Mesa Court	D1010 Elevators & Lifts	\$ 60,000	\$ 60,000	\$ -
137	San Diego	Juvenile Court	D1010 Elevators & Lifts	\$ 118,000	\$ 88,000	\$ 30,000
138	San Diego	North County Regional Center - South	D1010 Elevators & Lifts	\$ 344,000	\$ 232,000	\$ 113,000
139	San Diego	North County Regional Center - North	D1010 Elevators & Lifts	\$ 95,000	\$ 95,000	\$ -
140	San Diego	South County Regional Center	D1010 Elevators & Lifts	\$ 1,120,000	\$ 401,000	\$ 718,000
141	San Diego	East County Regional Center	D1010 Elevators & Lifts	\$ 524,000	\$ 355,000	\$ 169,000
142	San Mateo	Hall of Justice	D1010 Elevators & Lifts	\$ 16,000	\$ 9,000	\$ 8,000
143	San Mateo	Northern Branch Courthouse	D1010 Elevators & Lifts	\$ 101,000	\$ 84,000	\$ 17,000
144	Santa Clara	Hall of Justice (East)	D1010 Elevators & Lifts	\$ 219,000	\$ 219,000	\$ -
145	Santa Clara	Downtown Superior Court	D1010 Elevators & Lifts	\$ 1,225,000	\$ 1,225,000	\$ -
146	Santa Clara	Historic Courthouse	D1010 Elevators & Lifts	\$ 43,000	\$ 43,000	\$ -
147	Santa Clara	Santa Clara Courthouse	D1010 Elevators & Lifts	\$ 225,000	\$ 225,000	\$ -
148	Tulare	Visalia Superior Court	D1010 Elevators & Lifts	\$ 1,079,000	\$ 349,000	\$ 730,000
149	Ventura	Hall of Justice	D1010 Elevators & Lifts	\$ 2,932,000	\$ 2,049,000	\$ 884,000

150	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	D1010 Elevators & Lifts	\$ 12,500,000	\$ 8,600,000	\$ 3,900,000
151	Santa Barbara	Santa Maria Courts, Bldg G	D1010 Elevators & Lifts	\$ 8,000	\$ 8,000	\$ -
152	San Luis Obispo	Courthouse Annex	D1010 Elevators & Lifts	\$ 451,000	\$ 225,000	\$ 227,000
153	San Bernardino	Fontana Courthouse	D1010 Elevators & Lifts	\$ 96,000	\$ 79,000	\$ 17,000
154	Nevada	Nevada City Courthouse	B30 Roofing	\$ 198,000	\$ 130,000	\$ 68,000
155	Riverside	Riverside Juvenile Justice Trailers	D3050 Terminal & Package Units	\$ 24,000	\$ 24,000	\$ -
156	Riverside	Riverside Juvenile Justice Trailers	D3050 Terminal & Package Units	\$ 24,000	\$ 24,000	\$ -
157	Solano	Law and Justice Center	D2020-Domestic Water Distribution	\$ 966,000	\$ 122,000	\$ 844,000
158	Santa Barbara	Santa Maria Courts Bldgs C + D	D3050 Terminal & Package Units	\$ 768,000	\$ 768,000	\$ -
159	San Bernardino	Barstow Courthouse	D2020-Domestic Water Distribution	\$ 70,000	\$ 55,000	\$ 15,000
160	San Bernardino	Barstow Courthouse	D3050 Terminal & Package Units	\$ 13,000	\$ 10,000	\$ 3,000
161	Santa Barbara	Santa Maria Courts, Bldg F	D3050 Terminal & Package Units	\$ 29,000	\$ 29,000	\$ -
162	Riverside	Corona	D2020-Domestic Water Distribution	\$ 85,000	\$ 46,000	\$ 39,000
163	Riverside	Corona	D3050 Terminal & Package Units	\$ 63,000	\$ 34,000	\$ 29,000
164	San Bernardino	Rancho Cucamonga Courthouse	D2020-Domestic Water Distribution	\$ 913,000	\$ 695,000	\$ 219,000
165	San Bernardino	Rancho Cucamonga Courthouse	D3050 Terminal & Package Units	\$ 53,000	\$ 40,000	\$ 13,000
166	Riverside	Riverside Juvenile Court	D2020-Domestic Water Distribution	\$ 136,000	\$ 67,000	\$ 69,000
167	Riverside	Riverside Juvenile Court	G20 Site Improvements	\$ 76,000	\$ 37,000	\$ 38,000
168	Solano	Solano Justice Building	D3050 Terminal & Package Units	\$ 104,000	\$ 79,000	\$ 25,000
169	San Bernardino	Victorville Courthouse-Dept. N-1	D2020-Domestic Water Distribution	\$ 327,000	\$ 210,000	\$ 117,000
170	San Bernardino	Victorville Courthouse-Dept. N-1	D3030 Cooling Generating Systems	\$ 20,000	\$ 13,000	\$ 7,000
171	San Bernardino	Victorville Courthouse-Dept. N-1	D3050 Terminal & Package Units	\$ 898,000	\$ 577,000	\$ 321,000
172	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D3050 Terminal & Package Units	\$ 156,000	\$ 36,000	\$ 120,000
173	Alameda	Wiley W. Manuel Courthouse	D3050 Terminal & Package Units	\$ 18,000	\$ 15,000	\$ 3,000
174	Alameda	Wiley W. Manuel Courthouse	G20 Site Improvements	\$ 636,000	\$ 533,000	\$ 103,000
175	Alameda	Hayward Hall of Justice	D3050 Terminal & Package Units	\$ 31,000	\$ 28,000	\$ 4,000
176	Alameda	George E. McDonald Hall of Justice	D2020-Domestic Water Distribution	\$ 114,000	\$ 114,000	\$ -
177	Alameda	George E. McDonald Hall of Justice	G20 Site Improvements	\$ 15,000	\$ 15,000	\$ -
178	Alameda	Berkeley Courthouse	D3050 Terminal & Package Units	\$ 28,000	\$ 28,000	\$ -
179	Alameda	Fremont Hall of Justice	D3050 Terminal & Package Units	\$ 7,000	\$ 5,000	\$ 1,000
180	Butte	Butte County Courthouse	D3050 Terminal & Package Units	\$ 333,000	\$ 333,000	\$ -
181	El Dorado	Cameron Park	D2020-Domestic Water Distribution	\$ 21,000	\$ 21,000	\$ -
182	El Dorado	Cameron Park	D3050 Terminal & Package Units	\$ 40,000	\$ 40,000	\$ -
183	El Dorado	Johnson Bldg.	D2020-Domestic Water Distribution	\$ 55,000	\$ 55,000	\$ -
184	Fresno	Fresno County Courthouse	G20 Site Improvements	\$ 1,779,000	\$ 1,706,000	\$ 73,000
185	Glenn	Historic Courthouse	G20 Site Improvements	\$ 25,000	\$ 12,000	\$ 13,000
186	Humboldt	Humboldt County Courthouse (Eureka)	D3050 Terminal & Package Units	\$ 9,000	\$ 3,000	\$ 6,000
187	Imperial	Imperial County Courthouse	G20 Site Improvements	\$ 95,000	\$ 95,000	\$ -
188	Kern	Bakersfield Superior Court	D3050 Terminal & Package Units	\$ 561,000	\$ 352,000	\$ 210,000
189	Kern	Bakersfield Justice Bldg.	D2020-Domestic Water Distribution	\$ 517,000	\$ 264,000	\$ 253,000
190	Kern	Bakersfield Justice Bldg.	D3050 Terminal & Package Units	\$ 162,000	\$ 83,000	\$ 79,000
191	Kern	Bakersfield Juvenile Center	D2020-Domestic Water Distribution	\$ 281,000	\$ 188,000	\$ 93,000
192	Kern	Bakersfield Juvenile Center	D3050 Terminal & Package Units	\$ 8,000	\$ 5,000	\$ 3,000
193	Kern	Delano/North Kern Court	D2020-Domestic Water Distribution	\$ 28,000	\$ 23,000	\$ 5,000
194	Kern	Delano/North Kern Court	D3050 Terminal & Package Units	\$ 80,000	\$ 64,000	\$ 15,000
195	Kern	Shafter/Wasco Courts Bldg.	D3050 Terminal & Package Units	\$ 123,000	\$ 111,000	\$ 12,000
196	Kern	Taft Courts Bldg.	D2020-Domestic Water Distribution	\$ 12,000	\$ 12,000	\$ -
197	Kern	Arvin/ Lamont Branch	D2020-Domestic Water Distribution	\$ 52,000	\$ 32,000	\$ 20,000
198	Kings	Probation Building	G20 Site Improvements	\$ 30,000	\$ 3,000	\$ 26,000
199	Kings	Avenal Court	G20 Site Improvements	\$ 44,000	\$ 26,000	\$ 19,000
200	Kings	Corcoran Court	G20 Site Improvements	\$ 330,000	\$ 289,000	\$ 41,000
201	Los Angeles	San Fernando Courthouse	D3050 Terminal & Package Units	\$ 38,000	\$ 32,000	\$ 6,000
202	Los Angeles	Santa Clarita Courthouse	D2020-Domestic Water Distribution	\$ 66,000	\$ 58,000	\$ 8,000
203	Los Angeles	Alfred J. McCourtney Juvenile Justice Center	D3050 Terminal & Package Units	\$ 40,000	\$ 28,000	\$ 12,000
204	Los Angeles	Sylmar Juvenile Court	D2020-Domestic Water Distribution	\$ 30,000	\$ 10,000	\$ 20,000
205	Los Angeles	Sylmar Juvenile Court	G20 Site Improvements	\$ 29,000	\$ 10,000	\$ 19,000
206	Los Angeles	Compton Courthouse	D2020-Domestic Water Distribution	\$ 1,855,000	\$ 1,227,000	\$ 628,000
207	Los Angeles	Compton Courthouse	D3050 Terminal & Package Units	\$ 146,000	\$ 96,000	\$ 49,000
208	Los Angeles	Los Padrinos Juvenile Court	G20 Site Improvements	\$ 18,000	\$ 5,000	\$ 13,000
209	Los Angeles	Norwalk Courthouse	D2020-Domestic Water Distribution	\$ 866,000	\$ 736,000	\$ 130,000
210	Los Angeles	Norwalk Courthouse	D3050 Terminal & Package Units	\$ 37,000	\$ 32,000	\$ 6,000
211	Los Angeles	Bellflower Courthouse	D2020-Domestic Water Distribution	\$ 345,000	\$ 269,000	\$ 76,000
212	Los Angeles	Downey Courthouse	D2020-Domestic Water Distribution	\$ 394,000	\$ 330,000	\$ 64,000
213	Los Angeles	Downey Courthouse	D3050 Terminal & Package Units	\$ 27,000	\$ 23,000	\$ 4,000
214	Los Angeles	Downey Courthouse	G20 Site Improvements	\$ 161,000	\$ 135,000	\$ 26,000
215	Los Angeles	Santa Monica Courthouse	D3050 Terminal & Package Units	\$ 16,000	\$ 12,000	\$ 3,000
216	Los Angeles	Santa Monica Court Annex	D3050 Terminal & Package Units	\$ 117,000	\$ 117,000	\$ -
217	Los Angeles	Beverly Hills Courthouse	D3050 Terminal & Package Units	\$ 29,000	\$ 23,000	\$ 6,000
218	Los Angeles	Airport Courthouse	D3050 Terminal & Package Units	\$ 132,000	\$ 102,000	\$ 30,000
219	Los Angeles	Hall of Records	D3050 Terminal & Package Units	\$ 30,000	\$ 3,000	\$ 27,000
220	Los Angeles	Hall of Records	G20 Site Improvements	\$ 77,000	\$ 8,000	\$ 69,000
221	Los Angeles	Van Nuys Courthouse East	G20 Site Improvements	\$ 501,000	\$ 450,000	\$ 51,000
222	Los Angeles	Van Nuys Courthouse West	D3050 Terminal & Package Units	\$ 135,000	\$ 109,000	\$ 26,000
223	Los Angeles	Chatsworth Courthouse	D30 HVAC	\$ 22,000	\$ 18,000	\$ 4,000
224	Los Angeles	Chatsworth Courthouse	D3050 Terminal & Package Units	\$ 24,000	\$ 20,000	\$ 4,000
225	Los Angeles	Chatsworth Courthouse	G20 Site Improvements	\$ 726,000	\$ 608,000	\$ 118,000

226	Los Angeles	Michael D. Antonovich Antelope Vall	D3050 Terminal & Package Units	\$ 103,000	\$ 76,000	\$ 27,000
227	Los Angeles	Michael D. Antonovich Antelope Vall	G20 Site Improvements	\$ 14,000	\$ 10,000	\$ 4,000
228	Los Angeles	Torrance Courthouse	D3050 Terminal & Package Units	\$ 69,000	\$ 62,000	\$ 7,000
229	Los Angeles	Inglewood Courthouse	D2020-Domestic Water Distribution	\$ 590,000	\$ 440,000	\$ 150,000
230	Los Angeles	Burbank Courthouse	D3050 Terminal & Package Units	\$ 21,000	\$ 19,000	\$ 2,000
231	Los Angeles	Burbank Courthouse	G20 Site Improvements	\$ 81,000	\$ 73,000	\$ 7,000
232	Los Angeles	Glendale Courthouse	D3050 Terminal & Package Units	\$ 25,000	\$ 22,000	\$ 2,000
233	Los Angeles	Glendale Courthouse	G20 Site Improvements	\$ 66,000	\$ 60,000	\$ 6,000
234	Los Angeles	Alhambra Courthouse	D2020-Domestic Water Distribution	\$ 440,000	\$ 378,000	\$ 62,000
235	Los Angeles	Alhambra Courthouse	D3050 Terminal & Package Units	\$ 62,000	\$ 53,000	\$ 9,000
236	Los Angeles	Clara Shortridge Foltz Criminal Justice	D2020-Domestic Water Distribution	\$ 4,243,000	\$ 2,919,000	\$ 1,324,000
237	Los Angeles	Monrovia Training Center	D3050 Terminal & Package Units	\$ 223,000	\$ 157,000	\$ 66,000
238	Los Angeles	El Monte Courthouse	D2020-Domestic Water Distribution	\$ 458,000	\$ 266,000	\$ 192,000
239	Los Angeles	Edmund D. Edelman Children's Court	D3050 Terminal & Package Units	\$ 60,000	\$ 42,000	\$ 18,000
240	Los Angeles	Eastlake Juvenile Court	B30 Roofing	\$ 637,000	\$ 349,000	\$ 288,000
241	Los Angeles	Eastlake Juvenile Court	D3050 Terminal & Package Units	\$ 78,000	\$ 43,000	\$ 35,000
242	Los Angeles	Central Arraignment Courts	D2020-Domestic Water Distribution	\$ 282,000	\$ 254,000	\$ 28,000
243	Los Angeles	Central Arraignment Courts	D3050 Terminal & Package Units	\$ 38,000	\$ 34,000	\$ 4,000
244	Los Angeles	East Los Angeles Courthouse	D2020-Domestic Water Distribution	\$ 439,000	\$ 341,000	\$ 98,000
245	Los Angeles	East Los Angeles Courthouse	D3050 Terminal & Package Units	\$ 19,000	\$ 15,000	\$ 4,000
246	Los Angeles	Pomona Courthouse South	D3050 Terminal & Package Units	\$ 41,000	\$ 38,000	\$ 4,000
247	Los Angeles	West Covina Courthouse	D3050 Terminal & Package Units	\$ 14,000	\$ 11,000	\$ 2,000
248	Los Angeles	West Covina Courthouse	G20 Site Improvements	\$ 231,000	\$ 192,000	\$ 39,000
249	Merced	Old Court	D3050 Terminal & Package Units	\$ 40,000	\$ 40,000	\$ -
250	Napa	Criminal Court Building	G20 Site Improvements	\$ 13,000	\$ 13,000	\$ -
251	Orange	Central Justice Center	D3050 Terminal & Package Units	\$ 1,173,000	\$ 1,070,000	\$ 104,000
252	Orange	Civil Complex Center ("CXC")	D2020-Domestic Water Distribution	\$ 92,000	\$ 92,000	\$ -
253	Orange	Civil Complex Center ("CXC")	D3050 Terminal & Package Units	\$ 269,000	\$ 269,000	\$ -
254	Orange	Betty Lou Lamoreaux Justice Center	D3050 Terminal & Package Units	\$ 29,000	\$ 23,000	\$ 6,000
255	Orange	North Justice Center	D2020-Domestic Water Distribution	\$ 454,000	\$ 410,000	\$ 44,000
256	Orange	North Justice Center	D3050 Terminal & Package Units	\$ 1,340,000	\$ 1,210,000	\$ 130,000
257	Orange	West Justice Center	D3050 Terminal & Package Units	\$ 150,000	\$ 136,000	\$ 14,000
258	Placer	Juvenile Hall	D3050 Terminal & Package Units	\$ 31,000	\$ 5,000	\$ 26,000
259	San Diego	Kearny Mesa Court	D3050 Terminal & Package Units	\$ 279,000	\$ 279,000	\$ -
260	San Diego	Kearny Mesa Traffic Court KM3 Trail	D3050 Terminal & Package Units	\$ 47,000	\$ 47,000	\$ -
261	San Diego	Kearny Mesa Traffic Court KM4 Trail	D3050 Terminal & Package Units	\$ 50,000	\$ 50,000	\$ -
262	San Diego	Kearny Mesa Traffic Court KM5 & KM	D3050 Terminal & Package Units	\$ 50,000	\$ 50,000	\$ -
263	San Diego	Department 9 Trailer	D3050 Terminal & Package Units	\$ 47,000	\$ 47,000	\$ -
264	San Diego	Department 10 Trailer	D3050 Terminal & Package Units	\$ 47,000	\$ 47,000	\$ -
265	San Diego	North County Regional Center - South	D3050 Terminal & Package Units	\$ 151,000	\$ 101,000	\$ 49,000
266	San Diego	North County Regional Center - North	D2020-Domestic Water Distribution	\$ 759,000	\$ 759,000	\$ -
267	San Diego	North County Regional Center - Anne	D2020-Domestic Water Distribution	\$ 77,000	\$ 77,000	\$ -
268	San Diego	North County Regional Center - Anne	G20 Site Improvements	\$ 60,000	\$ 60,000	\$ -
269	San Diego	Trailer - Dept 34	D3050 Terminal & Package Units	\$ 50,000	\$ 50,000	\$ -
270	San Diego	Trailer - Dept 35	D3050 Terminal & Package Units	\$ 47,000	\$ 47,000	\$ -
271	San Diego	Trailer - Storage A	D3050 Terminal & Package Units	\$ 47,000	\$ 47,000	\$ -
272	San Diego	Trailer - Family Support	D3050 Terminal & Package Units	\$ 47,000	\$ 47,000	\$ -
273	San Diego	South County Regional Center	D2020-Domestic Water Distribution	\$ 501,000	\$ 180,000	\$ 321,000
274	San Diego	South County Regional Center	D3030 Cooling Generating Systems	\$ 17,000	\$ 6,000	\$ 11,000
275	San Diego	South County Regional Center	D3050 Terminal & Package Units	\$ 60,000	\$ 21,000	\$ 38,000
276	San Diego	South County Regional Center	G20 Site Improvements	\$ 512,000	\$ 184,000	\$ 329,000
277	San Diego	East County Regional Center	D2020-Domestic Water Distribution	\$ 1,072,000	\$ 726,000	\$ 346,000
278	San Diego	East County Regional Center	D3050 Terminal & Package Units	\$ 34,000	\$ 23,000	\$ 11,000
279	San Mateo	Central Branch	G20 Site Improvements	\$ 292,000	\$ 292,000	\$ -
280	San Mateo	Northern Branch Courthouse	G20 Site Improvements	\$ 944,000	\$ 785,000	\$ 158,000
281	Tulare	Visalia Superior Court	D3050 Terminal & Package Units	\$ 2,373,000	\$ 767,000	\$ 1,606,000
282	Tulare	Visalia Superior Court	G20 Site Improvements	\$ 448,000	\$ 145,000	\$ 303,000
283	Ventura	Hall of Justice	D2020-Domestic Water Distribution	\$ 1,237,000	\$ 864,000	\$ 373,000
284	Ventura	East County Courthouse	D3050 Terminal & Package Units	\$ 576,000	\$ 356,000	\$ 220,000
285	Santa Barbara	Santa Maria Courts, Bldg G	D3050 Terminal & Package Units	\$ 267,000	\$ 258,000	\$ 9,000
286	Riverside	Hall of Justice	D3050 Terminal & Package Units	\$ 87,000	\$ 87,000	\$ -
287	San Bernardino	Joshua Tree Courthouse	D2020-Domestic Water Distribution	\$ 127,000	\$ 43,000	\$ 84,000
288	San Bernardino	Fontana Courthouse	D2020-Domestic Water Distribution	\$ 82,000	\$ 67,000	\$ 15,000
289	San Bernardino	Fontana Courthouse	D3030 Cooling Generating Systems	\$ 10,000	\$ 8,000	\$ 2,000
290	San Bernardino	Fontana Courthouse	D3050 Terminal & Package Units	\$ 8,000	\$ 6,000	\$ 1,000
291	Riverside	Blythe Courthouse - Superior Court	D3050 Terminal & Package Units	\$ 102,000	\$ 102,000	\$ -
292	Santa Barbara	Santa Maria Juvenile Court (new)	D3050 Terminal & Package Units	\$ 19,000	\$ 13,000	\$ 6,000
293	San Francisco	Civic Center Courthouse	D3050 Terminal & Package Units	\$ 43,000	\$ 43,000	\$ -
294	Imperial	Imperial County Courthouse	D3030 Cooling Generating Systems	\$ 240,000	\$ 240,000	\$ -
295	Los Angeles	Compton Courthouse	D3030 Cooling Generating Systems	\$ 1,331,000	\$ 880,000	\$ 451,000
296	Los Angeles	Bellflower Courthouse	D3030 Cooling Generating Systems	\$ 199,000	\$ 155,000	\$ 44,000
297	San Diego	Hall of Justice	D3030 Cooling Generating Systems	\$ 82,000	\$ 33,000	\$ 49,000
298	San Bernardino	San Bernardino Courthouse	D3030 Cooling Generating Systems	\$ 2,563,000	\$ 2,451,000	\$ 112,000
299	San Bernardino	San Bernardino Courthouse	D3060 Controls & Instrumentation	\$ 852,000	\$ 815,000	\$ 37,000
300	Solano	Law and Justice Center	D3030 Cooling Generating Systems	\$ 43,000	\$ 5,000	\$ 37,000
301	Solano	Law and Justice Center	D3060 Controls & Instrumentation	\$ 989,000	\$ 125,000	\$ 864,000

302	Santa Barbara	Santa Maria Courts Bldgs C + D	D3060 Controls & Instrumentation	\$ 188,000	\$ 188,000	\$ -
303	San Bernardino	Barstow Courthouse	D3030 Cooling Generating Systems	\$ 694,000	\$ 541,000	\$ 153,000
304	San Bernardino	Barstow Courthouse	D3060 Controls & Instrumentation	\$ 120,000	\$ 94,000	\$ 27,000
305	Santa Barbara	Santa Maria Courts, Bldg F	D3060 Controls & Instrumentation	\$ 7,000	\$ 7,000	\$ -
306	Riverside	Corona	D3030 Cooling Generating Systems	\$ 342,000	\$ 185,000	\$ 157,000
307	Riverside	Corona	D3060 Controls & Instrumentation	\$ 34,000	\$ 18,000	\$ 15,000
308	San Bernardino	Rancho Cucamonga Courthouse	D3030 Cooling Generating Systems	\$ 992,000	\$ 755,000	\$ 238,000
309	Riverside	Riverside Juvenile Court	D3060 Controls & Instrumentation	\$ 177,000	\$ 87,000	\$ 90,000
310	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D3060 Controls & Instrumentation	\$ 18,000	\$ 4,000	\$ 14,000
311	Alameda	Wiley W. Manuel Courthouse	D3060 Controls & Instrumentation	\$ 1,702,000	\$ 1,426,000	\$ 276,000
312	Alameda	Hayward Hall of Justice	D3030 Cooling Generating Systems	\$ 16,000	\$ 14,000	\$ 2,000
313	Alameda	Hayward Hall of Justice	D3060 Controls & Instrumentation	\$ 1,608,000	\$ 1,420,000	\$ 188,000
314	Alameda	George E. McDonald Hall of Justice	D3030 Cooling Generating Systems	\$ 351,000	\$ 351,000	\$ -
315	Alameda	George E. McDonald Hall of Justice	D3060 Controls & Instrumentation	\$ 124,000	\$ 124,000	\$ -
316	Alameda	Berkeley Courthouse	D3060 Controls & Instrumentation	\$ 33,000	\$ 33,000	\$ -
317	Alameda	Fremont Hall of Justice	D3030 Cooling Generating Systems	\$ 118,000	\$ 94,000	\$ 24,000
318	Alameda	Fremont Hall of Justice	D3060 Controls & Instrumentation	\$ 1,571,000	\$ 1,248,000	\$ 324,000
319	Butte	Butte County Courthouse	D3030 Cooling Generating Systems	\$ 719,000	\$ 719,000	\$ -
320	Contra Costa	Family Law Center	D3060 Controls & Instrumentation	\$ 15,000	\$ 15,000	\$ -
321	El Dorado	Cameron Park	D3060 Controls & Instrumentation	\$ 11,000	\$ 11,000	\$ -
322	El Dorado	Johnson Bldg.	D3030 Cooling Generating Systems	\$ 150,000	\$ 150,000	\$ -
323	El Dorado	Johnson Bldg.	D3060 Controls & Instrumentation	\$ 111,000	\$ 111,000	\$ -
324	Fresno	Fresno County Courthouse	D3030 Cooling Generating Systems	\$ 79,000	\$ 76,000	\$ 3,000
325	Fresno	Fresno County Courthouse	D3060 Controls & Instrumentation	\$ 10,000	\$ 10,000	\$ -
326	Kern	Bakersfield Justice Bldg.	D3030 Cooling Generating Systems	\$ 143,000	\$ 73,000	\$ 70,000
327	Kern	Bakersfield Justice Bldg.	D3060 Controls & Instrumentation	\$ 12,000	\$ 6,000	\$ 6,000
328	Kern	Bakersfield Juvenile Center	D3030 Cooling Generating Systems	\$ 215,000	\$ 144,000	\$ 71,000
329	Kern	Bakersfield Juvenile Center	D3060 Controls & Instrumentation	\$ 594,000	\$ 397,000	\$ 197,000
330	Los Angeles	San Fernando Courthouse	D3030 Cooling Generating Systems	\$ 1,837,000	\$ 1,532,000	\$ 305,000
331	Los Angeles	San Fernando Courthouse	D3060 Controls & Instrumentation	\$ 1,116,000	\$ 931,000	\$ 185,000
332	Los Angeles	Sylmar Juvenile Court	D3030 Cooling Generating Systems	\$ 29,000	\$ 10,000	\$ 19,000
333	Los Angeles	Sylmar Juvenile Court	D3060 Controls & Instrumentation	\$ 78,000	\$ 27,000	\$ 51,000
334	Los Angeles	Compton Courthouse	D3060 Controls & Instrumentation	\$ 1,945,000	\$ 1,287,000	\$ 659,000
335	Los Angeles	Los Padrinos Juvenile Court	D3060 Controls & Instrumentation	\$ 52,000	\$ 15,000	\$ 36,000
336	Los Angeles	Norwalk Courthouse	D3060 Controls & Instrumentation	\$ 2,254,000	\$ 1,917,000	\$ 337,000
337	Los Angeles	Bellflower Courthouse	D3060 Controls & Instrumentation	\$ 687,000	\$ 536,000	\$ 152,000
338	Los Angeles	Downey Courthouse	D3030 Cooling Generating Systems	\$ 156,000	\$ 131,000	\$ 25,000
339	Los Angeles	Santa Monica Courthouse	D3030 Cooling Generating Systems	\$ 82,000	\$ 64,000	\$ 18,000
340	Los Angeles	Beverly Hills Courthouse	D3060 Controls & Instrumentation	\$ 1,315,000	\$ 1,046,000	\$ 269,000
341	Los Angeles	Airport Courthouse	D3030 Cooling Generating Systems	\$ 217,000	\$ 168,000	\$ 50,000
342	Los Angeles	Airport Courthouse	D3060 Controls & Instrumentation	\$ 472,000	\$ 364,000	\$ 108,000
343	Los Angeles	Hall of Records	D3030 Cooling Generating Systems	\$ 77,000	\$ 8,000	\$ 69,000
344	Los Angeles	Hall of Records	D3060 Controls & Instrumentation	\$ 210,000	\$ 22,000	\$ 188,000
345	Los Angeles	Van Nuys Courthouse East	D3030 Cooling Generating Systems	\$ 610,000	\$ 547,000	\$ 63,000
346	Los Angeles	Van Nuys Courthouse East	D3060 Controls & Instrumentation	\$ 1,432,000	\$ 1,285,000	\$ 147,000
347	Los Angeles	Van Nuys Courthouse West	D3030 Cooling Generating Systems	\$ 1,059,000	\$ 853,000	\$ 207,000
348	Los Angeles	Van Nuys Courthouse West	D3060 Controls & Instrumentation	\$ 2,060,000	\$ 1,658,000	\$ 402,000
349	Los Angeles	Chatsworth Courthouse	D3030 Cooling Generating Systems	\$ 798,000	\$ 669,000	\$ 129,000
350	Los Angeles	Michael D. Antonovich Antelope Vall	D3060 Controls & Instrumentation	\$ 459,000	\$ 337,000	\$ 122,000
351	Los Angeles	Torrance Courthouse	D3030 Cooling Generating Systems	\$ 405,000	\$ 366,000	\$ 39,000
352	Los Angeles	Inglewood Juvenile Court	D3060 Controls & Instrumentation	\$ 129,000	\$ 104,000	\$ 25,000
353	Los Angeles	Inglewood Courthouse	D3030 Cooling Generating Systems	\$ 330,000	\$ 246,000	\$ 84,000
354	Los Angeles	Burbank Courthouse	D3030 Cooling Generating Systems	\$ 120,000	\$ 109,000	\$ 11,000
355	Los Angeles	Glendale Courthouse	D3030 Cooling Generating Systems	\$ 398,000	\$ 361,000	\$ 38,000
356	Los Angeles	Glendale Courthouse	D3060 Controls & Instrumentation	\$ 399,000	\$ 361,000	\$ 38,000
357	Los Angeles	Alhambra Courthouse	D3030 Cooling Generating Systems	\$ 377,000	\$ 325,000	\$ 53,000
358	Los Angeles	Alhambra Courthouse	D3060 Controls & Instrumentation	\$ 990,000	\$ 852,000	\$ 139,000
359	Los Angeles	Pasadena Courthouse	D3030 Cooling Generating Systems	\$ 444,000	\$ 308,000	\$ 136,000
360	Los Angeles	Pasadena Courthouse	D3060 Controls & Instrumentation	\$ 1,347,000	\$ 934,000	\$ 413,000
361	Los Angeles	Stanley Mosk Courthouse	D3060 Controls & Instrumentation	\$ 4,277,000	\$ 4,160,000	\$ 117,000
362	Los Angeles	Clara Shortridge Foltz Criminal Justice	D3060 Controls & Instrumentation	\$ 8,137,000	\$ 5,597,000	\$ 2,540,000
363	Los Angeles	El Monte Courthouse	D3030 Cooling Generating Systems	\$ 575,000	\$ 334,000	\$ 241,000
364	Los Angeles	Edmund D. Edelman Children's Court	D3030 Cooling Generating Systems	\$ 807,000	\$ 565,000	\$ 242,000
365	Los Angeles	Eastlake Juvenile Court	D3030 Cooling Generating Systems	\$ 2,981,000	\$ 1,633,000	\$ 1,348,000
366	Los Angeles	Eastlake Juvenile Court	D3060 Controls & Instrumentation	\$ 338,000	\$ 185,000	\$ 153,000
367	Los Angeles	Metropolitan Courthouse	D3030 Cooling Generating Systems	\$ 441,000	\$ 416,000	\$ 24,000
368	Los Angeles	Metropolitan Courthouse	D3060 Controls & Instrumentation	\$ 1,624,000	\$ 1,535,000	\$ 89,000
369	Los Angeles	East Los Angeles Courthouse	D3060 Controls & Instrumentation	\$ 1,124,000	\$ 873,000	\$ 250,000
370	Los Angeles	Pomona Courthouse South	D3060 Controls & Instrumentation	\$ 1,372,000	\$ 1,250,000	\$ 122,000
371	Los Angeles	West Covina Courthouse	D3030 Cooling Generating Systems	\$ 202,000	\$ 167,000	\$ 34,000
372	Merced	Old Court	D3060 Controls & Instrumentation	\$ 82,000	\$ 82,000	\$ -
373	Monterey	Salinas Courthouse- North Wing	D3030 Cooling Generating Systems	\$ 6,000	\$ 6,000	\$ -
374	Napa	Criminal Court Building	D3060 Controls & Instrumentation	\$ 181,000	\$ 181,000	\$ -
375	Nevada	Nevada City Courthouse	D3030 Cooling Generating Systems	\$ 63,000	\$ 41,000	\$ 22,000
376	Orange	Central Justice Center	D3030 Cooling Generating Systems	\$ 3,105,000	\$ 2,831,000	\$ 274,000
377	Orange	Civil Complex Center ("CXC")	D3060 Controls & Instrumentation	\$ 77,000	\$ 77,000	\$ -

378	Orange	Betty Lou Lamoreaux Justice Center	D3030 Cooling Generating Systems	\$ 3,982,000	\$ 3,183,000	\$ 798,000
379	Orange	Betty Lou Lamoreaux Justice Center	D3060 Controls & Instrumentation	\$ 47,000	\$ 38,000	\$ 9,000
380	Orange	North Justice Center	D3030 Cooling Generating Systems	\$ 282,000	\$ 255,000	\$ 27,000
381	Orange	North Justice Center	D3060 Controls & Instrumentation	\$ 972,000	\$ 878,000	\$ 94,000
382	Orange	West Justice Center	D3030 Cooling Generating Systems	\$ 962,000	\$ 873,000	\$ 90,000
383	Orange	West Justice Center	D3060 Controls & Instrumentation	\$ 722,000	\$ 654,000	\$ 67,000
384	Placer	Historic Courthouse	D3030 Cooling Generating Systems	\$ 244,000	\$ 188,000	\$ 56,000
385	Placer	Bill Santucci Justice Center	D3060 Controls & Instrumentation	\$ 8,000	\$ 8,000	\$ -
386	Sacramento	Gordon Schaber Sacramento Superior	D3030 Cooling Generating Systems	\$ 70,000	\$ 70,000	\$ -
387	San Diego	Juvenile Court	D3060 Controls & Instrumentation	\$ 152,000	\$ 113,000	\$ 38,000
388	San Diego	North County Regional Center - South	D3060 Controls & Instrumentation	\$ 760,000	\$ 511,000	\$ 249,000
389	San Diego	North County Regional Center - North	D3060 Controls & Instrumentation	\$ 750,000	\$ 750,000	\$ -
390	San Diego	East County Regional Center	D3060 Controls & Instrumentation	\$ 1,494,000	\$ 1,011,000	\$ 482,000
391	San Mateo	Traffic/ Small Claims Annex	D3030 Cooling Generating Systems	\$ 38,000	\$ 38,000	\$ -
392	San Mateo	Central Branch	D3030 Cooling Generating Systems	\$ 130,000	\$ 130,000	\$ -
393	San Mateo	Northern Branch Courthouse	D3030 Cooling Generating Systems	\$ 423,000	\$ 352,000	\$ 71,000
394	Santa Clara	Downtown Superior Court	D3030 Cooling Generating Systems	\$ 59,000	\$ 59,000	\$ -
395	Santa Clara	Historic Courthouse	D3030 Cooling Generating Systems	\$ 480,000	\$ 480,000	\$ -
396	Ventura	East County Courthouse	D3030 Cooling Generating Systems	\$ 861,000	\$ 531,000	\$ 329,000
397	Santa Barbara	Santa Maria Courts, Bldg G	D3060 Controls & Instrumentation	\$ 67,000	\$ 64,000	\$ 2,000
398	Riverside	Hall of Justice	D3030 Cooling Generating Systems	\$ 1,665,000	\$ 1,665,000	\$ -
399	San Luis Obispo	Courthouse Annex	D3030 Cooling Generating Systems	\$ 210,000	\$ 105,000	\$ 106,000
400	San Luis Obispo	Courthouse Annex	D3060 Controls & Instrumentation	\$ 7,000	\$ 3,000	\$ 4,000
401	San Bernardino	Joshua Tree Courthouse	D3060 Controls & Instrumentation	\$ 9,000	\$ 3,000	\$ 6,000
402	Riverside	Larson Justice Center	D3030 Cooling Generating Systems	\$ 64,000	\$ 52,000	\$ 12,000
403	Riverside	Larson Justice Center	D3060 Controls & Instrumentation	\$ 909,000	\$ 735,000	\$ 174,000
404	San Francisco	Civic Center Courthouse	D3060 Controls & Instrumentation	\$ 1,204,000	\$ 1,204,000	\$ -
405	Contra Costa	Wakefield Taylor Courthouse	D3021 Boilers	\$ 21,000	\$ 21,000	\$ -
406	Fresno	Fresno County Courthouse	D3021 Boilers	\$ 459,000	\$ 440,000	\$ 19,000
407	Los Angeles	Pasadena Courthouse	D3021 Boilers	\$ 41,000	\$ 28,000	\$ 12,000
408	Sacramento	Gordon Schaber Sacramento Superior	D3021 Boilers	\$ 100,000	\$ 100,000	\$ -
409	Santa Clara	Sunnyvale Courthouse	D3021 Boilers	\$ 49,000	\$ 49,000	\$ -
410	Riverside	Corona	B30 Roofing	\$ 106,000	\$ 57,000	\$ 49,000
411	Fresno	Fresno County Courthouse	B30 Roofing	\$ 147,000	\$ 141,000	\$ 6,000
412	Los Angeles	Santa Clarita Courthouse	B30 Roofing	\$ 418,000	\$ 370,000	\$ 49,000
413	Orange	Central Justice Center	B30 Roofing	\$ 234,000	\$ 213,000	\$ 21,000
414	Orange	West Justice Center	B30 Roofing	\$ 12,000	\$ 11,000	\$ 1,000
415	San Diego	Kearny Mesa Court	B30 Roofing	\$ 442,000	\$ 442,000	\$ -
416	San Mateo	Traffic/ Small Claims Annex	B30 Roofing	\$ 98,000	\$ 98,000	\$ -
417	Santa Clara	Santa Clara Courthouse	B30 Roofing	\$ 196,000	\$ 196,000	\$ -
418	Butte	Butte County Courthouse	D3040 Distribution Systems	\$ 212,000	\$ 212,000	\$ -
419	Contra Costa	Family Law Center	D3040 Distribution Systems	\$ 67,000	\$ 67,000	\$ -
420	Contra Costa	Bray Courts	D3040 Distribution Systems	\$ 108,000	\$ 93,000	\$ 16,000
421	Contra Costa	Richard E. Arnason Justice Center	D3040 Distribution Systems	\$ 13,000	\$ 13,000	\$ -
422	El Dorado	Cameron Park	D3040 Distribution Systems	\$ 111,000	\$ 111,000	\$ -
423	Los Angeles	Chatsworth Courthouse	D3040 Distribution Systems	\$ 29,000	\$ 24,000	\$ 5,000
424	Merced	Old Court	D3040 Distribution Systems	\$ 7,000	\$ 7,000	\$ -
425	Napa	Napa Juvenile Court	D3040 Distribution Systems	\$ 44,000	\$ 23,000	\$ 22,000
426	San Mateo	Traffic/ Small Claims Annex	D3040 Distribution Systems	\$ 241,000	\$ 241,000	\$ -
427	Solano	Law and Justice Center	D3040 Distribution Systems	\$ 19,200,000	\$ 2,400,000	\$ 16,700,000
428	Alameda	Hayward Hall of Justice	D3040 Distribution Systems	\$ 5,096,000	\$ 4,500,000	\$ 596,000
429	San Bernardino	Rancho Cucamonga Courthouse	D3040 Distribution Systems	\$ 19,900,000	\$ 15,200,000	\$ 4,800,000
430	Alameda	Wiley W. Manuel Courthouse	D3040 Distribution Systems	\$ 6,007,000	\$ 5,034,000	\$ 973,000
431	Los Angeles	Pasadena Courthouse	D3040 Distribution Systems	\$ 14,900,000	\$ 10,400,000	\$ 4,600,000
432	San Bernardino	San Bernardino Courthouse	D3040 Distribution Systems	\$ 6,158,000	\$ 5,889,000	\$ 268,000
433	Fresno	Fresno County Courthouse	D3040 Distribution Systems	\$ 6,774,000	\$ 6,497,000	\$ 277,000
434	Los Angeles	Stanley Mosk Courthouse	D3040 Distribution Systems	\$ 30,000,000	\$ 29,100,000	\$ 800,000
435	San Mateo	Northern Branch Courthouse	D3040 Distribution Systems	\$ 1,543,000	\$ 1,284,000	\$ 259,000
436	Santa Clara	Santa Clara Courthouse	D3040 Distribution Systems	\$ 1,193,000	\$ 1,193,000	\$ -
437	Orange	North Justice Center	D3040 Distribution Systems	\$ 9,837,000	\$ 8,884,000	\$ 953,000
438	Contra Costa	Wakefield Taylor Courthouse	D3040 Distribution Systems	\$ 4,302,000	\$ 4,302,000	\$ -
439	Contra Costa	George D. Carroll Courthouse	D3040 Distribution Systems	\$ 2,821,000	\$ 2,115,000	\$ 705,000
440	Imperial	Imperial County Courthouse	D3040 Distribution Systems	\$ 3,019,000	\$ 3,019,000	\$ -
441	Orange	West Justice Center	D3040 Distribution Systems	\$ 495,000	\$ 449,000	\$ 46,000
442	Santa Clara	Hall of Justice (West)	D3040 Distribution Systems	\$ 3,540,000	\$ 3,540,000	\$ -
443	Riverside	Riverside Juvenile Court	D3040 Distribution Systems	\$ 646,000	\$ 319,000	\$ 327,000
444	Los Angeles	Van Nuys Courthouse East	D3040 Distribution Systems	\$ 3,204,000	\$ 2,876,000	\$ 329,000
445	Sacramento	Gordon Schaber Sacramento Superior	D3040 Distribution Systems	\$ 26,500,000	\$ 26,500,000	\$ -
446	Los Angeles	Van Nuys Courthouse West	D3040 Distribution Systems	\$ 5,346,000	\$ 4,302,000	\$ 1,044,000
447	Los Angeles	Clara Shortridge Foltz Criminal Justice	D3040 Distribution Systems	\$ 54,900,000	\$ 37,700,000	\$ 17,100,000
448	Los Angeles	Norwalk Courthouse	D3040 Distribution Systems	\$ 13,800,000	\$ 11,800,000	\$ 2,100,000
449	Los Angeles	Hall of Records	D3040 Distribution Systems	\$ 628,000	\$ 67,000	\$ 561,000
450	Alameda	George E. McDonald Hall of Justice	D3040 Distribution Systems	\$ 724,000	\$ 724,000	\$ -
451	El Dorado	Johnson Bldg.	D3040 Distribution Systems	\$ 282,000	\$ 282,000	\$ -
452	Kern	Bakersfield Justice Bldg.	D3040 Distribution Systems	\$ 4,992,000	\$ 2,550,000	\$ 2,442,000
453	Kern	Bakersfield Juvenile Center	D3040 Distribution Systems	\$ 918,000	\$ 613,000	\$ 305,000

454	Kings	Avenal Court	D3040 Distribution Systems	\$ 136,000	\$ 79,000	\$ 57,000
455	Los Angeles	Sylmar Juvenile Court	D3040 Distribution Systems	\$ 386,000	\$ 133,000	\$ 254,000
456	Los Angeles	Los Padrinos Juvenile Court	D3040 Distribution Systems	\$ 226,000	\$ 66,000	\$ 160,000
457	Los Angeles	Bellflower Courthouse	D3040 Distribution Systems	\$ 3,517,000	\$ 2,741,000	\$ 776,000
458	Los Angeles	Downey Courthouse	D3040 Distribution Systems	\$ 4,233,000	\$ 3,543,000	\$ 690,000
459	Los Angeles	Eastlake Juvenile Court	D3040 Distribution Systems	\$ 360,000	\$ 197,000	\$ 163,000
460	Los Angeles	Central Arraignment Courts	D3040 Distribution Systems	\$ 3,008,000	\$ 2,714,000	\$ 294,000
461	Madera	Sierra Courthouse	D3040 Distribution Systems	\$ 63,000	\$ 43,000	\$ 20,000
462	Nevada	Nevada City Courthouse	D3040 Distribution Systems	\$ 754,000	\$ 494,000	\$ 260,000
463	Riverside	Corona	D3040 Distribution Systems	\$ 713,000	\$ 385,000	\$ 328,000
464	Los Angeles	Torrance Courthouse	D3040 Distribution Systems	\$ 10,300,000	\$ 9,400,000	\$ 1,000,000
465	Los Angeles	Alhambra Courthouse	D3040 Distribution Systems	\$ 4,698,000	\$ 4,040,000	\$ 658,000
466	Los Angeles	El Monte Courthouse	D3040 Distribution Systems	\$ 10,500,000	\$ 6,100,000	\$ 4,400,000
467	Los Angeles	Edmund D. Edelman Children's Court	D3040 Distribution Systems	\$ 11,000,000	\$ 7,700,000	\$ 3,300,000
468	Los Angeles	Inglewood Courthouse	D3040 Distribution Systems	\$ 6,510,000	\$ 4,854,000	\$ 1,656,000
469	Los Angeles	Glendale Courthouse	D3040 Distribution Systems	\$ 1,249,000	\$ 1,130,000	\$ 118,000
470	Del Norte	Del Norte County Superior Court	D3040 Distribution Systems	\$ 68,000	\$ 41,000	\$ 26,000
471	Kern	Bakersfield Superior Court	D3040 Distribution Systems	\$ 8,010,000	\$ 5,017,000	\$ 2,993,000
472	Kings	Corcoran Court	D3040 Distribution Systems	\$ 31,000	\$ 27,000	\$ 4,000
473	Los Angeles	Inglewood Juvenile Court	D3040 Distribution Systems	\$ 558,000	\$ 451,000	\$ 107,000
474	Los Angeles	Monrovia Training Center	D3040 Distribution Systems	\$ 142,000	\$ 100,000	\$ 42,000
475	Los Angeles	West Covina Courthouse	D3040 Distribution Systems	\$ 4,282,000	\$ 3,554,000	\$ 728,000
476	Placer	Historic Courthouse	D3040 Distribution Systems	\$ 264,000	\$ 203,000	\$ 61,000
477	Sacramento	Carol Miller Justice Center Court Fac	D3040 Distribution Systems	\$ 973,000	\$ 951,000	\$ 22,000
478	San Diego	Juvenile Court	D3040 Distribution Systems	\$ 3,486,000	\$ 2,601,000	\$ 885,000
479	Santa Clara	Hall of Justice (East)	D3040 Distribution Systems	\$ 646,000	\$ 646,000	\$ -
480	Santa Clara	Historic Courthouse	D3040 Distribution Systems	\$ 1,275,000	\$ 1,275,000	\$ -
481	Solano	Hall of Justice	D3040 Distribution Systems	\$ 4,156,000	\$ 3,026,000	\$ 1,129,000
482	San Bernardino	Barstow Courthouse	D3040 Distribution Systems	\$ 530,000	\$ 413,000	\$ 117,000
483	Orange	Betty Lou Lamoreaux Justice Center	D3040 Distribution Systems	\$ 373,000	\$ 298,000	\$ 75,000
484	Santa Clara	Downtown Superior Court	D3040 Distribution Systems	\$ 925,000	\$ 925,000	\$ -
485	Tulare	Visalia Superior Court	D3040 Distribution Systems	\$ 6,366,000	\$ 2,058,000	\$ 4,308,000
486	San Luis Obispo	1070 Palm St.	D3040 Distribution Systems	\$ 12,000	\$ 12,000	\$ -
487	Orange	Central Justice Center	D3040 Distribution Systems	\$ 32,100,000	\$ 29,300,000	\$ 2,800,000
488	Los Angeles	Compton Courthouse	D3040 Distribution Systems	\$ 25,100,000	\$ 16,600,000	\$ 8,500,000
489	Solano	Solano Justice Building	D3040 Distribution Systems	\$ 2,241,000	\$ 1,705,000	\$ 536,000
490	Alameda	Fremont Hall of Justice	D3040 Distribution Systems	\$ 4,414,000	\$ 3,505,000	\$ 909,000
491	San Diego	East County Regional Center	D3040 Distribution Systems	\$ 21,700,000	\$ 14,700,000	\$ 7,000,000
492	Contra Costa	Danville District Courthouse	D3040 Distribution Systems	\$ 69,000	\$ 69,000	\$ -
493	Humboldt	Humboldt County Courthouse (Eureka)	D3040 Distribution Systems	\$ 664,000	\$ 221,000	\$ 442,000
494	Los Angeles	San Fernando Courthouse	D3040 Distribution Systems	\$ 67,000	\$ 56,000	\$ 11,000
495	Los Angeles	Airport Courthouse	D3040 Distribution Systems	\$ 309,000	\$ 238,000	\$ 70,000
496	Los Angeles	Michael D. Antonovich Antelope Vall	D3040 Distribution Systems	\$ 160,000	\$ 117,000	\$ 42,000
497	Los Angeles	East Los Angeles Courthouse	D3040 Distribution Systems	\$ 6,936,000	\$ 5,391,000	\$ 1,545,000
498	Los Angeles	Pomona Courthouse South	D3040 Distribution Systems	\$ 7,554,000	\$ 6,884,000	\$ 669,000
499	Napa	Criminal Court Building	D3040 Distribution Systems	\$ 34,000	\$ 34,000	\$ -
500	Nevada	Nevada City Courthouse Annex	D3040 Distribution Systems	\$ 612,000	\$ 261,000	\$ 351,000
501	Orange	Civil Complex Center ("CXC")	D3040 Distribution Systems	\$ 76,000	\$ 76,000	\$ -
502	San Diego	North County Regional Center - Nort	D3040 Distribution Systems	\$ 6,082,000	\$ 6,082,000	\$ -
503	San Diego	South County Regional Center	D3040 Distribution Systems	\$ 4,717,000	\$ 1,691,000	\$ 3,026,000
504	San Mateo	Central Branch	D3040 Distribution Systems	\$ 19,000	\$ 19,000	\$ -
505	Ventura	Hall of Justice	D3040 Distribution Systems	\$ 16,100,000	\$ 11,200,000	\$ 4,800,000
506	Ventura	East County Courthouse	D3040 Distribution Systems	\$ 103,000	\$ 64,000	\$ 39,000
507	Los Angeles	Metropolitan Courthouse	D3040 Distribution Systems	\$ 21,800,000	\$ 20,600,000	\$ 1,200,000
508	Los Angeles	Santa Monica Courthouse	D3040 Distribution Systems	\$ 1,053,000	\$ 827,000	\$ 227,000
509	Los Angeles	Beverly Hills Courthouse	D3040 Distribution Systems	\$ 4,944,000	\$ 3,931,000	\$ 1,013,000
510	Los Angeles	Santa Clarita Courthouse	D3040 Distribution Systems	\$ 43,000	\$ 38,000	\$ 5,000
511	Riverside	Hall of Justice	D3040 Distribution Systems	\$ 5,630,000	\$ 5,630,000	\$ -
512	Los Angeles	Alfred J. McCourtney Juvenile Justice	D3040 Distribution Systems	\$ 245,000	\$ 169,000	\$ 76,000
513	San Francisco	Hall of Justice	D5037 Fire Alarm Systems	\$ 619,000	\$ 144,000	\$ 475,000
514	San Luis Obispo	Courthouse Annex	D3040 Distribution Systems	\$ 181,000	\$ 90,000	\$ 91,000
515	Los Angeles	Burbank Courthouse	D3040 Distribution Systems	\$ 2,003,000	\$ 1,818,000	\$ 185,000
516	Solano	Law and Justice Center	D5037 Fire Alarm Systems	\$ 2,186,000	\$ 277,000	\$ 1,909,000
517	Santa Barbara	Santa Maria Courts Bldgs C + D	D3040 Distribution Systems	\$ 363,000	\$ 363,000	\$ -
518	San Bernardino	Barstow Courthouse	D5037 Fire Alarm Systems	\$ 178,000	\$ 138,000	\$ 39,000
519	Santa Barbara	Santa Maria Courts, Bldg F	D3040 Distribution Systems	\$ 20,000	\$ 20,000	\$ -
520	Santa Barbara	Santa Maria Courts, Bldg F	D5037 Fire Alarm Systems	\$ 26,000	\$ 26,000	\$ -
521	San Luis Obispo	1070 Palm St.	D5037 Fire Alarm Systems	\$ 9,000	\$ 9,000	\$ -
522	Riverside	Corona	D5037 Fire Alarm Systems	\$ 336,000	\$ 182,000	\$ 155,000
523	Solano	Hall of Justice	D5037 Fire Alarm Systems	\$ 925,000	\$ 674,000	\$ 251,000
524	San Bernardino	Rancho Cucamonga Courthouse	D5037 Fire Alarm Systems	\$ 2,620,000	\$ 1,993,000	\$ 628,000
525	Riverside	Riverside Juvenile Court	D5037 Fire Alarm Systems	\$ 213,000	\$ 105,000	\$ 108,000
526	Solano	Solano Justice Building	D5037 Fire Alarm Systems	\$ 501,000	\$ 382,000	\$ 120,000
527	Solano	Solano Justice Building	D2020-Domestic Water Distribution	\$ 255,000	\$ 194,000	\$ 61,000
528	San Bernardino	Victorville Courthouse-Dept. N-1	D3040 Distribution Systems	\$ 30,000	\$ 19,000	\$ 11,000
529	San Bernardino	Victorville Courthouse-Dept. N-1	D5037 Fire Alarm Systems	\$ 318,000	\$ 204,000	\$ 114,000

530	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D3040 Distribution Systems	\$ 53,000	\$ 12,000	\$ 41,000
531	Los Angeles	Van Nuys Courthouse East	D5037 Fire Alarm Systems	\$ 384,000	\$ 344,000	\$ 39,000
532	Alameda	Wiley W. Manuel Courthouse	D5037 Fire Alarm Systems	\$ 1,281,000	\$ 1,073,000	\$ 207,000
533	Alameda	Hayward Hall of Justice	D5037 Fire Alarm Systems	\$ 1,227,000	\$ 1,084,000	\$ 144,000
534	Alameda	George E. McDonald Hall of Justice	D5037 Fire Alarm Systems	\$ 172,000	\$ 172,000	\$ -
535	Alameda	Berkeley Courthouse	D5037 Fire Alarm Systems	\$ 78,000	\$ 78,000	\$ -
536	Alameda	Fremont Hall of Justice	D5037 Fire Alarm Systems	\$ 824,000	\$ 654,000	\$ 170,000
537	Amador	Amador County Courthouse	D5037 Fire Alarm Systems	\$ 119,000	\$ 119,000	\$ -
538	Butte	Butte County Courthouse	D5037 Fire Alarm Systems	\$ 391,000	\$ 391,000	\$ -
539	Contra Costa	Wakefield Taylor Courthouse	D5037 Fire Alarm Systems	\$ 657,000	\$ 657,000	\$ -
540	Contra Costa	Danville District Courthouse	D5037 Fire Alarm Systems	\$ 106,000	\$ 106,000	\$ -
541	El Dorado	Cameron Park	D5037 Fire Alarm Systems	\$ 45,000	\$ 45,000	\$ -
542	El Dorado	Johnson Bldg.	D5037 Fire Alarm Systems	\$ 171,000	\$ 171,000	\$ -
543	Fresno	Fresno County Courthouse	D5037 Fire Alarm Systems	\$ 1,202,000	\$ 1,153,000	\$ 49,000
544	Humboldt	Humboldt County Courthouse (Eureka)	D5037 Fire Alarm Systems	\$ 1,257,000	\$ 419,000	\$ 837,000
545	Imperial	Imperial County Courthouse	D5037 Fire Alarm Systems	\$ 368,000	\$ 368,000	\$ -
546	Kern	Bakersfield Superior Court	D5037 Fire Alarm Systems	\$ 1,008,000	\$ 631,000	\$ 376,000
547	Kern	Bakersfield Justice Bldg.	D5037 Fire Alarm Systems	\$ 1,747,000	\$ 892,000	\$ 855,000
548	Kern	Bakersfield Juvenile Center	D5037 Fire Alarm Systems	\$ 706,000	\$ 472,000	\$ 235,000
549	Kern	Delano/North Kern Court	D5037 Fire Alarm Systems	\$ 74,000	\$ 60,000	\$ 14,000
550	Kern	Shafter/Wasco Courts Bldg.	D3040 Distribution Systems	\$ 43,000	\$ 39,000	\$ 4,000
551	Kern	Shafter/Wasco Courts Bldg.	D5037 Fire Alarm Systems	\$ 100,000	\$ 90,000	\$ 10,000
552	Kern	Taft Courts Bldg.	D3040 Distribution Systems	\$ 29,000	\$ 29,000	\$ -
553	Kern	Taft Courts Bldg.	D5037 Fire Alarm Systems	\$ 36,000	\$ 36,000	\$ -
554	Kern	Arvin/ Lamont Branch	D5037 Fire Alarm Systems	\$ 159,000	\$ 97,000	\$ 62,000
555	Kings	Probation Building	D5037 Fire Alarm Systems	\$ 8,000	\$ 1,000	\$ 7,000
556	Los Angeles	San Fernando Courthouse	D5037 Fire Alarm Systems	\$ 1,114,000	\$ 929,000	\$ 185,000
557	Los Angeles	Santa Clarita Courthouse	D5037 Fire Alarm Systems	\$ 80,000	\$ 71,000	\$ 9,000
558	Los Angeles	Alfred J. McCourtney Juvenile Justice	D5037 Fire Alarm Systems	\$ 208,000	\$ 144,000	\$ 64,000
559	Los Angeles	Sylmar Juvenile Court	D5037 Fire Alarm Systems	\$ 17,000	\$ 6,000	\$ 11,000
560	Los Angeles	Compton Courthouse	D5037 Fire Alarm Systems	\$ 2,653,000	\$ 1,754,000	\$ 899,000
561	Los Angeles	Los Padrinos Juvenile Court	D5037 Fire Alarm Systems	\$ 9,000	\$ 3,000	\$ 7,000
562	Los Angeles	Norwalk Courthouse	D5037 Fire Alarm Systems	\$ 1,011,000	\$ 860,000	\$ 151,000
563	Los Angeles	Bellflower Courthouse	D5037 Fire Alarm Systems	\$ 577,000	\$ 450,000	\$ 127,000
564	Los Angeles	Downey Courthouse	D5037 Fire Alarm Systems	\$ 689,000	\$ 577,000	\$ 112,000
565	Los Angeles	Santa Monica Courthouse	D5037 Fire Alarm Systems	\$ 158,000	\$ 124,000	\$ 34,000
566	Los Angeles	Santa Monica Court Annex	D5037 Fire Alarm Systems	\$ 81,000	\$ 81,000	\$ -
567	Los Angeles	Beverly Hills Courthouse	D5037 Fire Alarm Systems	\$ 262,000	\$ 208,000	\$ 54,000
568	Los Angeles	Airport Courthouse	D5037 Fire Alarm Systems	\$ 1,369,000	\$ 1,056,000	\$ 313,000
569	Los Angeles	Hall of Records	D5037 Fire Alarm Systems	\$ 43,000	\$ 5,000	\$ 38,000
570	Los Angeles	Van Nuys Courthouse West	D5037 Fire Alarm Systems	\$ 863,000	\$ 695,000	\$ 168,000
571	Los Angeles	Chatsworth Courthouse	D5037 Fire Alarm Systems	\$ 1,527,000	\$ 1,279,000	\$ 247,000
572	Los Angeles	Michael D. Antonovich Antelope Vall	D5037 Fire Alarm Systems	\$ 2,405,000	\$ 1,768,000	\$ 637,000
573	Los Angeles	Torrance Courthouse	D5037 Fire Alarm Systems	\$ 732,000	\$ 662,000	\$ 70,000
574	Los Angeles	Inglewood Courthouse	D5037 Fire Alarm Systems	\$ 1,000,000	\$ 746,000	\$ 255,000
575	Los Angeles	Burbank Courthouse	D5037 Fire Alarm Systems	\$ 255,000	\$ 232,000	\$ 24,000
576	Los Angeles	Glendale Courthouse	D5037 Fire Alarm Systems	\$ 34,000	\$ 31,000	\$ 3,000
577	Los Angeles	Alhambra Courthouse	D5037 Fire Alarm Systems	\$ 543,000	\$ 467,000	\$ 76,000
578	Los Angeles	Pasadena Courthouse	D5037 Fire Alarm Systems	\$ 843,000	\$ 585,000	\$ 258,000
579	Los Angeles	Stanley Mosk Courthouse	D5037 Fire Alarm Systems	\$ 240,000	\$ 233,000	\$ 7,000
580	Los Angeles	Clara Shortridge Foltz Criminal Justice	D5037 Fire Alarm Systems	\$ 6,053,000	\$ 4,164,000	\$ 1,889,000
581	Los Angeles	Monrovia Training Center	D5037 Fire Alarm Systems	\$ 84,000	\$ 59,000	\$ 25,000
582	Los Angeles	El Monte Courthouse	D5037 Fire Alarm Systems	\$ 584,000	\$ 339,000	\$ 245,000
583	Los Angeles	Edmund D. Edelman Children's Court	D5037 Fire Alarm Systems	\$ 1,188,000	\$ 831,000	\$ 356,000
584	Los Angeles	Eastlake Juvenile Court	D5037 Fire Alarm Systems	\$ 303,000	\$ 166,000	\$ 137,000
585	Los Angeles	Metropolitan Courthouse	D5037 Fire Alarm Systems	\$ 859,000	\$ 812,000	\$ 47,000
586	Los Angeles	Central Arraignment Courts	D5037 Fire Alarm Systems	\$ 332,000	\$ 300,000	\$ 32,000
587	Los Angeles	East Los Angeles Courthouse	D5037 Fire Alarm Systems	\$ 513,000	\$ 399,000	\$ 114,000
588	Los Angeles	Pomona Courthouse South	D5037 Fire Alarm Systems	\$ 1,201,000	\$ 1,095,000	\$ 106,000
589	Los Angeles	West Covina Courthouse	D5037 Fire Alarm Systems	\$ 580,000	\$ 481,000	\$ 98,000
590	Madera	Sierra Courthouse	D5037 Fire Alarm Systems	\$ 21,000	\$ 15,000	\$ 7,000
591	Merced	Old Court	D5037 Fire Alarm Systems	\$ 101,000	\$ 101,000	\$ -
592	Merced	Downtown Merced Courthouse	D5037 Fire Alarm Systems	\$ 331,000	\$ 331,000	\$ -
593	Nevada	Nevada City Courthouse	D5037 Fire Alarm Systems	\$ 145,000	\$ 95,000	\$ 50,000
594	Nevada	Nevada City Courthouse Annex	D5037 Fire Alarm Systems	\$ 234,000	\$ 100,000	\$ 134,000
595	Orange	Central Justice Center	D5037 Fire Alarm Systems	\$ 354,000	\$ 323,000	\$ 31,000
596	Orange	Civil Complex Center ("CXC")	D5037 Fire Alarm Systems	\$ 159,000	\$ 159,000	\$ -
597	Orange	Betty Lou Lamoreaux Justice Center	D5037 Fire Alarm Systems	\$ 1,311,000	\$ 1,049,000	\$ 263,000
598	Orange	North Justice Center	D5037 Fire Alarm Systems	\$ 653,000	\$ 590,000	\$ 63,000
599	Orange	West Justice Center	D5037 Fire Alarm Systems	\$ 597,000	\$ 541,000	\$ 56,000
600	Placer	Historic Courthouse	D5037 Fire Alarm Systems	\$ 201,000	\$ 155,000	\$ 46,000
601	Placer	Bill Santucci Justice Center	D5037 Fire Alarm Systems	\$ 647,000	\$ 647,000	\$ -
602	Sacramento	Gordon Schaber Sacramento Superior	D5037 Fire Alarm Systems	\$ 1,700,000	\$ 1,700,000	\$ -
603	Sacramento	Juvenile Courthouse	D5037 Fire Alarm Systems	\$ 586,000	\$ 586,000	\$ -
604	Sacramento	Carol Miller Justice Center Court Faci	D5037 Fire Alarm Systems	\$ 797,000	\$ 779,000	\$ 18,000
605	San Diego	Hall of Justice	D3040 Distribution Systems	\$ 598,000	\$ 241,000	\$ 358,000

606	San Diego	Hall of Justice	D5037 Fire Alarm Systems	\$ 3,133,000	\$ 1,261,000	\$ 1,872,000
607	San Diego	Kearny Mesa Court	D3040 Distribution Systems	\$ 26,000	\$ 26,000	\$ -
608	San Diego	Kearny Mesa Court	D5037 Fire Alarm Systems	\$ 251,000	\$ 251,000	\$ -
609	San Diego	Juvenile Court	D5037 Fire Alarm Systems	\$ 278,000	\$ 207,000	\$ 70,000
610	San Diego	Department 9 Trailer	D5037 Fire Alarm Systems	\$ 8,000	\$ 8,000	\$ -
611	San Diego	Department 10 Trailer	D5037 Fire Alarm Systems	\$ 8,000	\$ 8,000	\$ -
612	San Diego	North County Regional Center - South	D3040 Distribution Systems	\$ 68,000	\$ 45,000	\$ 22,000
613	San Diego	North County Regional Center - South	D5037 Fire Alarm Systems	\$ 1,126,000	\$ 757,000	\$ 369,000
614	San Diego	North County Regional Center - North	D5037 Fire Alarm Systems	\$ 1,174,000	\$ 1,174,000	\$ -
615	San Diego	North County Regional Center - Annex	D3040 Distribution Systems	\$ 12,000	\$ 12,000	\$ -
616	San Diego	North County Regional Center - Annex	D5037 Fire Alarm Systems	\$ 119,000	\$ 119,000	\$ -
617	San Diego	South County Regional Center	D5037 Fire Alarm Systems	\$ 774,000	\$ 277,000	\$ 497,000
618	San Diego	East County Regional Center	D5037 Fire Alarm Systems	\$ 1,655,000	\$ 1,120,000	\$ 534,000
619	San Mateo	Hall of Justice	D5037 Fire Alarm Systems	\$ 729,000	\$ 384,000	\$ 345,000
620	San Mateo	Traffic/ Small Claims Annex	D5037 Fire Alarm Systems	\$ 56,000	\$ 56,000	\$ -
621	Santa Clara	Hall of Justice (East)	D5037 Fire Alarm Systems	\$ 866,000	\$ 866,000	\$ -
622	Santa Clara	Hall of Justice (West)	D5037 Fire Alarm Systems	\$ 475,000	\$ 475,000	\$ -
623	Santa Clara	Downtown Superior Court	D5037 Fire Alarm Systems	\$ 858,000	\$ 858,000	\$ -
624	Santa Clara	Historic Courthouse	D5037 Fire Alarm Systems	\$ 229,000	\$ 229,000	\$ -
625	Santa Clara	Santa Clara Courthouse	D5037 Fire Alarm Systems	\$ 65,000	\$ 65,000	\$ -
626	Tulare	Visalia Superior Court	D2020-Domestic Water Distribution	\$ 1,165,000	\$ 377,000	\$ 789,000
627	Tulare	Visalia Superior Court	D5037 Fire Alarm Systems	\$ 1,186,000	\$ 383,000	\$ 803,000
628	Ventura	Hall of Justice	D5037 Fire Alarm Systems	\$ 2,194,000	\$ 1,533,000	\$ 661,000
629	Ventura	East County Courthouse	D5037 Fire Alarm Systems	\$ 465,000	\$ 287,000	\$ 178,000
630	Santa Barbara	Santa Maria Courts, Bldg G	D3040 Distribution Systems	\$ 202,000	\$ 195,000	\$ 7,000
631	Santa Barbara	Santa Maria Courts, Bldg G	D5037 Fire Alarm Systems	\$ 254,000	\$ 245,000	\$ 9,000
632	Riverside	Hall of Justice	D5037 Fire Alarm Systems	\$ 1,289,000	\$ 1,289,000	\$ -
633	San Luis Obispo	Courthouse Annex	D5037 Fire Alarm Systems	\$ 641,000	\$ 319,000	\$ 322,000
634	San Bernardino	Joshua Tree Courthouse	D3040 Distribution Systems	\$ 205,000	\$ 69,000	\$ 136,000
635	San Bernardino	Joshua Tree Courthouse	D5037 Fire Alarm Systems	\$ 205,000	\$ 69,000	\$ 136,000
636	San Bernardino	Fontana Courthouse	D3040 Distribution Systems	\$ 54,000	\$ 44,000	\$ 10,000
637	San Bernardino	Fontana Courthouse	D5037 Fire Alarm Systems	\$ 15,000	\$ 12,000	\$ 3,000
638	Riverside	Blythe Courthouse - Superior Court	D3040 Distribution Systems	\$ 14,000	\$ 14,000	\$ -
639	Riverside	Blythe Courthouse - Superior Court	D5037 Fire Alarm Systems	\$ 61,000	\$ 61,000	\$ -
640	Riverside	Larson Justice Center	D5037 Fire Alarm Systems	\$ 1,179,000	\$ 952,000	\$ 226,000
641	Santa Barbara	Santa Maria Juvenile Court (new)	D5037 Fire Alarm Systems	\$ 91,000	\$ 60,000	\$ 31,000
642	San Francisco	Civic Center Courthouse	D3040 Distribution Systems	\$ 1,517,000	\$ 1,517,000	\$ -
643	San Francisco	Civic Center Courthouse	D5037 Fire Alarm Systems	\$ 1,793,000	\$ 1,793,000	\$ -
644	San Francisco	Hall of Justice	D5010 Electrical Service & Distribution	\$ 1,264,000	\$ 294,000	\$ 970,000
645	Riverside	Riverside Juvenile Justice Trailers	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
646	Riverside	Riverside Juvenile Justice Trailers	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
647	San Bernardino	San Bernardino Courthouse	D4020 Standpipes	\$ 407,000	\$ 390,000	\$ 18,000
648	Santa Barbara	Santa Maria Courts Bldgs C + D	D4020 Standpipes	\$ 219,000	\$ 219,000	\$ -
649	Santa Barbara	Santa Maria Courts Bldgs C + D	D4040 Sprinklers & Releasing Devices	\$ 174,000	\$ 174,000	\$ -
650	San Bernardino	Barstow Courthouse	D4010 Sprinklers	\$ 210,000	\$ 164,000	\$ 46,000
651	San Bernardino	Barstow Courthouse	D5010 Electrical Service & Distribution	\$ 226,000	\$ 176,000	\$ 50,000
652	San Luis Obispo	1070 Palm St.	D5010 Electrical Service & Distribution	\$ 14,000	\$ 14,000	\$ -
653	Riverside	Corona	D4040 Sprinklers & Releasing Devices	\$ 115,000	\$ 62,000	\$ 53,000
654	Riverside	Corona	D5010 Electrical Service & Distribution	\$ 425,000	\$ 230,000	\$ 195,000
655	San Bernardino	Rancho Cucamonga Courthouse	D4010 Sprinklers	\$ 1,811,000	\$ 1,377,000	\$ 434,000
656	Riverside	Riverside Juvenile Court	D5010 Electrical Service & Distribution	\$ 488,000	\$ 241,000	\$ 247,000
657	Solano	Solano Justice Building	D4040 Sprinklers & Releasing Devices	\$ 198,000	\$ 151,000	\$ 47,000
658	San Bernardino	Victorville Courthouse-Dept. N-1	D4010 Sprinklers	\$ 11,000	\$ 7,000	\$ 4,000
659	San Bernardino	Victorville Courthouse-Dept. N-1	D4040 Sprinklers & Releasing Devices	\$ 556,000	\$ 357,000	\$ 199,000
660	San Bernardino	Victorville Courthouse-Dept. N-1	D5010 Electrical Service & Distribution	\$ 178,000	\$ 114,000	\$ 64,000
661	San Diego	South County Regional Center	D5010 Electrical Service & Distribution	\$ 2,128,000	\$ 763,000	\$ 1,365,000
662	Imperial	Imperial County Courthouse	D5010 Electrical Service & Distribution	\$ 665,000	\$ 665,000	\$ -
663	Los Angeles	Clara Shortridge Foltz Criminal Justice	D5010 Electrical Service & Distribution	\$ 7,789,000	\$ 5,358,000	\$ 2,431,000
664	Alameda	Wiley W. Manuel Courthouse	D4040 Sprinklers & Releasing Devices	\$ 1,770,000	\$ 1,483,000	\$ 287,000
665	Alameda	Wiley W. Manuel Courthouse	D5010 Electrical Service & Distribution	\$ 1,646,000	\$ 1,379,000	\$ 267,000
666	Alameda	Hayward Hall of Justice	D4010 Sprinklers	\$ 1,057,000	\$ 933,000	\$ 124,000
667	Alameda	Hayward Hall of Justice	D5010 Electrical Service & Distribution	\$ 1,352,000	\$ 1,194,000	\$ 158,000
668	Butte	Butte County Courthouse	D4010 Sprinklers	\$ 167,000	\$ 167,000	\$ -
669	Contra Costa	Wakefield Taylor Courthouse	D4010 Sprinklers	\$ 631,000	\$ 631,000	\$ -
670	Contra Costa	George D. Carroll Courthouse	D4040 Sprinklers & Releasing Devices	\$ 106,000	\$ 80,000	\$ 27,000
671	El Dorado	Cameron Park	D4040 Sprinklers & Releasing Devices	\$ 38,000	\$ 38,000	\$ -
672	El Dorado	Cameron Park	D5010 Electrical Service & Distribution	\$ 51,000	\$ 51,000	\$ -
673	El Dorado	Johnson Bldg.	D4040 Sprinklers & Releasing Devices	\$ 96,000	\$ 96,000	\$ -
674	El Dorado	Johnson Bldg.	D5010 Electrical Service & Distribution	\$ 306,000	\$ 306,000	\$ -
675	Fresno	Fresno County Courthouse	D4010 Sprinklers	\$ 12,000	\$ 11,000	\$ -
676	Humboldt	Humboldt County Courthouse (Eureka)	D4040 Sprinklers & Releasing Devices	\$ 100,000	\$ 33,000	\$ 67,000
677	Imperial	Imperial County Courthouse	D4010 Sprinklers	\$ 431,000	\$ 431,000	\$ -
678	Kern	Bakersfield Superior Court	D4020 Standpipes	\$ 879,000	\$ 550,000	\$ 328,000
679	Kern	Bakersfield Superior Court	D4030 Fire Protection Specialties	\$ 61,000	\$ 38,000	\$ 23,000
680	Kern	Bakersfield Superior Court	D5010 Electrical Service & Distribution	\$ 2,618,000	\$ 1,640,000	\$ 978,000
681	Kern	Bakersfield Justice Bldg.	D4010 Sprinklers	\$ 116,000	\$ 59,000	\$ 57,000

682	Kern	Bakersfield Juvenile Center	D5010 Electrical Service & Distribution	\$ 642,000	\$ 429,000	\$ 213,000
683	Kern	Delano/North Kern Court	D5010 Electrical Service & Distribution	\$ 189,000	\$ 152,000	\$ 37,000
684	Kern	Shafter/Wasco Courts Bldg.	D5010 Electrical Service & Distribution	\$ 216,000	\$ 194,000	\$ 22,000
685	Kern	Taft Courts Bldg.	D5010 Electrical Service & Distribution	\$ 102,000	\$ 102,000	\$ -
686	Kern	Arvin/ Lamont Branch	D5010 Electrical Service & Distribution	\$ 330,000	\$ 201,000	\$ 129,000
687	Los Angeles	San Fernando Courthouse	D4010 Sprinklers	\$ 1,352,000	\$ 1,128,000	\$ 224,000
688	Los Angeles	San Fernando Courthouse	D4030 Fire Protection Specialties	\$ 31,000	\$ 26,000	\$ 5,000
689	Los Angeles	Santa Clarita Courthouse	D4040 Sprinklers & Releasing Devices	\$ 239,000	\$ 212,000	\$ 28,000
690	Los Angeles	Santa Clarita Courthouse	D5010 Electrical Service & Distribution	\$ 180,000	\$ 159,000	\$ 21,000
691	Los Angeles	Alfred J. McCourtney Juvenile Justice Center	D5010 Electrical Service & Distribution	\$ 228,000	\$ 157,000	\$ 70,000
692	Los Angeles	Sylmar Juvenile Court	D4010 Sprinklers	\$ 80,000	\$ 28,000	\$ 53,000
693	Los Angeles	Compton Courthouse	D4010 Sprinklers	\$ 9,000	\$ 6,000	\$ 3,000
694	Los Angeles	Compton Courthouse	D4040 Sprinklers & Releasing Devices	\$ 3,712,000	\$ 2,455,000	\$ 1,257,000
695	Los Angeles	Compton Courthouse	D5010 Electrical Service & Distribution	\$ 3,918,000	\$ 2,591,000	\$ 1,327,000
696	Los Angeles	Los Padrinos Juvenile Court	D4020 Standpipes	\$ 23,000	\$ 7,000	\$ 16,000
697	Los Angeles	Norwalk Courthouse	D4010 Sprinklers	\$ 1,822,000	\$ 1,549,000	\$ 273,000
698	Los Angeles	Norwalk Courthouse	D4040 Sprinklers & Releasing Devices	\$ 325,000	\$ 276,000	\$ 49,000
699	Los Angeles	Norwalk Courthouse	D5010 Electrical Service & Distribution	\$ 1,560,000	\$ 1,326,000	\$ 233,000
700	Los Angeles	Bellflower Courthouse	D4030 Fire Protection Specialties	\$ 7,000	\$ 5,000	\$ 1,000
701	Los Angeles	Bellflower Courthouse	D5010 Electrical Service & Distribution	\$ 1,457,000	\$ 1,136,000	\$ 321,000
702	Los Angeles	Downey Courthouse	D4030 Fire Protection Specialties	\$ 6,000	\$ 5,000	\$ 1,000
703	Los Angeles	Downey Courthouse	D5010 Electrical Service & Distribution	\$ 1,956,000	\$ 1,638,000	\$ 319,000
704	Los Angeles	Santa Monica Courthouse	D4020 Standpipes	\$ 246,000	\$ 193,000	\$ 53,000
705	Los Angeles	Santa Monica Courthouse	D4040 Sprinklers & Releasing Devices	\$ 645,000	\$ 506,000	\$ 139,000
706	Los Angeles	Santa Monica Courthouse	D5010 Electrical Service & Distribution	\$ 815,000	\$ 640,000	\$ 175,000
707	Los Angeles	Beverly Hills Courthouse	D4010 Sprinklers	\$ 783,000	\$ 623,000	\$ 160,000
708	Los Angeles	Beverly Hills Courthouse	D4040 Sprinklers & Releasing Devices	\$ 567,000	\$ 451,000	\$ 116,000
709	Los Angeles	Beverly Hills Courthouse	D5010 Electrical Service & Distribution	\$ 584,000	\$ 464,000	\$ 120,000
710	Los Angeles	Hall of Records	D4010 Sprinklers	\$ 167,000	\$ 18,000	\$ 149,000
711	Los Angeles	Hall of Records	D4020 Standpipes	\$ 99,000	\$ 11,000	\$ 89,000
712	Los Angeles	Hall of Records	D4030 Fire Protection Specialties	\$ 109,000	\$ 11,000	\$ 97,000
713	Los Angeles	Van Nuys Courthouse East	D4010 Sprinklers	\$ 578,000	\$ 519,000	\$ 59,000
714	Los Angeles	Van Nuys Courthouse East	D4020 Standpipes	\$ 579,000	\$ 520,000	\$ 59,000
715	Los Angeles	Van Nuys Courthouse East	D4030 Fire Protection Specialties	\$ 8,000	\$ 7,000	\$ 1,000
716	Los Angeles	Van Nuys Courthouse East	D4040 Sprinklers & Releasing Devices	\$ 140,000	\$ 126,000	\$ 14,000
717	Los Angeles	Van Nuys Courthouse West	D4030 Fire Protection Specialties	\$ 170,000	\$ 137,000	\$ 33,000
718	Los Angeles	Torrance Courthouse	D4010 Sprinklers	\$ 463,000	\$ 419,000	\$ 44,000
719	Los Angeles	Torrance Courthouse	D4020 Standpipes	\$ 56,000	\$ 50,000	\$ 5,000
720	Los Angeles	Torrance Courthouse	D4040 Sprinklers & Releasing Devices	\$ 263,000	\$ 238,000	\$ 25,000
721	Los Angeles	Inglewood Juvenile Court	D5010 Electrical Service & Distribution	\$ 133,000	\$ 107,000	\$ 26,000
722	Los Angeles	Inglewood Courthouse	D40 Fire Protection	\$ 335,000	\$ 250,000	\$ 85,000
723	Los Angeles	Inglewood Courthouse	D4040 Sprinklers & Releasing Devices	\$ 1,354,000	\$ 1,009,000	\$ 344,000
724	Los Angeles	Inglewood Courthouse	D5010 Electrical Service & Distribution	\$ 2,569,000	\$ 1,915,000	\$ 653,000
725	Los Angeles	Burbank Courthouse	D4010 Sprinklers	\$ 44,000	\$ 40,000	\$ 4,000
726	Los Angeles	Burbank Courthouse	D5010 Electrical Service & Distribution	\$ 117,000	\$ 106,000	\$ 11,000
727	Los Angeles	Glendale Courthouse	D4010 Sprinklers	\$ 205,000	\$ 185,000	\$ 19,000
728	Los Angeles	Glendale Courthouse	D4020 Standpipes	\$ 190,000	\$ 172,000	\$ 18,000
729	Los Angeles	Glendale Courthouse	D4040 Sprinklers & Releasing Devices	\$ 112,000	\$ 101,000	\$ 11,000
730	Los Angeles	Alhambra Courthouse	D4010 Sprinklers	\$ 829,000	\$ 713,000	\$ 116,000
731	Los Angeles	Alhambra Courthouse	D5010 Electrical Service & Distribution	\$ 1,225,000	\$ 1,053,000	\$ 171,000
732	Los Angeles	Pasadena Courthouse	D4010 Sprinklers	\$ 772,000	\$ 535,000	\$ 237,000
733	Los Angeles	Pasadena Courthouse	D4020 Standpipes	\$ 73,000	\$ 51,000	\$ 22,000
734	Los Angeles	Stanley Mosk Courthouse	D4010 Sprinklers	\$ 123,000	\$ 120,000	\$ 3,000
735	Los Angeles	Stanley Mosk Courthouse	D4020 Standpipes	\$ 2,549,000	\$ 2,479,000	\$ 70,000
736	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	D4010 Sprinklers	\$ 7,887,000	\$ 5,425,000	\$ 2,461,000
737	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	D4040 Sprinklers & Releasing Devices	\$ 2,756,000	\$ 1,896,000	\$ 860,000
738	Los Angeles	Monrovia Training Center	D4020 Standpipes	\$ 14,000	\$ 10,000	\$ 4,000
739	Los Angeles	El Monte Courthouse	D4020 Standpipes	\$ 54,000	\$ 31,000	\$ 23,000
740	Los Angeles	El Monte Courthouse	D4040 Sprinklers & Releasing Devices	\$ 978,000	\$ 568,000	\$ 410,000
741	Los Angeles	Edmund D. Edelman Children's Court	D4010 Sprinklers	\$ 6,000	\$ 4,000	\$ 2,000
742	Los Angeles	Eastlake Juvenile Court	D4020 Standpipes	\$ 39,000	\$ 21,000	\$ 17,000
743	Los Angeles	Metropolitan Courthouse	D4040 Sprinklers & Releasing Devices	\$ 395,000	\$ 373,000	\$ 22,000
744	Los Angeles	Metropolitan Courthouse	D5010 Electrical Service & Distribution	\$ 2,123,000	\$ 2,007,000	\$ 116,000
745	Los Angeles	Central Arraignment Courts	D4010 Sprinklers	\$ 216,000	\$ 195,000	\$ 21,000
746	Los Angeles	Central Arraignment Courts	D5010 Electrical Service & Distribution	\$ 1,022,000	\$ 922,000	\$ 100,000
747	Los Angeles	East Los Angeles Courthouse	D4030 Fire Protection Specialties	\$ 18,000	\$ 14,000	\$ 4,000
748	Los Angeles	East Los Angeles Courthouse	D5010 Electrical Service & Distribution	\$ 1,097,000	\$ 852,000	\$ 244,000
749	Los Angeles	Pomona Courthouse South	D4020 Standpipes	\$ 658,000	\$ 600,000	\$ 58,000
750	Los Angeles	Pomona Courthouse South	D4040 Sprinklers & Releasing Devices	\$ 191,000	\$ 174,000	\$ 17,000
751	Los Angeles	Pomona Courthouse South	D5010 Electrical Service & Distribution	\$ 1,484,000	\$ 1,353,000	\$ 131,000
752	Los Angeles	West Covina Courthouse	D4020 Standpipes	\$ 405,000	\$ 336,000	\$ 69,000
753	Los Angeles	West Covina Courthouse	D4040 Sprinklers & Releasing Devices	\$ 367,000	\$ 305,000	\$ 62,000
754	Los Angeles	West Covina Courthouse	D5010 Electrical Service & Distribution	\$ 1,432,000	\$ 1,189,000	\$ 243,000
755	Merced	Old Court	D5010 Electrical Service & Distribution	\$ 239,000	\$ 239,000	\$ -
756	Orange	Central Justice Center Annex	D5010 Electrical Service & Distribution	\$ 22,000	\$ 2,000	\$ 21,000
757	Orange	Civil Complex Center ("CXC")	D5010 Electrical Service & Distribution	\$ 341,000	\$ 341,000	\$ -

758	Orange	North Justice Center	D4010 Sprinklers	\$ 17,000	\$ 15,000	\$ 2,000
759	Orange	North Justice Center	D4020 Standpipes	\$ 85,000	\$ 77,000	\$ 8,000
760	Orange	North Justice Center	D4040 Sprinklers & Releasing Devices	\$ 40,000	\$ 36,000	\$ 4,000
761	Orange	West Justice Center	D4040 Sprinklers & Releasing Devices	\$ 696,000	\$ 631,000	\$ 65,000
762	Orange	West Justice Center	D5010 Electrical Service & Distribution	\$ 641,000	\$ 581,000	\$ 60,000
763	Placer	Bill Santucci Justice Center	D4010 Sprinklers	\$ 44,000	\$ 44,000	\$ -
764	Placer	Bill Santucci Justice Center	D4040 Sprinklers & Releasing Devices	\$ 62,000	\$ 62,000	\$ -
765	Sacramento	Gordon Schaber Sacramento Superio	D4010 Sprinklers	\$ 1,984,000	\$ 1,984,000	\$ -
766	Sacramento	Gordon Schaber Sacramento Superio	D4020 Standpipes	\$ 2,344,000	\$ 2,344,000	\$ -
767	Sacramento	Gordon Schaber Sacramento Superio	D4030 Fire Protection Specialties	\$ 7,000	\$ 7,000	\$ -
768	Sacramento	Gordon Schaber Sacramento Superio	D4040 Sprinklers & Releasing Devices	\$ 498,000	\$ 498,000	\$ -
769	San Diego	Hall of Justice	D4030 Fire Protection Specialties	\$ 41,000	\$ 16,000	\$ 24,000
770	San Diego	Kearny Mesa Court	D4040 Sprinklers & Releasing Devices	\$ 279,000	\$ 279,000	\$ -
771	San Diego	Kearny Mesa Court	D5010 Electrical Service & Distribution	\$ 627,000	\$ 627,000	\$ -
772	San Diego	Kearny Mesa Traffic Court KM3 Trail	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
773	San Diego	Kearny Mesa Traffic Court KM4 Trail	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
774	San Diego	Kearny Mesa Traffic Court KM5 & KM	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
775	San Diego	Juvenile Court	D4010 Sprinklers	\$ 292,000	\$ 218,000	\$ 74,000
776	San Diego	Juvenile Court	D5010 Electrical Service & Distribution	\$ 594,000	\$ 443,000	\$ 151,000
777	San Diego	Department 9 Trailer	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
778	San Diego	Department 10 Trailer	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
779	San Diego	North County Regional Center - Sout	D4010 Sprinklers	\$ 9,000	\$ 6,000	\$ 3,000
780	San Diego	North County Regional Center - Sout	D4030 Fire Protection Specialties	\$ 15,000	\$ 10,000	\$ 5,000
781	San Diego	North County Regional Center - Nort	D4040 Sprinklers & Releasing Devices	\$ 166,000	\$ 166,000	\$ -
782	San Diego	Trailer - Dept 34	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
783	San Diego	Trailer - Dept 35	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
784	San Diego	Trailer - Storage A	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
785	San Diego	Trailer - Family Support	D5010 Electrical Service & Distribution	\$ 9,000	\$ 9,000	\$ -
786	San Diego	South County Regional Center	D4030 Fire Protection Specialties	\$ 55,000	\$ 20,000	\$ 35,000
787	San Diego	South County Regional Center	D4040 Sprinklers & Releasing Devices	\$ 845,000	\$ 303,000	\$ 542,000
788	San Diego	East County Regional Center	D4010 Sprinklers	\$ 8,000	\$ 6,000	\$ 3,000
789	San Diego	East County Regional Center	D4040 Sprinklers & Releasing Devices	\$ 2,439,000	\$ 1,652,000	\$ 788,000
790	San Diego	East County Regional Center	D5010 Electrical Service & Distribution	\$ 3,338,000	\$ 2,260,000	\$ 1,078,000
791	San Mateo	Northern Branch Courthouse	D4040 Sprinklers & Releasing Devices	\$ 60,000	\$ 50,000	\$ 10,000
792	Santa Clara	Hall of Justice (West)	D4010 Sprinklers	\$ 381,000	\$ 381,000	\$ -
793	Santa Clara	Hall of Justice (West)	D4040 Sprinklers & Releasing Devices	\$ 109,000	\$ 109,000	\$ -
794	Santa Clara	Downtown Superior Court	D4010 Sprinklers	\$ 511,000	\$ 511,000	\$ -
795	Santa Clara	Downtown Superior Court	D4020 Standpipes	\$ 358,000	\$ 358,000	\$ -
796	Santa Clara	Downtown Superior Court	D4040 Sprinklers & Releasing Devices	\$ 146,000	\$ 146,000	\$ -
797	Tulare	Visalia Superior Court	D4010 Sprinklers	\$ 455,000	\$ 147,000	\$ 308,000
798	Tulare	Visalia Superior Court	D4020 Standpipes	\$ 258,000	\$ 83,000	\$ 174,000
799	Tulare	Visalia Superior Court	D4040 Sprinklers & Releasing Devices	\$ 149,000	\$ 48,000	\$ 101,000
800	Ventura	Hall of Justice	D4040 Sprinklers & Releasing Devices	\$ 228,000	\$ 159,000	\$ 69,000
801	San Luis Obispo	Courthouse Annex	D5010 Electrical Service & Distribution	\$ 901,000	\$ 448,000	\$ 453,000
802	San Bernardino	Joshua Tree Courthouse	D4010 Sprinklers	\$ 215,000	\$ 73,000	\$ 143,000
803	San Bernardino	Joshua Tree Courthouse	D5010 Electrical Service & Distribution	\$ 322,000	\$ 109,000	\$ 213,000
804	San Bernardino	Fontana Courthouse	D5010 Electrical Service & Distribution	\$ 340,000	\$ 280,000	\$ 61,000
805	Solano	Law and Justice Center	D4031 Fire Extinguishers	\$ 13,000	\$ 2,000	\$ 11,000
806	San Bernardino	Rancho Cucamonga Courthouse	D4031 Fire Extinguishers	\$ 12,000	\$ 9,000	\$ 3,000
807	Alameda	Wiley W. Manuel Courthouse	D4031 Fire Extinguishers	\$ 25,000	\$ 21,000	\$ 4,000
808	Los Angeles	San Fernando Courthouse	D4031 Fire Extinguishers	\$ 9,000	\$ 7,000	\$ 1,000
809	Los Angeles	Alfred J. McCourtney Juvenile Justice	D4031 Fire Extinguishers	\$ 32,000	\$ 22,000	\$ 10,000
810	Los Angeles	Compton Courthouse	D4031 Fire Extinguishers	\$ 17,000	\$ 11,000	\$ 6,000
811	Los Angeles	Norwalk Courthouse	D4031 Fire Extinguishers	\$ 158,000	\$ 135,000	\$ 24,000
812	Los Angeles	Torrance Courthouse	D4031 Fire Extinguishers	\$ 11,000	\$ 10,000	\$ 1,000
813	Los Angeles	Alhambra Courthouse	D4031 Fire Extinguishers	\$ 83,000	\$ 72,000	\$ 12,000
814	Los Angeles	Pasadena Courthouse	D4031 Fire Extinguishers	\$ 30,000	\$ 21,000	\$ 9,000
815	Los Angeles	Stanley Mosk Courthouse	D4031 Fire Extinguishers	\$ 4,097,000	\$ 3,985,000	\$ 112,000
816	Los Angeles	Clara Shortridge Foltz Criminal Justice	D4031 Fire Extinguishers	\$ 776,000	\$ 534,000	\$ 242,000
817	Los Angeles	Central Arraignment Courts	D4031 Fire Extinguishers	\$ 52,000	\$ 46,000	\$ 5,000
818	Los Angeles	East Los Angeles Courthouse	D4031 Fire Extinguishers	\$ 10,000	\$ 8,000	\$ 2,000
819	Orange	North Justice Center	D4031 Fire Extinguishers	\$ 11,000	\$ 10,000	\$ 1,000
820	Sacramento	Gordon Schaber Sacramento Superio	D4031 Fire Extinguishers	\$ 12,000	\$ 12,000	\$ -
821	San Diego	North County Regional Center - Nort	D4031 Fire Extinguishers	\$ 8,000	\$ 8,000	\$ -
822	San Diego	East County Regional Center	D4031 Fire Extinguishers	\$ 11,000	\$ 8,000	\$ 4,000
823	Santa Clara	Hall of Justice (West)	D4031 Fire Extinguishers	\$ 60,000	\$ 60,000	\$ -
824	San Bernardino	San Bernardino Courthouse	D2020-Domestic Water Distribution	\$ 1,171,000	\$ 1,120,000	\$ 51,000
825	Santa Barbara	Santa Maria Courts, Bldg F	D2020-Domestic Water Distribution	\$ 34,000	\$ 34,000	\$ -
826	San Luis Obispo	1070 Palm St.	D2020-Domestic Water Distribution	\$ 13,000	\$ 13,000	\$ -
827	Solano	Hall of Justice	D2020-Domestic Water Distribution	\$ 516,000	\$ 376,000	\$ 140,000
828	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D2020-Domestic Water Distribution	\$ 59,000	\$ 14,000	\$ 46,000
829	Alameda	Hayward Hall of Justice	D2020-Domestic Water Distribution	\$ 628,000	\$ 554,000	\$ 73,000
830	Imperial	Imperial County Courthouse	D2020-Domestic Water Distribution	\$ 448,000	\$ 448,000	\$ -
831	Los Angeles	Alfred J. McCourtney Juvenile Justice	D2020-Domestic Water Distribution	\$ 486,000	\$ 336,000	\$ 150,000
832	Los Angeles	Los Padrinos Juvenile Court	D2020-Domestic Water Distribution	\$ 35,000	\$ 10,000	\$ 25,000
833	Los Angeles	Hall of Records	D2020-Domestic Water Distribution	\$ 153,000	\$ 16,000	\$ 137,000

834	Los Angeles	Inglewood Juvenile Court	D2020-Domestic Water Distribution	\$ 122,000	\$ 99,000	\$ 24,000
835	Los Angeles	Eastlake Juvenile Court	D2020-Domestic Water Distribution	\$ 317,000	\$ 174,000	\$ 143,000
836	Los Angeles	Pomona Courthouse South	D2020-Domestic Water Distribution	\$ 1,318,000	\$ 1,201,000	\$ 117,000
837	San Diego	Kearny Mesa Court	D2020-Domestic Water Distribution	\$ 234,000	\$ 234,000	\$ -
838	San Diego	North County Regional Center - North	D5010 Electrical Service & Distribution	\$ 3,642,000	\$ 3,642,000	\$ -
839	Los Angeles	Pasadena Courthouse	D2020-Domestic Water Distribution	\$ 1,254,000	\$ 870,000	\$ 384,000
840	Los Angeles	Metropolitan Courthouse	D2020-Domestic Water Distribution	\$ 666,000	\$ 630,000	\$ 36,000
841	San Luis Obispo	Courthouse Annex	D2020-Domestic Water Distribution	\$ 592,000	\$ 294,000	\$ 297,000
842	Alameda	Wiley W. Manuel Courthouse	D2020-Domestic Water Distribution	\$ 632,000	\$ 530,000	\$ 102,000
843	Los Angeles	Beverly Hills Courthouse	D2020-Domestic Water Distribution	\$ 681,000	\$ 542,000	\$ 139,000
844	Los Angeles	Airport Courthouse	D2020-Domestic Water Distribution	\$ 88,000	\$ 68,000	\$ 20,000
845	Los Angeles	Van Nuys Courthouse West	D2020-Domestic Water Distribution	\$ 778,000	\$ 626,000	\$ 152,000
846	Los Angeles	Edmund D. Edelman Children's Court	D2020-Domestic Water Distribution	\$ 49,000	\$ 34,000	\$ 15,000
847	Solano	Solano Justice Building	D5010 Electrical Service & Distribution	\$ 747,000	\$ 568,000	\$ 178,000
848	Ventura	Hall of Justice	D5010 Electrical Service & Distribution	\$ 5,498,000	\$ 3,841,000	\$ 1,657,000
849	Santa Barbara	Santa Maria Courts Bldgs C + D	D2020-Domestic Water Distribution	\$ 642,000	\$ 642,000	\$ -
850	Tulare	Visalia Superior Court	D5010 Electrical Service & Distribution	\$ 4,675,000	\$ 1,512,000	\$ 3,164,000
851	Solano	Hall of Justice	D5010 Electrical Service & Distribution	\$ 1,333,000	\$ 970,000	\$ 362,000
852	Kern	Bakersfield Justice Bldg.	D5010 Electrical Service & Distribution	\$ 2,725,000	\$ 1,392,000	\$ 1,333,000
853	Los Angeles	Van Nuys Courthouse West	D5010 Electrical Service & Distribution	\$ 1,833,000	\$ 1,475,000	\$ 358,000
854	Orange	Central Justice Center	D2020-Domestic Water Distribution	\$ 7,505,000	\$ 6,842,000	\$ 663,000
855	Los Angeles	Stanley Mosk Courthouse	D5010 Electrical Service & Distribution	\$ 5,975,000	\$ 5,811,000	\$ 164,000
856	Los Angeles	Santa Monica Courthouse	D2020-Domestic Water Distribution	\$ 657,000	\$ 516,000	\$ 141,000
857	Los Angeles	Van Nuys Courthouse East	D2020-Domestic Water Distribution	\$ 584,000	\$ 524,000	\$ 60,000
858	Los Angeles	Burbank Courthouse	D2020-Domestic Water Distribution	\$ 352,000	\$ 320,000	\$ 33,000
859	Los Angeles	Monrovia Training Center	D2020-Domestic Water Distribution	\$ 132,000	\$ 93,000	\$ 39,000
860	Los Angeles	West Covina Courthouse	D2020-Domestic Water Distribution	\$ 815,000	\$ 677,000	\$ 138,000
861	Orange	West Justice Center	D2020-Domestic Water Distribution	\$ 529,000	\$ 480,000	\$ 49,000
862	Los Angeles	Los Padrinos Juvenile Court	D5010 Electrical Service & Distribution	\$ 163,000	\$ 48,000	\$ 115,000
863	Los Angeles	Glendale Courthouse	D2020-Domestic Water Distribution	\$ 318,000	\$ 288,000	\$ 30,000
864	San Bernardino	San Bernardino Courthouse	D5010 Electrical Service & Distribution	\$ 1,101,000	\$ 1,053,000	\$ 48,000
865	Los Angeles	Sylmar Juvenile Court	D5010 Electrical Service & Distribution	\$ 86,000	\$ 29,000	\$ 56,000
866	Los Angeles	Monrovia Training Center	D5010 Electrical Service & Distribution	\$ 216,000	\$ 152,000	\$ 64,000
867	Los Angeles	El Monte Courthouse	D5010 Electrical Service & Distribution	\$ 1,226,000	\$ 713,000	\$ 513,000
868	Los Angeles	Glendale Courthouse	D5010 Electrical Service & Distribution	\$ 225,000	\$ 203,000	\$ 21,000
869	Los Angeles	Hall of Records	D5010 Electrical Service & Distribution	\$ 97,000	\$ 10,000	\$ 86,000
870	Orange	Central Justice Center	D5010 Electrical Service & Distribution	\$ 1,869,000	\$ 1,704,000	\$ 165,000
871	Los Angeles	Torrance Courthouse	D2020-Domestic Water Distribution	\$ 978,000	\$ 885,000	\$ 94,000
872	Los Angeles	Van Nuys Courthouse East	D5010 Electrical Service & Distribution	\$ 1,095,000	\$ 983,000	\$ 112,000
873	Los Angeles	Torrance Courthouse	D5010 Electrical Service & Distribution	\$ 992,000	\$ 897,000	\$ 95,000
874	Los Angeles	Pasadena Courthouse	D5010 Electrical Service & Distribution	\$ 2,522,000	\$ 1,749,000	\$ 773,000
875	Orange	North Justice Center	D5010 Electrical Service & Distribution	\$ 1,128,000	\$ 1,019,000	\$ 109,000
876	San Francisco	Hall of Justice	D2010 Plumbing Fixtures	\$ 411,000	\$ 96,000	\$ 315,000
877	San Francisco	Hall of Justice	D5092 Emergency Light & Power Systems	\$ 253,000	\$ 59,000	\$ 194,000
878	San Bernardino	San Bernardino Courthouse	D5092 Emergency Light & Power Systems	\$ 275,000	\$ 263,000	\$ 12,000
879	Solano	Law and Justice Center	D5092 Emergency Light & Power Systems	\$ 928,000	\$ 118,000	\$ 811,000
880	Santa Barbara	Santa Maria Courts Bldgs C + D	D2090 Other Plumbing Systems	\$ 77,000	\$ 77,000	\$ -
881	Santa Barbara	Santa Maria Courts Bldgs C + D	D5092 Emergency Light & Power Systems	\$ 167,000	\$ 167,000	\$ -
882	San Bernardino	Barstow Courthouse	D2010 Plumbing Fixtures	\$ 117,000	\$ 92,000	\$ 26,000
883	San Bernardino	Barstow Courthouse	D5092 Emergency Light & Power Systems	\$ 88,000	\$ 69,000	\$ 19,000
884	San Luis Obispo	1070 Palm St.	D2010 Plumbing Fixtures	\$ 13,000	\$ 13,000	\$ -
885	Riverside	Corona	D2010 Plumbing Fixtures	\$ 210,000	\$ 113,000	\$ 96,000
886	Riverside	Corona	D5092 Emergency Light & Power Systems	\$ 126,000	\$ 68,000	\$ 58,000
887	Solano	Hall of Justice	D5092 Emergency Light & Power Systems	\$ 358,000	\$ 260,000	\$ 97,000
888	San Bernardino	Rancho Cucamonga Courthouse	D2090 Other Plumbing Systems	\$ 54,000	\$ 41,000	\$ 13,000
889	San Bernardino	Rancho Cucamonga Courthouse	D5092 Emergency Light & Power Systems	\$ 480,000	\$ 365,000	\$ 115,000
890	Riverside	Riverside Juvenile Court	D2010 Plumbing Fixtures	\$ 304,000	\$ 150,000	\$ 154,000
891	Riverside	Riverside Juvenile Court	D5092 Emergency Light & Power Systems	\$ 45,000	\$ 22,000	\$ 23,000
892	Solano	Solano Justice Building	D5092 Emergency Light & Power Systems	\$ 143,000	\$ 109,000	\$ 34,000
893	San Bernardino	Victorville Courthouse-Dept. N-1	D2010 Plumbing Fixtures	\$ 76,000	\$ 49,000	\$ 27,000
894	San Bernardino	Victorville Courthouse-Dept. N-1	D5092 Emergency Light & Power Systems	\$ 131,000	\$ 84,000	\$ 47,000
895	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D5092 Emergency Light & Power Systems	\$ 11,000	\$ 2,000	\$ 8,000
896	Alameda	Wiley W. Manuel Courthouse	D2010 Plumbing Fixtures	\$ 1,121,000	\$ 940,000	\$ 182,000
897	Alameda	Hayward Hall of Justice	D5092 Emergency Light & Power Systems	\$ 633,000	\$ 559,000	\$ 74,000
898	Alameda	Fremont Hall of Justice	D2010 Plumbing Fixtures	\$ 669,000	\$ 531,000	\$ 138,000
899	Contra Costa	George D. Carroll Courthouse	D2010 Plumbing Fixtures	\$ 1,075,000	\$ 806,000	\$ 269,000
900	Humboldt	Humboldt County Courthouse (Eureka)	D2010 Plumbing Fixtures	\$ 1,491,000	\$ 498,000	\$ 994,000
901	Imperial	Imperial County Courthouse	D2010 Plumbing Fixtures	\$ 258,000	\$ 258,000	\$ -
902	Kern	Bakersfield Justice Bldg.	D2010 Plumbing Fixtures	\$ 434,000	\$ 222,000	\$ 212,000
903	Kern	Delano/North Kern Court	D2010 Plumbing Fixtures	\$ 69,000	\$ 56,000	\$ 13,000
904	Kern	Taft Courts Bldg.	D2010 Plumbing Fixtures	\$ 55,000	\$ 55,000	\$ -
905	Los Angeles	Compton Courthouse	D2010 Plumbing Fixtures	\$ 2,960,000	\$ 1,958,000	\$ 1,003,000
906	Los Angeles	Compton Courthouse	D5092 Emergency Light & Power Systems	\$ 1,085,000	\$ 718,000	\$ 368,000
907	Los Angeles	Bellflower Courthouse	D2010 Plumbing Fixtures	\$ 302,000	\$ 235,000	\$ 67,000
908	Los Angeles	Van Nuys Courthouse East	D5092 Emergency Light & Power Systems	\$ 227,000	\$ 204,000	\$ 23,000
909	Los Angeles	Van Nuys Courthouse West	D5092 Emergency Light & Power Systems	\$ 704,000	\$ 566,000	\$ 137,000

910	Los Angeles	Chatsworth Courthouse	D5092 Emergency Light & Power Systems	\$ 445,000	\$ 373,000	\$ 72,000
911	Los Angeles	Inglewood Juvenile Court	D2010 Plumbing Fixtures	\$ 114,000	\$ 92,000	\$ 22,000
912	Los Angeles	Inglewood Courthouse	D2010 Plumbing Fixtures	\$ 607,000	\$ 452,000	\$ 154,000
913	Los Angeles	Glendale Courthouse	D5092 Emergency Light & Power Systems	\$ 45,000	\$ 41,000	\$ 4,000
914	Los Angeles	Monrovia Training Center	D2010 Plumbing Fixtures	\$ 79,000	\$ 56,000	\$ 24,000
915	Los Angeles	Edmund D. Edelman Children's Court	D2010 Plumbing Fixtures	\$ 359,000	\$ 251,000	\$ 108,000
916	Los Angeles	Eastlake Juvenile Court	D2010 Plumbing Fixtures	\$ 252,000	\$ 138,000	\$ 114,000
917	Los Angeles	Pomona Courthouse South	D2010 Plumbing Fixtures	\$ 871,000	\$ 794,000	\$ 77,000
918	Los Angeles	West Covina Courthouse	D2010 Plumbing Fixtures	\$ 442,000	\$ 367,000	\$ 75,000
919	Nevada	Nevada City Courthouse	D2010 Plumbing Fixtures	\$ 414,000	\$ 271,000	\$ 143,000
920	Orange	West Justice Center	D5092 Emergency Light & Power Systems	\$ 255,000	\$ 232,000	\$ 24,000
921	Sacramento	Gordon Schaber Sacramento Superior	D2010 Plumbing Fixtures	\$ 7,954,000	\$ 7,954,000	\$ -
922	San Diego	Juvenile Court	D2010 Plumbing Fixtures	\$ 598,000	\$ 446,000	\$ 152,000
923	San Diego	South County Regional Center	D2010 Plumbing Fixtures	\$ 479,000	\$ 172,000	\$ 307,000
924	San Diego	East County Regional Center	D2010 Plumbing Fixtures	\$ 868,000	\$ 588,000	\$ 280,000
925	San Mateo	Central Branch	D2010 Plumbing Fixtures	\$ 218,000	\$ 218,000	\$ -
926	San Mateo	Northern Branch Courthouse	D2010 Plumbing Fixtures	\$ 509,000	\$ 423,000	\$ 85,000
927	Santa Clara	Hall of Justice (West)	D2010 Plumbing Fixtures	\$ 1,062,000	\$ 1,062,000	\$ -
928	Santa Clara	Downtown Superior Court	D2010 Plumbing Fixtures	\$ 982,000	\$ 982,000	\$ -
929	Santa Clara	Historic Courthouse	D2010 Plumbing Fixtures	\$ 329,000	\$ 329,000	\$ -
930	Tulare	Visalia Superior Court	D2010 Plumbing Fixtures	\$ 1,237,000	\$ 400,000	\$ 837,000
931	Alameda	Wiley W. Manuel Courthouse	D5092 Emergency Light & Power Systems	\$ 890,000	\$ 746,000	\$ 144,000
932	Alameda	Hayward Hall of Justice	D20 Plumbing	\$ 8,000	\$ 7,000	\$ 1,000
933	Alameda	George E. McDonald Hall of Justice	D2010 Plumbing Fixtures	\$ 194,000	\$ 194,000	\$ -
934	Alameda	George E. McDonald Hall of Justice	D5092 Emergency Light & Power Systems	\$ 92,000	\$ 92,000	\$ -
935	Alameda	Berkeley Courthouse	D2010 Plumbing Fixtures	\$ 7,000	\$ 7,000	\$ -
936	Alameda	Berkeley Courthouse	D5092 Emergency Light & Power Systems	\$ 31,000	\$ 31,000	\$ -
937	Alameda	Fremont Hall of Justice	D5092 Emergency Light & Power Systems	\$ 1,082,000	\$ 859,000	\$ 223,000
938	Amador	Amador County Courthouse	D2010 Plumbing Fixtures	\$ 6,000	\$ 6,000	\$ -
939	Amador	Amador County Courthouse	D5092 Emergency Light & Power Systems	\$ 24,000	\$ 24,000	\$ -
940	Butte	Butte County Courthouse	D2010 Plumbing Fixtures	\$ 34,000	\$ 34,000	\$ -
941	Butte	Butte County Courthouse	D5092 Emergency Light & Power Systems	\$ 115,000	\$ 115,000	\$ -
942	Contra Costa	Family Law Center	D5092 Emergency Light & Power Systems	\$ 99,000	\$ 99,000	\$ -
943	Contra Costa	Wakefield Taylor Courthouse	D2010 Plumbing Fixtures	\$ 871,000	\$ 871,000	\$ -
944	Contra Costa	Wakefield Taylor Courthouse	D5092 Emergency Light & Power Systems	\$ 213,000	\$ 213,000	\$ -
945	Contra Costa	Bray Courts	D5092 Emergency Light & Power Systems	\$ 378,000	\$ 323,000	\$ 55,000
946	Contra Costa	Jail Annex	D2010 Plumbing Fixtures	\$ 102,000	\$ 6,000	\$ 96,000
947	Contra Costa	Jail Annex	D5092 Emergency Light & Power Systems	\$ 20,000	\$ 1,000	\$ 19,000
948	Contra Costa	Danville District Courthouse	D2010 Plumbing Fixtures	\$ 252,000	\$ 252,000	\$ -
949	Contra Costa	Danville District Courthouse	D5092 Emergency Light & Power Systems	\$ 53,000	\$ 53,000	\$ -
950	Contra Costa	George D. Carroll Courthouse	D5092 Emergency Light & Power Systems	\$ 625,000	\$ 469,000	\$ 156,000
951	Del Norte	Del Norte County Superior Court	D5092 Emergency Light & Power Systems	\$ 211,000	\$ 130,000	\$ 82,000
952	El Dorado	Cameron Park	D2010 Plumbing Fixtures	\$ 45,000	\$ 45,000	\$ -
953	El Dorado	Cameron Park	D5092 Emergency Light & Power Systems	\$ 12,000	\$ 12,000	\$ -
954	El Dorado	Johnson Bldg.	D5092 Emergency Light & Power Systems	\$ 69,000	\$ 69,000	\$ -
955	Fresno	Fresno County Courthouse	D2090 Other Plumbing Systems	\$ 7,000	\$ 6,000	\$ -
956	Fresno	Fresno County Courthouse	D5092 Emergency Light & Power Systems	\$ 408,000	\$ 391,000	\$ 17,000
957	Fresno	B.F. Sisk Federal Courthouse	D2010 Plumbing Fixtures	\$ 33,000	\$ 33,000	\$ -
958	Fresno	B.F. Sisk Federal Courthouse	D5092 Emergency Light & Power Systems	\$ 1,200,000	\$ 1,200,000	\$ -
959	Humboldt	Humboldt County Courthouse (Eureka)	D5092 Emergency Light & Power Systems	\$ 471,000	\$ 157,000	\$ 314,000
960	Imperial	Imperial County Courthouse	D5092 Emergency Light & Power Systems	\$ 147,000	\$ 147,000	\$ -
961	Kern	Bakersfield Superior Court	D2010 Plumbing Fixtures	\$ 524,000	\$ 328,000	\$ 196,000
962	Kern	Bakersfield Superior Court	D2020-Domestic Water Distribution	\$ 699,000	\$ 438,000	\$ 261,000
963	Kern	Bakersfield Superior Court	D2090 Other Plumbing Systems	\$ 686,000	\$ 430,000	\$ 256,000
964	Kern	Bakersfield Superior Court	D5092 Emergency Light & Power Systems	\$ 375,000	\$ 235,000	\$ 140,000
965	Kern	Bakersfield Justice Bldg.	D5092 Emergency Light & Power Systems	\$ 782,000	\$ 399,000	\$ 382,000
966	Kern	Bakersfield Juvenile Center	D5092 Emergency Light & Power Systems	\$ 215,000	\$ 144,000	\$ 72,000
967	Kern	Delano/North Kern Court	D5092 Emergency Light & Power Systems	\$ 38,000	\$ 31,000	\$ 7,000
968	Kern	Shafter/Wasco Courts Bldg.	D5092 Emergency Light & Power Systems	\$ 85,000	\$ 77,000	\$ 9,000
969	Kern	Arvin/ Lamont Branch	D5092 Emergency Light & Power Systems	\$ 173,000	\$ 105,000	\$ 68,000
970	Kings	Avenal Court	D5092 Emergency Light & Power Systems	\$ 9,000	\$ 5,000	\$ 4,000
971	Kings	Corcoran Court	D5092 Emergency Light & Power Systems	\$ 17,000	\$ 15,000	\$ 2,000
972	Los Angeles	San Fernando Courthouse	D5092 Emergency Light & Power Systems	\$ 686,000	\$ 572,000	\$ 114,000
973	Los Angeles	Santa Clarita Courthouse	D5092 Emergency Light & Power Systems	\$ 47,000	\$ 42,000	\$ 5,000
974	Los Angeles	Alfred J. McCourtney Juvenile Justice	D5092 Emergency Light & Power Systems	\$ 26,000	\$ 18,000	\$ 8,000
975	Los Angeles	Sylmar Juvenile Court	D5092 Emergency Light & Power Systems	\$ 65,000	\$ 22,000	\$ 43,000
976	Los Angeles	Los Padrinos Juvenile Court	D5092 Emergency Light & Power Systems	\$ 42,000	\$ 12,000	\$ 30,000
977	Los Angeles	Norwalk Courthouse	D5092 Emergency Light & Power Systems	\$ 356,000	\$ 303,000	\$ 53,000
978	Los Angeles	Bellflower Courthouse	D5092 Emergency Light & Power Systems	\$ 220,000	\$ 171,000	\$ 48,000
979	Los Angeles	Downey Courthouse	D5092 Emergency Light & Power Systems	\$ 375,000	\$ 314,000	\$ 61,000
980	Los Angeles	Santa Monica Courthouse	D5092 Emergency Light & Power Systems	\$ 265,000	\$ 208,000	\$ 57,000
981	Los Angeles	Santa Monica Court Annex	D5092 Emergency Light & Power Systems	\$ 40,000	\$ 40,000	\$ -
982	Los Angeles	Beverly Hills Courthouse	D5092 Emergency Light & Power Systems	\$ 207,000	\$ 164,000	\$ 42,000
983	Los Angeles	Airport Courthouse	D2010 Plumbing Fixtures	\$ 140,000	\$ 108,000	\$ 32,000
984	Los Angeles	Airport Courthouse	D5092 Emergency Light & Power Systems	\$ 781,000	\$ 603,000	\$ 178,000
985	Los Angeles	Hall of Records	D5092 Emergency Light & Power Systems	\$ 38,000	\$ 4,000	\$ 34,000

986	Los Angeles	County Records Center	D2090 Other Plumbing Systems	\$ 7,000	\$ 7,000	\$ 1,000
987	Los Angeles	Michael D. Antonovich Antelope Vall	D2010 Plumbing Fixtures	\$ 103,000	\$ 76,000	\$ 27,000
988	Los Angeles	Michael D. Antonovich Antelope Vall	D5092 Emergency Light & Power Systems	\$ 344,000	\$ 253,000	\$ 91,000
989	Los Angeles	Torrance Courthouse	D5092 Emergency Light & Power Systems	\$ 310,000	\$ 280,000	\$ 30,000
990	Los Angeles	Inglewood Juvenile Court	D2090 Other Plumbing Systems	\$ 58,000	\$ 47,000	\$ 11,000
991	Los Angeles	Inglewood Juvenile Court	D5092 Emergency Light & Power Systems	\$ 26,000	\$ 21,000	\$ 5,000
992	Los Angeles	Inglewood Courthouse	D5092 Emergency Light & Power Systems	\$ 334,000	\$ 249,000	\$ 85,000
993	Los Angeles	Burbank Courthouse	D5092 Emergency Light & Power Systems	\$ 119,000	\$ 108,000	\$ 11,000
994	Los Angeles	Alhambra Courthouse	D5092 Emergency Light & Power Systems	\$ 318,000	\$ 274,000	\$ 45,000
995	Los Angeles	Pasadena Courthouse	D5092 Emergency Light & Power Systems	\$ 317,000	\$ 220,000	\$ 97,000
996	Los Angeles	Stanley Mosk Courthouse	D2020-Domestic Water Distribution	\$ 4,390,000	\$ 4,270,000	\$ 120,000
997	Los Angeles	Stanley Mosk Courthouse	D5092 Emergency Light & Power Systems	\$ 1,788,000	\$ 1,739,000	\$ 49,000
998	Los Angeles	Clara Shortridge Foltz Criminal Justice	D5092 Emergency Light & Power Systems	\$ 1,895,000	\$ 1,304,000	\$ 592,000
999	Los Angeles	Monrovia Training Center	D5092 Emergency Light & Power Systems	\$ 32,000	\$ 22,000	\$ 9,000
1000	Los Angeles	El Monte Courthouse	D5092 Emergency Light & Power Systems	\$ 198,000	\$ 115,000	\$ 83,000
1001	Los Angeles	Edmund D. Edelman Children's Court	D5092 Emergency Light & Power Systems	\$ 617,000	\$ 432,000	\$ 185,000
1002	Los Angeles	Eastlake Juvenile Court	D5092 Emergency Light & Power Systems	\$ 104,000	\$ 57,000	\$ 47,000
1003	Los Angeles	Metropolitan Courthouse	D5092 Emergency Light & Power Systems	\$ 1,781,000	\$ 1,684,000	\$ 97,000
1004	Los Angeles	Central Arraignment Courts	D5092 Emergency Light & Power Systems	\$ 177,000	\$ 159,000	\$ 17,000
1005	Los Angeles	East Los Angeles Courthouse	D5092 Emergency Light & Power Systems	\$ 261,000	\$ 203,000	\$ 58,000
1006	Los Angeles	Pomona Courthouse South	D5092 Emergency Light & Power Systems	\$ 546,000	\$ 498,000	\$ 48,000
1007	Los Angeles	West Covina Courthouse	D5092 Emergency Light & Power Systems	\$ 235,000	\$ 195,000	\$ 40,000
1008	Madera	Sierra Courthouse	D2010 Plumbing Fixtures	\$ 26,000	\$ 18,000	\$ 8,000
1009	Madera	Sierra Courthouse	D5092 Emergency Light & Power Systems	\$ 11,000	\$ 8,000	\$ 4,000
1010	Merced	Old Court	D2010 Plumbing Fixtures	\$ 27,000	\$ 27,000	\$ -
1011	Merced	Old Court	D5092 Emergency Light & Power Systems	\$ 56,000	\$ 56,000	\$ -
1012	Merced	Downtown Merced Courthouse	D2090 Other Plumbing Systems	\$ 22,000	\$ 22,000	\$ -
1013	Merced	Downtown Merced Courthouse	D5092 Emergency Light & Power Systems	\$ 75,000	\$ 75,000	\$ -
1014	Napa	Criminal Court Building	D2010 Plumbing Fixtures	\$ 64,000	\$ 64,000	\$ -
1015	Napa	Criminal Court Building	D5092 Emergency Light & Power Systems	\$ 262,000	\$ 262,000	\$ -
1016	Nevada	Nevada City Courthouse	D5092 Emergency Light & Power Systems	\$ 60,000	\$ 39,000	\$ 21,000
1017	Nevada	Nevada City Courthouse Annex	D2010 Plumbing Fixtures	\$ 520,000	\$ 222,000	\$ 298,000
1018	Nevada	Nevada City Courthouse Annex	D5092 Emergency Light & Power Systems	\$ 69,000	\$ 29,000	\$ 39,000
1019	Orange	Central Justice Center	D2010 Plumbing Fixtures	\$ 177,000	\$ 162,000	\$ 16,000
1020	Orange	Central Justice Center	D5092 Emergency Light & Power Systems	\$ 303,000	\$ 276,000	\$ 27,000
1021	Orange	Central Justice Center Annex	D5092 Emergency Light & Power Systems	\$ 9,000	\$ 1,000	\$ 8,000
1022	Orange	Civil Complex Center ("CXC")	D2010 Plumbing Fixtures	\$ 193,000	\$ 193,000	\$ -
1023	Orange	Civil Complex Center ("CXC")	D5092 Emergency Light & Power Systems	\$ 36,000	\$ 36,000	\$ -
1024	Orange	Betty Lou Lamoreaux Justice Center	D2010 Plumbing Fixtures	\$ 6,000	\$ 5,000	\$ 1,000
1025	Orange	Betty Lou Lamoreaux Justice Center	D5092 Emergency Light & Power Systems	\$ 529,000	\$ 423,000	\$ 106,000
1026	Orange	North Justice Center	D5092 Emergency Light & Power Systems	\$ 123,000	\$ 111,000	\$ 12,000
1027	Orange	West Justice Center	D2010 Plumbing Fixtures	\$ 809,000	\$ 734,000	\$ 75,000
1028	Placer	Historic Courthouse	D5092 Emergency Light & Power Systems	\$ 104,000	\$ 80,000	\$ 24,000
1029	Placer	Bill Santucci Justice Center	D2010 Plumbing Fixtures	\$ 39,000	\$ 39,000	\$ -
1030	Placer	Bill Santucci Justice Center	D5092 Emergency Light & Power Systems	\$ 150,000	\$ 150,000	\$ -
1031	Sacramento	Gordon Schaber Sacramento Superior	D5092 Emergency Light & Power Systems	\$ 235,000	\$ 235,000	\$ -
1032	Sacramento	Juvenile Courthouse	D2010 Plumbing Fixtures	\$ 46,000	\$ 46,000	\$ -
1033	Sacramento	Juvenile Courthouse	D5092 Emergency Light & Power Systems	\$ 188,000	\$ 188,000	\$ -
1034	Sacramento	Carol Miller Justice Center Court Fac	D5092 Emergency Light & Power Systems	\$ 298,000	\$ 291,000	\$ 7,000
1035	San Diego	Hall of Justice	D2010 Plumbing Fixtures	\$ 49,000	\$ 20,000	\$ 29,000
1036	San Diego	Hall of Justice	D5092 Emergency Light & Power Systems	\$ 739,000	\$ 297,000	\$ 442,000
1037	San Diego	Kearny Mesa Court	D2010 Plumbing Fixtures	\$ 226,000	\$ 226,000	\$ -
1038	San Diego	Kearny Mesa Court	D5092 Emergency Light & Power Systems	\$ 87,000	\$ 87,000	\$ -
1039	San Diego	Juvenile Court	D2020-Domestic Water Distribution	\$ 151,000	\$ 112,000	\$ 38,000
1040	San Diego	Juvenile Court	D5092 Emergency Light & Power Systems	\$ 35,000	\$ 26,000	\$ 9,000
1041	San Diego	North County Regional Center - South	D2010 Plumbing Fixtures	\$ 98,000	\$ 66,000	\$ 32,000
1042	San Diego	North County Regional Center - South	D5092 Emergency Light & Power Systems	\$ 299,000	\$ 201,000	\$ 98,000
1043	San Diego	North County Regional Center - North	D2010 Plumbing Fixtures	\$ 207,000	\$ 207,000	\$ -
1044	San Diego	North County Regional Center - North	D5092 Emergency Light & Power Systems	\$ 63,000	\$ 63,000	\$ -
1045	San Diego	North County Regional Center - Anne	D2010 Plumbing Fixtures	\$ 9,000	\$ 9,000	\$ -
1046	San Diego	South County Regional Center	D5092 Emergency Light & Power Systems	\$ 449,000	\$ 161,000	\$ 288,000
1047	San Diego	East County Regional Center	D5092 Emergency Light & Power Systems	\$ 277,000	\$ 188,000	\$ 89,000
1048	San Joaquin	Lodi Branch- Dept. 2	D2010 Plumbing Fixtures	\$ 24,000	\$ 24,000	\$ -
1049	San Joaquin	Lodi Branch- Dept. 2	D5092 Emergency Light & Power Systems	\$ 24,000	\$ 24,000	\$ -
1050	San Mateo	Hall of Justice	D2010 Plumbing Fixtures	\$ 20,000	\$ 10,000	\$ 9,000
1051	San Mateo	Hall of Justice	D5092 Emergency Light & Power Systems	\$ 295,000	\$ 155,000	\$ 139,000
1052	San Mateo	Traffic/ Small Claims Annex	D2010 Plumbing Fixtures	\$ 73,000	\$ 73,000	\$ -
1053	San Mateo	Traffic/ Small Claims Annex	D5092 Emergency Light & Power Systems	\$ 22,000	\$ 22,000	\$ -
1054	San Mateo	Central Branch	D5092 Emergency Light & Power Systems	\$ 42,000	\$ 42,000	\$ -
1055	San Mateo	Northern Branch Courthouse	D5092 Emergency Light & Power Systems	\$ 73,000	\$ 60,000	\$ 12,000
1056	Santa Clara	Hall of Justice (East)	D2010 Plumbing Fixtures	\$ 90,000	\$ 90,000	\$ -
1057	Santa Clara	Hall of Justice (East)	D5092 Emergency Light & Power Systems	\$ 286,000	\$ 286,000	\$ -
1058	Santa Clara	Hall of Justice (West)	D5092 Emergency Light & Power Systems	\$ 127,000	\$ 127,000	\$ -
1059	Santa Clara	Downtown Superior Court	D5092 Emergency Light & Power Systems	\$ 229,000	\$ 229,000	\$ -
1060	Santa Clara	Historic Courthouse	D5092 Emergency Light & Power Systems	\$ 160,000	\$ 160,000	\$ -
1061	Santa Clara	Palo Alto Courthouse	D2010 Plumbing Fixtures	\$ 15,000	\$ 10,000	\$ 5,000

1062	Santa Clara	Santa Clara Courthouse	D2010 Plumbing Fixtures	\$ 173,000	\$ 173,000	\$ -
1063	Santa Clara	Santa Clara Courthouse	D5092 Emergency Light & Power Systems	\$ 319,000	\$ 319,000	\$ -
1064	Santa Cruz	Watsonville Courthouse	D2010 Plumbing Fixtures	\$ 8,000	\$ 8,000	\$ -
1065	Tulare	Visalia Superior Court	D2090 Other Plumbing Systems	\$ 385,000	\$ 125,000	\$ 261,000
1066	Tulare	Visalia Superior Court	D5092 Emergency Light & Power Systems	\$ 308,000	\$ 99,000	\$ 208,000
1067	Ventura	Hall of Justice	D2010 Plumbing Fixtures	\$ 1,615,000	\$ 1,128,000	\$ 487,000
1068	Ventura	Hall of Justice	D5092 Emergency Light & Power Systems	\$ 335,000	\$ 234,000	\$ 101,000
1069	Ventura	East County Courthouse	D2010 Plumbing Fixtures	\$ 39,000	\$ 24,000	\$ 15,000
1070	Ventura	East County Courthouse	D5092 Emergency Light & Power Systems	\$ 76,000	\$ 47,000	\$ 29,000
1071	Santa Barbara	Santa Maria Courts, Bldg G	D5092 Emergency Light & Power Systems	\$ 188,000	\$ 182,000	\$ 7,000
1072	Riverside	Hall of Justice	D2010 Plumbing Fixtures	\$ 13,000	\$ 13,000	\$ -
1073	Riverside	Hall of Justice	D5092 Emergency Light & Power Systems	\$ 640,000	\$ 640,000	\$ -
1074	San Luis Obispo	Courthouse Annex	D2010 Plumbing Fixtures	\$ 79,000	\$ 39,000	\$ 40,000
1075	San Luis Obispo	Courthouse Annex	D5092 Emergency Light & Power Systems	\$ 269,000	\$ 134,000	\$ 135,000
1076	San Bernardino	Joshua Tree Courthouse	D5092 Emergency Light & Power Systems	\$ 72,000	\$ 24,000	\$ 48,000
1077	San Bernardino	Fontana Courthouse	D2010 Plumbing Fixtures	\$ 118,000	\$ 97,000	\$ 21,000
1078	San Bernardino	Fontana Courthouse	D5092 Emergency Light & Power Systems	\$ 75,000	\$ 61,000	\$ 13,000
1079	Riverside	Blythe Courthouse - Superior Court	D2010 Plumbing Fixtures	\$ 7,000	\$ 7,000	\$ -
1080	Riverside	Blythe Courthouse - Superior Court	D5092 Emergency Light & Power Systems	\$ 8,000	\$ 8,000	\$ -
1081	Riverside	Larson Justice Center	D5092 Emergency Light & Power Systems	\$ 315,000	\$ 254,000	\$ 60,000
1082	Santa Barbara	Santa Maria Juvenile Court (new)	D5092 Emergency Light & Power Systems	\$ 47,000	\$ 31,000	\$ 16,000
1083	Alameda	Hayward Hall of Justice	D2010 Plumbing Fixtures	\$ 837,000	\$ 739,000	\$ 98,000
1084	San Francisco	Civic Center Courthouse	D5092 Emergency Light & Power Systems	\$ 662,000	\$ 662,000	\$ -
1085	Kern	Arvin/ Lamont Branch	D2010 Plumbing Fixtures	\$ 94,000	\$ 57,000	\$ 37,000
1086	Orange	North Justice Center	D2010 Plumbing Fixtures	\$ 974,000	\$ 880,000	\$ 94,000
1087	Kern	Bakersfield Juvenile Center	D2010 Plumbing Fixtures	\$ 175,000	\$ 117,000	\$ 58,000
1088	San Bernardino	Joshua Tree Courthouse	D2010 Plumbing Fixtures	\$ 104,000	\$ 35,000	\$ 69,000
1089	Los Angeles	Burbank Courthouse	D2010 Plumbing Fixtures	\$ 54,000	\$ 49,000	\$ 5,000
1090	Kern	Shafter/Wasco Courts Bldg.	D2010 Plumbing Fixtures	\$ 51,000	\$ 46,000	\$ 5,000
1091	Los Angeles	Santa Monica Courthouse	D2010 Plumbing Fixtures	\$ 585,000	\$ 459,000	\$ 126,000
1092	Los Angeles	Santa Clarita Courthouse	D2010 Plumbing Fixtures	\$ 27,000	\$ 24,000	\$ 3,000
1093	Solano	Law and Justice Center	D5010 Electrical Service & Distribution	\$ 4,274,000	\$ 542,000	\$ 3,733,000
1094	Santa Barbara	Santa Maria Courts Bldgs C + D	D5010 Electrical Service & Distribution	\$ 452,000	\$ 452,000	\$ -
1095	San Bernardino	Rancho Cucamonga Courthouse	D5010 Electrical Service & Distribution	\$ 3,779,000	\$ 2,874,000	\$ 905,000
1096	San Bernardino	Rancho Cucamonga Courthouse	D5090 Other Electrical Systems	\$ 35,000	\$ 27,000	\$ 8,000
1097	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D5010 Electrical Service & Distribution	\$ 127,000	\$ 29,000	\$ 98,000
1098	Alameda	Fremont Hall of Justice	D5010 Electrical Service & Distribution	\$ 543,000	\$ 431,000	\$ 112,000
1099	Butte	Butte County Courthouse	D5010 Electrical Service & Distribution	\$ 203,000	\$ 203,000	\$ -
1100	Contra Costa	Wakefield Taylor Courthouse	D5010 Electrical Service & Distribution	\$ 820,000	\$ 820,000	\$ -
1101	Contra Costa	Jail Annex	D5010 Electrical Service & Distribution	\$ 119,000	\$ 7,000	\$ 112,000
1102	Contra Costa	Danville District Courthouse	D5010 Electrical Service & Distribution	\$ 144,000	\$ 144,000	\$ -
1103	Contra Costa	George D. Carroll Courthouse	D5010 Electrical Service & Distribution	\$ 615,000	\$ 461,000	\$ 154,000
1104	Fresno	Fresno County Courthouse	D2020-Domestic Water Distribution	\$ 71,000	\$ 68,000	\$ 3,000
1105	Fresno	Fresno County Courthouse	D5010 Electrical Service & Distribution	\$ 2,848,000	\$ 2,732,000	\$ 116,000
1106	Fresno	B.F. Sisk Federal Courthouse	D5010 Electrical Service & Distribution	\$ 326,000	\$ 326,000	\$ -
1107	Humboldt	Humboldt County Courthouse (Eureka)	D5010 Electrical Service & Distribution	\$ 2,007,000	\$ 669,000	\$ 1,337,000
1108	Kings	Probation Building	D5010 Electrical Service & Distribution	\$ 8,000	\$ 1,000	\$ 7,000
1109	Kings	Avenal Court	D5010 Electrical Service & Distribution	\$ 30,000	\$ 17,000	\$ 13,000
1110	Los Angeles	San Fernando Courthouse	D5010 Electrical Service & Distribution	\$ 493,000	\$ 411,000	\$ 82,000
1111	Los Angeles	Chatsworth Courthouse	D2020-Domestic Water Distribution	\$ 48,000	\$ 40,000	\$ 8,000
1112	Los Angeles	Chatsworth Courthouse	D5010 Electrical Service & Distribution	\$ 111,000	\$ 93,000	\$ 18,000
1113	Los Angeles	Eastlake Juvenile Court	D5010 Electrical Service & Distribution	\$ 522,000	\$ 286,000	\$ 236,000
1114	Madera	Sierra Courthouse	D5010 Electrical Service & Distribution	\$ 26,000	\$ 18,000	\$ 8,000
1115	Nevada	Nevada City Courthouse	D5010 Electrical Service & Distribution	\$ 129,000	\$ 85,000	\$ 45,000
1116	Nevada	Nevada City Courthouse Annex	D5010 Electrical Service & Distribution	\$ 323,000	\$ 138,000	\$ 185,000
1117	Orange	Central Justice Center	D5090 Other Electrical Systems	\$ 46,000	\$ 42,000	\$ 4,000
1118	Orange	West Justice Center	D5090 Other Electrical Systems	\$ 34,000	\$ 30,000	\$ 3,000
1119	Placer	Historic Courthouse	D5010 Electrical Service & Distribution	\$ 302,000	\$ 233,000	\$ 70,000
1120	Sacramento	Gordon Schaber Sacramento Superior	D5010 Electrical Service & Distribution	\$ 3,165,000	\$ 3,165,000	\$ -
1121	San Mateo	Hall of Justice	D5010 Electrical Service & Distribution	\$ 1,447,000	\$ 763,000	\$ 685,000
1122	San Mateo	Northern Branch Courthouse	D5010 Electrical Service & Distribution	\$ 280,000	\$ 233,000	\$ 47,000
1123	Santa Clara	Hall of Justice (West)	D5010 Electrical Service & Distribution	\$ 1,578,000	\$ 1,578,000	\$ -
1124	Santa Clara	Downtown Superior Court	D5010 Electrical Service & Distribution	\$ 1,705,000	\$ 1,705,000	\$ -
1125	Santa Clara	Santa Clara Courthouse	D5010 Electrical Service & Distribution	\$ 239,000	\$ 239,000	\$ -
1126	Santa Barbara	Santa Maria Courts, Bldg G	D2020-Domestic Water Distribution	\$ 10,000	\$ 10,000	\$ -
1127	San Diego	Kearny Mesa Court	D2090 Other Plumbing Systems	\$ 133,000	\$ 133,000	\$ -
1128	San Diego	Juvenile Court	D2090 Other Plumbing Systems	\$ 221,000	\$ 165,000	\$ 56,000
1129	San Bernardino	Rancho Cucamonga Courthouse	D5036 Clock & Program Systems	\$ 1,602,000	\$ 1,218,000	\$ 384,000
1130	Riverside	Riverside Juvenile Court	D5036 Clock & Program Systems	\$ 93,000	\$ 46,000	\$ 47,000
1131	Kern	Bakersfield Superior Court	D5036 Clock & Program Systems	\$ 396,000	\$ 248,000	\$ 148,000
1132	Kern	Bakersfield Justice Bldg.	D5036 Clock & Program Systems	\$ 241,000	\$ 123,000	\$ 118,000
1133	Los Angeles	Alfred J. McCourtney Juvenile Justice	D5036 Clock & Program Systems	\$ 22,000	\$ 15,000	\$ 7,000
1134	Los Angeles	Norwalk Courthouse	D5036 Clock & Program Systems	\$ 802,000	\$ 682,000	\$ 120,000
1135	Los Angeles	Bellflower Courthouse	D5036 Clock & Program Systems	\$ 252,000	\$ 196,000	\$ 56,000
1136	Los Angeles	Downey Courthouse	D5036 Clock & Program Systems	\$ 212,000	\$ 178,000	\$ 35,000
1137	Los Angeles	Beverly Hills Courthouse	D5036 Clock & Program Systems	\$ 121,000	\$ 97,000	\$ 25,000

1138	Los Angeles	Van Nuys Courthouse East	D5036 Clock & Program Systems	\$ 70,000	\$ 63,000	\$ 7,000
1139	Los Angeles	Van Nuys Courthouse West	D5036 Clock & Program Systems	\$ 117,000	\$ 94,000	\$ 23,000
1140	Los Angeles	Inglewood Courthouse	D5036 Clock & Program Systems	\$ 443,000	\$ 330,000	\$ 113,000
1141	Los Angeles	Glendale Courthouse	D5036 Clock & Program Systems	\$ 18,000	\$ 16,000	\$ 2,000
1142	Los Angeles	Alhambra Courthouse	D5036 Clock & Program Systems	\$ 376,000	\$ 323,000	\$ 53,000
1143	Los Angeles	Stanley Mosk Courthouse	D5036 Clock & Program Systems	\$ 25,000	\$ 24,000	\$ 1,000
1144	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	D5036 Clock & Program Systems	\$ 3,932,000	\$ 2,705,000	\$ 1,227,000
1145	Los Angeles	Central Arraignment Courts	D5036 Clock & Program Systems	\$ 221,000	\$ 199,000	\$ 22,000
1146	Los Angeles	Pomona Courthouse South	D5036 Clock & Program Systems	\$ 259,000	\$ 236,000	\$ 23,000
1147	Orange	West Justice Center	D5036 Clock & Program Systems	\$ 320,000	\$ 290,000	\$ 30,000
1148	Sacramento	Carol Miller Justice Center Court Facility	D2010 Plumbing Fixtures	\$ 173,000	\$ 169,000	\$ 4,000
1149	San Diego	Kearny Mesa Court	D5036 Clock & Program Systems	\$ 283,000	\$ 283,000	\$ -
1150	San Diego	North County Regional Center - North	D5036 Clock & Program Systems	\$ 519,000	\$ 519,000	\$ -
1151	Santa Clara	Downtown Superior Court	G20 Site Improvements	\$ 168,000	\$ 168,000	\$ -
1152	Riverside	Hall of Justice	D5036 Clock & Program Systems	\$ 1,037,000	\$ 1,037,000	\$ -
1153	San Francisco	Civic Center Courthouse	D5036 Clock & Program Systems	\$ 1,301,000	\$ 1,301,000	\$ -
1154	San Bernardino	San Bernardino Courthouse	D2090 Other Plumbing Systems	\$ 300,000	\$ 287,000	\$ 13,000
1155	Riverside	Corona	D2090 Other Plumbing Systems	\$ 37,000	\$ 20,000	\$ 17,000
1156	Solano	Hall of Justice	D2090 Other Plumbing Systems	\$ 98,000	\$ 71,000	\$ 27,000
1157	San Bernardino	Rancho Cucamonga Courthouse	D5020 Lighting & Branch Wiring	\$ 502,000	\$ 382,000	\$ 120,000
1158	Solano	Solano Justice Building	D2090 Other Plumbing Systems	\$ 65,000	\$ 50,000	\$ 16,000
1159	Del Norte	Del Norte County Superior Court	D2090 Other Plumbing Systems	\$ 30,000	\$ 18,000	\$ 12,000
1160	Los Angeles	Santa Clarita Courthouse	D2090 Other Plumbing Systems	\$ 102,000	\$ 90,000	\$ 12,000
1161	Los Angeles	Los Padrinos Juvenile Court	D2090 Other Plumbing Systems	\$ 39,000	\$ 12,000	\$ 28,000
1162	Los Angeles	Airport Courthouse	D5020 Lighting & Branch Wiring	\$ 1,813,000	\$ 1,399,000	\$ 414,000
1163	Los Angeles	Hall of Records	D2090 Other Plumbing Systems	\$ 73,000	\$ 8,000	\$ 65,000
1164	Los Angeles	Van Nuys Courthouse East	D2090 Other Plumbing Systems	\$ 426,000	\$ 383,000	\$ 44,000
1165	Los Angeles	Chatsworth Courthouse	D2090 Other Plumbing Systems	\$ 8,000	\$ 7,000	\$ 1,000
1166	Los Angeles	Torrance Courthouse	D2090 Other Plumbing Systems	\$ 87,000	\$ 78,000	\$ 8,000
1167	Los Angeles	Burbank Courthouse	D2090 Other Plumbing Systems	\$ 18,000	\$ 16,000	\$ 2,000
1168	Los Angeles	Glendale Courthouse	D2090 Other Plumbing Systems	\$ 162,000	\$ 147,000	\$ 15,000
1169	Los Angeles	Pasadena Courthouse	D2090 Other Plumbing Systems	\$ 72,000	\$ 50,000	\$ 22,000
1170	Los Angeles	Stanley Mosk Courthouse	D2090 Other Plumbing Systems	\$ 2,748,000	\$ 2,673,000	\$ 75,000
1171	Los Angeles	Eastlake Juvenile Court	D2090 Other Plumbing Systems	\$ 75,000	\$ 41,000	\$ 34,000
1172	Los Angeles	Pomona Courthouse South	D2090 Other Plumbing Systems	\$ 617,000	\$ 562,000	\$ 55,000
1173	Los Angeles	West Covina Courthouse	D2090 Other Plumbing Systems	\$ 380,000	\$ 316,000	\$ 65,000
1174	Nevada	Nevada City Courthouse Annex	D2090 Other Plumbing Systems	\$ 106,000	\$ 45,000	\$ 61,000
1175	Orange	Central Justice Center	D2090 Other Plumbing Systems	\$ 1,362,000	\$ 1,241,000	\$ 120,000
1176	Orange	West Justice Center	D2090 Other Plumbing Systems	\$ 87,000	\$ 79,000	\$ 8,000
1177	San Francisco	Youth Guidance Center	D5020 Lighting & Branch Wiring	\$ 12,000	\$ 2,000	\$ 11,000
1178	Santa Clara	Downtown Superior Court	D2090 Other Plumbing Systems	\$ 179,000	\$ 179,000	\$ -
1179	Los Angeles	Downey Courthouse	D2010 Plumbing Fixtures	\$ 571,000	\$ 478,000	\$ 93,000
1180	San Luis Obispo	Courthouse Annex	D2090 Other Plumbing Systems	\$ 133,000	\$ 66,000	\$ 67,000
1181	Los Angeles	Van Nuys Courthouse West	D2010 Plumbing Fixtures	\$ 565,000	\$ 454,000	\$ 110,000
1182	San Bernardino	Rancho Cucamonga Courthouse	G20 Site Improvements	\$ 2,755,000	\$ 2,095,000	\$ 660,000
1183	Del Norte	Del Norte County Superior Court	D5020 Lighting & Branch Wiring	\$ 229,000	\$ 140,000	\$ 89,000
1184	Napa	Criminal Court Building	D5020 Lighting & Branch Wiring	\$ 356,000	\$ 356,000	\$ -
1185	Ventura	East County Courthouse	D5020 Lighting & Branch Wiring	\$ 140,000	\$ 87,000	\$ 54,000
1186	Los Angeles	East Los Angeles Courthouse	D2010 Plumbing Fixtures	\$ 953,000	\$ 740,000	\$ 212,000
1187	San Diego	North County Regional Center - South	D5020 Lighting & Branch Wiring	\$ 1,893,000	\$ 1,273,000	\$ 620,000
1188	San Diego	Hall of Justice	D5020 Lighting & Branch Wiring	\$ 3,346,000	\$ 1,346,000	\$ 2,000,000
1189	Orange	Betty Lou Lamoreaux Justice Center	D5020 Lighting & Branch Wiring	\$ 1,624,000	\$ 1,298,000	\$ 326,000
1190	Los Angeles	El Monte Courthouse	D2010 Plumbing Fixtures	\$ 986,000	\$ 573,000	\$ 413,000
1191	Riverside	Blythe Courthouse - Superior Court	D5020 Lighting & Branch Wiring	\$ 73,000	\$ 73,000	\$ -
1192	San Joaquin	Lodi Branch- Dept. 2	D5020 Lighting & Branch Wiring	\$ 1,288,000	\$ 1,288,000	\$ -
1193	Kings	Avenal Court	D2010 Plumbing Fixtures	\$ 137,000	\$ 79,000	\$ 57,000
1194	Los Angeles	Glendale Courthouse	D2010 Plumbing Fixtures	\$ 157,000	\$ 142,000	\$ 15,000
1195	Los Angeles	Stanley Mosk Courthouse	D2010 Plumbing Fixtures	\$ 5,172,000	\$ 5,031,000	\$ 142,000
1196	Santa Barbara	Santa Maria Courts Bldgs C + D	D5020 Lighting & Branch Wiring	\$ 762,000	\$ 762,000	\$ -
1197	Santa Barbara	Santa Maria Courts, Bldg F	D5020 Lighting & Branch Wiring	\$ 30,000	\$ 30,000	\$ -
1198	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D5020 Lighting & Branch Wiring	\$ 74,000	\$ 17,000	\$ 57,000
1199	Alameda	George E. McDonald Hall of Justice	D5020 Lighting & Branch Wiring	\$ 233,000	\$ 233,000	\$ -
1200	Amador	Amador County Courthouse	D5020 Lighting & Branch Wiring	\$ 74,000	\$ 74,000	\$ -
1201	Kern	Taft Courts Bldg.	D5020 Lighting & Branch Wiring	\$ 6,000	\$ 6,000	\$ -
1202	Kings	Corcoran Court	D5020 Lighting & Branch Wiring	\$ 64,000	\$ 56,000	\$ 8,000
1203	Merced	Adobe	D5020 Lighting & Branch Wiring	\$ 22,000	\$ 7,000	\$ 15,000
1204	Merced	Downtown Merced Courthouse	D5020 Lighting & Branch Wiring	\$ 33,000	\$ 33,000	\$ -
1205	Monterey	Marina Courthouse	D5020 Lighting & Branch Wiring	\$ 38,000	\$ 38,000	\$ -
1206	Sacramento	Juvenile Courthouse	D5020 Lighting & Branch Wiring	\$ 24,000	\$ 24,000	\$ -
1207	San Diego	Kearny Mesa Court	D5020 Lighting & Branch Wiring	\$ 10,000	\$ 10,000	\$ -
1208	San Diego	North County Regional Center - Annex	D5020 Lighting & Branch Wiring	\$ 10,000	\$ 10,000	\$ -
1209	San Mateo	Hall of Justice	D5020 Lighting & Branch Wiring	\$ 346,000	\$ 182,000	\$ 164,000
1210	San Mateo	Central Branch	D5020 Lighting & Branch Wiring	\$ 134,000	\$ 134,000	\$ -
1211	Santa Barbara	Santa Maria Courts, Bldg G	D5020 Lighting & Branch Wiring	\$ 270,000	\$ 261,000	\$ 9,000
1212	Riverside	Family Law Court	G20 Site Improvements	\$ 626,000	\$ 626,000	\$ -
1213	San Bernardino	Juvenile Dependency Courthouse	D3050 Terminal & Package Units	\$ 224,000	\$ 122,000	\$ 102,000

1214	Los Angeles	Van Nuys Courthouse East	D2010 Plumbing Fixtures	\$ 401,000	\$ 360,000	\$ 41,000
1215	Solano	Hall of Justice	D2010 Plumbing Fixtures	\$ 1,096,000	\$ 798,000	\$ 298,000
1216	El Dorado	Johnson Bldg.	D2010 Plumbing Fixtures	\$ 129,000	\$ 129,000	\$ -
1217	Los Angeles	Alfred J. McCourtney Juvenile Justice	D2010 Plumbing Fixtures	\$ 306,000	\$ 212,000	\$ 95,000
1218	Los Angeles	Metropolitan Courthouse	D2010 Plumbing Fixtures	\$ 3,467,000	\$ 3,278,000	\$ 189,000
1219	San Bernardino	Rancho Cucamonga Courthouse	D2010 Plumbing Fixtures	\$ 2,129,000	\$ 1,619,000	\$ 510,000
1220	Solano	Hall of Justice	D5020 Lighting & Branch Wiring	\$ 1,886,000	\$ 1,374,000	\$ 513,000
1221	Kern	Bakersfield Superior Court	D5020 Lighting & Branch Wiring	\$ 3,206,000	\$ 2,008,000	\$ 1,198,000
1222	Fresno	Fresno County Courthouse	D2010 Plumbing Fixtures	\$ 1,572,000	\$ 1,508,000	\$ 64,000
1223	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D3060 Controls & Instrumentation	\$ 11,000	\$ 11,000	\$ -
1224	Los Angeles	Alfred J. McCourtney Juvenile Justice	D5020 Lighting & Branch Wiring	\$ 275,000	\$ 190,000	\$ 85,000
1225	San Diego	South County Regional Center	D5020 Lighting & Branch Wiring	\$ 1,652,000	\$ 592,000	\$ 1,060,000
1226	San Bernardino	San Bernardino Courthouse	D2010 Plumbing Fixtures	\$ 874,000	\$ 836,000	\$ 38,000
1227	Riverside	Larson Justice Center	D5020 Lighting & Branch Wiring	\$ 1,346,000	\$ 1,087,000	\$ 258,000
1228	Solano	Law and Justice Center	D2010 Plumbing Fixtures	\$ 1,087,000	\$ 138,000	\$ 949,000
1229	Los Angeles	Hall of Records	D5020 Lighting & Branch Wiring	\$ 281,000	\$ 30,000	\$ 251,000
1230	Solano	Solano Justice Building	D2010 Plumbing Fixtures	\$ 512,000	\$ 390,000	\$ 122,000
1231	Kings	Probation Building	D2010 Plumbing Fixtures	\$ 38,000	\$ 4,000	\$ 33,000
1232	Los Angeles	Beverly Hills Courthouse	D2010 Plumbing Fixtures	\$ 713,000	\$ 567,000	\$ 146,000
1233	Los Angeles	Glendale Courthouse	D5020 Lighting & Branch Wiring	\$ 523,000	\$ 473,000	\$ 49,000
1234	Riverside	Riverside Juvenile Court	D5020 Lighting & Branch Wiring	\$ 533,000	\$ 263,000	\$ 270,000
1235	Contra Costa	Wakefield Taylor Courthouse	D5020 Lighting & Branch Wiring	\$ 975,000	\$ 975,000	\$ -
1236	Los Angeles	Bellflower Courthouse	D5020 Lighting & Branch Wiring	\$ 1,494,000	\$ 1,164,000	\$ 329,000
1237	Los Angeles	Alhambra Courthouse	D5020 Lighting & Branch Wiring	\$ 1,606,000	\$ 1,382,000	\$ 225,000
1238	Los Angeles	Edmund D. Edelman Children's Court	D5020 Lighting & Branch Wiring	\$ 1,459,000	\$ 1,021,000	\$ 438,000
1239	Merced	Old Court	D5020 Lighting & Branch Wiring	\$ 24,000	\$ 24,000	\$ -
1240	Orange	Civil Complex Center ("CXC")	D5020 Lighting & Branch Wiring	\$ 412,000	\$ 412,000	\$ -
1241	Los Angeles	Burbank Courthouse	D5020 Lighting & Branch Wiring	\$ 908,000	\$ 824,000	\$ 84,000
1242	Los Angeles	San Fernando Courthouse	D5020 Lighting & Branch Wiring	\$ 1,745,000	\$ 1,456,000	\$ 290,000
1243	Riverside	Riverside Juvenile Justice Trailers	D5020 Lighting & Branch Wiring	\$ 24,000	\$ 24,000	\$ -
1244	Riverside	Riverside Juvenile Justice Trailers	D5020 Lighting & Branch Wiring	\$ 24,000	\$ 24,000	\$ -
1245	Solano	Solano Justice Building	D5020 Lighting & Branch Wiring	\$ 664,000	\$ 505,000	\$ 159,000
1246	San Bernardino	Victorville Courthouse-Dept. N-1	D5020 Lighting & Branch Wiring	\$ 364,000	\$ 234,000	\$ 130,000
1247	San Diego	North County Regional Center - North	D5020 Lighting & Branch Wiring	\$ 818,000	\$ 818,000	\$ -
1248	Los Angeles	Santa Monica Courthouse	D5020 Lighting & Branch Wiring	\$ 1,281,000	\$ 1,005,000	\$ 275,000
1249	Los Angeles	Inglewood Juvenile Court	D5020 Lighting & Branch Wiring	\$ 297,000	\$ 240,000	\$ 57,000
1250	Los Angeles	East Los Angeles Courthouse	D5020 Lighting & Branch Wiring	\$ 1,269,000	\$ 986,000	\$ 283,000
1251	Santa Clara	Historic Courthouse	D5020 Lighting & Branch Wiring	\$ 313,000	\$ 313,000	\$ -
1252	Los Angeles	Beverly Hills Courthouse	D5020 Lighting & Branch Wiring	\$ 1,450,000	\$ 1,153,000	\$ 297,000
1253	San Francisco	Civic Center Courthouse	D5020 Lighting & Branch Wiring	\$ 2,182,000	\$ 2,182,000	\$ -
1254	Los Angeles	Downey Courthouse	D5020 Lighting & Branch Wiring	\$ 1,717,000	\$ 1,437,000	\$ 280,000
1255	Los Angeles	Torrance Courthouse	D5020 Lighting & Branch Wiring	\$ 1,421,000	\$ 1,285,000	\$ 136,000
1256	El Dorado	Cameron Park	D5020 Lighting & Branch Wiring	\$ 105,000	\$ 105,000	\$ -
1257	Los Angeles	Clara Shortridge Foltz Criminal Justice	D5020 Lighting & Branch Wiring	\$ 8,842,000	\$ 6,082,000	\$ 2,760,000
1258	Los Angeles	Monrovia Training Center	D5020 Lighting & Branch Wiring	\$ 93,000	\$ 66,000	\$ 28,000
1259	Orange	West Justice Center	D5020 Lighting & Branch Wiring	\$ 414,000	\$ 375,000	\$ 39,000
1260	San Diego	East County Regional Center	D5020 Lighting & Branch Wiring	\$ 3,489,000	\$ 2,363,000	\$ 1,127,000
1261	Los Angeles	Norwalk Courthouse	D2010 Plumbing Fixtures	\$ 1,572,000	\$ 1,337,000	\$ 235,000
1262	Contra Costa	Bray Courts	D2010 Plumbing Fixtures	\$ 405,000	\$ 346,000	\$ 59,000
1263	El Dorado	Johnson Bldg.	D5020 Lighting & Branch Wiring	\$ 131,000	\$ 131,000	\$ -
1264	Los Angeles	Hall of Records	D2010 Plumbing Fixtures	\$ 23,000	\$ 2,000	\$ 21,000
1265	Riverside	Hall of Justice	D5020 Lighting & Branch Wiring	\$ 1,060,000	\$ 1,060,000	\$ -
1266	San Francisco	Hall of Justice	D5020 Lighting & Branch Wiring	\$ 1,702,000	\$ 396,000	\$ 1,306,000
1267	Solano	Law and Justice Center	D5020 Lighting & Branch Wiring	\$ 1,849,000	\$ 234,000	\$ 1,615,000
1268	San Mateo	Northern Branch Courthouse	D5020 Lighting & Branch Wiring	\$ 609,000	\$ 507,000	\$ 102,000
1269	Contra Costa	George D. Carroll Courthouse	D5020 Lighting & Branch Wiring	\$ 380,000	\$ 285,000	\$ 95,000
1270	Kern	Bakersfield Juvenile Center	D5020 Lighting & Branch Wiring	\$ 706,000	\$ 471,000	\$ 235,000
1271	Kern	Delano/North Kern Court	D5020 Lighting & Branch Wiring	\$ 247,000	\$ 199,000	\$ 48,000
1272	Kern	Shafter/Wasco Courts Bldg.	D5020 Lighting & Branch Wiring	\$ 162,000	\$ 145,000	\$ 16,000
1273	Kern	Arvin/ Lamont Branch	D5020 Lighting & Branch Wiring	\$ 444,000	\$ 270,000	\$ 173,000
1274	Kings	Probation Building	D5020 Lighting & Branch Wiring	\$ 24,000	\$ 3,000	\$ 21,000
1275	Los Angeles	Santa Clarita Courthouse	D5020 Lighting & Branch Wiring	\$ 266,000	\$ 235,000	\$ 31,000
1276	Los Angeles	Central Arraignment Courts	D5020 Lighting & Branch Wiring	\$ 425,000	\$ 384,000	\$ 42,000
1277	Nevada	Nevada City Courthouse	D5020 Lighting & Branch Wiring	\$ 67,000	\$ 44,000	\$ 23,000
1278	Nevada	Nevada City Courthouse Annex	D5020 Lighting & Branch Wiring	\$ 179,000	\$ 77,000	\$ 103,000
1279	San Diego	Kearny Mesa Traffic Court KM3 Trailers	D5020 Lighting & Branch Wiring	\$ 15,000	\$ 15,000	\$ -
1280	San Diego	Kearny Mesa Traffic Court KM4 Trailers	D5020 Lighting & Branch Wiring	\$ 15,000	\$ 15,000	\$ -
1281	San Diego	Kearny Mesa Traffic Court KM5 & KM6	D5020 Lighting & Branch Wiring	\$ 15,000	\$ 15,000	\$ -
1282	San Diego	Juvenile Court	D5020 Lighting & Branch Wiring	\$ 333,000	\$ 248,000	\$ 84,000
1283	San Diego	Trailer - Dept 34	D5020 Lighting & Branch Wiring	\$ 15,000	\$ 15,000	\$ -
1284	San Diego	Trailer - Dept 35	D5020 Lighting & Branch Wiring	\$ 15,000	\$ 15,000	\$ -
1285	San Diego	Trailer - Storage A	D5020 Lighting & Branch Wiring	\$ 9,000	\$ 9,000	\$ -
1286	San Diego	Trailer - Family Support	D5020 Lighting & Branch Wiring	\$ 15,000	\$ 15,000	\$ -
1287	Santa Clara	Hall of Justice (East)	D5020 Lighting & Branch Wiring	\$ 1,214,000	\$ 1,214,000	\$ -
1288	Santa Clara	Downtown Superior Court	D5020 Lighting & Branch Wiring	\$ 2,584,000	\$ 2,584,000	\$ -
1289	Fresno	Fresno County Courthouse	D5020 Lighting & Branch Wiring	\$ 231,000	\$ 222,000	\$ 9,000

1290	San Bernardino	Fontana Courthouse	D5020 Lighting & Branch Wiring	\$ 209,000	\$ 172,000	\$ 37,000
1291	Los Angeles	Eastlake Juvenile Court	D5020 Lighting & Branch Wiring	\$ 442,000	\$ 242,000	\$ 200,000
1292	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D3040 Distribution Systems	\$ 49,000	\$ 49,000	\$ -
1293	Los Angeles	El Monte Courthouse	D5020 Lighting & Branch Wiring	\$ 621,000	\$ 361,000	\$ 260,000
1294	Los Angeles	San Fernando Courthouse	D2010 Plumbing Fixtures	\$ 1,786,000	\$ 1,490,000	\$ 296,000
1295	Los Angeles	Compton Courthouse	D5020 Lighting & Branch Wiring	\$ 6,995,000	\$ 4,626,000	\$ 2,369,000
1296	Alameda	Fremont Hall of Justice	D2020-Domestic Water Distribution	\$ 448,000	\$ 356,000	\$ 92,000
1297	Butte	Butte County Courthouse	D5020 Lighting & Branch Wiring	\$ 165,000	\$ 165,000	\$ -
1298	Los Angeles	Metropolitan Courthouse	D5020 Lighting & Branch Wiring	\$ 2,297,000	\$ 2,172,000	\$ 125,000
1299	Imperial	Imperial County Courthouse	D5020 Lighting & Branch Wiring	\$ 474,000	\$ 474,000	\$ -
1300	San Bernardino	Barstow Courthouse	D5020 Lighting & Branch Wiring	\$ 481,000	\$ 375,000	\$ 106,000
1301	Tulare	Visalia Superior Court	D5020 Lighting & Branch Wiring	\$ 2,606,000	\$ 842,000	\$ 1,763,000
1302	Sacramento	Carol Miller Justice Center Court Fac	D5020 Lighting & Branch Wiring	\$ 1,594,000	\$ 1,558,000	\$ 36,000
1303	Los Angeles	Van Nuys Courthouse East	D5020 Lighting & Branch Wiring	\$ 1,048,000	\$ 940,000	\$ 108,000
1304	San Bernardino	San Bernardino Courthouse	D5020 Lighting & Branch Wiring	\$ 1,391,000	\$ 1,330,000	\$ 61,000
1305	Riverside	Family Law Court	D5037 Fire Alarm Systems	\$ 583,000	\$ 583,000	\$ -
1306	Riverside	Southwest Justice Center	D5037 Fire Alarm Systems	\$ 1,065,000	\$ 797,000	\$ 268,000
1307	San Bernardino	Juvenile Dependency Courthouse	D5037 Fire Alarm Systems	\$ 158,000	\$ 86,000	\$ 72,000
1308	San Luis Obispo	Paso Robles Courthouse	D5037 Fire Alarm Systems	\$ 127,000	\$ 127,000	\$ -
1309	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D5037 Fire Alarm Systems	\$ 64,000	\$ 64,000	\$ -
1310	San Luis Obispo	1070 Palm St.	D5020 Lighting & Branch Wiring	\$ 37,000	\$ 37,000	\$ -
1311	Contra Costa	Bray Courts	D5020 Lighting & Branch Wiring	\$ 548,000	\$ 469,000	\$ 79,000
1312	Contra Costa	Danville District Courthouse	D5020 Lighting & Branch Wiring	\$ 345,000	\$ 345,000	\$ -
1313	Kings	Avenal Court	D5020 Lighting & Branch Wiring	\$ 86,000	\$ 50,000	\$ 36,000
1314	Los Angeles	Sylmar Juvenile Court	D5020 Lighting & Branch Wiring	\$ 116,000	\$ 40,000	\$ 76,000
1315	Los Angeles	Stanley Mosk Courthouse	D5020 Lighting & Branch Wiring	\$ 1,296,000	\$ 1,261,000	\$ 36,000
1316	Santa Clara	Hall of Justice (West)	D5020 Lighting & Branch Wiring	\$ 1,524,000	\$ 1,524,000	\$ -
1317	Alameda	Hayward Hall of Justice	D5020 Lighting & Branch Wiring	\$ 1,875,000	\$ 1,656,000	\$ 219,000
1318	Sacramento	Gordon Schaber Sacramento Superior	D5020 Lighting & Branch Wiring	\$ 3,014,000	\$ 3,014,000	\$ -
1319	San Bernardino	Joshua Tree Courthouse	D5020 Lighting & Branch Wiring	\$ 265,000	\$ 90,000	\$ 175,000
1320	Alameda	Wiley W. Manuel Courthouse	D5020 Lighting & Branch Wiring	\$ 1,891,000	\$ 1,585,000	\$ 306,000
1321	Alameda	Fremont Hall of Justice	D5020 Lighting & Branch Wiring	\$ 1,295,000	\$ 1,028,000	\$ 267,000
1322	Humboldt	Humboldt County Courthouse (Eureka	D5020 Lighting & Branch Wiring	\$ 746,000	\$ 249,000	\$ 497,000
1323	Los Angeles	Norwalk Courthouse	D5020 Lighting & Branch Wiring	\$ 1,406,000	\$ 1,196,000	\$ 211,000
1324	Los Angeles	West Covina Courthouse	D5020 Lighting & Branch Wiring	\$ 946,000	\$ 785,000	\$ 161,000
1325	Madera	Sierra Courthouse	D5020 Lighting & Branch Wiring	\$ 101,000	\$ 69,000	\$ 32,000
1326	Orange	North Justice Center	D5020 Lighting & Branch Wiring	\$ 719,000	\$ 649,000	\$ 70,000
1327	Santa Clara	Santa Clara Courthouse	D5020 Lighting & Branch Wiring	\$ 528,000	\$ 528,000	\$ -
1328	Los Angeles	Van Nuys Courthouse West	D5020 Lighting & Branch Wiring	\$ 3,290,000	\$ 2,647,000	\$ 642,000
1329	Los Angeles	Pasadena Courthouse	D2010 Plumbing Fixtures	\$ 1,266,000	\$ 878,000	\$ 388,000
1330	Del Norte	Del Norte County Superior Court	D2010 Plumbing Fixtures	\$ 10,000	\$ 6,000	\$ 4,000
1331	Los Angeles	Clara Shortridge Foltz Criminal Justice	D2010 Plumbing Fixtures	\$ 6,739,000	\$ 4,636,000	\$ 2,103,000
1332	Kern	Bakersfield Justice Bldg.	D5020 Lighting & Branch Wiring	\$ 1,074,000	\$ 549,000	\$ 525,000
1333	San Luis Obispo	Courthouse Annex	D5020 Lighting & Branch Wiring	\$ 807,000	\$ 401,000	\$ 405,000
1334	Los Angeles	Torrance Courthouse	D2010 Plumbing Fixtures	\$ 774,000	\$ 700,000	\$ 74,000
1335	Los Angeles	Sylmar Juvenile Court	D2010 Plumbing Fixtures	\$ 50,000	\$ 17,000	\$ 33,000
1336	Riverside	Larson Justice Center	D2010 Plumbing Fixtures	\$ 363,000	\$ 293,000	\$ 70,000
1337	Santa Barbara	Santa Maria Courts Bldgs C + D	D2010 Plumbing Fixtures	\$ 553,000	\$ 553,000	\$ -
1338	Alameda	Hayward Hall of Justice	G20 Site Improvements	\$ 1,193,000	\$ 1,053,000	\$ 140,000
1339	Los Angeles	Van Nuys Courthouse West	G20 Site Improvements	\$ 786,000	\$ 632,000	\$ 153,000
1340	Riverside	Corona	D5020 Lighting & Branch Wiring	\$ 235,000	\$ 127,000	\$ 108,000
1341	Contra Costa	Family Law Center	D5020 Lighting & Branch Wiring	\$ 20,000	\$ 20,000	\$ -
1342	Contra Costa	Jail Annex	D5020 Lighting & Branch Wiring	\$ 302,000	\$ 18,000	\$ 284,000
1343	Fresno	B.F. Sisk Federal Courthouse	D5020 Lighting & Branch Wiring	\$ 73,000	\$ 73,000	\$ -
1344	Los Angeles	Los Padrinos Juvenile Court	D5020 Lighting & Branch Wiring	\$ 40,000	\$ 12,000	\$ 28,000
1345	Los Angeles	Inglewood Courthouse	D5020 Lighting & Branch Wiring	\$ 1,156,000	\$ 862,000	\$ 294,000
1346	Los Angeles	Pasadena Courthouse	D5020 Lighting & Branch Wiring	\$ 847,000	\$ 587,000	\$ 260,000
1347	Los Angeles	Pomona Courthouse South	D5020 Lighting & Branch Wiring	\$ 1,571,000	\$ 1,432,000	\$ 139,000
1348	Modoc	Barclay Justice Center	D5020 Lighting & Branch Wiring	\$ 40,000	\$ 40,000	\$ -
1349	Placer	Historic Courthouse	D5020 Lighting & Branch Wiring	\$ 202,000	\$ 155,000	\$ 46,000
1350	San Diego	Department 9 Trailer	D5020 Lighting & Branch Wiring	\$ 10,000	\$ 10,000	\$ -
1351	San Diego	Department 10 Trailer	D5020 Lighting & Branch Wiring	\$ 10,000	\$ 10,000	\$ -
1352	Santa Clara	Palo Alto Courthouse	D5020 Lighting & Branch Wiring	\$ 37,000	\$ 24,000	\$ 13,000
1353	Santa Clara	Sunnyvale Courthouse	D5020 Lighting & Branch Wiring	\$ 9,000	\$ 9,000	\$ -
1354	Ventura	Hall of Justice	D5020 Lighting & Branch Wiring	\$ 2,843,000	\$ 1,986,000	\$ 857,000
1355	Santa Barbara	Santa Maria Courts, Bldg F	D2010 Plumbing Fixtures	\$ 18,000	\$ 18,000	\$ -
1356	Los Angeles	Alhambra Courthouse	D2010 Plumbing Fixtures	\$ 338,000	\$ 290,000	\$ 47,000
1357	Los Angeles	Central Arraignment Courts	D2010 Plumbing Fixtures	\$ 437,000	\$ 394,000	\$ 43,000
1358	Santa Clara	Hall of Justice (East)	G20 Site Improvements	\$ 5,460,000	\$ 5,460,000	\$ -
1359	Solano	Solano Justice Building	D3010 Energy Supply	\$ 7,000	\$ 5,000	\$ 2,000
1360	Alameda	Wiley W. Manuel Courthouse	D3010 Energy Supply	\$ 20,000	\$ 17,000	\$ 3,000
1361	Kings	Corcoran Court	D2010 Plumbing Fixtures	\$ 50,000	\$ 44,000	\$ 6,000
1362	Los Angeles	Norwalk Courthouse	D3010 Energy Supply	\$ 394,000	\$ 335,000	\$ 59,000
1363	Los Angeles	Van Nuys Courthouse East	D3010 Energy Supply	\$ 18,000	\$ 16,000	\$ 2,000
1364	Los Angeles	Chatsworth Courthouse	D2010 Plumbing Fixtures	\$ 105,000	\$ 88,000	\$ 17,000
1365	Los Angeles	Alhambra Courthouse	D3010 Energy Supply	\$ 62,000	\$ 54,000	\$ 9,000

1366	Los Angeles	Pasadena Courthouse	D3010 Energy Supply	\$	70,000	\$	48,000	\$	21,000
1367	Los Angeles	Edmund D. Edelman Children's Court	D3010 Energy Supply	\$	69,000	\$	49,000	\$	21,000
1368	Los Angeles	Metropolitan Courthouse	D3010 Energy Supply	\$	15,000	\$	14,000	\$	1,000
1369	Merced	Downtown Merced Courthouse	D3010 Energy Supply	\$	7,000	\$	7,000	\$	-
1370	Sacramento	Gordon Schaber Sacramento Superior Court	G20 Site Improvements	\$	737,000	\$	737,000	\$	-
1371	San Bernardino	San Bernardino Courthouse	G2012 Paving & Surfacing	\$	83,000	\$	79,000	\$	4,000
1372	Santa Barbara	Santa Maria Courts Bldgs C + D	G2012 Paving & Surfacing	\$	16,000	\$	16,000	\$	-
1373	San Bernardino	Barstow Courthouse	G2012 Paving & Surfacing	\$	237,000	\$	185,000	\$	52,000
1374	Riverside	Corona	G2012 Paving & Surfacing	\$	21,000	\$	12,000	\$	10,000
1375	Solano	Hall of Justice	G2012 Paving & Surfacing	\$	120,000	\$	87,000	\$	33,000
1376	Solano	Solano Justice Building	G2012 Paving & Surfacing	\$	94,000	\$	71,000	\$	22,000
1377	Alameda	George E. McDonald Hall of Justice	G2012 Paving & Surfacing	\$	15,000	\$	15,000	\$	-
1378	Amador	Amador County Courthouse	G2012 Paving & Surfacing	\$	8,000	\$	8,000	\$	-
1379	Butte	Butte County Courthouse	G2012 Paving & Surfacing	\$	109,000	\$	109,000	\$	-
1380	Contra Costa	Wakefield Taylor Courthouse	G2012 Paving & Surfacing	\$	24,000	\$	24,000	\$	-
1381	Contra Costa	Jail Annex	G2012 Paving & Surfacing	\$	8,000	\$	-	\$	7,000
1382	Contra Costa	Danville District Courthouse	G2012 Paving & Surfacing	\$	33,000	\$	33,000	\$	-
1383	Contra Costa	George D. Carroll Courthouse	G2012 Paving & Surfacing	\$	24,000	\$	18,000	\$	6,000
1384	Del Norte	Del Norte County Superior Court	G2012 Paving & Surfacing	\$	11,000	\$	7,000	\$	4,000
1385	El Dorado	Johnson Bldg.	G2012 Paving & Surfacing	\$	23,000	\$	23,000	\$	-
1386	Fresno	Fresno County Courthouse	G2012 Paving & Surfacing	\$	109,000	\$	104,000	\$	4,000
1387	Humboldt	Humboldt County Courthouse (Eureka)	G2012 Paving & Surfacing	\$	44,000	\$	15,000	\$	29,000
1388	Kern	Bakersfield Superior Court	G2012 Paving & Surfacing	\$	40,000	\$	25,000	\$	15,000
1389	Kern	Shafter/Wasco Courts Bldg.	G2012 Paving & Surfacing	\$	94,000	\$	84,000	\$	9,000
1390	Kern	Mojave-Main Court Facility	G2012 Paving & Surfacing	\$	87,000	\$	42,000	\$	45,000
1391	Kings	Avenal Court	G2012 Paving & Surfacing	\$	18,000	\$	10,000	\$	8,000
1392	Kings	Corcoran Court	G2012 Paving & Surfacing	\$	30,000	\$	26,000	\$	4,000
1393	Los Angeles	Compton Courthouse	G2012 Paving & Surfacing	\$	137,000	\$	91,000	\$	46,000
1394	Los Angeles	Norwalk Courthouse	G2012 Paving & Surfacing	\$	13,000	\$	11,000	\$	2,000
1395	Los Angeles	Downey Courthouse	G2012 Paving & Surfacing	\$	15,000	\$	12,000	\$	2,000
1396	Los Angeles	Beverly Hills Courthouse	G2012 Paving & Surfacing	\$	49,000	\$	39,000	\$	10,000
1397	Los Angeles	Airport Courthouse	G2012 Paving & Surfacing	\$	64,000	\$	49,000	\$	15,000
1398	Los Angeles	Van Nuys Courthouse East	G2012 Paving & Surfacing	\$	39,000	\$	35,000	\$	4,000
1399	Los Angeles	Michael D. Antonovich Antelope Valley	G2012 Paving & Surfacing	\$	11,000	\$	8,000	\$	3,000
1400	Los Angeles	Torrance Courthouse	G2012 Paving & Surfacing	\$	294,000	\$	266,000	\$	28,000
1401	Los Angeles	Inglewood Juvenile Court	G2012 Paving & Surfacing	\$	15,000	\$	12,000	\$	3,000
1402	Los Angeles	Burbank Courthouse	G2012 Paving & Surfacing	\$	68,000	\$	62,000	\$	6,000
1403	Los Angeles	Edmund D. Edelman Children's Court	G2012 Paving & Surfacing	\$	10,000	\$	7,000	\$	3,000
1404	Los Angeles	Pomona Courthouse South	G2012 Paving & Surfacing	\$	7,000	\$	7,000	\$	1,000
1405	Madera	Sierra Courthouse	G2012 Paving & Surfacing	\$	230,000	\$	157,000	\$	74,000
1406	Merced	Old Court	G2012 Paving & Surfacing	\$	24,000	\$	24,000	\$	-
1407	Mono	New Mammoth Lakes Parking Lot	G2012 Paving & Surfacing	\$	11,000	\$	11,000	\$	-
1408	Monterey	Marina Courthouse	G2012 Paving & Surfacing	\$	63,000	\$	63,000	\$	-
1409	Nevada	Nevada City Courthouse	G2012 Paving & Surfacing	\$	23,000	\$	15,000	\$	8,000
1410	Placer	Juvenile Hall	G2012 Paving & Surfacing	\$	28,000	\$	4,000	\$	24,000
1411	Placer	Bill Santucci Justice Center	G2012 Paving & Surfacing	\$	88,000	\$	88,000	\$	-
1412	San Diego	Kearny Mesa Court	G2012 Paving & Surfacing	\$	29,000	\$	29,000	\$	-
1413	San Diego	North County Regional Center - North	G2012 Paving & Surfacing	\$	11,000	\$	11,000	\$	-
1414	San Mateo	Central Branch	G2012 Paving & Surfacing	\$	156,000	\$	156,000	\$	-
1415	San Mateo	Northern Branch Courthouse	G2012 Paving & Surfacing	\$	261,000	\$	217,000	\$	44,000
1416	Santa Clara	Hall of Justice (East)	G2012 Paving & Surfacing	\$	35,000	\$	35,000	\$	-
1417	Santa Clara	Hall of Justice (West)	G20 Site Improvements	\$	49,000	\$	49,000	\$	-
1418	Santa Clara	Hall of Justice (West)	G2012 Paving & Surfacing	\$	12,000	\$	12,000	\$	-
1419	Santa Clara	Downtown Superior Court	G2012 Paving & Surfacing	\$	35,000	\$	35,000	\$	-
1420	Santa Clara	Historic Courthouse	G2012 Paving & Surfacing	\$	23,000	\$	23,000	\$	-
1421	Santa Clara	Palo Alto Courthouse	G2012 Paving & Surfacing	\$	28,000	\$	18,000	\$	10,000
1422	Santa Clara	Sunnyvale Courthouse	G2012 Paving & Surfacing	\$	14,000	\$	14,000	\$	-
1423	Santa Clara	Santa Clara Courthouse	G2012 Paving & Surfacing	\$	52,000	\$	52,000	\$	-
1424	Tulare	Visalia Superior Court	G2012 Paving & Surfacing	\$	100,000	\$	32,000	\$	68,000
1425	Ventura	Hall of Justice	G2012 Paving & Surfacing	\$	229,000	\$	160,000	\$	69,000
1426	Ventura	East County Courthouse	G2012 Paving & Surfacing	\$	218,000	\$	135,000	\$	83,000
1427	Riverside	Hall of Justice	G2012 Paving & Surfacing	\$	19,000	\$	19,000	\$	-
1428	San Luis Obispo	Courthouse Annex	G2012 Paving & Surfacing	\$	74,000	\$	37,000	\$	37,000
1429	Los Angeles	Los Padrinos Juvenile Court	D2010 Plumbing Fixtures	\$	36,000	\$	11,000	\$	26,000
1430	Riverside	Family Law Court	D5092 Emergency Light & Power Systems	\$	178,000	\$	178,000	\$	-
1431	Riverside	Southwest Justice Center	D5092 Emergency Light & Power Systems	\$	93,000	\$	69,000	\$	23,000
1432	San Bernardino	Juvenile Dependency Courthouse	D2010 Plumbing Fixtures	\$	10,000	\$	6,000	\$	5,000
1433	San Bernardino	Juvenile Dependency Courthouse	D5092 Emergency Light & Power Systems	\$	22,000	\$	12,000	\$	10,000
1434	San Luis Obispo	Paso Robles Courthouse	D5092 Emergency Light & Power Systems	\$	29,000	\$	29,000	\$	-
1435	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D2010 Plumbing Fixtures	\$	38,000	\$	38,000	\$	-
1436	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D5092 Emergency Light & Power Systems	\$	20,000	\$	20,000	\$	-
1437	Nevada	Nevada City Courthouse Annex	G2012 Paving & Surfacing	\$	38,000	\$	16,000	\$	22,000
1438	Los Angeles	Glendale Courthouse	G2012 Paving & Surfacing	\$	399,000	\$	361,000	\$	38,000
1439	Los Angeles	Metropolitan Courthouse	G2012 Paving & Surfacing	\$	114,000	\$	108,000	\$	6,000
1440	Riverside	Larson Justice Center	G2012 Paving & Surfacing	\$	491,000	\$	397,000	\$	94,000
1441	Los Angeles	Norwalk Courthouse	G20 Site Improvements	\$	404,000	\$	343,000	\$	60,000

1442	San Bernardino	Rancho Cucamonga Courthouse	G2012 Paving & Surfacing	\$ 282,000	\$ 214,000	\$ 67,000
1443	Los Angeles	Santa Monica Courthouse	G2012 Paving & Surfacing	\$ 77,000	\$ 60,000	\$ 17,000
1444	Santa Barbara	Santa Maria Courts, Bldgs. A + B	D2010 Plumbing Fixtures	\$ 33,000	\$ 8,000	\$ 26,000
1445	Santa Barbara	Santa Maria Courts, Bldg G	D2010 Plumbing Fixtures	\$ 24,000	\$ 23,000	\$ 1,000
1446	Riverside	Family Law Court	D5020 Lighting & Branch Wiring	\$ 552,000	\$ 552,000	\$ -
1447	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D5020 Lighting & Branch Wiring	\$ 74,000	\$ 74,000	\$ -
1448	Los Angeles	Torrance Courthouse	B30 Roofing	\$ 919,000	\$ 831,000	\$ 88,000
1449	Santa Barbara	Santa Maria Courts Bldgs C + D	G20 Site Improvements	\$ 13,000	\$ 13,000	\$ -
1450	Contra Costa	Danville District Courthouse	G20 Site Improvements	\$ 418,000	\$ 418,000	\$ -
1451	Contra Costa	George D. Carroll Courthouse	G20 Site Improvements	\$ 11,000	\$ 8,000	\$ 3,000
1452	Los Angeles	Torrance Courthouse	G20 Site Improvements	\$ 130,000	\$ 117,000	\$ 12,000
1453	Los Angeles	Monrovia Training Center	G20 Site Improvements	\$ 63,000	\$ 44,000	\$ 19,000
1454	Placer	Historic Courthouse	D2010 Plumbing Fixtures	\$ 7,000	\$ 5,000	\$ 2,000
1455	San Francisco	Civic Center Courthouse	D2010 Plumbing Fixtures	\$ 61,000	\$ 61,000	\$ -
1456	Ventura	Juvenile Courthouse	C1020 Interior Doors	\$ 73,000	\$ 23,000	\$ 50,000
1457	Riverside	Family Law Court	D2010 Plumbing Fixtures	\$ 146,000	\$ 146,000	\$ -
1458	San Luis Obispo	Paso Robles Courthouse	G2012 Paving & Surfacing	\$ 44,000	\$ 44,000	\$ -
1459	Alameda	Fremont Hall of Justice	G20 Site Improvements	\$ 662,000	\$ 526,000	\$ 136,000
1460	Los Angeles	Inglewood Courthouse	G20 Site Improvements	\$ 107,000	\$ 80,000	\$ 27,000
1461	Los Angeles	Metropolitan Courthouse	G20 Site Improvements	\$ 172,000	\$ 162,000	\$ 9,000
1462	Los Angeles	East Los Angeles Courthouse	G20 Site Improvements	\$ 20,000	\$ 16,000	\$ 5,000
1463	Los Angeles	Pomona Courthouse South	G20 Site Improvements	\$ 47,000	\$ 43,000	\$ 4,000
1464	Madera	Sierra Courthouse	G20 Site Improvements	\$ 17,000	\$ 12,000	\$ 6,000
1465	Sacramento	Carol Miller Justice Center Court Fac	G20 Site Improvements	\$ 32,000	\$ 31,000	\$ 1,000
1466	Santa Clara	Morgan Hill Courthouse	G20 Site Improvements	\$ 64,000	\$ 64,000	\$ -
1467	San Bernardino	San Bernardino Courthouse	C2010 Stair Construction	\$ 91,000	\$ 87,000	\$ 4,000
1468	Solano	Hall of Justice	C2010 Stair Construction	\$ 25,000	\$ 18,000	\$ 7,000
1469	Solano	Solano Justice Building	C2010 Stair Construction	\$ 10,000	\$ 8,000	\$ 2,000
1470	Alameda	Wiley W. Manuel Courthouse	C2010 Stair Construction	\$ 10,000	\$ 8,000	\$ 2,000
1471	Alameda	Hayward Hall of Justice	C2010 Stair Construction	\$ 194,000	\$ 171,000	\$ 23,000
1472	Alameda	Berkeley Courthouse	C2010 Stair Construction	\$ 6,000	\$ 6,000	\$ -
1473	Alameda	Fremont Hall of Justice	C2010 Stair Construction	\$ 27,000	\$ 21,000	\$ 5,000
1474	Butte	Butte County Courthouse	C2010 Stair Construction	\$ 17,000	\$ 17,000	\$ -
1475	Contra Costa	Family Law Center	C2010 Stair Construction	\$ 34,000	\$ 34,000	\$ -
1476	Fresno	Fresno County Courthouse	C2010 Stair Construction	\$ 566,000	\$ 543,000	\$ 23,000
1477	Humboldt	Humboldt County Courthouse (Eureka)	C2010 Stair Construction	\$ 178,000	\$ 59,000	\$ 119,000
1478	Los Angeles	Compton Courthouse	C2010 Stair Construction	\$ 404,000	\$ 267,000	\$ 137,000
1479	Los Angeles	Norwalk Courthouse	C2010 Stair Construction	\$ 117,000	\$ 100,000	\$ 18,000
1480	Los Angeles	Bellflower Courthouse	C2010 Stair Construction	\$ 43,000	\$ 33,000	\$ 9,000
1481	Los Angeles	Santa Monica Courthouse	C2010 Stair Construction	\$ 64,000	\$ 50,000	\$ 14,000
1482	Los Angeles	Van Nuys Courthouse East	C2010 Stair Construction	\$ 134,000	\$ 120,000	\$ 14,000
1483	Los Angeles	Torrance Courthouse	C2010 Stair Construction	\$ 80,000	\$ 72,000	\$ 8,000
1484	Los Angeles	Alhambra Courthouse	C2010 Stair Construction	\$ 89,000	\$ 76,000	\$ 12,000
1485	Los Angeles	Pasadena Courthouse	C2010 Stair Construction	\$ 98,000	\$ 68,000	\$ 30,000
1486	Los Angeles	Stanley Mosk Courthouse	C2010 Stair Construction	\$ 318,000	\$ 309,000	\$ 9,000
1487	Los Angeles	Clara Shortridge Foltz Criminal Justice	C2010 Stair Construction	\$ 1,173,000	\$ 807,000	\$ 366,000
1488	Los Angeles	El Monte Courthouse	C2010 Stair Construction	\$ 17,000	\$ 10,000	\$ 7,000
1489	Los Angeles	Eastlake Juvenile Court	C2010 Stair Construction	\$ 17,000	\$ 9,000	\$ 8,000
1490	Los Angeles	Metropolitan Courthouse	C2010 Stair Construction	\$ 257,000	\$ 243,000	\$ 14,000
1491	Los Angeles	Central Arraignment Courts	C2010 Stair Construction	\$ 58,000	\$ 52,000	\$ 6,000
1492	Los Angeles	East Los Angeles Courthouse	C2010 Stair Construction	\$ 98,000	\$ 76,000	\$ 22,000
1493	Los Angeles	West Covina Courthouse	C2010 Stair Construction	\$ 23,000	\$ 19,000	\$ 4,000
1494	Nevada	Nevada City Courthouse	C2010 Stair Construction	\$ 271,000	\$ 178,000	\$ 94,000
1495	Nevada	Nevada City Courthouse Annex	C2010 Stair Construction	\$ 40,000	\$ 17,000	\$ 23,000
1496	Sacramento	Gordon Schaber Sacramento Superior	C2010 Stair Construction	\$ 437,000	\$ 437,000	\$ -
1497	San Diego	South County Regional Center	C2010 Stair Construction	\$ 44,000	\$ 16,000	\$ 29,000
1498	Santa Clara	Downtown Superior Court	C2010 Stair Construction	\$ 36,000	\$ 36,000	\$ -
1499	Santa Clara	Santa Clara Courthouse	C2010 Stair Construction	\$ 7,000	\$ 7,000	\$ -
1500	Ventura	Hall of Justice	C2010 Stair Construction	\$ 53,000	\$ 37,000	\$ 16,000
1501	Orange	North Justice Center	C2010 Stair Construction	\$ 55,000	\$ 50,000	\$ 5,000
1502	Santa Barbara	Santa Maria Courts, Bldg G	C2010 Stair Construction	\$ 70,000	\$ 68,000	\$ 2,000
1503	Riverside	Hall of Justice	C2010 Stair Construction	\$ 10,000	\$ 10,000	\$ -
1504	San Luis Obispo	Courthouse Annex	C2010 Stair Construction	\$ 105,000	\$ 52,000	\$ 53,000
1505	San Bernardino	Joshua Tree Courthouse	C2010 Stair Construction	\$ 12,000	\$ 4,000	\$ 8,000
1506	Riverside	Riverside Juvenile Justice Trailers	B2020 Exterior Windows	\$ 12,000	\$ 12,000	\$ -
1507	Riverside	Riverside Juvenile Justice Trailers	B2020 Exterior Windows	\$ 12,000	\$ 12,000	\$ -
1508	San Bernardino	San Bernardino Courthouse	B2030 Exterior Doors	\$ 56,000	\$ 54,000	\$ 2,000
1509	Santa Barbara	Santa Maria Courts Bldgs C + D	B2020 Exterior Windows	\$ 154,000	\$ 154,000	\$ -
1510	Santa Barbara	Santa Maria Courts Bldgs C + D	B2030 Exterior Doors	\$ 145,000	\$ 145,000	\$ -
1511	San Bernardino	Barstow Courthouse	B2030 Exterior Doors	\$ 20,000	\$ 16,000	\$ 4,000
1512	Santa Barbara	Santa Maria Courts, Bldg F	B2020 Exterior Windows	\$ 28,000	\$ 28,000	\$ -
1513	Santa Barbara	Santa Maria Courts, Bldg F	B2030 Exterior Doors	\$ 17,000	\$ 17,000	\$ -
1514	San Luis Obispo	1070 Palm St.	B2020 Exterior Windows	\$ 11,000	\$ 11,000	\$ -
1515	San Luis Obispo	1070 Palm St.	B2030 Exterior Doors	\$ 7,000	\$ 7,000	\$ -
1516	Solano	Hall of Justice	B2030 Exterior Doors	\$ 53,000	\$ 38,000	\$ 14,000
1517	San Bernardino	Rancho Cucamonga Courthouse	B2020 Exterior Windows	\$ 2,576,000	\$ 1,959,000	\$ 617,000

1518	San Bernardino	Rancho Cucamonga Courthouse	B2030 Exterior Doors	\$	24,000	\$	18,000	\$	6,000
1519	San Bernardino	Rancho Cucamonga Courthouse	B2039 Other Doors & Entrances	\$	13,000	\$	10,000	\$	3,000
1520	Riverside	Riverside Juvenile Court	B2030 Exterior Doors	\$	9,000	\$	4,000	\$	4,000
1521	Solano	Solano Justice Building	B2030 Exterior Doors	\$	19,000	\$	15,000	\$	5,000
1522	San Bernardino	Victorville Courthouse-Dept. N-1	B2030 Exterior Doors	\$	29,000	\$	18,000	\$	10,000
1523	Santa Barbara	Santa Maria Courts, Bldgs. A + B	B2020 Exterior Windows	\$	20,000	\$	5,000	\$	15,000
1524	Santa Barbara	Santa Maria Courts, Bldgs. A + B	B2030 Exterior Doors	\$	20,000	\$	5,000	\$	16,000
1525	Alameda	Hayward Hall of Justice	B2010 Exterior Walls	\$	97,000	\$	86,000	\$	11,000
1526	Alameda	George E. McDonald Hall of Justice	B2030 Exterior Doors	\$	8,000	\$	8,000	\$	-
1527	Alameda	George E. McDonald Hall of Justice	B2034 Overhead Doors	\$	16,000	\$	16,000	\$	-
1528	Alameda	Berkeley Courthouse	B2020 Exterior Windows	\$	94,000	\$	94,000	\$	-
1529	Alameda	Fremont Hall of Justice	B2030 Exterior Doors	\$	66,000	\$	53,000	\$	14,000
1530	Alameda	Fremont Hall of Justice	B2034 Overhead Doors	\$	23,000	\$	18,000	\$	5,000
1531	Amador	Amador County Courthouse	B2020 Exterior Windows	\$	24,000	\$	24,000	\$	-
1532	Contra Costa	Wakefield Taylor Courthouse	B2020 Exterior Windows	\$	68,000	\$	68,000	\$	-
1533	Contra Costa	Bray Courts	B2020 Exterior Windows	\$	1,691,000	\$	1,446,000	\$	245,000
1534	Contra Costa	Bray Courts	B2030 Exterior Doors	\$	16,000	\$	14,000	\$	2,000
1535	Contra Costa	Danville District Courthouse	B2030 Exterior Doors	\$	8,000	\$	8,000	\$	-
1536	Contra Costa	George D. Carroll Courthouse	B2020 Exterior Windows	\$	113,000	\$	85,000	\$	28,000
1537	Contra Costa	George D. Carroll Courthouse	B2030 Exterior Doors	\$	8,000	\$	6,000	\$	2,000
1538	Del Norte	Del Norte County Superior Court	B2030 Exterior Doors	\$	8,000	\$	5,000	\$	3,000
1539	El Dorado	Cameron Park	B2030 Exterior Doors	\$	9,000	\$	9,000	\$	-
1540	El Dorado	Johnson Bldg.	B2030 Exterior Doors	\$	15,000	\$	15,000	\$	-
1541	Fresno	B.F. Sisk Federal Courthouse	B2020 Exterior Windows	\$	1,576,000	\$	1,576,000	\$	-
1542	Fresno	B.F. Sisk Federal Courthouse	B2030 Exterior Doors	\$	7,000	\$	7,000	\$	-
1543	Imperial	Imperial County Courthouse	B2030 Exterior Doors	\$	30,000	\$	30,000	\$	-
1544	Kern	Bakersfield Superior Court	B2030 Exterior Doors	\$	33,000	\$	21,000	\$	12,000
1545	Kern	Bakersfield Justice Bldg.	B2030 Exterior Doors	\$	40,000	\$	21,000	\$	20,000
1546	Kern	Bakersfield Justice Bldg.	B2034 Overhead Doors	\$	20,000	\$	10,000	\$	10,000
1547	Kern	Bakersfield Juvenile Center	B2030 Exterior Doors	\$	31,000	\$	21,000	\$	10,000
1548	Kern	Bakersfield Juvenile Center	B2034 Overhead Doors	\$	20,000	\$	13,000	\$	7,000
1549	Kern	Delano/North Kern Court	B2030 Exterior Doors	\$	18,000	\$	14,000	\$	3,000
1550	Kern	Shafter/Wasco Courts Bldg.	B2030 Exterior Doors	\$	18,000	\$	16,000	\$	2,000
1551	Kern	Taft Courts Bldg.	B2030 Exterior Doors	\$	8,000	\$	8,000	\$	-
1552	Kern	Arvin/ Lamont Branch	B2030 Exterior Doors	\$	8,000	\$	5,000	\$	3,000
1553	Kings	Probation Building	B2020 Exterior Windows	\$	57,000	\$	7,000	\$	50,000
1554	Kings	Probation Building	B2030 Exterior Doors	\$	14,000	\$	2,000	\$	12,000
1555	Kings	Avenal Court	B2030 Exterior Doors	\$	14,000	\$	8,000	\$	6,000
1556	Lake	South Civic Center	B2030 Exterior Doors	\$	10,000	\$	7,000	\$	3,000
1557	Los Angeles	San Fernando Courthouse	B2020 Exterior Windows	\$	600,000	\$	500,000	\$	99,000
1558	Los Angeles	San Fernando Courthouse	B2030 Exterior Doors	\$	7,000	\$	6,000	\$	1,000
1559	Los Angeles	San Fernando Courthouse	B2034 Overhead Doors	\$	115,000	\$	96,000	\$	19,000
1560	Los Angeles	Santa Clarita Courthouse	B2030 Exterior Doors	\$	10,000	\$	9,000	\$	1,000
1561	Los Angeles	Santa Clarita Courthouse	B2034 Overhead Doors	\$	16,000	\$	14,000	\$	2,000
1562	Los Angeles	Alfred J. McCourtney Juvenile Justice	B2030 Exterior Doors	\$	17,000	\$	12,000	\$	5,000
1563	Los Angeles	Sylmar Juvenile Court	B2020 Exterior Windows	\$	35,000	\$	12,000	\$	23,000
1564	Los Angeles	Compton Courthouse	B2030 Exterior Doors	\$	77,000	\$	51,000	\$	26,000
1565	Los Angeles	Los Padrinos Juvenile Court	B2020 Exterior Windows	\$	37,000	\$	11,000	\$	26,000
1566	Los Angeles	Los Padrinos Juvenile Court	B2030 Exterior Doors	\$	12,000	\$	3,000	\$	8,000
1567	Los Angeles	Norwalk Courthouse	B2030 Exterior Doors	\$	69,000	\$	59,000	\$	10,000
1568	Los Angeles	Bellflower Courthouse	B2030 Exterior Doors	\$	242,000	\$	189,000	\$	53,000
1569	Los Angeles	Bellflower Courthouse	B2034 Overhead Doors	\$	7,000	\$	5,000	\$	1,000
1570	Los Angeles	Downey Courthouse	B2030 Exterior Doors	\$	35,000	\$	29,000	\$	6,000
1571	Los Angeles	Santa Monica Courthouse	B2030 Exterior Doors	\$	33,000	\$	26,000	\$	7,000
1572	Los Angeles	Beverly Hills Courthouse	B2030 Exterior Doors	\$	41,000	\$	32,000	\$	8,000
1573	Los Angeles	Beverly Hills Courthouse	B2034 Overhead Doors	\$	34,000	\$	27,000	\$	7,000
1574	Los Angeles	Van Nuys Courthouse East	B2030 Exterior Doors	\$	15,000	\$	14,000	\$	2,000
1575	Los Angeles	Van Nuys Courthouse East	B2034 Overhead Doors	\$	6,000	\$	6,000	\$	1,000
1576	Los Angeles	Van Nuys Courthouse East	B2039 Other Doors & Entrances	\$	39,000	\$	35,000	\$	4,000
1577	Los Angeles	Van Nuys Courthouse West	B2039 Other Doors & Entrances	\$	16,000	\$	13,000	\$	3,000
1578	Los Angeles	Torrance Courthouse	B2030 Exterior Doors	\$	68,000	\$	62,000	\$	7,000
1579	Los Angeles	Inglewood Courthouse	B2010 Exterior Walls	\$	24,000	\$	18,000	\$	6,000
1580	Los Angeles	Inglewood Courthouse	B2030 Exterior Doors	\$	36,000	\$	27,000	\$	9,000
1581	Los Angeles	Inglewood Courthouse	B2034 Overhead Doors	\$	34,000	\$	25,000	\$	9,000
1582	Los Angeles	Glendale Courthouse	B2030 Exterior Doors	\$	20,000	\$	18,000	\$	2,000
1583	Los Angeles	Glendale Courthouse	B2039 Other Doors & Entrances	\$	15,000	\$	13,000	\$	1,000
1584	Los Angeles	Alhambra Courthouse	B2030 Exterior Doors	\$	90,000	\$	77,000	\$	13,000
1585	Los Angeles	Stanley Mosk Courthouse	B2030 Exterior Doors	\$	103,000	\$	100,000	\$	3,000
1586	Los Angeles	Stanley Mosk Courthouse	B2034 Overhead Doors	\$	23,000	\$	23,000	\$	1,000
1587	Los Angeles	Clara Shortridge Foltz Criminal Justice	B2030 Exterior Doors	\$	145,000	\$	100,000	\$	45,000
1588	Los Angeles	Clara Shortridge Foltz Criminal Justice	B2034 Overhead Doors	\$	76,000	\$	52,000	\$	24,000
1589	Los Angeles	Monrovia Training Center	B2020 Exterior Windows	\$	51,000	\$	36,000	\$	15,000
1590	Los Angeles	Eastlake Juvenile Court	B2020 Exterior Windows	\$	37,000	\$	20,000	\$	17,000
1591	Los Angeles	Metropolitan Courthouse	B2030 Exterior Doors	\$	140,000	\$	132,000	\$	8,000
1592	Los Angeles	Metropolitan Courthouse	B2034 Overhead Doors	\$	26,000	\$	24,000	\$	1,000
1593	Los Angeles	Central Arraignment Courts	B2020 Exterior Windows	\$	3,377,000	\$	3,047,000	\$	330,000

1594	Los Angeles	Central Arraignment Courts	B2030 Exterior Doors	\$ 136,000	\$ 122,000	\$ 13,000
1595	Los Angeles	Central Arraignment Courts	B2034 Overhead Doors	\$ 9,000	\$ 8,000	\$ 1,000
1596	Los Angeles	East Los Angeles Courthouse	B2034 Overhead Doors	\$ 46,000	\$ 36,000	\$ 10,000
1597	Los Angeles	Pomona Courthouse South	B2030 Exterior Doors	\$ 22,000	\$ 20,000	\$ 2,000
1598	Los Angeles	Pomona Courthouse South	B2034 Overhead Doors	\$ 13,000	\$ 12,000	\$ 1,000
1599	Napa	Criminal Court Building	B2020 Exterior Windows	\$ 416,000	\$ 416,000	\$ -
1600	Nevada	Nevada City Courthouse	B2030 Exterior Doors	\$ 12,000	\$ 8,000	\$ 4,000
1601	Nevada	Nevada City Courthouse Annex	B2034 Overhead Doors	\$ 12,000	\$ 5,000	\$ 7,000
1602	Orange	Central Justice Center	G2020 Exterior Windows	\$ 18,300,000	\$ 16,700,000	\$ 1,600,000
1603	Orange	Central Justice Center	G20 Site Improvements	\$ 119,000	\$ 108,000	\$ 10,000
1604	Orange	Civil Complex Center ("CXC")	B2034 Overhead Doors	\$ 6,000	\$ 6,000	\$ -
1605	Orange	North Justice Center	B2030 Exterior Doors	\$ 6,000	\$ 6,000	\$ 1,000
1606	Placer	Historic Courthouse	B2030 Exterior Doors	\$ 122,000	\$ 94,000	\$ 28,000
1607	Sacramento	Gordon Schaber Sacramento Superior	B2034 Overhead Doors	\$ 12,000	\$ 12,000	\$ -
1608	Sacramento	Carol Miller Justice Center Court Fac	B2010 Exterior Walls	\$ 18,000	\$ 18,000	\$ -
1609	San Diego	Kearny Mesa Court	B2030 Exterior Doors	\$ 14,000	\$ 14,000	\$ -
1610	San Diego	Kearny Mesa Traffic Court KM3 Trail	B2020 Exterior Windows	\$ 7,000	\$ 7,000	\$ -
1611	San Diego	Kearny Mesa Traffic Court KM3 Trail	B2030 Exterior Doors	\$ 11,000	\$ 11,000	\$ -
1612	San Diego	Kearny Mesa Traffic Court KM4 Trail	B2020 Exterior Windows	\$ 7,000	\$ 7,000	\$ -
1613	San Diego	Kearny Mesa Traffic Court KM5 & KM	B2020 Exterior Windows	\$ 7,000	\$ 7,000	\$ -
1614	San Diego	Juvenile Court	B2030 Exterior Doors	\$ 11,000	\$ 8,000	\$ 3,000
1615	San Diego	Department 9 Trailer	B2020 Exterior Windows	\$ 11,000	\$ 11,000	\$ -
1616	San Diego	Department 9 Trailer	B2030 Exterior Doors	\$ 8,000	\$ 8,000	\$ -
1617	San Diego	Department 10 Trailer	B2020 Exterior Windows	\$ 11,000	\$ 11,000	\$ -
1618	San Diego	Department 10 Trailer	B2030 Exterior Doors	\$ 8,000	\$ 8,000	\$ -
1619	San Diego	North County Regional Center - Anne	B2030 Exterior Doors	\$ 8,000	\$ 8,000	\$ -
1620	San Diego	Trailer - Dept 34	B2020 Exterior Windows	\$ 20,000	\$ 20,000	\$ -
1621	San Diego	Trailer - Dept 35	B2020 Exterior Windows	\$ 20,000	\$ 20,000	\$ -
1622	San Diego	Trailer - Storage A	B2020 Exterior Windows	\$ 9,000	\$ 9,000	\$ -
1623	San Diego	Trailer - Family Support	B2020 Exterior Windows	\$ 20,000	\$ 20,000	\$ -
1624	San Diego	Trailer - Family Support	B2030 Exterior Doors	\$ 8,000	\$ 8,000	\$ -
1625	San Diego	East County Regional Center	B2030 Exterior Doors	\$ 11,000	\$ 7,000	\$ 4,000
1626	San Mateo	Traffic/ Small Claims Annex	B2030 Exterior Doors	\$ 14,000	\$ 14,000	\$ -
1627	San Mateo	Northern Branch Courthouse	B2030 Exterior Doors	\$ 7,000	\$ 6,000	\$ 1,000
1628	Santa Clara	Hall of Justice (West)	B2030 Exterior Doors	\$ 9,000	\$ 9,000	\$ -
1629	Santa Clara	Downtown Superior Court	B2020 Exterior Windows	\$ 1,026,000	\$ 1,026,000	\$ -
1630	Santa Clara	Downtown Superior Court	B2030 Exterior Doors	\$ 9,000	\$ 9,000	\$ -
1631	Santa Clara	Santa Clara Courthouse	B2020 Exterior Windows	\$ 186,000	\$ 186,000	\$ -
1632	Tulare	Visalia Superior Court	B2034 Overhead Doors	\$ 8,000	\$ 3,000	\$ 5,000
1633	Alameda	Wiley W. Manuel Courthouse	B2030 Exterior Doors	\$ 55,000	\$ 46,000	\$ 9,000
1634	Alameda	Hayward Hall of Justice	B2030 Exterior Doors	\$ 35,000	\$ 31,000	\$ 4,000
1635	Los Angeles	East Los Angeles Courthouse	B2030 Exterior Doors	\$ 71,000	\$ 55,000	\$ 16,000
1636	Los Angeles	West Covina Courthouse	B2030 Exterior Doors	\$ 33,000	\$ 27,000	\$ 6,000
1637	Orange	Central Justice Center	B2030 Exterior Doors	\$ 233,000	\$ 212,000	\$ 21,000
1638	Orange	Civil Complex Center ("CXC")	B2030 Exterior Doors	\$ 14,000	\$ 14,000	\$ -
1639	Orange	West Justice Center	B2030 Exterior Doors	\$ 210,000	\$ 191,000	\$ 20,000
1640	Sacramento	Gordon Schaber Sacramento Superior	B2030 Exterior Doors	\$ 23,000	\$ 23,000	\$ -
1641	San Diego	North County Regional Center - Nort	B2030 Exterior Doors	\$ 49,000	\$ 49,000	\$ -
1642	Santa Clara	Historic Courthouse	B2030 Exterior Doors	\$ 30,000	\$ 30,000	\$ -
1643	Tulare	Visalia Superior Court	B2030 Exterior Doors	\$ 38,000	\$ 12,000	\$ 26,000
1644	Ventura	Hall of Justice	B2030 Exterior Doors	\$ 116,000	\$ 81,000	\$ 35,000
1645	Santa Barbara	Santa Maria Courts, Bldg G	B2030 Exterior Doors	\$ 27,000	\$ 26,000	\$ 1,000
1646	Santa Barbara	Santa Maria Courts, Bldg G	B2034 Overhead Doors	\$ 61,000	\$ 58,000	\$ 2,000
1647	San Bernardino	Joshua Tree Courthouse	B2030 Exterior Doors	\$ 17,000	\$ 6,000	\$ 11,000
1648	San Bernardino	Fontana Courthouse	B2030 Exterior Doors	\$ 11,000	\$ 9,000	\$ 2,000
1649	Orange	Central Justice Center	B2010 Exterior Walls	\$ 6,356,000	\$ 5,795,000	\$ 561,000
1650	San Bernardino	San Bernardino Courthouse	B2020 Exterior Windows	\$ 544,000	\$ 520,000	\$ 24,000
1651	Solano	Law and Justice Center	C1020 Interior Doors	\$ 19,000	\$ 2,000	\$ 17,000
1652	Santa Barbara	Santa Maria Courts, Bldgs. A + B	C1020 Interior Doors	\$ 24,000	\$ 6,000	\$ 19,000
1653	Orange	West Justice Center	C1020 Interior Doors	\$ 1,294,000	\$ 1,173,000	\$ 121,000
1654	Nevada	Joseph Center	C1020 Interior Doors	\$ 26,000	\$ 8,000	\$ 18,000
1655	Alameda	Fremont Hall of Justice	B2020 Exterior Windows	\$ 244,000	\$ 194,000	\$ 50,000
1656	Los Angeles	Alhambra Courthouse	B2020 Exterior Windows	\$ 2,607,000	\$ 2,242,000	\$ 365,000
1657	Madera	Sierra Courthouse	B2020 Exterior Windows	\$ 390,000	\$ 265,000	\$ 125,000
1658	Santa Clara	Hall of Justice (West)	B2020 Exterior Windows	\$ 408,000	\$ 408,000	\$ -
1659	Los Angeles	Compton Courthouse	G20 Site Improvements	\$ 215,000	\$ 142,000	\$ 73,000
1660	San Francisco	Civic Center Courthouse	C1020 Interior Doors	\$ 35,000	\$ 35,000	\$ -
1661	Santa Barbara	Santa Maria Courts Bldgs C + D	B2010 Exterior Walls	\$ 11,000	\$ 11,000	\$ -
1662	San Bernardino	Rancho Cucamonga Courthouse	B2010 Exterior Walls	\$ 364,000	\$ 277,000	\$ 87,000
1663	Contra Costa	Wakefield Taylor Courthouse	B2010 Exterior Walls	\$ 489,000	\$ 489,000	\$ -
1664	Los Angeles	Beverly Hills Courthouse	B2010 Exterior Walls	\$ 45,000	\$ 36,000	\$ 9,000
1665	Los Angeles	Chatsworth Courthouse	B2010 Exterior Walls	\$ 15,000	\$ 12,000	\$ 2,000
1666	Los Angeles	Edmund D. Edelman Children's Court	B2010 Exterior Walls	\$ 1,609,000	\$ 1,126,000	\$ 483,000
1667	Orange	Civil Complex Center ("CXC")	B2010 Exterior Walls	\$ 133,000	\$ 133,000	\$ -
1668	Orange	Betty Lou Lamoreaux Justice Center	B2010 Exterior Walls	\$ 63,000	\$ 50,000	\$ 13,000
1669	Sacramento	Gordon Schaber Sacramento Superior	B2010 Exterior Walls	\$ 71,000	\$ 71,000	\$ -

1670	Solano	Hall of Justice	B2020 Exterior Windows	\$ 1,650,000	\$ 1,202,000	\$ 449,000
1671	Contra Costa	Family Law Center	B2020 Exterior Windows	\$ 32,000	\$ 32,000	\$ -
1672	Humboldt	Humboldt County Courthouse (Eureka)	B2020 Exterior Windows	\$ 402,000	\$ 134,000	\$ 268,000
1673	Kern	Bakersfield Justice Bldg.	B2020 Exterior Windows	\$ 780,000	\$ 399,000	\$ 382,000
1674	Kern	Taft Courts Bldg.	B2020 Exterior Windows	\$ 56,000	\$ 56,000	\$ -
1675	Kings	Avenal Court	B2020 Exterior Windows	\$ 115,000	\$ 67,000	\$ 48,000
1676	Los Angeles	Compton Courthouse	B2020 Exterior Windows	\$ 1,928,000	\$ 1,275,000	\$ 653,000
1677	Los Angeles	Norwalk Courthouse	B2020 Exterior Windows	\$ 3,212,000	\$ 2,731,000	\$ 481,000
1678	Los Angeles	Santa Monica Courthouse	B2020 Exterior Windows	\$ 516,000	\$ 405,000	\$ 111,000
1679	Los Angeles	Inglewood Juvenile Court	B2020 Exterior Windows	\$ 169,000	\$ 137,000	\$ 33,000
1680	Los Angeles	Clara Shortridge Foltz Criminal Justice	B2020 Exterior Windows	\$ 24,900,000	\$ 17,100,000	\$ 7,800,000
1681	Los Angeles	Metropolitan Courthouse	B2020 Exterior Windows	\$ 840,000	\$ 794,000	\$ 46,000
1682	Los Angeles	Pomona Courthouse South	B2020 Exterior Windows	\$ 1,219,000	\$ 1,111,000	\$ 108,000
1683	Los Angeles	West Covina Courthouse	B2020 Exterior Windows	\$ 449,000	\$ 373,000	\$ 76,000
1684	Nevada	Nevada City Courthouse Annex	B2020 Exterior Windows	\$ 617,000	\$ 263,000	\$ 353,000
1685	Orange	Civil Complex Center ("CXC")	B2020 Exterior Windows	\$ 57,000	\$ 57,000	\$ -
1686	Orange	West Justice Center	B2010 Exterior Walls	\$ 172,000	\$ 156,000	\$ 16,000
1687	Orange	West Justice Center	B2020 Exterior Windows	\$ 1,401,000	\$ 1,270,000	\$ 131,000
1688	Sacramento	Gordon Schaber Sacramento Superior	B2020 Exterior Windows	\$ 7,615,000	\$ 7,615,000	\$ -
1689	San Diego	Juvenile Court	B2020 Exterior Windows	\$ 412,000	\$ 308,000	\$ 105,000
1690	San Diego	North County Regional Center - North	B2020 Exterior Windows	\$ 385,000	\$ 385,000	\$ -
1691	San Diego	South County Regional Center	B2020 Exterior Windows	\$ 1,430,000	\$ 513,000	\$ 918,000
1692	San Mateo	Traffic/ Small Claims Annex	B2020 Exterior Windows	\$ 100,000	\$ 100,000	\$ -
1693	San Mateo	Central Branch	B2020 Exterior Windows	\$ 203,000	\$ 203,000	\$ -
1694	San Mateo	Northern Branch Courthouse	B2020 Exterior Windows	\$ 602,000	\$ 501,000	\$ 101,000
1695	Los Angeles	Norwalk Courthouse	B2010 Exterior Walls	\$ 615,000	\$ 523,000	\$ 92,000
1696	Los Angeles	Torrance Courthouse	B2010 Exterior Walls	\$ 76,000	\$ 69,000	\$ 7,000
1697	Los Angeles	Eastlake Juvenile Court	B2010 Exterior Walls	\$ 183,000	\$ 100,000	\$ 83,000
1698	Los Angeles	Alfred J. McCourtney Juvenile Justice	B2020 Exterior Windows	\$ 539,000	\$ 372,000	\$ 167,000
1699	Tulare	Visalia Superior Court	B2020 Exterior Windows	\$ 3,201,000	\$ 1,035,000	\$ 2,166,000
1700	Fresno	Fresno County Courthouse	B2010 Exterior Walls	\$ 1,372,000	\$ 1,316,000	\$ 56,000
1701	Tulare	Visalia Superior Court	B2010 Exterior Walls	\$ 211,000	\$ 68,000	\$ 143,000
1702	San Bernardino	San Bernardino Courthouse	E1010 Equipment	\$ 841,000	\$ 805,000	\$ 37,000
1703	San Bernardino	Barstow Courthouse	B2020 Exterior Windows	\$ 256,000	\$ 199,000	\$ 56,000
1704	Riverside	Riverside Juvenile Court	B2020 Exterior Windows	\$ 241,000	\$ 119,000	\$ 122,000
1705	Solano	Solano Justice Building	B2020 Exterior Windows	\$ 303,000	\$ 231,000	\$ 72,000
1706	Solano	Solano Justice Building	E1010 Equipment	\$ 331,000	\$ 252,000	\$ 79,000
1707	Butte	Butte County Courthouse	E1010 Equipment	\$ 289,000	\$ 289,000	\$ -
1708	Los Angeles	Santa Clarita Courthouse	E1010 Equipment	\$ 108,000	\$ 95,000	\$ 12,000
1709	Los Angeles	Beverly Hills Courthouse	E1010 Equipment	\$ 194,000	\$ 154,000	\$ 40,000
1710	Los Angeles	Metropolitan Courthouse	E1010 Equipment	\$ 889,000	\$ 841,000	\$ 49,000
1711	Alameda	George E. McDonald Hall of Justice	B2020 Exterior Windows	\$ 194,000	\$ 194,000	\$ -
1712	Contra Costa	Jail Annex	B2020 Exterior Windows	\$ 179,000	\$ 11,000	\$ 169,000
1713	El Dorado	Cameron Park	B2020 Exterior Windows	\$ 43,000	\$ 43,000	\$ -
1714	Kern	Bakersfield Juvenile Center	B2020 Exterior Windows	\$ 428,000	\$ 286,000	\$ 142,000
1715	Kern	Delano/North Kern Court	B2020 Exterior Windows	\$ 210,000	\$ 170,000	\$ 41,000
1716	Kern	Shafter/Wasco Courts Bldg.	B2020 Exterior Windows	\$ 121,000	\$ 109,000	\$ 12,000
1717	Los Angeles	Santa Clarita Courthouse	B2020 Exterior Windows	\$ 76,000	\$ 68,000	\$ 9,000
1718	Los Angeles	Downey Courthouse	B2020 Exterior Windows	\$ 376,000	\$ 314,000	\$ 61,000
1719	Los Angeles	Santa Monica Courthouse	E1010 Equipment	\$ 303,000	\$ 238,000	\$ 65,000
1720	Los Angeles	Beverly Hills Courthouse	B2020 Exterior Windows	\$ 608,000	\$ 484,000	\$ 125,000
1721	Los Angeles	Van Nuys Courthouse East	B2020 Exterior Windows	\$ 242,000	\$ 218,000	\$ 25,000
1722	Los Angeles	Torrance Courthouse	B2020 Exterior Windows	\$ 1,258,000	\$ 1,137,000	\$ 120,000
1723	Los Angeles	Stanley Mosk Courthouse	B2020 Exterior Windows	\$ 6,073,000	\$ 5,907,000	\$ 166,000
1724	San Bernardino	Joshua Tree Courthouse	B2020 Exterior Windows	\$ 183,000	\$ 62,000	\$ 121,000
1725	San Bernardino	Fontana Courthouse	B2020 Exterior Windows	\$ 120,000	\$ 98,000	\$ 21,000
1726	San Luis Obispo	Courthouse Annex	B2020 Exterior Windows	\$ 1,352,000	\$ 673,000	\$ 680,000
1727	Kern	Bakersfield Superior Court	B2020 Exterior Windows	\$ 4,276,000	\$ 2,679,000	\$ 1,598,000
1728	Los Angeles	Inglewood Courthouse	B2020 Exterior Windows	\$ 1,354,000	\$ 1,010,000	\$ 345,000
1729	San Diego	East County Regional Center	B2020 Exterior Windows	\$ 2,597,000	\$ 1,758,000	\$ 838,000
1730	Los Angeles	Hall of Records	C1020 Interior Doors	\$ 49,000	\$ 5,000	\$ 44,000
1731	San Bernardino	San Bernardino Courthouse	B2010 Exterior Walls	\$ 55,000	\$ 53,000	\$ 2,000
1732	San Luis Obispo	1070 Palm St.	B2010 Exterior Walls	\$ 20,000	\$ 20,000	\$ -
1733	Solano	Hall of Justice	B2010 Exterior Walls	\$ 135,000	\$ 98,000	\$ 37,000
1734	Solano	Solano Justice Building	B2010 Exterior Walls	\$ 79,000	\$ 60,000	\$ 19,000
1735	Del Norte	Del Norte County Superior Court	B2010 Exterior Walls	\$ 25,000	\$ 15,000	\$ 10,000
1736	Humboldt	Humboldt County Courthouse (Eureka)	B2010 Exterior Walls	\$ 96,000	\$ 32,000	\$ 64,000
1737	Imperial	Imperial County Courthouse	B2010 Exterior Walls	\$ 73,000	\$ 73,000	\$ -
1738	Kern	Bakersfield Justice Bldg.	B2010 Exterior Walls	\$ 147,000	\$ 75,000	\$ 72,000
1739	Los Angeles	San Fernando Courthouse	B2010 Exterior Walls	\$ 11,000	\$ 9,000	\$ 2,000
1740	Los Angeles	Santa Monica Courthouse	B2010 Exterior Walls	\$ 27,000	\$ 21,000	\$ 6,000
1741	Los Angeles	Van Nuys Courthouse West	B2010 Exterior Walls	\$ 30,000	\$ 24,000	\$ 6,000
1742	Los Angeles	Burbank Courthouse	B2010 Exterior Walls	\$ 224,000	\$ 203,000	\$ 21,000
1743	Los Angeles	Glendale Courthouse	B2010 Exterior Walls	\$ 42,000	\$ 38,000	\$ 4,000
1744	Los Angeles	Pasadena Courthouse	B2010 Exterior Walls	\$ 112,000	\$ 78,000	\$ 34,000
1745	Los Angeles	Clara Shortridge Foltz Criminal Justice	B2010 Exterior Walls	\$ 479,000	\$ 329,000	\$ 149,000

1746	Los Angeles	Monrovia Training Center	B2010 Exterior Walls	\$ 37,000	\$ 26,000	\$ 11,000
1747	Los Angeles	El Monte Courthouse	B2010 Exterior Walls	\$ 87,000	\$ 51,000	\$ 37,000
1748	Los Angeles	West Covina Courthouse	B2010 Exterior Walls	\$ 37,000	\$ 31,000	\$ 6,000
1749	Madera	Sierra Courthouse	B2010 Exterior Walls	\$ 11,000	\$ 7,000	\$ 4,000
1750	Monterey	Marina Courthouse	B2010 Exterior Walls	\$ 21,000	\$ 21,000	\$ -
1751	Nevada	Nevada City Courthouse	B2010 Exterior Walls	\$ 127,000	\$ 83,000	\$ 44,000
1752	Nevada	Nevada City Courthouse Annex	B2010 Exterior Walls	\$ 101,000	\$ 43,000	\$ 58,000
1753	Orange	North Justice Center	B2010 Exterior Walls	\$ 110,000	\$ 100,000	\$ 11,000
1754	Placer	Historic Courthouse	B2010 Exterior Walls	\$ 78,000	\$ 60,000	\$ 18,000
1755	San Diego	Kearny Mesa Traffic Court KM3 Trail	B2010 Exterior Walls	\$ 12,000	\$ 12,000	\$ -
1756	San Diego	Kearny Mesa Traffic Court KM4 Trail	B2010 Exterior Walls	\$ 12,000	\$ 12,000	\$ -
1757	San Diego	Kearny Mesa Traffic Court KM5 & KM	B2010 Exterior Walls	\$ 12,000	\$ 12,000	\$ -
1758	San Diego	North County Regional Center - Nort	B2010 Exterior Walls	\$ 107,000	\$ 107,000	\$ -
1759	San Mateo	Northern Branch Courthouse	B2010 Exterior Walls	\$ 6,000	\$ 5,000	\$ 1,000
1760	Santa Clara	Historic Courthouse	B2010 Exterior Walls	\$ 279,000	\$ 279,000	\$ -
1761	Santa Cruz	Jury Assembly Room	B2010 Exterior Walls	\$ 1,708,000	\$ 1,708,000	\$ -
1762	San Mateo	Traffic/ Small Claims Annex	B2010 Exterior Walls	\$ 74,000	\$ 74,000	\$ -
1763	Riverside	Hall of Justice	B2010 Exterior Walls	\$ 14,000	\$ 14,000	\$ -
1764	San Bernardino	Fontana Courthouse	B2010 Exterior Walls	\$ 25,000	\$ 21,000	\$ 5,000
1765	Riverside	Larson Justice Center	B2010 Exterior Walls	\$ 26,000	\$ 21,000	\$ 5,000
1766	San Francisco	Civic Center Courthouse	B2010 Exterior Walls	\$ 89,000	\$ 89,000	\$ -
1767	Orange	Central Justice Center	C1020 Interior Doors	\$ 5,444,000	\$ 4,963,000	\$ 481,000
1768	Los Angeles	Torrance Courthouse	C1020 Interior Doors	\$ 1,758,000	\$ 1,590,000	\$ 168,000
1769	Riverside	Corona	B2020 Exterior Windows	\$ 467,000	\$ 252,000	\$ 214,000
1770	San Bernardino	Victorville Courthouse-Dept. N-1	B2020 Exterior Windows	\$ 57,000	\$ 37,000	\$ 20,000
1771	Alameda	Hayward Hall of Justice	B2020 Exterior Windows	\$ 590,000	\$ 521,000	\$ 69,000
1772	Kern	Arvin/ Lamont Branch	B2020 Exterior Windows	\$ 81,000	\$ 50,000	\$ 32,000
1773	Los Angeles	Bellflower Courthouse	B2020 Exterior Windows	\$ 152,000	\$ 118,000	\$ 33,000
1774	Los Angeles	Hall of Records	B2020 Exterior Windows	\$ 18,000	\$ 2,000	\$ 16,000
1775	Los Angeles	Glendale Courthouse	B2020 Exterior Windows	\$ 55,000	\$ 50,000	\$ 5,000
1776	Los Angeles	East Los Angeles Courthouse	B2020 Exterior Windows	\$ 70,000	\$ 54,000	\$ 16,000
1777	Merced	Downtown Merced Courthouse	B2020 Exterior Windows	\$ 705,000	\$ 705,000	\$ -
1778	Nevada	Nevada City Courthouse	B2020 Exterior Windows	\$ 24,000	\$ 16,000	\$ 8,000
1779	San Diego	North County Regional Center - Anne	B2020 Exterior Windows	\$ 18,000	\$ 18,000	\$ -
1780	Santa Clara	Hall of Justice (East)	B2020 Exterior Windows	\$ 41,000	\$ 41,000	\$ -
1781	Ventura	Hall of Justice	B2020 Exterior Windows	\$ 1,413,000	\$ 987,000	\$ 426,000
1782	Alameda	Wiley W. Manuel Courthouse	B2020 Exterior Windows	\$ 3,051,000	\$ 2,557,000	\$ 494,000
1783	Fresno	Fresno County Courthouse	B2020 Exterior Windows	\$ 1,960,000	\$ 1,880,000	\$ 80,000
1784	San Diego	Kearny Mesa Court	B2020 Exterior Windows	\$ 47,000	\$ 47,000	\$ -
1785	Solano	Hall of Justice	G20 Site Improvements	\$ 163,000	\$ 119,000	\$ 44,000
1786	Butte	Butte County Courthouse	G20 Site Improvements	\$ 50,000	\$ 50,000	\$ -
1787	Riverside	Larson Justice Center	G20 Site Improvements	\$ 15,000	\$ 12,000	\$ 3,000
1788	San Bernardino	San Bernardino Courthouse	C1020 Interior Doors	\$ 1,659,000	\$ 1,587,000	\$ 72,000
1789	Los Angeles	Inglewood Juvenile Court	C1020 Interior Doors	\$ 272,000	\$ 220,000	\$ 52,000
1790	Orange	Betty Lou Lamoreaux Justice Center	C1020 Interior Doors	\$ 70,000	\$ 56,000	\$ 14,000
1791	Los Angeles	Clara Shortridge Foltz Criminal Justice	G20 Site Improvements	\$ 1,249,000	\$ 859,000	\$ 390,000
1792	Kern	Bakersfield Superior Court	C1020 Interior Doors	\$ 2,230,000	\$ 1,397,000	\$ 833,000
1793	Los Angeles	Glendale Courthouse	C1020 Interior Doors	\$ 120,000	\$ 108,000	\$ 11,000
1794	Solano	Hall of Justice	E1010 Equipment	\$ 331,000	\$ 241,000	\$ 90,000
1795	Los Angeles	Van Nuys Courthouse West	E1010 Equipment	\$ 69,000	\$ 55,000	\$ 13,000
1796	Orange	Central Justice Center	E1010 Equipment	\$ 1,557,000	\$ 1,420,000	\$ 138,000
1797	Orange	Civil Complex Center ("CXC")	E1010 Equipment	\$ 49,000	\$ 49,000	\$ -
1798	Los Angeles	Chatsworth Courthouse	E1010 Equipment	\$ 90,000	\$ 76,000	\$ 15,000
1799	Los Angeles	Glendale Courthouse	E1010 Equipment	\$ 290,000	\$ 263,000	\$ 27,000
1800	Tulare	Visalia Superior Court	C1020 Interior Doors	\$ 1,347,000	\$ 435,000	\$ 912,000
1801	Sacramento	Gordon Schaber Sacramento Superior	C1020 Interior Doors	\$ 2,469,000	\$ 2,469,000	\$ -
1802	Santa Clara	Historic Courthouse	C1020 Interior Doors	\$ 756,000	\$ 756,000	\$ -
1803	San Bernardino	San Bernardino Courthouse	A10 Foundations	\$ 36,000	\$ 34,000	\$ 2,000
1804	Solano	Solano Justice Building	A10 Foundations	\$ 30,000	\$ 23,000	\$ 7,000
1805	Humboldt	Humboldt County Courthouse (Eureka	C1020 Interior Doors	\$ 1,220,000	\$ 407,000	\$ 813,000
1806	Santa Clara	Downtown Superior Court	C1020 Interior Doors	\$ 1,286,000	\$ 1,286,000	\$ -
1807	San Francisco	Hall of Justice	C1010 Interior Construction	\$ 275,000	\$ 64,000	\$ 211,000
1808	San Bernardino	San Bernardino Courthouse	C1010 Interior Construction	\$ 441,000	\$ 422,000	\$ 19,000
1809	Solano	Law and Justice Center	C1010 Interior Construction	\$ 40,000	\$ 5,000	\$ 35,000
1810	Santa Barbara	Santa Maria Courts Bldgs C + D	C1010 Interior Construction	\$ 179,000	\$ 179,000	\$ -
1811	San Bernardino	Barstow Courthouse	C1010 Interior Construction	\$ 18,000	\$ 14,000	\$ 4,000
1812	Santa Barbara	Santa Maria Courts, Bldg F	C1010 Interior Construction	\$ 28,000	\$ 28,000	\$ -
1813	San Luis Obispo	1070 Palm St.	C1010 Interior Construction	\$ 20,000	\$ 20,000	\$ -
1814	Riverside	Corona	C1010 Interior Construction	\$ 692,000	\$ 374,000	\$ 318,000
1815	Solano	Hall of Justice	C1010 Interior Construction	\$ 1,047,000	\$ 763,000	\$ 285,000
1816	Riverside	Riverside Juvenile Court	C1010 Interior Construction	\$ 32,000	\$ 16,000	\$ 16,000
1817	Solano	Solano Justice Building	C1010 Interior Construction	\$ 49,000	\$ 37,000	\$ 12,000
1818	San Bernardino	Victorville Courthouse-Dept. N-1	C1010 Interior Construction	\$ 53,000	\$ 34,000	\$ 19,000
1819	Santa Barbara	Santa Maria Courts, Bldgs. A + B	C1010 Interior Construction	\$ 38,000	\$ 9,000	\$ 29,000
1820	Contra Costa	George D. Carroll Courthouse	C1010 Interior Construction	\$ 2,688,000	\$ 2,016,000	\$ 672,000
1821	Humboldt	Humboldt County Courthouse (Eureka	C1010 Interior Construction	\$ 4,818,000	\$ 1,607,000	\$ 3,211,000

1822	Nevada	Nevada City Courthouse	C1010 Interior Construction	\$ 607,000	\$ 398,000	\$ 209,000
1823	Orange	West Justice Center	C1010 Interior Construction	\$ 829,000	\$ 751,000	\$ 77,000
1824	Alameda	Wiley W. Manuel Courthouse	C1010 Interior Construction	\$ 79,000	\$ 67,000	\$ 13,000
1825	Butte	Butte County Courthouse	C1010 Interior Construction	\$ 47,000	\$ 47,000	\$ -
1826	Contra Costa	Wakefield Taylor Courthouse	C1010 Interior Construction	\$ 3,706,000	\$ 3,706,000	\$ -
1827	Contra Costa	Jail Annex	C1010 Interior Construction	\$ 55,000	\$ 3,000	\$ 52,000
1828	Contra Costa	Danville District Courthouse	C1010 Interior Construction	\$ 17,000	\$ 17,000	\$ -
1829	Del Norte	Del Norte County Superior Court	C1010 Interior Construction	\$ 120,000	\$ 74,000	\$ 46,000
1830	Fresno	Fresno County Courthouse	C1010 Interior Construction	\$ 586,000	\$ 562,000	\$ 24,000
1831	Imperial	Imperial County Courthouse	C1010 Interior Construction	\$ 19,000	\$ 19,000	\$ -
1832	Kern	Bakersfield Superior Court	C1010 Interior Construction	\$ 149,000	\$ 93,000	\$ 56,000
1833	Kern	Bakersfield Justice Bldg.	C1010 Interior Construction	\$ 655,000	\$ 334,000	\$ 320,000
1834	Kern	Delano/North Kern Court	C1010 Interior Construction	\$ 235,000	\$ 190,000	\$ 46,000
1835	Kern	Shafter/Wasco Courts Bldg.	C1010 Interior Construction	\$ 127,000	\$ 115,000	\$ 13,000
1836	Kern	Taft Courts Bldg.	C1010 Interior Construction	\$ 50,000	\$ 50,000	\$ -
1837	Kings	Avenal Court	C1010 Interior Construction	\$ 14,000	\$ 8,000	\$ 6,000
1838	Los Angeles	San Fernando Courthouse	C1010 Interior Construction	\$ 125,000	\$ 104,000	\$ 21,000
1839	Los Angeles	Compton Courthouse	C1010 Interior Construction	\$ 592,000	\$ 391,000	\$ 200,000
1840	Los Angeles	Norwalk Courthouse	C1010 Interior Construction	\$ 1,730,000	\$ 1,471,000	\$ 259,000
1841	Los Angeles	Norwalk Courthouse	C1017 Interior Windows & Storefronts	\$ 111,000	\$ 94,000	\$ 17,000
1842	Los Angeles	Bellflower Courthouse	C1010 Interior Construction	\$ 148,000	\$ 116,000	\$ 33,000
1843	Los Angeles	Downey Courthouse	C1010 Interior Construction	\$ 7,000	\$ 6,000	\$ 1,000
1844	Los Angeles	Beverly Hills Courthouse	C1010 Interior Construction	\$ 182,000	\$ 145,000	\$ 37,000
1845	Los Angeles	Airport Courthouse	C1010 Interior Construction	\$ 28,000	\$ 22,000	\$ 6,000
1846	Los Angeles	Van Nuys Courthouse East	C1010 Interior Construction	\$ 27,000	\$ 24,000	\$ 3,000
1847	Los Angeles	Torrance Courthouse	C1010 Interior Construction	\$ 41,000	\$ 37,000	\$ 4,000
1848	Los Angeles	Inglewood Juvenile Court	C1010 Interior Construction	\$ 10,000	\$ 8,000	\$ 2,000
1849	Los Angeles	Alhambra Courthouse	C1010 Interior Construction	\$ 92,000	\$ 79,000	\$ 13,000
1850	Los Angeles	Pasadena Courthouse	C1010 Interior Construction	\$ 10,000	\$ 7,000	\$ 3,000
1851	Los Angeles	Clara Shortridge Foltz Criminal Justice	C1010 Interior Construction	\$ 493,000	\$ 339,000	\$ 154,000
1852	Los Angeles	El Monte Courthouse	C1010 Interior Construction	\$ 67,000	\$ 39,000	\$ 28,000
1853	Los Angeles	Central Arraignment Courts	C1010 Interior Construction	\$ 32,000	\$ 29,000	\$ 3,000
1854	Los Angeles	Pomona Courthouse South	C1010 Interior Construction	\$ 628,000	\$ 573,000	\$ 56,000
1855	Nevada	Nevada City Courthouse Annex	C1010 Interior Construction	\$ 358,000	\$ 153,000	\$ 205,000
1856	Orange	Central Justice Center	C1010 Interior Construction	\$ 3,838,000	\$ 3,499,000	\$ 339,000
1857	Orange	Betty Lou Lamoreaux Justice Center	C1010 Interior Construction	\$ 71,000	\$ 56,000	\$ 14,000
1858	Orange	North Justice Center	C1010 Interior Construction	\$ 69,000	\$ 62,000	\$ 7,000
1859	Placer	Historic Courthouse	C1010 Interior Construction	\$ 82,000	\$ 63,000	\$ 19,000
1860	Sacramento	Gordon Schaber Sacramento Superior	C1010 Interior Construction	\$ 895,000	\$ 895,000	\$ -
1861	San Diego	Kearny Mesa Court	C1010 Interior Construction	\$ 220,000	\$ 220,000	\$ -
1862	San Diego	Juvenile Court	C1010 Interior Construction	\$ 1,238,000	\$ 924,000	\$ 314,000
1863	San Diego	Department 9 Trailer	C1010 Interior Construction	\$ 112,000	\$ 112,000	\$ -
1864	San Diego	South County Regional Center	C1010 Interior Construction	\$ 243,000	\$ 87,000	\$ 156,000
1865	San Diego	East County Regional Center	C1010 Interior Construction	\$ 161,000	\$ 109,000	\$ 52,000
1866	San Joaquin	Lodi Branch- Dept. 2	C1010 Interior Construction	\$ 64,000	\$ 64,000	\$ -
1867	San Mateo	Hall of Justice	C1010 Interior Construction	\$ 746,000	\$ 393,000	\$ 353,000
1868	San Mateo	Traffic/ Small Claims Annex	C1010 Interior Construction	\$ 19,000	\$ 19,000	\$ -
1869	Santa Clara	Hall of Justice (West)	C1010 Interior Construction	\$ 2,170,000	\$ 2,170,000	\$ -
1870	Santa Clara	Santa Clara Courthouse	C1010 Interior Construction	\$ 34,000	\$ 34,000	\$ -
1871	Tulare	Visalia Superior Court	C1010 Interior Construction	\$ 3,059,000	\$ 989,000	\$ 2,070,000
1872	Alameda	Hayward Hall of Justice	C1010 Interior Construction	\$ 201,000	\$ 178,000	\$ 24,000
1873	Alameda	Fremont Hall of Justice	C1010 Interior Construction	\$ 470,000	\$ 373,000	\$ 97,000
1874	El Dorado	Johnson Bldg.	C1010 Interior Construction	\$ 81,000	\$ 81,000	\$ -
1875	Los Angeles	West Covina Courthouse	C1010 Interior Construction	\$ 35,000	\$ 29,000	\$ 6,000
1876	Merced	Old Court	C1010 Interior Construction	\$ 206,000	\$ 206,000	\$ -
1877	Merced	Downtown Merced Courthouse	C1010 Interior Construction	\$ 21,000	\$ 21,000	\$ -
1878	Orange	Civil Complex Center ("CXC")	C1010 Interior Construction	\$ 156,000	\$ 156,000	\$ -
1879	San Diego	North County Regional Center - North	C1010 Interior Construction	\$ 21,000	\$ 21,000	\$ -
1880	San Mateo	Central Branch	C1010 Interior Construction	\$ 126,000	\$ 126,000	\$ -
1881	San Mateo	Northern Branch Courthouse	C1010 Interior Construction	\$ 317,000	\$ 264,000	\$ 53,000
1882	Santa Clara	Downtown Superior Court	C1010 Interior Construction	\$ 3,140,000	\$ 3,140,000	\$ -
1883	Ventura	Hall of Justice	C1010 Interior Construction	\$ 554,000	\$ 387,000	\$ 167,000
1884	Santa Barbara	Santa Maria Courts, Bldg G	C1010 Interior Construction	\$ 13,000	\$ 12,000	\$ -
1885	San Luis Obispo	Courthouse Annex	C1010 Interior Construction	\$ 673,000	\$ 335,000	\$ 338,000
1886	San Bernardino	Joshua Tree Courthouse	C1010 Interior Construction	\$ 69,000	\$ 23,000	\$ 46,000
1887	San Bernardino	Fontana Courthouse	C1010 Interior Construction	\$ 16,000	\$ 13,000	\$ 3,000
1888	Riverside	Larson Justice Center	C1010 Interior Construction	\$ 220,000	\$ 178,000	\$ 42,000
1889	Alameda	Wiley W. Manuel Courthouse	E1010 Equipment	\$ 818,000	\$ 685,000	\$ 132,000
1890	Los Angeles	Van Nuys Courthouse East	E1010 Equipment	\$ 74,000	\$ 66,000	\$ 8,000
1891	Solano	Solano Justice Building	G20 Site Improvements	\$ 46,000	\$ 35,000	\$ 11,000
1892	San Mateo	Northern Branch Courthouse	C1020 Interior Doors	\$ 335,000	\$ 278,000	\$ 56,000
1893	San Bernardino	Rancho Cucamonga Courthouse	C1020 Interior Doors	\$ 59,000	\$ 45,000	\$ 14,000
1894	Contra Costa	George D. Carroll Courthouse	C1020 Interior Doors	\$ 694,000	\$ 520,000	\$ 174,000
1895	San Diego	East County Regional Center	C1020 Interior Doors	\$ 446,000	\$ 302,000	\$ 144,000
1896	Merced	Downtown Merced Courthouse	C1020 Interior Doors	\$ 63,000	\$ 63,000	\$ -
1897	Riverside	Family Law Court	B2020 Exterior Windows	\$ 118,000	\$ 118,000	\$ -

1898	Riverside	Family Law Court	B2030 Exterior Doors	\$ 156,000	\$ 156,000	\$ -
1899	Riverside	Family Law Court	B2039 Other Doors & Entrances	\$ 56,000	\$ 56,000	\$ -
1900	Merced	Old Court	C1020 Interior Doors	\$ 167,000	\$ 167,000	\$ -
1901	Fresno	Fresno County Courthouse	C1020 Interior Doors	\$ 1,948,000	\$ 1,869,000	\$ 80,000
1902	Los Angeles	Clara Shortridge Foltz Criminal Justice	C1020 Interior Doors	\$ 3,424,000	\$ 2,355,000	\$ 1,069,000
1903	Los Angeles	Central Arraignment Courts	C3020 Interior Doors	\$ 186,000	\$ 168,000	\$ 18,000
1904	San Diego	Kearny Mesa Court	C1020 Interior Doors	\$ 221,000	\$ 221,000	\$ -
1905	Merced	Downtown Merced Courthouse	C3020 Floor Finishes	\$ 365,000	\$ 365,000	\$ -
1906	Riverside	Riverside Juvenile Justice Trailers	C3020 Floor Finishes	\$ 13,000	\$ 13,000	\$ -
1907	San Bernardino	San Bernardino Courthouse	C3020 Floor Finishes	\$ 853,000	\$ 816,000	\$ 37,000
1908	Solano	Law and Justice Center	C3020 Floor Finishes	\$ 257,000	\$ 33,000	\$ 225,000
1909	San Francisco	Hall of Justice	C3020 Floor Finishes	\$ 1,656,000	\$ 385,000	\$ 1,271,000
1910	Santa Barbara	Santa Maria Courts Bldgs C + D	C3020 Floor Finishes	\$ 1,028,000	\$ 1,028,000	\$ -
1911	San Bernardino	Barstow Courthouse	C3020 Floor Finishes	\$ 261,000	\$ 204,000	\$ 58,000
1912	Santa Barbara	Santa Maria Courts, Bldg F	C3020 Floor Finishes	\$ 112,000	\$ 112,000	\$ -
1913	San Luis Obispo	1070 Palm St.	C3020 Floor Finishes	\$ 23,000	\$ 23,000	\$ -
1914	Solano	Hall of Justice	C3020 Floor Finishes	\$ 1,282,000	\$ 933,000	\$ 348,000
1915	San Bernardino	Rancho Cucamonga Courthouse	C3020 Floor Finishes	\$ 2,260,000	\$ 1,719,000	\$ 541,000
1916	Solano	Solano Justice Building	C3020 Floor Finishes	\$ 649,000	\$ 494,000	\$ 155,000
1917	San Bernardino	Victorville Courthouse-Dept. N-1	C3020 Floor Finishes	\$ 882,000	\$ 567,000	\$ 315,000
1918	Santa Barbara	Santa Maria Courts, Bldgs. A + B	C3020 Floor Finishes	\$ 228,000	\$ 53,000	\$ 175,000
1919	Alameda	Hayward Hall of Justice	C3020 Floor Finishes	\$ 1,217,000	\$ 1,074,000	\$ 142,000
1920	Alameda	George E. McDonald Hall of Justice	C3020 Floor Finishes	\$ 139,000	\$ 139,000	\$ -
1921	Alameda	Berkeley Courthouse	C3020 Floor Finishes	\$ 132,000	\$ 132,000	\$ -
1922	Amador	Amador County Courthouse	C3020 Floor Finishes	\$ 23,000	\$ 23,000	\$ -
1923	Contra Costa	Bray Courts	C3020 Floor Finishes	\$ 66,000	\$ 57,000	\$ 10,000
1924	Contra Costa	George D. Carroll Courthouse	C3020 Floor Finishes	\$ 835,000	\$ 626,000	\$ 209,000
1925	Fresno	B.F. Sisk Federal Courthouse	C3020 Floor Finishes	\$ 1,263,000	\$ 1,263,000	\$ -
1926	Humboldt	Humboldt County Courthouse (Eureka)	C3020 Floor Finishes	\$ 2,958,000	\$ 987,000	\$ 1,971,000
1927	Imperial	Imperial County Courthouse	C1020 Interior Doors	\$ 826,000	\$ 826,000	\$ -
1928	Inyo	Inyo Historic Courthouse	C3020 Floor Finishes	\$ 112,000	\$ 38,000	\$ 74,000
1929	Kern	Bakersfield Justice Bldg.	C3020 Floor Finishes	\$ 1,935,000	\$ 988,000	\$ 946,000
1930	Kern	Delano/North Kern Court	C3020 Floor Finishes	\$ 165,000	\$ 133,000	\$ 32,000
1931	Kern	Shafter/Wasco Courts Bldg.	C3020 Floor Finishes	\$ 192,000	\$ 173,000	\$ 19,000
1932	Kern	Taft Courts Bldg.	C3020 Floor Finishes	\$ 72,000	\$ 72,000	\$ -
1933	Kern	Arvin/ Lamont Branch	C3020 Floor Finishes	\$ 322,000	\$ 196,000	\$ 126,000
1934	Kings	Probation Building	C3020 Floor Finishes	\$ 63,000	\$ 7,000	\$ 56,000
1935	Kings	Avenal Court	C3020 Floor Finishes	\$ 65,000	\$ 38,000	\$ 27,000
1936	Kings	Corcoran Court	C3020 Floor Finishes	\$ 107,000	\$ 94,000	\$ 13,000
1937	Los Angeles	San Fernando Courthouse	C3020 Floor Finishes	\$ 1,396,000	\$ 1,165,000	\$ 232,000
1938	Los Angeles	Alfred J. McCourtney Juvenile Justice	C3020 Floor Finishes	\$ 286,000	\$ 197,000	\$ 89,000
1939	Los Angeles	Sylmar Juvenile Court	C3020 Floor Finishes	\$ 60,000	\$ 21,000	\$ 40,000
1940	Los Angeles	Los Padrinos Juvenile Court	C3020 Floor Finishes	\$ 51,000	\$ 15,000	\$ 36,000
1941	Los Angeles	Norwalk Courthouse	C3020 Floor Finishes	\$ 966,000	\$ 822,000	\$ 145,000
1942	Los Angeles	Bellflower Courthouse	C3020 Floor Finishes	\$ 401,000	\$ 312,000	\$ 88,000
1943	Los Angeles	Santa Monica Court Annex	C3020 Floor Finishes	\$ 127,000	\$ 127,000	\$ -
1944	Los Angeles	Airport Courthouse	C3020 Floor Finishes	\$ 1,705,000	\$ 1,316,000	\$ 389,000
1945	Los Angeles	Hall of Records	C3020 Floor Finishes	\$ 229,000	\$ 24,000	\$ 205,000
1946	Los Angeles	Van Nuys Courthouse East	C3020 Floor Finishes	\$ 889,000	\$ 798,000	\$ 91,000
1947	Los Angeles	Van Nuys Courthouse West	C3020 Floor Finishes	\$ 1,690,000	\$ 1,360,000	\$ 330,000
1948	Los Angeles	Chatsworth Courthouse	C3020 Floor Finishes	\$ 1,510,000	\$ 1,266,000	\$ 245,000
1949	Los Angeles	Torrance Courthouse	C3020 Floor Finishes	\$ 649,000	\$ 587,000	\$ 62,000
1950	Los Angeles	Inglewood Juvenile Court	C3020 Floor Finishes	\$ 136,000	\$ 110,000	\$ 26,000
1951	Los Angeles	Glendale Courthouse	C3020 Floor Finishes	\$ 273,000	\$ 247,000	\$ 26,000
1952	Los Angeles	Alhambra Courthouse	C3020 Floor Finishes	\$ 253,000	\$ 217,000	\$ 35,000
1953	Los Angeles	Pasadena Courthouse	C3020 Floor Finishes	\$ 745,000	\$ 517,000	\$ 228,000
1954	Los Angeles	Monrovia Training Center	C3020 Floor Finishes	\$ 183,000	\$ 129,000	\$ 54,000
1955	Los Angeles	El Monte Courthouse	C3020 Floor Finishes	\$ 540,000	\$ 314,000	\$ 226,000
1956	Los Angeles	Eastlake Juvenile Court	C3020 Floor Finishes	\$ 258,000	\$ 142,000	\$ 117,000
1957	Los Angeles	Central Arraignment Courts	C3020 Floor Finishes	\$ 232,000	\$ 209,000	\$ 23,000
1958	Los Angeles	East Los Angeles Courthouse	C3020 Floor Finishes	\$ 432,000	\$ 336,000	\$ 96,000
1959	Los Angeles	Pomona Courthouse South	C3020 Floor Finishes	\$ 2,864,000	\$ 2,610,000	\$ 254,000
1960	Los Angeles	West Covina Courthouse	C3020 Floor Finishes	\$ 772,000	\$ 641,000	\$ 131,000
1961	Madera	Sierra Courthouse	C3020 Floor Finishes	\$ 83,000	\$ 57,000	\$ 27,000
1962	Merced	Old Court	C3020 Floor Finishes	\$ 310,000	\$ 310,000	\$ -
1963	Napa	Criminal Court Building	C3020 Floor Finishes	\$ 312,000	\$ 312,000	\$ -
1964	Nevada	Nevada City Courthouse	C3020 Floor Finishes	\$ 356,000	\$ 233,000	\$ 123,000
1965	Orange	Central Justice Center	C3020 Floor Finishes	\$ 5,720,000	\$ 5,215,000	\$ 505,000
1966	Orange	Central Justice Center Annex	C3020 Floor Finishes	\$ 41,000	\$ 3,000	\$ 38,000
1967	Orange	Civil Complex Center ("CXC")	C3020 Floor Finishes	\$ 346,000	\$ 346,000	\$ -
1968	Orange	Betty Lou Lamoreaux Justice Center	C3020 Floor Finishes	\$ 1,854,000	\$ 1,482,000	\$ 372,000
1969	Orange	West Justice Center	C3020 Floor Finishes	\$ 1,203,000	\$ 1,091,000	\$ 112,000
1970	Placer	Historic Courthouse	C3020 Floor Finishes	\$ 465,000	\$ 358,000	\$ 107,000
1971	Placer	Bill Santucci Justice Center	C3020 Floor Finishes	\$ 625,000	\$ 625,000	\$ -
1972	Sacramento	Juvenile Courthouse	C3020 Floor Finishes	\$ 689,000	\$ 689,000	\$ -
1973	Sacramento	Carol Miller Justice Center Court Fac	C3020 Floor Finishes	\$ 957,000	\$ 936,000	\$ 22,000

1974	San Diego	Hall of Justice	C3020 Floor Finishes	\$ 2,636,000	\$ 1,061,000	\$ 1,575,000
1975	San Diego	Kearny Mesa Court	C3020 Floor Finishes	\$ 138,000	\$ 138,000	\$ -
1976	San Diego	Kearny Mesa Traffic Court KM3 Trailer	C3020 Floor Finishes	\$ 12,000	\$ 12,000	\$ -
1977	San Diego	Kearny Mesa Traffic Court KM4 Trailer	C3020 Floor Finishes	\$ 12,000	\$ 12,000	\$ -
1978	San Diego	Kearny Mesa Traffic Court KM5 & KM6 Trailer	C3020 Floor Finishes	\$ 12,000	\$ 12,000	\$ -
1979	San Diego	Department 9 Trailer	C3020 Floor Finishes	\$ 13,000	\$ 13,000	\$ -
1980	San Diego	Department 10 Trailer	C3020 Floor Finishes	\$ 13,000	\$ 13,000	\$ -
1981	San Diego	North County Regional Center - South	C3020 Floor Finishes	\$ 1,398,000	\$ 940,000	\$ 458,000
1982	San Diego	North County Regional Center - North	C3020 Floor Finishes	\$ 465,000	\$ 465,000	\$ -
1983	San Diego	Trailer - Dept 34	C3020 Floor Finishes	\$ 13,000	\$ 13,000	\$ -
1984	San Diego	Trailer - Dept 35	C3020 Floor Finishes	\$ 13,000	\$ 13,000	\$ -
1985	San Diego	Trailer - Storage A	C3020 Floor Finishes	\$ 6,000	\$ 6,000	\$ -
1986	San Diego	Trailer - Family Support	C3020 Floor Finishes	\$ 13,000	\$ 13,000	\$ -
1987	San Francisco	Youth Guidance Center	C3020 Floor Finishes	\$ 21,000	\$ 3,000	\$ 18,000
1988	San Mateo	Traffic/ Small Claims Annex	C3020 Floor Finishes	\$ 67,000	\$ 67,000	\$ -
1989	Santa Cruz	Main Courthouse	C3020 Floor Finishes	\$ 182,000	\$ 180,000	\$ 2,000
1990	Alameda	Wiley W. Manuel Courthouse	C3020 Floor Finishes	\$ 2,293,000	\$ 1,921,000	\$ 371,000
1991	Imperial	Imperial County Courthouse	C3020 Floor Finishes	\$ 775,000	\$ 775,000	\$ -
1992	Kern	Bakersfield Superior Court	C3020 Floor Finishes	\$ 1,489,000	\$ 933,000	\$ 556,000
1993	Kern	Bakersfield Juvenile Center	C3020 Floor Finishes	\$ 564,000	\$ 376,000	\$ 187,000
1994	Los Angeles	Santa Clarita Courthouse	C3020 Floor Finishes	\$ 379,000	\$ 335,000	\$ 44,000
1995	Los Angeles	Downey Courthouse	C3020 Floor Finishes	\$ 793,000	\$ 664,000	\$ 129,000
1996	Los Angeles	Santa Monica Courthouse	C3020 Floor Finishes	\$ 640,000	\$ 502,000	\$ 138,000
1997	Los Angeles	Beverly Hills Courthouse	C3020 Floor Finishes	\$ 689,000	\$ 548,000	\$ 141,000
1998	Los Angeles	Michael D. Antonovich Antelope Valley	C3020 Floor Finishes	\$ 1,900,000	\$ 1,397,000	\$ 503,000
1999	Los Angeles	Inglewood Courthouse	C3020 Floor Finishes	\$ 822,000	\$ 613,000	\$ 209,000
2000	Los Angeles	Stanley Mosk Courthouse	C3020 Floor Finishes	\$ 3,570,000	\$ 3,472,000	\$ 98,000
2001	Los Angeles	Clara Shortridge Foltz Criminal Justice	C3020 Floor Finishes	\$ 4,550,000	\$ 3,130,000	\$ 1,420,000
2002	Los Angeles	Metropolitan Courthouse	C3020 Floor Finishes	\$ 1,020,000	\$ 965,000	\$ 56,000
2003	Orange	North Justice Center	C3020 Floor Finishes	\$ 718,000	\$ 649,000	\$ 70,000
2004	San Diego	South County Regional Center	C3020 Floor Finishes	\$ 1,049,000	\$ 376,000	\$ 673,000
2005	Santa Barbara	Santa Maria Courts Bldgs C + D	C1020 Interior Doors	\$ 413,000	\$ 413,000	\$ -
2006	Los Angeles	Burbank Courthouse	C3020 Floor Finishes	\$ 601,000	\$ 546,000	\$ 56,000
2007	Los Angeles	Edmund D. Edelman Children's Court	C3020 Floor Finishes	\$ 1,708,000	\$ 1,196,000	\$ 513,000
2008	Alameda	Fremont Hall of Justice	C3020 Floor Finishes	\$ 1,696,000	\$ 1,346,000	\$ 349,000
2009	Contra Costa	Wakefield Taylor Courthouse	C3020 Floor Finishes	\$ 2,549,000	\$ 2,549,000	\$ -
2010	Sacramento	Gordon Schaber Sacramento Superior	C3020 Floor Finishes	\$ 6,450,000	\$ 6,450,000	\$ -
2011	San Mateo	Hall of Justice	C3020 Floor Finishes	\$ 1,250,000	\$ 659,000	\$ 591,000
2012	Santa Clara	Downtown Superior Court	C3020 Floor Finishes	\$ 1,908,000	\$ 1,908,000	\$ -
2013	Santa Barbara	Santa Maria Courts, Bldg G	C3020 Floor Finishes	\$ 787,000	\$ 759,000	\$ 28,000
2014	Riverside	Hall of Justice	C3020 Floor Finishes	\$ 10,800,000	\$ 10,800,000	\$ -
2015	San Bernardino	Joshua Tree Courthouse	C3020 Floor Finishes	\$ 223,000	\$ 75,000	\$ 148,000
2016	Contra Costa	Danville District Courthouse	C3020 Floor Finishes	\$ 322,000	\$ 322,000	\$ -
2017	San Mateo	Northern Branch Courthouse	C3020 Floor Finishes	\$ 641,000	\$ 534,000	\$ 108,000
2018	San Bernardino	Fontana Courthouse	C3020 Floor Finishes	\$ 246,000	\$ 202,000	\$ 44,000
2019	Riverside	Blythe Courthouse - Superior Court	C3020 Floor Finishes	\$ 112,000	\$ 112,000	\$ -
2020	Riverside	Larson Justice Center	C3020 Floor Finishes	\$ 1,116,000	\$ 902,000	\$ 214,000
2021	Santa Clara	Hall of Justice (West)	C3020 Floor Finishes	\$ 1,315,000	\$ 1,315,000	\$ -
2022	Santa Clara	Santa Clara Courthouse	C3020 Floor Finishes	\$ 587,000	\$ 587,000	\$ -
2023	Santa Barbara	Santa Maria Juvenile Court (new)	C3020 Floor Finishes	\$ 42,000	\$ 28,000	\$ 14,000
2024	El Dorado	Johnson Bldg.	C3020 Floor Finishes	\$ 318,000	\$ 318,000	\$ -
2025	San Mateo	Central Branch	C3020 Floor Finishes	\$ 157,000	\$ 157,000	\$ -
2026	Santa Clara	Hall of Justice (East)	C3020 Floor Finishes	\$ 2,489,000	\$ 2,489,000	\$ -
2027	Riverside	Riverside Juvenile Court	C3020 Floor Finishes	\$ 390,000	\$ 192,000	\$ 197,000
2028	Riverside	Family Law Court	C1020 Interior Doors	\$ 388,000	\$ 388,000	\$ -
2029	San Francisco	Civic Center Courthouse	C3020 Floor Finishes	\$ 2,986,000	\$ 2,986,000	\$ -
2030	Ventura	Hall of Justice	C3020 Floor Finishes	\$ 6,298,000	\$ 4,400,000	\$ 1,898,000
2031	Butte	Butte County Courthouse	C3020 Floor Finishes	\$ 1,054,000	\$ 1,054,000	\$ -
2032	El Dorado	Cameron Park	C3020 Floor Finishes	\$ 133,000	\$ 133,000	\$ -
2033	Nevada	Nevada City Courthouse Annex	C3020 Floor Finishes	\$ 383,000	\$ 164,000	\$ 220,000
2034	San Diego	Juvenile Court	C3020 Floor Finishes	\$ 573,000	\$ 428,000	\$ 145,000
2035	San Diego	East County Regional Center	C3020 Floor Finishes	\$ 3,608,000	\$ 2,443,000	\$ 1,165,000
2036	Fresno	Fresno County Courthouse	C3020 Floor Finishes	\$ 4,683,000	\$ 4,492,000	\$ 192,000
2037	Contra Costa	Wakefield Taylor Courthouse	C1020 Interior Doors	\$ 670,000	\$ 670,000	\$ -
2038	Los Angeles	Compton Courthouse	C3020 Floor Finishes	\$ 5,959,000	\$ 3,941,000	\$ 2,018,000
2039	Santa Clara	Historic Courthouse	C3020 Floor Finishes	\$ 568,000	\$ 568,000	\$ -
2040	Contra Costa	Jail Annex	C3020 Floor Finishes	\$ 165,000	\$ 10,000	\$ 155,000
2041	Del Norte	Del Norte County Superior Court	C3020 Floor Finishes	\$ 366,000	\$ 224,000	\$ 142,000
2042	Riverside	Corona	C3020 Floor Finishes	\$ 515,000	\$ 278,000	\$ 237,000
2043	Ventura	East County Courthouse	C3020 Floor Finishes	\$ 1,352,000	\$ 835,000	\$ 517,000
2044	Tulare	Visalia Superior Court	C3020 Floor Finishes	\$ 3,506,000	\$ 1,133,000	\$ 2,372,000
2045	San Luis Obispo	1070 Palm St.	C1020 Interior Doors	\$ 11,000	\$ 11,000	\$ -
2046	Riverside	Riverside Juvenile Court	C1020 Interior Doors	\$ 48,000	\$ 24,000	\$ 25,000
2047	Solano	Solano Justice Building	C1020 Interior Doors	\$ 87,000	\$ 66,000	\$ 21,000
2048	Madera	Sierra Courthouse	C1020 Interior Doors	\$ 24,000	\$ 16,000	\$ 8,000
2049	San Diego	North County Regional Center - Annex	C3020 Floor Finishes	\$ 178,000	\$ 178,000	\$ -

2050	San Luis Obispo	Courthouse Annex	C3020 Floor Finishes	\$ 1,548,000	\$ 770,000	\$ 778,000
2051	Alameda	Hayward Hall of Justice	C1020 Interior Doors	\$ 960,000	\$ 848,000	\$ 112,000
2052	Los Angeles	Norwalk Courthouse	C1020 Interior Doors	\$ 3,316,000	\$ 2,820,000	\$ 496,000
2053	San Luis Obispo	Courthouse Annex	C1020 Interior Doors	\$ 96,000	\$ 48,000	\$ 48,000
2054	Alameda	Hayward Hall of Justice	E1010 Equipment	\$ 1,259,000	\$ 1,112,000	\$ 147,000
2055	Alameda	Berkeley Courthouse	E2010 Fixed Furnishings	\$ 46,000	\$ 46,000	\$ -
2056	Los Angeles	San Fernando Courthouse	E1010 Equipment	\$ 35,000	\$ 29,000	\$ 6,000
2057	Los Angeles	Clara Shortridge Foltz Criminal Justice	E1010 Equipment	\$ 283,000	\$ 195,000	\$ 88,000
2058	Orange	North Justice Center	E2010 Fixed Furnishings	\$ 193,000	\$ 175,000	\$ 19,000
2059	Orange	West Justice Center	E1010 Equipment	\$ 110,000	\$ 100,000	\$ 10,000
2060	Riverside	Hall of Justice	E1010 Equipment	\$ 58,000	\$ 58,000	\$ -
2061	Riverside	Larson Justice Center	E2010 Fixed Furnishings	\$ 90,000	\$ 72,000	\$ 17,000
2062	San Luis Obispo	Paso Robles Courthouse	E1010 Equipment	\$ 465,000	\$ 465,000	\$ -
2063	Los Angeles	Pomona Courthouse South	C1020 Interior Doors	\$ 2,008,000	\$ 1,830,000	\$ 178,000
2064	Nevada	Nevada City Courthouse	C1020 Interior Doors	\$ 408,000	\$ 267,000	\$ 141,000
2065	Nevada	Nevada City Courthouse Annex	C1020 Interior Doors	\$ 258,000	\$ 110,000	\$ 148,000
2066	San Mateo	Hall of Justice	C1020 Interior Doors	\$ 706,000	\$ 372,000	\$ 334,000
2067	Los Angeles	San Fernando Courthouse	E2010 Fixed Furnishings	\$ 1,400,000	\$ 1,167,000	\$ 232,000
2068	Los Angeles	Santa Monica Courthouse	C1020 Interior Doors	\$ 1,724,000	\$ 1,353,000	\$ 371,000
2069	Los Angeles	Chatsworth Courthouse	C1020 Interior Doors	\$ 222,000	\$ 186,000	\$ 36,000
2070	Los Angeles	Stanley Mosk Courthouse	C1020 Interior Doors	\$ 11,000,000	\$ 10,700,000	\$ 300,000
2071	Los Angeles	Compton Courthouse	C1020 Interior Doors	\$ 995,000	\$ 658,000	\$ 337,000
2072	Riverside	Family Law Court	B2010 Exterior Walls	\$ 17,000	\$ 17,000	\$ -
2073	Napa	Criminal Court Building	E2010 Fixed Furnishings	\$ 206,000	\$ 206,000	\$ -
2074	San Diego	Juvenile Court	C1020 Interior Doors	\$ 386,000	\$ 288,000	\$ 98,000
2075	San Mateo	Central Branch	C1020 Interior Doors	\$ 123,000	\$ 123,000	\$ -
2076	Los Angeles	Torrance Courthouse	E2010 Fixed Furnishings	\$ 345,000	\$ 312,000	\$ 33,000
2077	Santa Barbara	Santa Maria Courts, Bldg G	C1020 Interior Doors	\$ 386,000	\$ 372,000	\$ 14,000
2078	Riverside	Corona	C1020 Interior Doors	\$ 43,000	\$ 23,000	\$ 20,000
2079	Alameda	Fremont Hall of Justice	C1020 Interior Doors	\$ 600,000	\$ 476,000	\$ 124,000
2080	Contra Costa	Danville District Courthouse	C1020 Interior Doors	\$ 270,000	\$ 270,000	\$ -
2081	Los Angeles	El Monte Courthouse	E2010 Fixed Furnishings	\$ 307,000	\$ 178,000	\$ 129,000
2082	Los Angeles	Edmund D. Edelman Children's Court	E2010 Fixed Furnishings	\$ 1,063,000	\$ 744,000	\$ 319,000
2083	Los Angeles	Eastlake Juvenile Court	C1020 Interior Doors	\$ 530,000	\$ 290,000	\$ 240,000
2084	Orange	Civil Complex Center ("CXC")	E2010 Fixed Furnishings	\$ 345,000	\$ 345,000	\$ -
2085	Alameda	Wiley W. Manuel Courthouse	E2010 Fixed Furnishings	\$ 622,000	\$ 521,000	\$ 101,000
2086	Los Angeles	Hall of Records	E2010 Fixed Furnishings	\$ 179,000	\$ 19,000	\$ 160,000
2087	Los Angeles	Clara Shortridge Foltz Criminal Justice	E2010 Fixed Furnishings	\$ 1,989,000	\$ 1,368,000	\$ 621,000
2088	Orange	Central Justice Center	E2010 Fixed Furnishings	\$ 5,408,000	\$ 4,930,000	\$ 478,000
2089	Los Angeles	Van Nuys Courthouse East	E2010 Fixed Furnishings	\$ 2,522,000	\$ 2,263,000	\$ 259,000
2090	Orange	West Justice Center	E2010 Fixed Furnishings	\$ 1,755,000	\$ 1,591,000	\$ 164,000
2091	Butte	Butte County Courthouse	E2010 Fixed Furnishings	\$ 327,000	\$ 327,000	\$ -
2092	Los Angeles	Van Nuys Courthouse West	E2010 Fixed Furnishings	\$ 662,000	\$ 532,000	\$ 129,000
2093	Los Angeles	Alhambra Courthouse	E2010 Fixed Furnishings	\$ 1,302,000	\$ 1,119,000	\$ 182,000
2094	Merced	Old Court	E2010 Fixed Furnishings	\$ 610,000	\$ 610,000	\$ -
2095	Orange	Betty Lou Lamoreaux Justice Center	E2010 Fixed Furnishings	\$ 2,588,000	\$ 2,069,000	\$ 519,000
2096	San Francisco	Hall of Justice	C1020 Interior Doors	\$ 665,000	\$ 155,000	\$ 511,000
2097	Los Angeles	Glendale Courthouse	E2010 Fixed Furnishings	\$ 1,263,000	\$ 1,143,000	\$ 119,000
2098	San Luis Obispo	Courthouse Annex	E2010 Fixed Furnishings	\$ 1,391,000	\$ 692,000	\$ 699,000
2099	Contra Costa	Wakefield Taylor Courthouse	E2010 Fixed Furnishings	\$ 1,174,000	\$ 1,174,000	\$ -
2100	San Francisco	Hall of Justice	E2010 Fixed Furnishings	\$ 1,382,000	\$ 321,000	\$ 1,060,000
2101	Los Angeles	Compton Courthouse	E2010 Fixed Furnishings	\$ 4,225,000	\$ 2,794,000	\$ 1,431,000
2102	San Bernardino	San Bernardino Courthouse	E2010 Fixed Furnishings	\$ 2,227,000	\$ 2,130,000	\$ 97,000
2103	Solano	Law and Justice Center	E2010 Fixed Furnishings	\$ 208,000	\$ 26,000	\$ 182,000
2104	Santa Barbara	Santa Maria Courts Bldgs C + D	E2010 Fixed Furnishings	\$ 292,000	\$ 292,000	\$ -
2105	San Bernardino	Barstow Courthouse	E2010 Fixed Furnishings	\$ 264,000	\$ 206,000	\$ 58,000
2106	Santa Barbara	Santa Maria Courts, Bldg F	E2010 Fixed Furnishings	\$ 20,000	\$ 20,000	\$ -
2107	San Luis Obispo	1070 Palm St.	E2010 Fixed Furnishings	\$ 42,000	\$ 42,000	\$ -
2108	Riverside	Corona	E2010 Fixed Furnishings	\$ 371,000	\$ 201,000	\$ 171,000
2109	Solano	Hall of Justice	E2010 Fixed Furnishings	\$ 1,187,000	\$ 865,000	\$ 323,000
2110	San Bernardino	Rancho Cucamonga Courthouse	E2010 Fixed Furnishings	\$ 305,000	\$ 232,000	\$ 73,000
2111	Riverside	Riverside Juvenile Court	E2010 Fixed Furnishings	\$ 377,000	\$ 186,000	\$ 191,000
2112	Solano	Solano Justice Building	E2010 Fixed Furnishings	\$ 1,557,000	\$ 1,185,000	\$ 372,000
2113	San Bernardino	Victorville Courthouse-Dept. N-1	E2010 Fixed Furnishings	\$ 868,000	\$ 558,000	\$ 310,000
2114	Santa Barbara	Santa Maria Courts, Bldgs. A + B	E2010 Fixed Furnishings	\$ 75,000	\$ 17,000	\$ 57,000
2115	Alameda	Wiley W. Manuel Courthouse	D5035 Intrusion Alarm	\$ 8,000	\$ 6,000	\$ 1,000
2116	Alameda	Hayward Hall of Justice	D5035 Intrusion Alarm	\$ 8,000	\$ 7,000	\$ 1,000
2117	Alameda	Hayward Hall of Justice	E2010 Fixed Furnishings	\$ 699,000	\$ 618,000	\$ 82,000
2118	Alameda	George E. McDonald Hall of Justice	E2010 Fixed Furnishings	\$ 312,000	\$ 312,000	\$ -
2119	Alameda	Fremont Hall of Justice	D5035 Intrusion Alarm	\$ 6,000	\$ 5,000	\$ 1,000
2120	Amador	Amador County Courthouse	E2010 Fixed Furnishings	\$ 156,000	\$ 156,000	\$ -
2121	Contra Costa	Bray Courts	E2010 Fixed Furnishings	\$ 86,000	\$ 74,000	\$ 12,000
2122	Contra Costa	Jail Annex	E2010 Fixed Furnishings	\$ 159,000	\$ 9,000	\$ 149,000
2123	Contra Costa	Danville District Courthouse	E2010 Fixed Furnishings	\$ 480,000	\$ 480,000	\$ -
2124	Contra Costa	George D. Carroll Courthouse	E2010 Fixed Furnishings	\$ 957,000	\$ 718,000	\$ 239,000
2125	Del Norte	Del Norte County Superior Court	E2010 Fixed Furnishings	\$ 342,000	\$ 209,000	\$ 132,000

2126	El Dorado	Cameron Park	E2010 Fixed Furnishings	\$ 129,000	\$ 129,000	\$ -
2127	El Dorado	Johnson Bldg.	E2010 Fixed Furnishings	\$ 634,000	\$ 634,000	\$ -
2128	Fresno	Fresno County Courthouse	E2010 Fixed Furnishings	\$ 4,691,000	\$ 4,499,000	\$ 192,000
2129	Kern	Bakersfield Justice Bldg.	E2010 Fixed Furnishings	\$ 594,000	\$ 303,000	\$ 291,000
2130	Kern	Bakersfield Juvenile Center	E2010 Fixed Furnishings	\$ 215,000	\$ 144,000	\$ 71,000
2131	Kern	Delano/North Kern Court	E2010 Fixed Furnishings	\$ 146,000	\$ 118,000	\$ 28,000
2132	Kern	Shafter/Wasco Courts Bldg.	E2010 Fixed Furnishings	\$ 122,000	\$ 109,000	\$ 12,000
2133	Kern	Taft Courts Bldg.	E2010 Fixed Furnishings	\$ 45,000	\$ 45,000	\$ -
2134	Kern	Arvin/ Lamont Branch	E2010 Fixed Furnishings	\$ 155,000	\$ 94,000	\$ 60,000
2135	Kings	Probation Building	E2010 Fixed Furnishings	\$ 228,000	\$ 27,000	\$ 201,000
2136	Kings	Avenal Court	E2010 Fixed Furnishings	\$ 238,000	\$ 138,000	\$ 100,000
2137	Kings	Corcoran Court	D5032 Intercommunication & Paging System	\$ 13,000	\$ 11,000	\$ 2,000
2138	Kings	Corcoran Court	E2010 Fixed Furnishings	\$ 212,000	\$ 185,000	\$ 26,000
2139	Los Angeles	Santa Clarita Courthouse	D5035 Intrusion Alarm	\$ 14,000	\$ 12,000	\$ 2,000
2140	Los Angeles	Santa Clarita Courthouse	E2010 Fixed Furnishings	\$ 506,000	\$ 447,000	\$ 59,000
2141	Los Angeles	Sylmar Juvenile Court	E2010 Fixed Furnishings	\$ 396,000	\$ 136,000	\$ 260,000
2142	Los Angeles	Los Padrinos Juvenile Court	E2010 Fixed Furnishings	\$ 262,000	\$ 77,000	\$ 185,000
2143	Los Angeles	Norwalk Courthouse	D5035 Intrusion Alarm	\$ 35,000	\$ 30,000	\$ 5,000
2144	Los Angeles	Norwalk Courthouse	E2010 Fixed Furnishings	\$ 3,568,000	\$ 3,034,000	\$ 534,000
2145	Los Angeles	Bellflower Courthouse	E2010 Fixed Furnishings	\$ 505,000	\$ 394,000	\$ 111,000
2146	Los Angeles	Downey Courthouse	E2010 Fixed Furnishings	\$ 450,000	\$ 377,000	\$ 73,000
2147	Los Angeles	Santa Monica Courthouse	D5035 Intrusion Alarm	\$ 52,000	\$ 41,000	\$ 11,000
2148	Los Angeles	Santa Monica Courthouse	E2010 Fixed Furnishings	\$ 1,690,000	\$ 1,326,000	\$ 363,000
2149	Los Angeles	Beverly Hills Courthouse	D5035 Intrusion Alarm	\$ 31,000	\$ 25,000	\$ 6,000
2150	Los Angeles	Michael D. Antonovich Antelope Vall	E2010 Fixed Furnishings	\$ 16,000	\$ 12,000	\$ 4,000
2151	Los Angeles	Inglewood Juvenile Court	E2010 Fixed Furnishings	\$ 170,000	\$ 138,000	\$ 33,000
2152	Los Angeles	Inglewood Courthouse	E2010 Fixed Furnishings	\$ 915,000	\$ 682,000	\$ 233,000
2153	Los Angeles	Burbank Courthouse	D5032 Intercommunication & Paging System	\$ 40,000	\$ 36,000	\$ 4,000
2154	Los Angeles	Burbank Courthouse	D5035 Intrusion Alarm	\$ 28,000	\$ 25,000	\$ 3,000
2155	Los Angeles	Alhambra Courthouse	D5035 Intrusion Alarm	\$ 26,000	\$ 22,000	\$ 4,000
2156	Los Angeles	Pasadena Courthouse	D5035 Intrusion Alarm	\$ 6,000	\$ 4,000	\$ 2,000
2157	Los Angeles	Pasadena Courthouse	E2010 Fixed Furnishings	\$ 1,238,000	\$ 858,000	\$ 379,000
2158	Los Angeles	Stanley Mosk Courthouse	D5035 Intrusion Alarm	\$ 320,000	\$ 311,000	\$ 9,000
2159	Los Angeles	Stanley Mosk Courthouse	E2010 Fixed Furnishings	\$ 13,600,000	\$ 13,200,000	\$ 400,000
2160	Los Angeles	Monrovia Training Center	E2010 Fixed Furnishings	\$ 51,000	\$ 36,000	\$ 15,000
2161	Los Angeles	El Monte Courthouse	D5035 Intrusion Alarm	\$ 7,000	\$ 4,000	\$ 3,000
2162	Los Angeles	Eastlake Juvenile Court	E2010 Fixed Furnishings	\$ 301,000	\$ 165,000	\$ 136,000
2163	Los Angeles	Metropolitan Courthouse	D5035 Intrusion Alarm	\$ 154,000	\$ 145,000	\$ 8,000
2164	Los Angeles	Central Arraignment Courts	E2010 Fixed Furnishings	\$ 619,000	\$ 559,000	\$ 60,000
2165	Los Angeles	East Los Angeles Courthouse	E2010 Fixed Furnishings	\$ 504,000	\$ 392,000	\$ 112,000
2166	Los Angeles	Pomona Courthouse South	E2010 Fixed Furnishings	\$ 1,600,000	\$ 1,458,000	\$ 142,000
2167	Madera	Sierra Courthouse	E2010 Fixed Furnishings	\$ 625,000	\$ 425,000	\$ 200,000
2168	Mono	New Mammoth Lakes Courthouse	E2010 Fixed Furnishings	\$ 20,000	\$ 20,000	\$ -
2169	Nevada	Nevada City Courthouse	E2010 Fixed Furnishings	\$ 87,000	\$ 57,000	\$ 30,000
2170	Nevada	Nevada City Courthouse Annex	E2010 Fixed Furnishings	\$ 509,000	\$ 217,000	\$ 291,000
2171	Orange	Central Justice Center Annex	D5032 Intercommunication & Paging System	\$ 12,000	\$ 1,000	\$ 12,000
2172	Orange	Betty Lou Lamoreaux Justice Center	D5032 Intercommunication & Paging System	\$ 151,000	\$ 121,000	\$ 30,000
2173	Sacramento	Gordon Schaber Sacramento Superior	E2010 Fixed Furnishings	\$ 6,123,000	\$ 6,123,000	\$ -
2174	Sacramento	Carol Miller Justice Center Court Fac	E2010 Fixed Furnishings	\$ 47,000	\$ 45,000	\$ 1,000
2175	San Diego	Kearny Mesa Court	D5032 Intercommunication & Paging System	\$ 8,000	\$ 8,000	\$ -
2176	San Diego	Kearny Mesa Court	E2010 Fixed Furnishings	\$ 275,000	\$ 275,000	\$ -
2177	San Diego	Juvenile Court	E2010 Fixed Furnishings	\$ 1,050,000	\$ 784,000	\$ 266,000
2178	San Diego	North County Regional Center - South	D5032 Intercommunication & Paging System	\$ 17,000	\$ 11,000	\$ 5,000
2179	San Diego	North County Regional Center - North	E2010 Fixed Furnishings	\$ 2,033,000	\$ 2,033,000	\$ -
2180	San Diego	Trailer - Storage A	E2010 Fixed Furnishings	\$ 24,000	\$ 24,000	\$ -
2181	San Diego	East County Regional Center	E2010 Fixed Furnishings	\$ 2,536,000	\$ 1,717,000	\$ 819,000
2182	San Mateo	Hall of Justice	E2010 Fixed Furnishings	\$ 1,081,000	\$ 570,000	\$ 511,000
2183	San Mateo	Central Branch	E2010 Fixed Furnishings	\$ 180,000	\$ 180,000	\$ -
2184	San Mateo	Northern Branch Courthouse	E2010 Fixed Furnishings	\$ 395,000	\$ 328,000	\$ 66,000
2185	Santa Clara	Hall of Justice (East)	E2010 Fixed Furnishings	\$ 808,000	\$ 808,000	\$ -
2186	Santa Clara	Hall of Justice (West)	E2010 Fixed Furnishings	\$ 1,765,000	\$ 1,765,000	\$ -
2187	Santa Clara	Downtown Superior Court	E2010 Fixed Furnishings	\$ 2,768,000	\$ 2,768,000	\$ -
2188	Santa Clara	Historic Courthouse	E2010 Fixed Furnishings	\$ 785,000	\$ 785,000	\$ -
2189	Santa Clara	Santa Clara Courthouse	E2010 Fixed Furnishings	\$ 620,000	\$ 620,000	\$ -
2190	Ventura	Hall of Justice	E2010 Fixed Furnishings	\$ 3,466,000	\$ 2,421,000	\$ 1,045,000
2191	Alameda	Fremont Hall of Justice	E2010 Fixed Furnishings	\$ 808,000	\$ 642,000	\$ 166,000
2192	Humboldt	Humboldt County Courthouse (Eureka)	E2010 Fixed Furnishings	\$ 1,118,000	\$ 373,000	\$ 745,000
2193	Imperial	Imperial County Courthouse	E2010 Fixed Furnishings	\$ 499,000	\$ 499,000	\$ -
2194	Kern	Bakersfield Superior Court	E2010 Fixed Furnishings	\$ 1,158,000	\$ 725,000	\$ 433,000
2195	Los Angeles	Beverly Hills Courthouse	E2010 Fixed Furnishings	\$ 842,000	\$ 669,000	\$ 172,000
2196	Los Angeles	Burbank Courthouse	E2010 Fixed Furnishings	\$ 308,000	\$ 279,000	\$ 28,000
2197	Los Angeles	Metropolitan Courthouse	E2010 Fixed Furnishings	\$ 2,989,000	\$ 2,826,000	\$ 163,000
2198	Los Angeles	West Covina Courthouse	E2010 Fixed Furnishings	\$ 804,000	\$ 667,000	\$ 137,000
2199	San Diego	South County Regional Center	E2010 Fixed Furnishings	\$ 658,000	\$ 236,000	\$ 422,000
2200	Tulare	Visalia Superior Court	E2010 Fixed Furnishings	\$ 1,090,000	\$ 352,000	\$ 737,000
2201	Santa Barbara	Santa Maria Courts, Bldg G	E2010 Fixed Furnishings	\$ 97,000	\$ 94,000	\$ 3,000

2202	Riverside	Hall of Justice	E2010 Fixed Furnishings	\$ 765,000	\$ 765,000	\$ -
2203	San Bernardino	Joshua Tree Courthouse	E2010 Fixed Furnishings	\$ 190,000	\$ 64,000	\$ 126,000
2204	San Bernardino	Fontana Courthouse	E2010 Fixed Furnishings	\$ 336,000	\$ 276,000	\$ 60,000
2205	Santa Barbara	Santa Maria Juvenile Court (new)	E2010 Fixed Furnishings	\$ 44,000	\$ 29,000	\$ 15,000
2206	Los Angeles	Van Nuys Courthouse East	C1020 Interior Doors	\$ 1,373,000	\$ 1,232,000	\$ 141,000
2207	Alameda	Wiley W. Manuel Courthouse	C1020 Interior Doors	\$ 749,000	\$ 628,000	\$ 121,000
2208	Santa Barbara	Santa Maria Courts, Bldg F	C1020 Interior Doors	\$ 28,000	\$ 28,000	\$ -
2209	El Dorado	Johnson Bldg.	C1020 Interior Doors	\$ 59,000	\$ 59,000	\$ -
2210	Del Norte	Del Norte County Superior Court	C1020 Interior Doors	\$ 60,000	\$ 37,000	\$ 23,000
2211	Los Angeles	Metropolitan Courthouse	C1020 Interior Doors	\$ 544,000	\$ 515,000	\$ 30,000
2212	Butte	Butte County Courthouse	C1020 Interior Doors	\$ 57,000	\$ 57,000	\$ -
2213	Butte	Butte County Courthouse	G10 Demolition	\$ 38,000	\$ 38,000	\$ -
2214	Los Angeles	Alhambra Courthouse	C1020 Interior Doors	\$ 425,000	\$ 365,000	\$ 59,000
2215	Los Angeles	West Covina Courthouse	C1020 Interior Doors	\$ 184,000	\$ 153,000	\$ 31,000
2216	Kings	Avenal Court	C1020 Interior Doors	\$ 104,000	\$ 60,000	\$ 44,000
2217	Los Angeles	Chatsworth Courthouse	D5038 Security & Detection Systems	\$ 212,000	\$ 177,000	\$ 34,000
2218	Los Angeles	Monrovia Training Center	C1020 Interior Doors	\$ 26,000	\$ 18,000	\$ 8,000
2219	Solano	Hall of Justice	C1020 Interior Doors	\$ 335,000	\$ 244,000	\$ 91,000
2220	Los Angeles	Burbank Courthouse	C1020 Interior Doors	\$ 478,000	\$ 434,000	\$ 44,000
2221	Los Angeles	Beverly Hills Courthouse	C1020 Interior Doors	\$ 1,159,000	\$ 922,000	\$ 237,000
2222	Riverside	Larson Justice Center	C1020 Interior Doors	\$ 7,000	\$ 6,000	\$ 1,000
2223	Orange	Civil Complex Center ("CXC")	D5038 Security & Detection Systems	\$ 128,000	\$ 128,000	\$ -
2224	Los Angeles	Edmund D. Edelman Children's Court	C1020 Interior Doors	\$ 313,000	\$ 219,000	\$ 94,000
2225	San Bernardino	Joshua Tree Courthouse	C1020 Interior Doors	\$ 70,000	\$ 24,000	\$ 46,000
2226	Riverside	Family Law Court	C1010 Interior Construction	\$ 278,000	\$ 278,000	\$ -
2227	Los Angeles	Sylmar Juvenile Court	C1020 Interior Doors	\$ 71,000	\$ 24,000	\$ 47,000
2228	Los Angeles	Los Padrinos Juvenile Court	C1020 Interior Doors	\$ 28,000	\$ 8,000	\$ 20,000
2229	San Francisco	Hall of Justice	D5038 Security & Detection Systems	\$ 185,000	\$ 43,000	\$ 142,000
2230	San Bernardino	San Bernardino Courthouse	D5038 Security & Detection Systems	\$ 431,000	\$ 412,000	\$ 19,000
2231	San Bernardino	San Bernardino Courthouse	G20 Site Improvements	\$ 8,000	\$ 8,000	\$ -
2232	Solano	Law and Justice Center	D5030 Communications & Security	\$ 1,648,000	\$ 209,000	\$ 1,439,000
2233	Santa Barbara	Santa Maria Courts Bldgs C + D	D5030 Communications & Security	\$ 228,000	\$ 228,000	\$ -
2234	Santa Barbara	Santa Maria Courts Bldgs C + D	G2050 Landscaping	\$ 18,000	\$ 18,000	\$ -
2235	San Bernardino	Barstow Courthouse	D5038 Security & Detection Systems	\$ 58,000	\$ 45,000	\$ 13,000
2236	San Bernardino	Barstow Courthouse	G2050 Landscaping	\$ 27,000	\$ 21,000	\$ 6,000
2237	San Luis Obispo	1070 Palm St.	D5038 Security & Detection Systems	\$ 7,000	\$ 7,000	\$ -
2238	Riverside	Corona	D5038 Security & Detection Systems	\$ 280,000	\$ 151,000	\$ 129,000
2239	Solano	Hall of Justice	D5030 Communications & Security	\$ 110,000	\$ 80,000	\$ 30,000
2240	Solano	Hall of Justice	D5038 Security & Detection Systems	\$ 588,000	\$ 428,000	\$ 160,000
2241	San Bernardino	Rancho Cucamonga Courthouse	D5030 Communications & Security	\$ 1,579,000	\$ 1,201,000	\$ 378,000
2242	San Bernardino	Rancho Cucamonga Courthouse	D5038 Security & Detection Systems	\$ 1,311,000	\$ 997,000	\$ 314,000
2243	Riverside	Riverside Juvenile Court	D5038 Security & Detection Systems	\$ 154,000	\$ 76,000	\$ 78,000
2244	Solano	Solano Justice Building	D5030 Communications & Security	\$ 55,000	\$ 42,000	\$ 13,000
2245	Solano	Solano Justice Building	D5038 Security & Detection Systems	\$ 337,000	\$ 256,000	\$ 80,000
2246	San Bernardino	Victorville Courthouse-Dept. N-1	D5038 Security & Detection Systems	\$ 258,000	\$ 166,000	\$ 92,000
2247	Santa Barbara	Santa Maria Courts, Bldgs. A + B	G2050 Landscaping	\$ 13,000	\$ 3,000	\$ 10,000
2248	Alameda	Wiley W. Manuel Courthouse	D5038 Security & Detection Systems	\$ 543,000	\$ 455,000	\$ 88,000
2249	Alameda	Hayward Hall of Justice	D5038 Security & Detection Systems	\$ 247,000	\$ 218,000	\$ 29,000
2250	Alameda	George E. McDonald Hall of Justice	D5038 Security & Detection Systems	\$ 116,000	\$ 116,000	\$ -
2251	Alameda	Berkeley Courthouse	D5038 Security & Detection Systems	\$ 205,000	\$ 205,000	\$ -
2252	Alameda	Fremont Hall of Justice	D5030 Communications & Security	\$ 239,000	\$ 190,000	\$ 49,000
2253	Alameda	Fremont Hall of Justice	D5038 Security & Detection Systems	\$ 39,000	\$ 31,000	\$ 8,000
2254	Amador	Amador County Courthouse	D5030 Communications & Security	\$ 84,000	\$ 84,000	\$ -
2255	Butte	Butte County Courthouse	D5030 Communications & Security	\$ 174,000	\$ 174,000	\$ -
2256	Contra Costa	Family Law Center	D5030 Communications & Security	\$ 278,000	\$ 278,000	\$ -
2257	Contra Costa	Wakefield Taylor Courthouse	G20 Site Improvements	\$ 7,000	\$ 7,000	\$ -
2258	Contra Costa	Jail Annex	D5030 Communications & Security	\$ 19,000	\$ 1,000	\$ 18,000
2259	Contra Costa	Danville District Courthouse	D5030 Communications & Security	\$ 43,000	\$ 43,000	\$ -
2260	Contra Costa	George D. Carroll Courthouse	D5030 Communications & Security	\$ 133,000	\$ 100,000	\$ 33,000
2261	Contra Costa	George D. Carroll Courthouse	G2050 Landscaping	\$ 8,000	\$ 6,000	\$ 2,000
2262	Del Norte	Del Norte County Superior Court	D5030 Communications & Security	\$ 48,000	\$ 29,000	\$ 18,000
2263	El Dorado	Cameron Park	D5038 Security & Detection Systems	\$ 43,000	\$ 43,000	\$ -
2264	El Dorado	Johnson Bldg.	D5038 Security & Detection Systems	\$ 132,000	\$ 132,000	\$ -
2265	Fresno	Fresno County Courthouse	D5030 Communications & Security	\$ 610,000	\$ 585,000	\$ 25,000
2266	Fresno	Fresno County Courthouse	G2050 Landscaping	\$ 23,000	\$ 22,000	\$ 1,000
2267	Fresno	B.F. Sisk Federal Courthouse	D5030 Communications & Security	\$ 518,000	\$ 518,000	\$ -
2268	Fresno	B.F. Sisk Federal Courthouse	G2050 Landscaping	\$ 12,000	\$ 12,000	\$ -
2269	Humboldt	Humboldt County Courthouse (Eureka)	D5030 Communications & Security	\$ 400,000	\$ 133,000	\$ 266,000
2270	Humboldt	Humboldt County Courthouse (Eureka)	G20 Site Improvements	\$ 33,000	\$ 11,000	\$ 22,000
2271	Imperial	Imperial County Courthouse	D5038 Security & Detection Systems	\$ 273,000	\$ 273,000	\$ -
2272	Kern	Bakersfield Superior Court	D5038 Security & Detection Systems	\$ 1,325,000	\$ 830,000	\$ 495,000
2273	Kern	Bakersfield Justice Bldg.	D5030 Communications & Security	\$ 476,000	\$ 243,000	\$ 233,000
2274	Kern	Bakersfield Justice Bldg.	D5038 Security & Detection Systems	\$ 878,000	\$ 448,000	\$ 429,000
2275	Kern	Bakersfield Juvenile Center	D5038 Security & Detection Systems	\$ 359,000	\$ 240,000	\$ 119,000
2276	Kern	Bakersfield Juvenile Center	G2050 Landscaping	\$ 7,000	\$ 5,000	\$ 2,000
2277	Kern	Delano/North Kern Court	D5038 Security & Detection Systems	\$ 132,000	\$ 106,000	\$ 25,000

2278	Kern	Delano/North Kern Court	G2050 Landscaping	\$ 20,000	\$ 16,000	\$ 4,000
2279	Kern	Shafter/Wasco Courts Bldg.	D5038 Security & Detection Systems	\$ 154,000	\$ 139,000	\$ 15,000
2280	Kern	Shafter/Wasco Courts Bldg.	G2050 Landscaping	\$ 12,000	\$ 11,000	\$ 1,000
2281	Kern	Taft Courts Bldg.	D5038 Security & Detection Systems	\$ 7,000	\$ 7,000	\$ -
2282	Kern	Arvin/ Lamont Branch	D5038 Security & Detection Systems	\$ 236,000	\$ 144,000	\$ 92,000
2283	Kern	Arvin/ Lamont Branch	G2050 Landscaping	\$ 16,000	\$ 9,000	\$ 6,000
2284	Kings	Avenal Court	D5030 Communications & Security	\$ 23,000	\$ 13,000	\$ 10,000
2285	Kings	Corcoran Court	D5030 Communications & Security	\$ 29,000	\$ 26,000	\$ 4,000
2286	Los Angeles	San Fernando Courthouse	D5030 Communications & Security	\$ 528,000	\$ 441,000	\$ 88,000
2287	Los Angeles	San Fernando Courthouse	G20 Site Improvements	\$ 33,000	\$ 27,000	\$ 5,000
2288	Los Angeles	Santa Clarita Courthouse	D5038 Security & Detection Systems	\$ 139,000	\$ 123,000	\$ 16,000
2289	Los Angeles	Alfred J. McCourtney Juvenile Justice	D5038 Security & Detection Systems	\$ 94,000	\$ 65,000	\$ 29,000
2290	Los Angeles	Alfred J. McCourtney Juvenile Justice	G20 Site Improvements	\$ 152,000	\$ 105,000	\$ 47,000
2291	Los Angeles	Sylmar Juvenile Court	D5038 Security & Detection Systems	\$ 16,000	\$ 6,000	\$ 11,000
2292	Los Angeles	Compton Courthouse	D5038 Security & Detection Systems	\$ 806,000	\$ 533,000	\$ 273,000
2293	Los Angeles	Compton Courthouse	G2050 Landscaping	\$ 127,000	\$ 84,000	\$ 43,000
2294	Los Angeles	Los Padrinos Juvenile Court	D5038 Security & Detection Systems	\$ 12,000	\$ 4,000	\$ 9,000
2295	Los Angeles	Norwalk Courthouse	D5038 Security & Detection Systems	\$ 261,000	\$ 222,000	\$ 39,000
2296	Los Angeles	Bellflower Courthouse	D5038 Security & Detection Systems	\$ 373,000	\$ 291,000	\$ 82,000
2297	Los Angeles	Bellflower Courthouse	G2050 Landscaping	\$ 16,000	\$ 12,000	\$ 3,000
2298	Los Angeles	Downey Courthouse	D5030 Communications & Security	\$ 94,000	\$ 79,000	\$ 15,000
2299	Los Angeles	Downey Courthouse	D5038 Security & Detection Systems	\$ 779,000	\$ 652,000	\$ 127,000
2300	Los Angeles	Downey Courthouse	G2050 Landscaping	\$ 24,000	\$ 20,000	\$ 4,000
2301	Los Angeles	Santa Monica Courthouse	D5038 Security & Detection Systems	\$ 233,000	\$ 183,000	\$ 50,000
2302	Los Angeles	Santa Monica Court Annex	D5038 Security & Detection Systems	\$ 34,000	\$ 34,000	\$ -
2303	Los Angeles	Beverly Hills Courthouse	D5038 Security & Detection Systems	\$ 377,000	\$ 300,000	\$ 77,000
2304	Los Angeles	Airport Courthouse	D5030 Communications & Security	\$ 21,000	\$ 16,000	\$ 5,000
2305	Los Angeles	Airport Courthouse	D5038 Security & Detection Systems	\$ 1,525,000	\$ 1,177,000	\$ 348,000
2306	Los Angeles	Hall of Records	D5038 Security & Detection Systems	\$ 10,000	\$ 1,000	\$ 9,000
2307	Los Angeles	Hall of Records	G2050 Landscaping	\$ 38,000	\$ 4,000	\$ 34,000
2308	Los Angeles	Van Nuys Courthouse East	D5038 Security & Detection Systems	\$ 38,000	\$ 34,000	\$ 4,000
2309	Los Angeles	Van Nuys Courthouse West	D5038 Security & Detection Systems	\$ 69,000	\$ 56,000	\$ 14,000
2310	Los Angeles	Michael D. Antonovich Antelope Vall	D5038 Security & Detection Systems	\$ 1,109,000	\$ 815,000	\$ 294,000
2311	Los Angeles	Torrance Courthouse	D5038 Security & Detection Systems	\$ 51,000	\$ 46,000	\$ 5,000
2312	Los Angeles	Inglewood Juvenile Court	D5038 Security & Detection Systems	\$ 82,000	\$ 66,000	\$ 16,000
2313	Los Angeles	Inglewood Courthouse	D5038 Security & Detection Systems	\$ 1,122,000	\$ 836,000	\$ 285,000
2314	Los Angeles	Inglewood Courthouse	G2050 Landscaping	\$ 49,000	\$ 37,000	\$ 12,000
2315	Los Angeles	Burbank Courthouse	D5038 Security & Detection Systems	\$ 201,000	\$ 183,000	\$ 19,000
2316	Los Angeles	Glendale Courthouse	D5038 Security & Detection Systems	\$ 56,000	\$ 51,000	\$ 5,000
2317	Los Angeles	Glendale Courthouse	G2050 Landscaping	\$ 17,000	\$ 15,000	\$ 2,000
2318	Los Angeles	Alhambra Courthouse	D5038 Security & Detection Systems	\$ 128,000	\$ 110,000	\$ 18,000
2319	Los Angeles	Pasadena Courthouse	D5038 Security & Detection Systems	\$ 49,000	\$ 34,000	\$ 15,000
2320	Los Angeles	Stanley Mosk Courthouse	D5038 Security & Detection Systems	\$ 369,000	\$ 359,000	\$ 10,000
2321	Los Angeles	Clara Shortridge Foltz Criminal Justice	D5030 Communications & Security	\$ 7,000	\$ 5,000	\$ 2,000
2322	Los Angeles	El Monte Courthouse	D5038 Security & Detection Systems	\$ 63,000	\$ 36,000	\$ 26,000
2323	Los Angeles	El Monte Courthouse	G2050 Landscaping	\$ 7,000	\$ 4,000	\$ 3,000
2324	Los Angeles	Edmund D. Edelman Children's Court	D5038 Security & Detection Systems	\$ 1,306,000	\$ 914,000	\$ 392,000
2325	Los Angeles	Edmund D. Edelman Children's Court	G2050 Landscaping	\$ 53,000	\$ 37,000	\$ 16,000
2326	Los Angeles	Eastlake Juvenile Court	D5038 Security & Detection Systems	\$ 6,000	\$ 3,000	\$ 3,000
2327	Los Angeles	Metropolitan Courthouse	D5038 Security & Detection Systems	\$ 369,000	\$ 349,000	\$ 20,000
2328	Los Angeles	Central Arraignment Courts	D5038 Security & Detection Systems	\$ 99,000	\$ 89,000	\$ 10,000
2329	Los Angeles	East Los Angeles Courthouse	D5038 Security & Detection Systems	\$ 355,000	\$ 276,000	\$ 79,000
2330	Los Angeles	Pomona Courthouse South	D5038 Security & Detection Systems	\$ 1,111,000	\$ 1,013,000	\$ 98,000
2331	Los Angeles	West Covina Courthouse	D5038 Security & Detection Systems	\$ 442,000	\$ 367,000	\$ 75,000
2332	Madera	Sierra Courthouse	D5030 Communications & Security	\$ 48,000	\$ 33,000	\$ 16,000
2333	Madera	Sierra Courthouse	G2050 Landscaping	\$ 43,000	\$ 29,000	\$ 14,000
2334	Merced	Old Court	D5038 Security & Detection Systems	\$ 112,000	\$ 112,000	\$ -
2335	Merced	Downtown Merced Courthouse	D5038 Security & Detection Systems	\$ 331,000	\$ 331,000	\$ -
2336	Merced	Downtown Merced Courthouse	G2050 Landscaping	\$ 134,000	\$ 134,000	\$ -
2337	Napa	Criminal Court Building	D5038 Security & Detection Systems	\$ 117,000	\$ 117,000	\$ -
2338	Nevada	Nevada City Courthouse	D5030 Communications & Security	\$ 40,000	\$ 26,000	\$ 14,000
2339	Nevada	Nevada City Courthouse	G20 Site Improvements	\$ 7,000	\$ 4,000	\$ 2,000
2340	Nevada	Nevada City Courthouse Annex	D5030 Communications & Security	\$ 65,000	\$ 28,000	\$ 37,000
2341	Nevada	Nevada City Courthouse Annex	G20 Site Improvements	\$ 7,000	\$ 3,000	\$ 4,000
2342	Orange	Central Justice Center	D5030 Communications & Security	\$ 941,000	\$ 858,000	\$ 83,000
2343	Orange	Central Justice Center	D5038 Security & Detection Systems	\$ 164,000	\$ 150,000	\$ 14,000
2344	Orange	Central Justice Center Annex	D5038 Security & Detection Systems	\$ 44,000	\$ 4,000	\$ 41,000
2345	Orange	Betty Lou Lamoreaux Justice Center	D5038 Security & Detection Systems	\$ 754,000	\$ 603,000	\$ 151,000
2346	Orange	Betty Lou Lamoreaux Justice Center	G20 Site Improvements	\$ 11,000	\$ 9,000	\$ 2,000
2347	Orange	North Justice Center	D5038 Security & Detection Systems	\$ 657,000	\$ 594,000	\$ 64,000
2348	Orange	West Justice Center	D5038 Security & Detection Systems	\$ 347,000	\$ 314,000	\$ 32,000
2349	Orange	West Justice Center	G20 Site Improvements	\$ 336,000	\$ 304,000	\$ 31,000
2350	Placer	Historic Courthouse	D5030 Communications & Security	\$ 35,000	\$ 27,000	\$ 8,000
2351	Placer	Bill Santucci Justice Center	D5030 Communications & Security	\$ 456,000	\$ 456,000	\$ -
2352	Sacramento	Gordon Schaber Sacramento Superior	D5030 Communications & Security	\$ 898,000	\$ 898,000	\$ -
2353	Sacramento	Juvenile Courthouse	D5030 Communications & Security	\$ 586,000	\$ 586,000	\$ -

2354	Sacramento	Carol Miller Justice Center Court Fac	D5030 Communications & Security	\$ 620,000	\$ 606,000	\$ 14,000
2355	San Diego	Hall of Justice	D5038 Security & Detection Systems	\$ 1,621,000	\$ 652,000	\$ 969,000
2356	San Diego	Hall of Justice	G20 Site Improvements	\$ 36,000	\$ 14,000	\$ 21,000
2357	San Diego	Kearny Mesa Court	D5038 Security & Detection Systems	\$ 318,000	\$ 318,000	\$ -
2358	San Diego	Juvenile Court	D5038 Security & Detection Systems	\$ 323,000	\$ 241,000	\$ 82,000
2359	San Diego	Juvenile Court	G2050 Landscaping	\$ 74,000	\$ 55,000	\$ 19,000
2360	San Diego	North County Regional Center - South	D5038 Security & Detection Systems	\$ 1,428,000	\$ 960,000	\$ 468,000
2361	San Diego	North County Regional Center - North	D5038 Security & Detection Systems	\$ 1,488,000	\$ 1,488,000	\$ -
2362	San Diego	North County Regional Center - North	G20 Site Improvements	\$ 13,000	\$ 13,000	\$ -
2363	San Diego	North County Regional Center - Anne	D5038 Security & Detection Systems	\$ 151,000	\$ 151,000	\$ -
2364	San Diego	South County Regional Center	D5030 Communications & Security	\$ 102,000	\$ 37,000	\$ 65,000
2365	San Diego	South County Regional Center	D5038 Security & Detection Systems	\$ 739,000	\$ 265,000	\$ 474,000
2366	San Diego	East County Regional Center	D5038 Security & Detection Systems	\$ 1,743,000	\$ 1,180,000	\$ 563,000
2367	San Mateo	Hall of Justice	D5030 Communications & Security	\$ 255,000	\$ 135,000	\$ 121,000
2368	San Mateo	Traffic/ Small Claims Annex	D5030 Communications & Security	\$ 22,000	\$ 22,000	\$ -
2369	San Mateo	Central Branch	D5030 Communications & Security	\$ 102,000	\$ 102,000	\$ -
2370	San Mateo	Northern Branch Courthouse	D5030 Communications & Security	\$ 84,000	\$ 70,000	\$ 14,000
2371	Santa Clara	Hall of Justice (East)	D5030 Communications & Security	\$ 260,000	\$ 260,000	\$ -
2372	Santa Clara	Hall of Justice (West)	D5030 Communications & Security	\$ 290,000	\$ 290,000	\$ -
2373	Santa Clara	Downtown Superior Court	D5030 Communications & Security	\$ 308,000	\$ 308,000	\$ -
2374	Santa Clara	Historic Courthouse	D5030 Communications & Security	\$ 147,000	\$ 147,000	\$ -
2375	Santa Clara	Sunnyvale Courthouse	G2050 Landscaping	\$ 9,000	\$ 9,000	\$ -
2376	Santa Clara	Santa Clara Courthouse	D5030 Communications & Security	\$ 206,000	\$ 206,000	\$ -
2377	Santa Clara	Santa Clara Courthouse	G2050 Landscaping	\$ 9,000	\$ 9,000	\$ -
2378	Tulare	Visalia Superior Court	D5038 Security & Detection Systems	\$ 1,303,000	\$ 421,000	\$ 882,000
2379	Ventura	Hall of Justice	D5038 Security & Detection Systems	\$ 1,469,000	\$ 1,026,000	\$ 443,000
2380	Ventura	Hall of Justice	G20 Site Improvements	\$ 21,000	\$ 15,000	\$ 6,000
2381	Ventura	East County Courthouse	D5030 Communications & Security	\$ 12,000	\$ 8,000	\$ 5,000
2382	Ventura	East County Courthouse	D5038 Security & Detection Systems	\$ 143,000	\$ 88,000	\$ 55,000
2383	Santa Barbara	Santa Maria Courts, Bldg G	D5030 Communications & Security	\$ 199,000	\$ 192,000	\$ 7,000
2384	Santa Barbara	Santa Maria Courts, Bldg G	G20 Site Improvements	\$ 1,554,000	\$ 1,499,000	\$ 55,000
2385	Riverside	Hall of Justice	D5030 Communications & Security	\$ 1,022,000	\$ 1,022,000	\$ -
2386	San Luis Obispo	Courthouse Annex	D5038 Security & Detection Systems	\$ 290,000	\$ 144,000	\$ 146,000
2387	San Luis Obispo	Courthouse Annex	G2050 Landscaping	\$ 25,000	\$ 13,000	\$ 13,000
2388	San Bernardino	Joshua Tree Courthouse	D5038 Security & Detection Systems	\$ 60,000	\$ 20,000	\$ 40,000
2389	San Bernardino	Fontana Courthouse	D5038 Security & Detection Systems	\$ 66,000	\$ 54,000	\$ 12,000
2390	San Bernardino	Fontana Courthouse	G2050 Landscaping	\$ 12,000	\$ 9,000	\$ 2,000
2391	Riverside	Blythe Courthouse - Superior Court	D5038 Security & Detection Systems	\$ 59,000	\$ 59,000	\$ -
2392	Riverside	Larson Justice Center	D5030 Communications & Security	\$ 1,881,000	\$ 1,520,000	\$ 361,000
2393	Santa Barbara	Santa Maria Juvenile Court (new)	D5030 Communications & Security	\$ 71,000	\$ 47,000	\$ 24,000
2394	San Francisco	Civic Center Courthouse	D5030 Communications & Security	\$ 1,250,000	\$ 1,250,000	\$ -
2395	San Francisco	Hall of Justice	C3010 Wall Finishes	\$ 2,769,000	\$ 644,000	\$ 2,125,000
2396	San Bernardino	San Bernardino Courthouse	C3010 Wall Finishes	\$ 515,000	\$ 492,000	\$ 22,000
2397	Solano	Law and Justice Center	C30 Interior Finishes	\$ 50,000	\$ 6,000	\$ 44,000
2398	Solano	Law and Justice Center	C3010 Wall Finishes	\$ 110,000	\$ 14,000	\$ 96,000
2399	Santa Barbara	Santa Maria Courts Bldgs C + D	B10 Superstructure	\$ 20,000	\$ 20,000	\$ -
2400	Santa Barbara	Santa Maria Courts Bldgs C + D	C3010 Wall Finishes	\$ 141,000	\$ 141,000	\$ -
2401	San Bernardino	Barstow Courthouse	C3010 Wall Finishes	\$ 140,000	\$ 109,000	\$ 31,000
2402	Santa Barbara	Santa Maria Courts, Bldg F	C3010 Wall Finishes	\$ 25,000	\$ 25,000	\$ -
2403	San Luis Obispo	1070 Palm St.	C3010 Wall Finishes	\$ 50,000	\$ 50,000	\$ -
2404	Riverside	Corona	C3010 Wall Finishes	\$ 67,000	\$ 36,000	\$ 31,000
2405	Solano	Hall of Justice	C3010 Wall Finishes	\$ 398,000	\$ 290,000	\$ 108,000
2406	San Bernardino	Rancho Cucamonga Courthouse	C3010 Wall Finishes	\$ 2,152,000	\$ 1,637,000	\$ 515,000
2407	Riverside	Riverside Juvenile Court	C3010 Wall Finishes	\$ 320,000	\$ 158,000	\$ 162,000
2408	Solano	Solano Justice Building	C3010 Wall Finishes	\$ 572,000	\$ 435,000	\$ 137,000
2409	San Bernardino	Victorville Courthouse-Dept. N-1	C3010 Wall Finishes	\$ 346,000	\$ 222,000	\$ 124,000
2410	Santa Barbara	Santa Maria Courts, Bldgs. A + B	C3010 Wall Finishes	\$ 35,000	\$ 8,000	\$ 27,000
2411	Alameda	Wiley W. Manuel Courthouse	C3010 Wall Finishes	\$ 1,451,000	\$ 1,216,000	\$ 235,000
2412	Alameda	Hayward Hall of Justice	B10 Superstructure	\$ 7,000	\$ 7,000	\$ 1,000
2413	Alameda	Hayward Hall of Justice	C3010 Wall Finishes	\$ 1,638,000	\$ 1,447,000	\$ 192,000
2414	Alameda	George E. McDonald Hall of Justice	C3010 Wall Finishes	\$ 62,000	\$ 62,000	\$ -
2415	Alameda	Berkeley Courthouse	C3010 Wall Finishes	\$ 32,000	\$ 32,000	\$ -
2416	Alameda	Fremont Hall of Justice	C3010 Wall Finishes	\$ 440,000	\$ 349,000	\$ 91,000
2417	Amador	Amador County Courthouse	C3010 Wall Finishes	\$ 61,000	\$ 61,000	\$ -
2418	Butte	Butte County Courthouse	C3010 Wall Finishes	\$ 396,000	\$ 396,000	\$ -
2419	Contra Costa	Family Law Center	C3010 Wall Finishes	\$ 274,000	\$ 274,000	\$ -
2420	Contra Costa	Wakefield Taylor Courthouse	B10 Superstructure	\$ 30,000	\$ 30,000	\$ -
2421	Contra Costa	Wakefield Taylor Courthouse	C3010 Wall Finishes	\$ 1,171,000	\$ 1,171,000	\$ -
2422	Contra Costa	Bray Courts	C3010 Wall Finishes	\$ 92,000	\$ 78,000	\$ 13,000
2423	Contra Costa	Jail Annex	C3010 Wall Finishes	\$ 64,000	\$ 4,000	\$ 60,000
2424	Contra Costa	Danville District Courthouse	C3010 Wall Finishes	\$ 80,000	\$ 80,000	\$ -
2425	Contra Costa	George D. Carroll Courthouse	B10 Superstructure	\$ 29,000	\$ 22,000	\$ 7,000
2426	Contra Costa	George D. Carroll Courthouse	C3010 Wall Finishes	\$ 416,000	\$ 312,000	\$ 104,000
2427	Del Norte	Del Norte County Superior Court	C3010 Wall Finishes	\$ 233,000	\$ 143,000	\$ 90,000
2428	El Dorado	Cameron Park	C3010 Wall Finishes	\$ 67,000	\$ 67,000	\$ -
2429	El Dorado	Johnson Bldg.	C3010 Wall Finishes	\$ 146,000	\$ 146,000	\$ -

2430	Fresno	Fresno County Courthouse	C3010 Wall Finishes	\$ 4,093,000	\$ 3,926,000	\$ 167,000
2431	Fresno	B.F. Sisk Federal Courthouse	C3010 Wall Finishes	\$ 1,118,000	\$ 1,118,000	\$ -
2432	Humboldt	Humboldt County Courthouse (Eureka)	B10 Superstructure	\$ 110,000	\$ 37,000	\$ 73,000
2433	Humboldt	Humboldt County Courthouse (Eureka)	C3010 Wall Finishes	\$ 832,000	\$ 278,000	\$ 554,000
2434	Imperial	Imperial County Courthouse	C3010 Wall Finishes	\$ 369,000	\$ 369,000	\$ -
2435	Kern	Bakersfield Superior Court	C3010 Wall Finishes	\$ 1,767,000	\$ 1,107,000	\$ 660,000
2436	Kern	Bakersfield Juvenile Center	C3010 Wall Finishes	\$ 616,000	\$ 412,000	\$ 205,000
2437	Kern	Delano/North Kern Court	C3010 Wall Finishes	\$ 51,000	\$ 41,000	\$ 10,000
2438	Kern	Shafter/Wasco Courts Bldg.	C3010 Wall Finishes	\$ 83,000	\$ 74,000	\$ 8,000
2439	Kern	Taft Courts Bldg.	C3010 Wall Finishes	\$ 35,000	\$ 35,000	\$ -
2440	Kern	Arvin/ Lamont Branch	C3010 Wall Finishes	\$ 146,000	\$ 89,000	\$ 57,000
2441	Kings	Avenal Court	C3010 Wall Finishes	\$ 43,000	\$ 25,000	\$ 18,000
2442	Kings	Corcoran Court	C3010 Wall Finishes	\$ 14,000	\$ 12,000	\$ 2,000
2443	Los Angeles	San Fernando Courthouse	C3010 Wall Finishes	\$ 281,000	\$ 234,000	\$ 47,000
2444	Los Angeles	Santa Clarita Courthouse	C3010 Wall Finishes	\$ 141,000	\$ 124,000	\$ 16,000
2445	Los Angeles	Alfred J. McCourtney Juvenile Justice	C3010 Wall Finishes	\$ 255,000	\$ 176,000	\$ 79,000
2446	Los Angeles	Sylmar Juvenile Court	C3010 Wall Finishes	\$ 23,000	\$ 8,000	\$ 15,000
2447	Los Angeles	Compton Courthouse	C3010 Wall Finishes	\$ 1,203,000	\$ 795,000	\$ 407,000
2448	Los Angeles	Los Padrinos Juvenile Court	C3010 Wall Finishes	\$ 19,000	\$ 6,000	\$ 13,000
2449	Los Angeles	Norwalk Courthouse	C3010 Wall Finishes	\$ 1,561,000	\$ 1,328,000	\$ 234,000
2450	Los Angeles	Bellflower Courthouse	C3010 Wall Finishes	\$ 482,000	\$ 375,000	\$ 106,000
2451	Los Angeles	Downey Courthouse	C3010 Wall Finishes	\$ 1,026,000	\$ 858,000	\$ 167,000
2452	Los Angeles	Santa Monica Courthouse	C3010 Wall Finishes	\$ 660,000	\$ 518,000	\$ 142,000
2453	Los Angeles	Santa Monica Court Annex	C3010 Wall Finishes	\$ 10,000	\$ 10,000	\$ -
2454	Los Angeles	Beverly Hills Courthouse	B10 Superstructure	\$ 12,000	\$ 9,000	\$ 2,000
2455	Los Angeles	Airport Courthouse	C3010 Wall Finishes	\$ 1,468,000	\$ 1,133,000	\$ 335,000
2456	Los Angeles	Hall of Records	C3010 Wall Finishes	\$ 120,000	\$ 13,000	\$ 108,000
2457	Los Angeles	Van Nuys Courthouse East	C3010 Wall Finishes	\$ 681,000	\$ 611,000	\$ 70,000
2458	Los Angeles	Van Nuys Courthouse West	C3010 Wall Finishes	\$ 1,877,000	\$ 1,510,000	\$ 366,000
2459	Los Angeles	Chatsworth Courthouse	C3010 Wall Finishes	\$ 1,187,000	\$ 994,000	\$ 192,000
2460	Los Angeles	Michael D. Antonovich Antelope Vall	C3010 Wall Finishes	\$ 2,440,000	\$ 1,794,000	\$ 646,000
2461	Los Angeles	Torrance Courthouse	C3010 Wall Finishes	\$ 844,000	\$ 763,000	\$ 81,000
2462	Los Angeles	Inglewood Juvenile Court	C3010 Wall Finishes	\$ 212,000	\$ 172,000	\$ 41,000
2463	Los Angeles	Inglewood Courthouse	C3010 Wall Finishes	\$ 1,183,000	\$ 882,000	\$ 301,000
2464	Los Angeles	Burbank Courthouse	C3010 Wall Finishes	\$ 442,000	\$ 401,000	\$ 41,000
2465	Los Angeles	Glendale Courthouse	C3010 Wall Finishes	\$ 395,000	\$ 357,000	\$ 37,000
2466	Los Angeles	Alhambra Courthouse	C3010 Wall Finishes	\$ 932,000	\$ 802,000	\$ 131,000
2467	Los Angeles	Pasadena Courthouse	C3010 Wall Finishes	\$ 3,277,000	\$ 2,273,000	\$ 1,004,000
2468	Los Angeles	Clara Shortridge Foltz Criminal Justice	C3010 Wall Finishes	\$ 14,100,000	\$ 9,700,000	\$ 4,400,000
2469	Los Angeles	Monrovia Training Center	C3010 Wall Finishes	\$ 99,000	\$ 70,000	\$ 30,000
2470	Los Angeles	El Monte Courthouse	B10 Superstructure	\$ 11,000	\$ 6,000	\$ 4,000
2471	Los Angeles	El Monte Courthouse	C3010 Wall Finishes	\$ 725,000	\$ 421,000	\$ 304,000
2472	Los Angeles	Edmund D. Edelman Children's Court	C3010 Wall Finishes	\$ 1,945,000	\$ 1,361,000	\$ 584,000
2473	Los Angeles	Eastlake Juvenile Court	B10 Superstructure	\$ 11,000	\$ 6,000	\$ 5,000
2474	Los Angeles	Eastlake Juvenile Court	C3010 Wall Finishes	\$ 451,000	\$ 247,000	\$ 204,000
2475	Los Angeles	Metropolitan Courthouse	C3010 Wall Finishes	\$ 1,310,000	\$ 1,239,000	\$ 72,000
2476	Los Angeles	Central Arraignment Courts	C3010 Wall Finishes	\$ 557,000	\$ 503,000	\$ 54,000
2477	Los Angeles	East Los Angeles Courthouse	C3010 Wall Finishes	\$ 2,086,000	\$ 1,621,000	\$ 465,000
2478	Los Angeles	Pomona Courthouse South	B10 Superstructure	\$ 10,000	\$ 9,000	\$ 1,000
2479	Los Angeles	West Covina Courthouse	C3010 Wall Finishes	\$ 1,441,000	\$ 1,196,000	\$ 245,000
2480	Madera	Sierra Courthouse	C3010 Wall Finishes	\$ 58,000	\$ 39,000	\$ 19,000
2481	Merced	Old Court	C3010 Wall Finishes	\$ 144,000	\$ 144,000	\$ -
2482	Merced	Downtown Merced Courthouse	C3010 Wall Finishes	\$ 269,000	\$ 269,000	\$ -
2483	Napa	Criminal Court Building	C3010 Wall Finishes	\$ 369,000	\$ 369,000	\$ -
2484	Nevada	Nevada City Courthouse	B10 Superstructure	\$ 103,000	\$ 68,000	\$ 36,000
2485	Nevada	Nevada City Courthouse	C3010 Wall Finishes	\$ 105,000	\$ 68,000	\$ 36,000
2486	Nevada	Nevada City Courthouse Annex	B10 Superstructure	\$ 87,000	\$ 37,000	\$ 50,000
2487	Nevada	Nevada City Courthouse Annex	C3010 Wall Finishes	\$ 348,000	\$ 149,000	\$ 200,000
2488	Orange	Central Justice Center	C30 Interior Finishes	\$ 30,000	\$ 27,000	\$ 3,000
2489	Orange	Central Justice Center	C3010 Wall Finishes	\$ 1,719,000	\$ 1,567,000	\$ 152,000
2490	Orange	Central Justice Center Annex	C3010 Wall Finishes	\$ 27,000	\$ 2,000	\$ 24,000
2491	Orange	Civil Complex Center ("CXC")	C3010 Wall Finishes	\$ 146,000	\$ 146,000	\$ -
2492	Orange	Betty Lou Lamoreaux Justice Center	C3010 Wall Finishes	\$ 1,225,000	\$ 979,000	\$ 246,000
2493	Orange	North Justice Center	B10 Superstructure	\$ 8,000	\$ 7,000	\$ 1,000
2494	Orange	North Justice Center	C3010 Wall Finishes	\$ 986,000	\$ 890,000	\$ 96,000
2495	Orange	West Justice Center	C3010 Wall Finishes	\$ 491,000	\$ 445,000	\$ 46,000
2496	Placer	Historic Courthouse	C3010 Wall Finishes	\$ 385,000	\$ 297,000	\$ 89,000
2497	Placer	Bill Santucci Justice Center	C3010 Wall Finishes	\$ 479,000	\$ 479,000	\$ -
2498	Sacramento	Gordon Schaber Sacramento Superior	B10 Superstructure	\$ 68,000	\$ 68,000	\$ -
2499	Sacramento	Gordon Schaber Sacramento Superior	C3010 Wall Finishes	\$ 4,038,000	\$ 4,038,000	\$ -
2500	Sacramento	Juvenile Courthouse	C3010 Wall Finishes	\$ 542,000	\$ 542,000	\$ -
2501	Sacramento	Carol Miller Justice Center Court Faci	C3010 Wall Finishes	\$ 330,000	\$ 322,000	\$ 7,000
2502	San Diego	Hall of Justice	C3010 Wall Finishes	\$ 1,082,000	\$ 435,000	\$ 647,000
2503	San Diego	Kearny Mesa Court	C3010 Wall Finishes	\$ 235,000	\$ 235,000	\$ -
2504	San Diego	Juvenile Court	C3010 Wall Finishes	\$ 550,000	\$ 410,000	\$ 140,000
2505	San Diego	North County Regional Center - South	C3010 Wall Finishes	\$ 1,172,000	\$ 788,000	\$ 384,000

2506	San Diego	North County Regional Center - North	C3010 Wall Finishes	\$ 509,000	\$ 509,000	\$ -
2507	San Diego	North County Regional Center - Anne	C3010 Wall Finishes	\$ 119,000	\$ 119,000	\$ -
2508	San Diego	South County Regional Center	C3010 Wall Finishes	\$ 611,000	\$ 219,000	\$ 392,000
2509	San Diego	East County Regional Center	C3010 Wall Finishes	\$ 1,697,000	\$ 1,149,000	\$ 548,000
2510	San Joaquin	Lodi Branch- Dept. 2	C3010 Wall Finishes	\$ 55,000	\$ 55,000	\$ -
2511	San Mateo	Hall of Justice	C3010 Wall Finishes	\$ 1,888,000	\$ 995,000	\$ 893,000
2512	San Mateo	Traffic/ Small Claims Annex	C3010 Wall Finishes	\$ 74,000	\$ 74,000	\$ -
2513	San Mateo	Central Branch	C3010 Wall Finishes	\$ 267,000	\$ 267,000	\$ -
2514	San Mateo	Northern Branch Courthouse	B10 Superstructure	\$ 7,000	\$ 6,000	\$ 1,000
2515	San Mateo	Northern Branch Courthouse	C3010 Wall Finishes	\$ 933,000	\$ 776,000	\$ 157,000
2516	Santa Clara	Hall of Justice (East)	C3010 Wall Finishes	\$ 2,455,000	\$ 2,455,000	\$ -
2517	Santa Clara	Hall of Justice (West)	C3010 Wall Finishes	\$ 205,000	\$ 205,000	\$ -
2518	Santa Clara	Downtown Superior Court	C3010 Wall Finishes	\$ 2,027,000	\$ 2,027,000	\$ -
2519	Santa Clara	Historic Courthouse	C3010 Wall Finishes	\$ 955,000	\$ 955,000	\$ -
2520	Santa Clara	Santa Clara Courthouse	C3010 Wall Finishes	\$ 181,000	\$ 181,000	\$ -
2521	Tulare	Visalia Superior Court	B10 Superstructure	\$ 41,000	\$ 13,000	\$ 28,000
2522	Ventura	East County Courthouse	C3010 Wall Finishes	\$ 272,000	\$ 168,000	\$ 104,000
2523	Kern	Bakersfield Justice Bldg.	C3010 Wall Finishes	\$ 1,163,000	\$ 594,000	\$ 569,000
2524	Los Angeles	Beverly Hills Courthouse	C3010 Wall Finishes	\$ 1,527,000	\$ 1,214,000	\$ 313,000
2525	Los Angeles	Stanley Mosk Courthouse	C3010 Wall Finishes	\$ 3,485,000	\$ 3,390,000	\$ 95,000
2526	Los Angeles	Pomona Courthouse South	C3010 Wall Finishes	\$ 6,889,000	\$ 6,279,000	\$ 610,000
2527	Tulare	Visalia Superior Court	C3010 Wall Finishes	\$ 2,017,000	\$ 652,000	\$ 1,365,000
2528	Ventura	Hall of Justice	C3010 Wall Finishes	\$ 2,901,000	\$ 2,027,000	\$ 874,000
2529	Santa Barbara	Santa Maria Courts, Bldg G	C3010 Wall Finishes	\$ 165,000	\$ 159,000	\$ 6,000
2530	Riverside	Hall of Justice	C3010 Wall Finishes	\$ 2,642,000	\$ 2,642,000	\$ -
2531	San Luis Obispo	Courthouse Annex	C3010 Wall Finishes	\$ 535,000	\$ 266,000	\$ 269,000
2532	San Bernardino	Joshua Tree Courthouse	C3010 Wall Finishes	\$ 124,000	\$ 42,000	\$ 82,000
2533	San Bernardino	Fontana Courthouse	C3010 Wall Finishes	\$ 152,000	\$ 125,000	\$ 27,000
2534	Riverside	Blythe Courthouse - Superior Court	C3010 Wall Finishes	\$ 34,000	\$ 34,000	\$ -
2535	Riverside	Larson Justice Center	C3010 Wall Finishes	\$ 861,000	\$ 696,000	\$ 165,000
2536	Santa Barbara	Santa Maria Juvenile Court (new)	C3010 Wall Finishes	\$ 42,000	\$ 28,000	\$ 14,000
2537	San Francisco	Civic Center Courthouse	C3010 Wall Finishes	\$ 1,326,000	\$ 1,326,000	\$ -
2538	San Bernardino	San Bernardino Courthouse	B10 Superstructure	\$ 305,000	\$ 292,000	\$ 13,000
2539	San Francisco	Hall of Justice	C3030 Ceiling Finishes	\$ 2,044,000	\$ 475,000	\$ 1,568,000
2540	Riverside	Riverside Juvenile Justice Trailers	C3030 Ceiling Finishes	\$ 13,000	\$ 13,000	\$ -
2541	Riverside	Riverside Juvenile Justice Trailers	C3030 Ceiling Finishes	\$ 13,000	\$ 13,000	\$ -
2542	San Bernardino	San Bernardino Courthouse	C3030 Ceiling Finishes	\$ 803,000	\$ 768,000	\$ 35,000
2543	Santa Barbara	Santa Maria Courts Bldgs C + D	C3030 Ceiling Finishes	\$ 372,000	\$ 372,000	\$ -
2544	San Bernardino	Barstow Courthouse	C3030 Ceiling Finishes	\$ 294,000	\$ 229,000	\$ 65,000
2545	Santa Barbara	Santa Maria Courts, Bldg F	C3030 Ceiling Finishes	\$ 11,000	\$ 11,000	\$ -
2546	San Luis Obispo	1070 Palm St.	C3030 Ceiling Finishes	\$ 36,000	\$ 36,000	\$ -
2547	Riverside	Corona	C3030 Ceiling Finishes	\$ 21,000	\$ 11,000	\$ 10,000
2548	Solano	Hall of Justice	C3030 Ceiling Finishes	\$ 1,071,000	\$ 780,000	\$ 291,000
2549	San Bernardino	Rancho Cucamonga Courthouse	C3030 Ceiling Finishes	\$ 457,000	\$ 348,000	\$ 110,000
2550	Riverside	Riverside Juvenile Court	C3030 Ceiling Finishes	\$ 402,000	\$ 198,000	\$ 204,000
2551	Solano	Solano Justice Building	C3030 Ceiling Finishes	\$ 430,000	\$ 327,000	\$ 103,000
2552	San Bernardino	Victorville Courthouse-Dept. N-1	C1020 Interior Doors	\$ 88,000	\$ 56,000	\$ 31,000
2553	San Bernardino	Victorville Courthouse-Dept. N-1	C3030 Ceiling Finishes	\$ 781,000	\$ 502,000	\$ 279,000
2554	Santa Barbara	Santa Maria Courts, Bldgs. A + B	C3030 Ceiling Finishes	\$ 15,000	\$ 4,000	\$ 12,000
2555	Alameda	Wiley W. Manuel Courthouse	C3030 Ceiling Finishes	\$ 2,623,000	\$ 2,198,000	\$ 425,000
2556	Alameda	Hayward Hall of Justice	C3030 Ceiling Finishes	\$ 2,597,000	\$ 2,293,000	\$ 304,000
2557	Alameda	George E. McDonald Hall of Justice	C3030 Ceiling Finishes	\$ 160,000	\$ 160,000	\$ -
2558	Alameda	Fremont Hall of Justice	C3030 Ceiling Finishes	\$ 1,426,000	\$ 1,132,000	\$ 294,000
2559	Butte	Butte County Courthouse	C3030 Ceiling Finishes	\$ 518,000	\$ 518,000	\$ -
2560	Butte	Juvenile Hall	C3030 Ceiling Finishes	\$ 33,000	\$ 2,000	\$ 31,000
2561	Contra Costa	Wakefield Taylor Courthouse	C3030 Ceiling Finishes	\$ 555,000	\$ 555,000	\$ -
2562	Contra Costa	Bray Courts	C3030 Ceiling Finishes	\$ 70,000	\$ 60,000	\$ 10,000
2563	Contra Costa	Jail Annex	C3030 Ceiling Finishes	\$ 149,000	\$ 9,000	\$ 140,000
2564	Contra Costa	Danville District Courthouse	C3030 Ceiling Finishes	\$ 26,000	\$ 26,000	\$ -
2565	Contra Costa	George D. Carroll Courthouse	C3030 Ceiling Finishes	\$ 600,000	\$ 450,000	\$ 150,000
2566	Del Norte	Del Norte County Superior Court	C3030 Ceiling Finishes	\$ 247,000	\$ 151,000	\$ 96,000
2567	El Dorado	Cameron Park	C3030 Ceiling Finishes	\$ 79,000	\$ 79,000	\$ -
2568	El Dorado	Johnson Bldg.	C3030 Ceiling Finishes	\$ 177,000	\$ 177,000	\$ -
2569	Fresno	Fresno County Courthouse	C3030 Ceiling Finishes	\$ 1,644,000	\$ 1,577,000	\$ 67,000
2570	Fresno	B.F. Sisk Federal Courthouse	C3030 Ceiling Finishes	\$ 69,000	\$ 69,000	\$ -
2571	Humboldt	Humboldt County Courthouse (Eureka)	C3030 Ceiling Finishes	\$ 1,599,000	\$ 534,000	\$ 1,066,000
2572	Imperial	Imperial County Courthouse	C3030 Ceiling Finishes	\$ 442,000	\$ 442,000	\$ -
2573	Kern	Bakersfield Superior Court	C3030 Ceiling Finishes	\$ 1,518,000	\$ 951,000	\$ 567,000
2574	Kern	Bakersfield Justice Bldg.	C3030 Ceiling Finishes	\$ 1,122,000	\$ 573,000	\$ 549,000
2575	Kern	Bakersfield Juvenile Center	C3030 Ceiling Finishes	\$ 368,000	\$ 246,000	\$ 122,000
2576	Kern	Delano/North Kern Court	C3030 Ceiling Finishes	\$ 117,000	\$ 94,000	\$ 23,000
2577	Kern	Shafter/Wasco Courts Bldg.	C3030 Ceiling Finishes	\$ 136,000	\$ 123,000	\$ 14,000
2578	Kern	Taft Courts Bldg.	C3030 Ceiling Finishes	\$ 49,000	\$ 49,000	\$ -
2579	Kern	Arvin/ Lamont Branch	C3030 Ceiling Finishes	\$ 220,000	\$ 134,000	\$ 86,000
2580	Kings	Probation Building	C3030 Ceiling Finishes	\$ 32,000	\$ 4,000	\$ 28,000
2581	Kings	Avenal Court	C3030 Ceiling Finishes	\$ 68,000	\$ 39,000	\$ 29,000

2582	Kings	Corcoran Court	C3030 Ceiling Finishes	\$ 27,000	\$ 23,000	\$ 3,000
2583	Los Angeles	San Fernando Courthouse	C3030 Ceiling Finishes	\$ 1,293,000	\$ 1,078,000	\$ 215,000
2584	Los Angeles	Santa Clarita Courthouse	C3030 Ceiling Finishes	\$ 216,000	\$ 191,000	\$ 25,000
2585	Los Angeles	Alfred J. McCourtney Juvenile Justice	C3030 Ceiling Finishes	\$ 118,000	\$ 81,000	\$ 37,000
2586	Los Angeles	Sylmar Juvenile Court	C3030 Ceiling Finishes	\$ 26,000	\$ 9,000	\$ 17,000
2587	Los Angeles	Compton Courthouse	C3030 Ceiling Finishes	\$ 3,064,000	\$ 2,026,000	\$ 1,038,000
2588	Los Angeles	Los Padrinos Juvenile Court	C3030 Ceiling Finishes	\$ 40,000	\$ 12,000	\$ 28,000
2589	Los Angeles	Norwalk Courthouse	C3030 Ceiling Finishes	\$ 1,566,000	\$ 1,331,000	\$ 234,000
2590	Los Angeles	Bellflower Courthouse	C3030 Ceiling Finishes	\$ 1,870,000	\$ 1,457,000	\$ 413,000
2591	Los Angeles	Downey Courthouse	C3030 Ceiling Finishes	\$ 1,107,000	\$ 927,000	\$ 180,000
2592	Los Angeles	Airport Courthouse	C3030 Ceiling Finishes	\$ 1,603,000	\$ 1,237,000	\$ 366,000
2593	Los Angeles	Hall of Records	C3030 Ceiling Finishes	\$ 218,000	\$ 23,000	\$ 195,000
2594	Los Angeles	Van Nuys Courthouse East	C3030 Ceiling Finishes	\$ 1,796,000	\$ 1,612,000	\$ 184,000
2595	Los Angeles	Van Nuys Courthouse West	C3030 Ceiling Finishes	\$ 2,034,000	\$ 1,637,000	\$ 397,000
2596	Los Angeles	Chatsworth Courthouse	C3030 Ceiling Finishes	\$ 16,000	\$ 13,000	\$ 3,000
2597	Los Angeles	Michael D. Antonovich Antelope Vall	C3030 Ceiling Finishes	\$ 69,000	\$ 51,000	\$ 18,000
2598	Los Angeles	Torrance Courthouse	C3030 Ceiling Finishes	\$ 1,040,000	\$ 940,000	\$ 99,000
2599	Los Angeles	Inglewood Juvenile Court	C3030 Ceiling Finishes	\$ 144,000	\$ 117,000	\$ 28,000
2600	Los Angeles	Inglewood Courthouse	C3030 Ceiling Finishes	\$ 889,000	\$ 663,000	\$ 226,000
2601	Los Angeles	Burbank Courthouse	C3030 Ceiling Finishes	\$ 368,000	\$ 334,000	\$ 34,000
2602	Los Angeles	Glendale Courthouse	C3030 Ceiling Finishes	\$ 588,000	\$ 533,000	\$ 56,000
2603	Los Angeles	Alhambra Courthouse	C3030 Ceiling Finishes	\$ 474,000	\$ 408,000	\$ 66,000
2604	Los Angeles	Pasadena Courthouse	C3030 Ceiling Finishes	\$ 765,000	\$ 530,000	\$ 234,000
2605	Los Angeles	Stanley Mosk Courthouse	C3030 Ceiling Finishes	\$ 3,074,000	\$ 2,990,000	\$ 84,000
2606	Los Angeles	Clara Shortridge Foltz Criminal Justice	C3030 Ceiling Finishes	\$ 6,743,000	\$ 4,639,000	\$ 2,105,000
2607	Los Angeles	Monrovia Training Center	C3030 Ceiling Finishes	\$ 92,000	\$ 64,000	\$ 27,000
2608	Los Angeles	El Monte Courthouse	C3030 Ceiling Finishes	\$ 897,000	\$ 521,000	\$ 376,000
2609	Los Angeles	Eastlake Juvenile Court	C3030 Ceiling Finishes	\$ 363,000	\$ 199,000	\$ 164,000
2610	Los Angeles	Metropolitan Courthouse	C3030 Ceiling Finishes	\$ 1,520,000	\$ 1,437,000	\$ 83,000
2611	Los Angeles	Central Arraignment Courts	C3030 Ceiling Finishes	\$ 403,000	\$ 364,000	\$ 39,000
2612	Los Angeles	East Los Angeles Courthouse	C3030 Ceiling Finishes	\$ 347,000	\$ 270,000	\$ 77,000
2613	Los Angeles	Pomona Courthouse South	C3030 Ceiling Finishes	\$ 1,482,000	\$ 1,350,000	\$ 131,000
2614	Los Angeles	West Covina Courthouse	C3030 Ceiling Finishes	\$ 735,000	\$ 610,000	\$ 125,000
2615	Madera	Sierra Courthouse	C3030 Ceiling Finishes	\$ 46,000	\$ 31,000	\$ 15,000
2616	Merced	Old Court	C3030 Ceiling Finishes	\$ 29,000	\$ 29,000	\$ -
2617	Napa	Criminal Court Building	C3030 Ceiling Finishes	\$ 364,000	\$ 364,000	\$ -
2618	Nevada	Nevada City Courthouse	C3030 Ceiling Finishes	\$ 258,000	\$ 169,000	\$ 89,000
2619	Nevada	Nevada City Courthouse Annex	C3030 Ceiling Finishes	\$ 245,000	\$ 105,000	\$ 140,000
2620	Orange	Central Justice Center	C3030 Ceiling Finishes	\$ 2,769,000	\$ 2,524,000	\$ 244,000
2621	Orange	Civil Complex Center ("CXC")	C3030 Ceiling Finishes	\$ 343,000	\$ 343,000	\$ -
2622	Orange	Betty Lou Lamoreaux Justice Center	C3030 Ceiling Finishes	\$ 1,052,000	\$ 841,000	\$ 211,000
2623	Orange	North Justice Center	C3030 Ceiling Finishes	\$ 45,000	\$ 41,000	\$ 4,000
2624	Orange	West Justice Center	C3030 Ceiling Finishes	\$ 950,000	\$ 861,000	\$ 89,000
2625	Sacramento	Gordon Schaber Sacramento Superior	C3030 Ceiling Finishes	\$ 5,042,000	\$ 5,042,000	\$ -
2626	Sacramento	Carol Miller Justice Center Court Faci	C3030 Ceiling Finishes	\$ 677,000	\$ 662,000	\$ 15,000
2627	San Diego	Hall of Justice	C3030 Ceiling Finishes	\$ 3,056,000	\$ 1,230,000	\$ 1,826,000
2628	San Diego	Kearny Mesa Court	C3030 Ceiling Finishes	\$ 254,000	\$ 254,000	\$ -
2629	San Diego	Kearny Mesa Traffic Court KM3 Trail	C3030 Ceiling Finishes	\$ 12,000	\$ 12,000	\$ -
2630	San Diego	Kearny Mesa Traffic Court KM4 Trail	C3030 Ceiling Finishes	\$ 12,000	\$ 12,000	\$ -
2631	San Diego	Kearny Mesa Traffic Court KM5 & KM	C3030 Ceiling Finishes	\$ 12,000	\$ 12,000	\$ -
2632	San Diego	Juvenile Court	C3030 Ceiling Finishes	\$ 454,000	\$ 339,000	\$ 115,000
2633	San Diego	North County Regional Center - South	C3030 Ceiling Finishes	\$ 1,570,000	\$ 1,056,000	\$ 514,000
2634	San Diego	North County Regional Center - North	C3030 Ceiling Finishes	\$ 589,000	\$ 589,000	\$ -
2635	San Diego	Trailer - Family Support	C3030 Ceiling Finishes	\$ 13,000	\$ 13,000	\$ -
2636	San Diego	South County Regional Center	C1020 Interior Doors	\$ 145,000	\$ 52,000	\$ 93,000
2637	San Diego	South County Regional Center	C3030 Ceiling Finishes	\$ 1,157,000	\$ 415,000	\$ 742,000
2638	San Diego	East County Regional Center	C3030 Ceiling Finishes	\$ 2,012,000	\$ 1,362,000	\$ 650,000
2639	San Mateo	Hall of Justice	C3030 Ceiling Finishes	\$ 1,001,000	\$ 527,000	\$ 473,000
2640	San Mateo	Traffic/ Small Claims Annex	C3030 Ceiling Finishes	\$ 42,000	\$ 42,000	\$ -
2641	San Mateo	Central Branch	C3030 Ceiling Finishes	\$ 284,000	\$ 284,000	\$ -
2642	San Mateo	Northern Branch Courthouse	C3030 Ceiling Finishes	\$ 790,000	\$ 657,000	\$ 133,000
2643	Santa Clara	Hall of Justice (East)	C3030 Ceiling Finishes	\$ 933,000	\$ 933,000	\$ -
2644	Santa Clara	Hall of Justice (West)	C3030 Ceiling Finishes	\$ 1,155,000	\$ 1,155,000	\$ -
2645	Santa Clara	Downtown Superior Court	C3030 Ceiling Finishes	\$ 259,000	\$ 259,000	\$ -
2646	Santa Clara	Historic Courthouse	C3030 Ceiling Finishes	\$ 612,000	\$ 612,000	\$ -
2647	Santa Clara	Santa Clara Courthouse	C3030 Ceiling Finishes	\$ 69,000	\$ 69,000	\$ -
2648	Tulare	Visalia Superior Court	C3030 Ceiling Finishes	\$ 2,128,000	\$ 688,000	\$ 1,440,000
2649	Ventura	Hall of Justice	C3030 Ceiling Finishes	\$ 2,716,000	\$ 1,897,000	\$ 819,000
2650	Los Angeles	Santa Monica Courthouse	C3030 Ceiling Finishes	\$ 713,000	\$ 560,000	\$ 153,000
2651	Los Angeles	Beverly Hills Courthouse	C3030 Ceiling Finishes	\$ 450,000	\$ 358,000	\$ 92,000
2652	Santa Barbara	Santa Maria Courts, Bldg G	C3030 Ceiling Finishes	\$ 311,000	\$ 300,000	\$ 11,000
2653	Riverside	Hall of Justice	C3030 Ceiling Finishes	\$ 1,299,000	\$ 1,299,000	\$ -
2654	San Luis Obispo	Courthouse Annex	C3030 Ceiling Finishes	\$ 502,000	\$ 250,000	\$ 252,000
2655	San Bernardino	Joshua Tree Courthouse	C3030 Ceiling Finishes	\$ 226,000	\$ 76,000	\$ 149,000
2656	San Bernardino	Fontana Courthouse	C3030 Ceiling Finishes	\$ 255,000	\$ 210,000	\$ 46,000
2657	Riverside	Blythe Courthouse - Superior Court	C3030 Ceiling Finishes	\$ 94,000	\$ 94,000	\$ -

2658	Riverside	Larson Justice Center	C3030 Ceiling Finishes	\$ 1,009,000	\$ 816,000	\$ 194,000
2659	Riverside	Family Law Court	C3020 Floor Finishes	\$ 376,000	\$ 376,000	\$ -
2660	Riverside	Southwest Justice Center	C3020 Floor Finishes	\$ 1,367,000	\$ 1,023,000	\$ 344,000
2661	San Bernardino	Juvenile Dependency Courthouse	C3020 Floor Finishes	\$ 235,000	\$ 128,000	\$ 107,000
2662	San Francisco	Civic Center Courthouse	C3030 Ceiling Finishes	\$ 1,156,000	\$ 1,156,000	\$ -
2663	San Luis Obispo	Paso Robles Courthouse	C3020 Floor Finishes	\$ 140,000	\$ 140,000	\$ -
2664	Santa Barbara	Santa Barbara Jury Assembly Bldg.	C3020 Floor Finishes	\$ 63,000	\$ 63,000	\$ -
2665	San Bernardino	Barstow Courthouse	C1020 Interior Doors	\$ 27,000	\$ 21,000	\$ 6,000
2666	Alameda	Berkeley Courthouse	C1020 Interior Doors	\$ 9,000	\$ 9,000	\$ -
2667	Amador	Amador County Courthouse	C1020 Interior Doors	\$ 16,000	\$ 16,000	\$ -
2668	Contra Costa	Jail Annex	C1020 Interior Doors	\$ 10,000	\$ 1,000	\$ 10,000
2669	Fresno	B.F. Sisk Federal Courthouse	C1020 Interior Doors	\$ 163,000	\$ 163,000	\$ -
2670	Kern	Bakersfield Justice Bldg.	C1020 Interior Doors	\$ 117,000	\$ 60,000	\$ 57,000
2671	Kern	Bakersfield Juvenile Center	C1020 Interior Doors	\$ 64,000	\$ 42,000	\$ 21,000
2672	Kern	Delano/North Kern Court	C1020 Interior Doors	\$ 11,000	\$ 9,000	\$ 2,000
2673	Kern	Shafter/Wasco Courts Bldg.	C1020 Interior Doors	\$ 13,000	\$ 12,000	\$ 1,000
2674	Los Angeles	Santa Clarita Courthouse	C1020 Interior Doors	\$ 47,000	\$ 41,000	\$ 5,000
2675	Los Angeles	Alfred J. McCourtney Juvenile Justice	C1020 Interior Doors	\$ 33,000	\$ 23,000	\$ 10,000
2676	Los Angeles	Santa Monica Court Annex	C1020 Interior Doors	\$ 8,000	\$ 8,000	\$ -
2677	Los Angeles	Airport Courthouse	C1020 Interior Doors	\$ 178,000	\$ 138,000	\$ 41,000
2678	Los Angeles	Michael D. Antonovich Antelope Vall	C1020 Interior Doors	\$ 513,000	\$ 377,000	\$ 136,000
2679	Napa	Criminal Court Building	C1020 Interior Doors	\$ 15,000	\$ 15,000	\$ -
2680	Placer	Bill Santucci Justice Center	C1020 Interior Doors	\$ 88,000	\$ 88,000	\$ -
2681	Sacramento	Juvenile Courthouse	C1020 Interior Doors	\$ 80,000	\$ 80,000	\$ -
2682	San Diego	Hall of Justice	C1020 Interior Doors	\$ 417,000	\$ 168,000	\$ 249,000
2683	San Diego	North County Regional Center - Sout	C1020 Interior Doors	\$ 159,000	\$ 107,000	\$ 52,000
2684	San Diego	North County Regional Center - Anne	C1020 Interior Doors	\$ 17,000	\$ 17,000	\$ -
2685	San Mateo	Traffic/ Small Claims Annex	C1020 Interior Doors	\$ 7,000	\$ 7,000	\$ -
2686	Santa Clara	Santa Clara Courthouse	C1020 Interior Doors	\$ 35,000	\$ 35,000	\$ -
2687	Riverside	Blythe Courthouse - Superior Court	C1020 Interior Doors	\$ 9,000	\$ 9,000	\$ -
2688	Orange	Central Justice Center	B10 Superstructure	\$ 1,220,000	\$ 1,113,000	\$ 108,000
2689	Orange	West Justice Center	B10 Superstructure	\$ 355,000	\$ 322,000	\$ 33,000
2690	Riverside	Family Law Court	E2010 Fixed Furnishings	\$ 34,000	\$ 34,000	\$ -
2691	Santa Barbara	Santa Barbara Jury Assembly Bldg.	E2010 Fixed Furnishings	\$ 155,000	\$ 155,000	\$ -
2692	Alameda	George E. McDonald Hall of Justice	C1020 Interior Doors	\$ 50,000	\$ 50,000	\$ -
2693	El Dorado	Cameron Park	C1020 Interior Doors	\$ 11,000	\$ 11,000	\$ -
2694	Santa Clara	Hall of Justice (West)	C1020 Interior Doors	\$ 88,000	\$ 88,000	\$ -
2695	San Bernardino	Fontana Courthouse	C1020 Interior Doors	\$ 77,000	\$ 63,000	\$ 14,000
2696	Ventura	Hall of Justice	C1020 Interior Doors	\$ 350,000	\$ 244,000	\$ 105,000
2697	San Francisco	Hall of Justice	D5031 Public Address	\$ 264,000	\$ 61,000	\$ 203,000
2698	Riverside	Riverside Juvenile Justice Trailers	B Shell	\$ 111,000	\$ 111,000	\$ -
2699	Riverside	Riverside Juvenile Justice Trailers	B Shell	\$ 111,000	\$ 111,000	\$ -
2700	San Bernardino	San Bernardino Courthouse	D5031 Public Address	\$ 136,000	\$ 130,000	\$ 6,000
2701	Solano	Law and Justice Center	D5031 Public Address	\$ 654,000	\$ 83,000	\$ 571,000
2702	Santa Barbara	Santa Maria Courts Bldgs C + D	D5031 Public Address	\$ 139,000	\$ 139,000	\$ -
2703	San Bernardino	Barstow Courthouse	D5031 Public Address	\$ 54,000	\$ 42,000	\$ 12,000
2704	Santa Barbara	Santa Maria Courts, Bldg F	D5031 Public Address	\$ 8,000	\$ 8,000	\$ -
2705	Riverside	Corona	D5031 Public Address	\$ 79,000	\$ 43,000	\$ 36,000
2706	Solano	Hall of Justice	B10 Superstructure	\$ 19,000	\$ 14,000	\$ 5,000
2707	Solano	Hall of Justice	D5031 Public Address	\$ 115,000	\$ 84,000	\$ 31,000
2708	San Bernardino	Rancho Cucamonga Courthouse	D5031 Public Address	\$ 461,000	\$ 350,000	\$ 110,000
2709	Solano	Solano Justice Building	B10 Superstructure	\$ 42,000	\$ 32,000	\$ 10,000
2710	Solano	Solano Justice Building	D5031 Public Address	\$ 68,000	\$ 52,000	\$ 16,000
2711	San Bernardino	Victorville Courthouse-Dept. N-1	D5031 Public Address	\$ 161,000	\$ 103,000	\$ 57,000
2712	Alameda	Wiley W. Manuel Courthouse	B10 Superstructure	\$ 7,000	\$ 6,000	\$ 1,000
2713	Alameda	Wiley W. Manuel Courthouse	D5031 Public Address	\$ 224,000	\$ 188,000	\$ 36,000
2714	Alameda	Hayward Hall of Justice	D5031 Public Address	\$ 230,000	\$ 203,000	\$ 27,000
2715	Alameda	George E. McDonald Hall of Justice	D5031 Public Address	\$ 29,000	\$ 29,000	\$ -
2716	Alameda	Fremont Hall of Justice	D5031 Public Address	\$ 144,000	\$ 114,000	\$ 30,000
2717	Amador	Amador County Courthouse	D5031 Public Address	\$ 87,000	\$ 87,000	\$ -
2718	Butte	Butte County Courthouse	D5031 Public Address	\$ 396,000	\$ 396,000	\$ -
2719	Contra Costa	Wakefield Taylor Courthouse	D5031 Public Address	\$ 357,000	\$ 357,000	\$ -
2720	Contra Costa	Bray Courts	D5031 Public Address	\$ 137,000	\$ 117,000	\$ 20,000
2721	Contra Costa	Jail Annex	D5031 Public Address	\$ 45,000	\$ 3,000	\$ 43,000
2722	Contra Costa	Danville District Courthouse	D5031 Public Address	\$ 87,000	\$ 87,000	\$ -
2723	Contra Costa	George D. Carroll Courthouse	D5031 Public Address	\$ 625,000	\$ 468,000	\$ 156,000
2724	Del Norte	Del Norte County Superior Court	D5031 Public Address	\$ 128,000	\$ 78,000	\$ 49,000
2725	El Dorado	Johnson Bldg.	D5031 Public Address	\$ 43,000	\$ 43,000	\$ -
2726	Fresno	Fresno County Courthouse	D5031 Public Address	\$ 1,265,000	\$ 1,213,000	\$ 52,000
2727	Humboldt	Humboldt County Courthouse (Eureka)	D5031 Public Address	\$ 1,071,000	\$ 357,000	\$ 714,000
2728	Imperial	Imperial County Courthouse	D5031 Public Address	\$ 179,000	\$ 179,000	\$ -
2729	Kern	Bakersfield Superior Court	D5031 Public Address	\$ 729,000	\$ 457,000	\$ 272,000
2730	Kern	Bakersfield Justice Bldg.	D5031 Public Address	\$ 130,000	\$ 67,000	\$ 64,000
2731	Kern	Bakersfield Juvenile Center	D5031 Public Address	\$ 351,000	\$ 234,000	\$ 117,000
2732	Kern	Shafter/Wasco Courts Bldg.	D5031 Public Address	\$ 27,000	\$ 24,000	\$ 3,000
2733	Kern	Taft Courts Bldg.	D5031 Public Address	\$ 19,000	\$ 19,000	\$ -

2734	Kern	Arvin/ Lamont Branch	D5031 Public Address	\$ 27,000	\$ 17,000	\$ 11,000
2735	Kings	Avenal Court	D5031 Public Address	\$ 16,000	\$ 9,000	\$ 7,000
2736	Los Angeles	San Fernando Courthouse	D5031 Public Address	\$ 474,000	\$ 395,000	\$ 79,000
2737	Los Angeles	Santa Clarita Courthouse	D5031 Public Address	\$ 52,000	\$ 46,000	\$ 6,000
2738	Los Angeles	Alfred J. McCourtney Juvenile Justice	D5031 Public Address	\$ 95,000	\$ 65,000	\$ 29,000
2739	Los Angeles	Sylmar Juvenile Court	D5031 Public Address	\$ 9,000	\$ 3,000	\$ 6,000
2740	Los Angeles	Compton Courthouse	D5031 Public Address	\$ 1,421,000	\$ 940,000	\$ 481,000
2741	Los Angeles	Los Padrinos Juvenile Court	D5031 Public Address	\$ 11,000	\$ 3,000	\$ 8,000
2742	Los Angeles	Norwalk Courthouse	D5031 Public Address	\$ 478,000	\$ 406,000	\$ 71,000
2743	Los Angeles	Bellflower Courthouse	D5031 Public Address	\$ 297,000	\$ 232,000	\$ 66,000
2744	Los Angeles	Downey Courthouse	D5031 Public Address	\$ 340,000	\$ 285,000	\$ 55,000
2745	Los Angeles	Santa Monica Courthouse	B10 Superstructure	\$ 22,000	\$ 17,000	\$ 5,000
2746	Los Angeles	Santa Monica Courthouse	D5031 Public Address	\$ 174,000	\$ 137,000	\$ 37,000
2747	Los Angeles	Santa Monica Court Annex	D5031 Public Address	\$ 39,000	\$ 39,000	\$ -
2748	Los Angeles	Beverly Hills Courthouse	D5031 Public Address	\$ 65,000	\$ 52,000	\$ 13,000
2749	Los Angeles	Hall of Records	B10 Superstructure	\$ 14,000	\$ 1,000	\$ 12,000
2750	Los Angeles	Van Nuys Courthouse East	D5031 Public Address	\$ 203,000	\$ 182,000	\$ 21,000
2751	Los Angeles	Van Nuys Courthouse West	D5031 Public Address	\$ 505,000	\$ 406,000	\$ 99,000
2752	Los Angeles	Chatsworth Courthouse	D5031 Public Address	\$ 657,000	\$ 551,000	\$ 106,000
2753	Los Angeles	Michael D. Antonovich Antelope Vall	D5031 Public Address	\$ 740,000	\$ 544,000	\$ 196,000
2754	Los Angeles	Inglewood Juvenile Court	D5031 Public Address	\$ 58,000	\$ 47,000	\$ 11,000
2755	Los Angeles	Inglewood Courthouse	D5031 Public Address	\$ 534,000	\$ 398,000	\$ 136,000
2756	Los Angeles	Burbank Courthouse	D5031 Public Address	\$ 105,000	\$ 95,000	\$ 10,000
2757	Los Angeles	Glendale Courthouse	D5031 Public Address	\$ 69,000	\$ 63,000	\$ 7,000
2758	Los Angeles	Alhambra Courthouse	B10 Superstructure	\$ 22,000	\$ 19,000	\$ 3,000
2759	Los Angeles	Alhambra Courthouse	D5031 Public Address	\$ 255,000	\$ 219,000	\$ 36,000
2760	Los Angeles	Stanley Mosk Courthouse	D5031 Public Address	\$ 1,283,000	\$ 1,247,000	\$ 35,000
2761	Los Angeles	El Monte Courthouse	D5031 Public Address	\$ 299,000	\$ 174,000	\$ 125,000
2762	Los Angeles	Edmund D. Edelman Children's Court	D5031 Public Address	\$ 611,000	\$ 428,000	\$ 183,000
2763	Los Angeles	Metropolitan Courthouse	D5031 Public Address	\$ 1,283,000	\$ 1,213,000	\$ 70,000
2764	Los Angeles	Central Arraignment Courts	D5031 Public Address	\$ 128,000	\$ 116,000	\$ 13,000
2765	Los Angeles	East Los Angeles Courthouse	D5031 Public Address	\$ 213,000	\$ 166,000	\$ 47,000
2766	Los Angeles	Pomona Courthouse South	D5031 Public Address	\$ 1,160,000	\$ 1,057,000	\$ 103,000
2767	Los Angeles	West Covina Courthouse	D5031 Public Address	\$ 366,000	\$ 303,000	\$ 62,000
2768	Madera	Sierra Courthouse	D5031 Public Address	\$ 13,000	\$ 9,000	\$ 4,000
2769	Merced	Old Court	D5031 Public Address	\$ 51,000	\$ 51,000	\$ -
2770	Napa	Criminal Court Building	D5031 Public Address	\$ 63,000	\$ 63,000	\$ -
2771	Nevada	Nevada City Courthouse	D5031 Public Address	\$ 107,000	\$ 70,000	\$ 37,000
2772	Nevada	Nevada City Courthouse Annex	D5031 Public Address	\$ 172,000	\$ 73,000	\$ 98,000
2773	Orange	Civil Complex Center ("CXC")	D5031 Public Address	\$ 58,000	\$ 58,000	\$ -
2774	Orange	Betty Lou Lamoreaux Justice Center	D5031 Public Address	\$ 536,000	\$ 428,000	\$ 107,000
2775	Orange	North Justice Center	D5031 Public Address	\$ 337,000	\$ 304,000	\$ 33,000
2776	Orange	West Justice Center	D5031 Public Address	\$ 15,000	\$ 14,000	\$ 1,000
2777	Placer	Historic Courthouse	B10 Superstructure	\$ 46,000	\$ 36,000	\$ 11,000
2778	Placer	Bill Santucci Justice Center	D5031 Public Address	\$ 475,000	\$ 475,000	\$ -
2779	Sacramento	Gordon Schaber Sacramento Superior	D5031 Public Address	\$ 1,832,000	\$ 1,832,000	\$ -
2780	Sacramento	Juvenile Courthouse	D5031 Public Address	\$ 292,000	\$ 292,000	\$ -
2781	San Diego	Hall of Justice	D5031 Public Address	\$ 1,036,000	\$ 417,000	\$ 619,000
2782	San Diego	Kearny Mesa Court	D5031 Public Address	\$ 126,000	\$ 126,000	\$ -
2783	San Diego	Kearny Mesa Traffic Court KM3 Trailer	B Shell	\$ 112,000	\$ 112,000	\$ -
2784	San Diego	Kearny Mesa Traffic Court KM4 Trailer	B Shell	\$ 112,000	\$ 112,000	\$ -
2785	San Diego	Kearny Mesa Traffic Court KM5 & KM	B Shell	\$ 112,000	\$ 112,000	\$ -
2786	San Diego	Juvenile Court	D5031 Public Address	\$ 128,000	\$ 95,000	\$ 32,000
2787	San Diego	Department 10 Trailer	B Shell	\$ 112,000	\$ 112,000	\$ -
2788	San Diego	North County Regional Center - South	D5031 Public Address	\$ 565,000	\$ 380,000	\$ 185,000
2789	San Diego	North County Regional Center - Anne	D5031 Public Address	\$ 60,000	\$ 60,000	\$ -
2790	San Diego	Trailer - Dept 34	B Shell	\$ 112,000	\$ 112,000	\$ -
2791	San Diego	Trailer - Dept 35	B Shell	\$ 112,000	\$ 112,000	\$ -
2792	San Diego	Trailer - Storage A	B Shell	\$ 56,000	\$ 56,000	\$ -
2793	San Diego	Trailer - Family Support	B Shell	\$ 112,000	\$ 112,000	\$ -
2794	San Diego	South County Regional Center	D5031 Public Address	\$ 389,000	\$ 139,000	\$ 249,000
2795	San Diego	East County Regional Center	D5031 Public Address	\$ 831,000	\$ 563,000	\$ 268,000
2796	San Mateo	Hall of Justice	D5031 Public Address	\$ 851,000	\$ 449,000	\$ 403,000
2797	San Mateo	Traffic/ Small Claims Annex	D5031 Public Address	\$ 65,000	\$ 65,000	\$ -
2798	San Mateo	Central Branch	D5031 Public Address	\$ 39,000	\$ 39,000	\$ -
2799	San Mateo	Northern Branch Courthouse	D5031 Public Address	\$ 77,000	\$ 64,000	\$ 13,000
2800	Santa Clara	Hall of Justice (East)	D5031 Public Address	\$ 1,110,000	\$ 1,110,000	\$ -
2801	Santa Clara	Hall of Justice (West)	D5031 Public Address	\$ 257,000	\$ 257,000	\$ -
2802	Santa Clara	Downtown Superior Court	D5031 Public Address	\$ 464,000	\$ 464,000	\$ -
2803	Santa Clara	Historic Courthouse	D5031 Public Address	\$ 123,000	\$ 123,000	\$ -
2804	Santa Clara	Santa Clara Courthouse	D5031 Public Address	\$ 124,000	\$ 124,000	\$ -
2805	Santa Clara	Morgan Hill Courthouse	D5031 Public Address	\$ 13,000	\$ 13,000	\$ -
2806	Tulare	Visalia Superior Court	D5031 Public Address	\$ 544,000	\$ 176,000	\$ 368,000
2807	Ventura	Hall of Justice	D5031 Public Address	\$ 1,058,000	\$ 739,000	\$ 319,000
2808	Santa Barbara	Santa Maria Courts, Bldg G	D5031 Public Address	\$ 74,000	\$ 71,000	\$ 3,000
2809	Riverside	Hall of Justice	B10 Superstructure	\$ 7,000	\$ 7,000	\$ -

2810	Riverside	Hall of Justice	D5031 Public Address	\$ 374,000	\$ 374,000	\$ -
2811	San Luis Obispo	Courthouse Annex	D5031 Public Address	\$ 306,000	\$ 152,000	\$ 154,000
2812	San Bernardino	Joshua Tree Courthouse	D5031 Public Address	\$ 30,000	\$ 10,000	\$ 20,000
2813	San Bernardino	Fontana Courthouse	D5031 Public Address	\$ 45,000	\$ 37,000	\$ 8,000
2814	Riverside	Blythe Courthouse - Superior Court	D5031 Public Address	\$ 30,000	\$ 30,000	\$ -
2815	Riverside	Larson Justice Center	D5031 Public Address	\$ 342,000	\$ 276,000	\$ 66,000
2816	Santa Barbara	Santa Maria Juvenile Court (new)	D5031 Public Address	\$ 27,000	\$ 18,000	\$ 9,000
2817	San Francisco	Civic Center Courthouse	B Shell	\$ 7,000	\$ 7,000	\$ -
2818	Kings	Corcoran Court	C1020 Interior Doors	\$ 14,000	\$ 12,000	\$ 2,000
2819	Los Angeles	Van Nuys Courthouse West	C1020 Interior Doors	\$ 504,000	\$ 406,000	\$ 98,000
2820	Los Angeles	East Los Angeles Courthouse	C1020 Interior Doors	\$ 180,000	\$ 140,000	\$ 40,000
2821	San Diego	North County Regional Center - North	C1020 Interior Doors	\$ 179,000	\$ 179,000	\$ -
2822	Santa Clara	Hall of Justice (East)	C1020 Interior Doors	\$ 195,000	\$ 195,000	\$ -
2823	Ventura	East County Courthouse	C1020 Interior Doors	\$ 68,000	\$ 42,000	\$ 26,000
2824	Contra Costa	Bray Courts	C1020 Interior Doors	\$ 10,000	\$ 8,000	\$ 1,000
2825	Los Angeles	San Fernando Courthouse	C1020 Interior Doors	\$ 26,000	\$ 22,000	\$ 4,000
2826	Sacramento	Carol Miller Justice Center Court Facility	C1020 Interior Doors	\$ 54,000	\$ 52,000	\$ 1,000
2827	Riverside	Hall of Justice	C1020 Interior Doors	\$ 93,000	\$ 93,000	\$ -
2828	Riverside	Family Law Court	D5030 Communications & Security	\$ 462,000	\$ 462,000	\$ -
2829	Riverside	Southwest Justice Center	D5038 Security & Detection Systems	\$ 1,353,000	\$ 1,013,000	\$ 341,000
2830	San Bernardino	Juvenile Dependency Courthouse	D5038 Security & Detection Systems	\$ 152,000	\$ 83,000	\$ 69,000
2831	San Luis Obispo	Paso Robles Courthouse	D5038 Security & Detection Systems	\$ 128,000	\$ 128,000	\$ -
2832	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D5030 Communications & Security	\$ 11,000	\$ 11,000	\$ -
2833	Los Angeles	El Monte Courthouse	C1020 Interior Doors	\$ 161,000	\$ 94,000	\$ 67,000
2834	Orange	North Justice Center	C1020 Interior Doors	\$ 230,000	\$ 208,000	\$ 22,000
2835	Riverside	Family Law Court	C3010 Wall Finishes	\$ 162,000	\$ 162,000	\$ -
2836	Riverside	Southwest Justice Center	C3010 Wall Finishes	\$ 1,352,000	\$ 1,012,000	\$ 340,000
2837	San Bernardino	Juvenile Dependency Courthouse	C3010 Wall Finishes	\$ 82,000	\$ 45,000	\$ 37,000
2838	San Luis Obispo	Paso Robles Courthouse	C3010 Wall Finishes	\$ 76,000	\$ 76,000	\$ -
2839	Santa Barbara	Santa Barbara Jury Assembly Bldg.	C3010 Wall Finishes	\$ 20,000	\$ 20,000	\$ -
2840	Imperial	Imperial County Courthouse	A2021 Basement Wall Construction	\$ 9,000	\$ 9,000	\$ -
2841	Orange	Central Justice Center	A2021 Basement Wall Construction	\$ 41,000	\$ 37,000	\$ 4,000
2842	Placer	Historic Courthouse	A2021 Basement Wall Construction	\$ 759,000	\$ 584,000	\$ 174,000
2843	Kern	Arvin/ Lamont Branch	C1020 Interior Doors	\$ 28,000	\$ 17,000	\$ 11,000
2844	Los Angeles	Bellflower Courthouse	C1020 Interior Doors	\$ 82,000	\$ 64,000	\$ 18,000
2845	Riverside	Family Law Court	C3030 Ceiling Finishes	\$ 312,000	\$ 312,000	\$ -
2846	Santa Barbara	Santa Barbara Jury Assembly Bldg.	C3030 Ceiling Finishes	\$ 59,000	\$ 59,000	\$ -
2847	Riverside	Southwest Justice Center	C1020 Interior Doors	\$ 148,000	\$ 110,000	\$ 37,000
2848	San Bernardino	Juvenile Dependency Courthouse	C1020 Interior Doors	\$ 22,000	\$ 12,000	\$ 10,000
2849	San Luis Obispo	Paso Robles Courthouse	C1020 Interior Doors	\$ 18,000	\$ 18,000	\$ -
2850	Los Angeles	Downey Courthouse	C1020 Interior Doors	\$ 115,000	\$ 96,000	\$ 19,000
2851	Riverside	Southwest Justice Center	D5031 Public Address	\$ 518,000	\$ 387,000	\$ 130,000
2852	San Bernardino	Juvenile Dependency Courthouse	D5031 Public Address	\$ 78,000	\$ 43,000	\$ 36,000
2853	Santa Barbara	Santa Barbara Jury Assembly Bldg.	D5031 Public Address	\$ 19,000	\$ 19,000	\$ -
2854	Contra Costa	Family Law Center	C1020 Interior Doors	\$ 9,000	\$ 9,000	\$ -
2855	Los Angeles	Pasadena Courthouse	C1020 Interior Doors	\$ 255,000	\$ 177,000	\$ 78,000
2856	Los Angeles	Inglewood Courthouse	C1020 Interior Doors	\$ 434,000	\$ 323,000	\$ 110,000
Grand Total				\$ 2,122,563,000	\$ 1,658,515,000	\$ 464,010,000



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Action Item 7 – (Action Required) – Fiscal Year 2015-2016 Budget Plans

Summary:

Review and discuss finalized Fiscal Year 2015-2016 budget plans, previously presented at the May 22, 2015 meeting.

Supporting Documentation:

- Memo on budget


Action Requested:

Approve FY 2015-2016 budget.

This page intentionally left blank

Action Item 7 – FY 15-16 O&M Spending Plan Per Gov. Budget

Program Need	\$117,617
Utilities	\$50,428
Leases	\$16,240
Insurance	\$1,938
Routine Maintenance	\$49,011
Routine Maintenance Allocation	
County	\$7,572
Delegation	\$4,009
Ancillary RM Costs	\$1,539
FMU Budget	\$35,891




Action Item 7 – FY 15-16 O&M Spending Plan Per Gov. Budget

Current Appropriation	121,498,000
Current Appropriation (Reimb)	(7,000,000)
Total	114,498,000
Needed Appropriation	127,620,000
Needed Appropriation (Reimb)	(10,000,000)
Total Need	117,620,000
Difference = Budget Revision (BR)	
Additional Appropriation	6,122,000
Additional Appropriation (Reimb)	(3,000,000)
Total	3,122,000

- Need DOF approved BR of \$3.1M
- Budget Team to submit to DOF
- Timeline –
 - Post BCP process
 - Dec/Jan timeframe


FY 15-16 O&M Spending Plan Per Gov. Budget

- Change Factors
 - Capital Construction
 - Economic Adjustment
 - 3% Inflation Factors
- Scope Change
 - PM Cut Back
 - Vacant Bldgs



FY 15-16 FM Spending Plan

FY 15-16 Projected FM Budget (\$1,000s)	
Statewide Planning	\$4,000
Priority 1 FMs	\$10,000
Planned FMs	\$2,900
Less than \$50k FMs	\$8,000
Unplanned FMs over \$15k	\$40,100
Total	\$65,000



FY 15-16 FM Spending Plan

FM Budget Category		FM Budget Plan	Historical FFP Allocation	Total Remaining FM Budget
Statewide Planning		\$4,000,000	\$2,106,909	\$1,893,091
		6%		
Priority 1 FMs		\$10,000,000	\$1,072,395	\$8,927,605
		15%		
Planned FMs		\$2,880,000	\$0	\$2,880,000
		4%		
Priority 2-6 FMs	Less than \$50k FMs	\$8,000,000	\$3,016,055	\$4,983,945
		12%		
	FMs over \$50k	\$40,120,000	\$2,823,943	\$37,296,057
		62%		
FM Budget Impact		\$65,000,000	\$9,019,302	\$55,980,698
			13.88%	

Recommended Planned Projects

FM-0017040	Los Angeles	Compton Courthouse	2	Fire - Phase II - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$1,834,800	\$1,213,353	66.13%
FM-0028322	Orange	Central Justice Center	2	Fire - Phase II - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$1,827,947	\$1,666,539	91.17%

Approved but Unfunded

FM's On Hold Until FY 15-16	Number of Projects	Anticipated Funding
Mendocino	2	\$560,000
Total	2	\$560,000

Energy Conservation Projects

October	\$1,000,000
January	\$1,000,000
FY 15-16 Total	\$2,000,000

FY 14-15 FM Spending Plan Detail by Month

FY 2015-2016 Spending Plan (\$1,000s)	
Month/Item	Spending
JUL 2015	\$32,430
AUG 2015	\$3,000
OCT 2015	\$7,000
DEC 2015	\$3,000
JAN 2016	\$7,010
MAR 2016	\$4,000
APR 2016	\$3,000
MAY 2016	\$3,000
Energy Efficiency – OCT 2015	\$1,000
Energy Efficiency – JAN 2016	\$1,000
Approved Projects Pending County Funds	\$560
TOTAL	\$65,000

Statewide Planning	\$4,000
Priority 1 FMs	\$10,000
Planned FMs	\$2,900
FM Less Than \$50k	\$8,000
FM Greater Than \$50k	\$7,530
Total	\$32,430

Note: Numbers rounded to simplify math functions

Action Item 7 FY 2015-2016 Budget Plans

- Comment and Input
- Recommendation:
Approve proposed FY 2015-2016 budget plans.



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

**Trial Court Facility Modification
Planned Facility Modifications
FY 2015-2016**

	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	ESTIMATED COST	FACILITY MODIFICATION PROGRAM SHARE OF COST	FACILITY MODIFICATION PROGRAM BUDGET % OF COST
1	FM-0017040	Los Angeles	Compton Courthouse	19-AG1	2	Fire - Phase 2 - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$ 1,834,800	\$ 1,213,353	66.13%
2	FM-0028322	Orange	Central Justice Center	30-A1	2	Fire - Phase 2 - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$ 1,827,947	\$ 1,666,539	91.17%
							\$ 3,662,747	\$ 2,879,893	



JUDICIAL COUNCIL OF CALIFORNIA

2860 Gateway Oaks Drive, Suite 400 • Sacramento, California 95833-4336

Telephone 916-263-7885 • Fax 916-263-1966 • TDD 415-865-4272

MEMORANDUM

Date	Action Requested
June 30, 2015	Review of Fiscal Year 2015-2016 CFTF Budget Allocation
To	Deadline
Trial Court Facility Modification Advisory Committee	N/A
From	Contact
Angela Guzman, Financial Manager, Capital Program	Angela Guzman 916-643-8041 Michele Allan 916-263-1374
Subject	
FY 2015-2016 Court Facilities Trust Fund (CFTF) Budget Allocation	

The FY 2015-16 Court Facilities Trust Fund budget allocation is summarized below.

Budget Authority:

The CFTF budget authority for FY 2015-16 is \$121,498,000, including reimbursements of \$7,000,000. We will submit a current year request to increase our authority to address the increased costs of newly constructed and renovated courthouses scheduled to take occupancy this fiscal year and increased costs in existing court facilities. Additionally, we will submit a request to increase our reimbursement authority to support our need.

Revenue:

The CFTF receives revenue from various sources, including County Facility Payments (CFP), rental revenue, General Fund transfers, Night Court, and miscellaneous revenue.

1. County Facility Payments (CFPs)

Counties make County Facility Payments in perpetuity to the Judicial Council to provide funding for ongoing operations and maintenance of transferred court facilities. The CFP is based on historical costs counties spent for operating and maintaining the court facility. The CFP revenue projection includes CFP adjustments and CFPs initiating mid-year for newly constructed or renovated court facilities.

2. Rental/Miscellaneous Revenue

A. Rental Revenue

The CFTF receives rental revenue from various sources including parking, leases and licenses between the Judicial Council and third party occupants, food service providers, rooftop agreements for cell sites, and miscellaneous services such as ATMs.

B. Surplus Money Investment Fund (SMIF)

The CFTF earns interest on funds invested in the SMIF. The revenue projection for FY 2015-16 decreased due to continued lower interest rates and use of cash reserves, resulting in a lower fund balance upon which to earn interest.

C. Night Court Fees

Pursuant to SB 1732 and Vehicle Code Section 42006, transferred facilities holding night court collect assessments and transmit them to the CFTF. Revenue from night court fees has been declining since FY 2013-14 and we anticipate the trend to continue into FY 2015-16. Revenue projections were reduced 4% from FY 2014-15. In June 2015 Santa Clara Superior Court notified the Judicial Council it would be closing one of two traffic night court departments effective August 3, 2015, which will further impact the receipt of reduced night court fees.

D. General Fund and Miscellaneous

The CFTF receives an ongoing General Fund augmentation in the amount of \$8,053,000 as General Fund transfers in support of the new judgeships, costs for new courthouses and inflation. General Fund transfers in support of new courthouses and inflationary adjustments have remained the same since FY 2009-10.

Budget Allocation:

The CFTF budget is allocated to various categories of expense within different classifications of expenditures. Judicial Council managed expenditures are for Judicial Council responsible expenditures in transferred facilities. Judicial Council reimbursement expenditures are for costs in Judicial Council managed facilities shared with, and billed to the counties. The Judicial Council has entered into Intra-Branch agreements (IBAs) with four superior courts; Imperial, Orange, Riverside and San Luis Obispo, delegating facilities maintenance and facility modifications responsibility.

Regular maintenance allocations are based on the service provider annual contract value as of July 1, 2015, including 7% Performance Based Compensation (PBC) and miscellaneous expenditures such as permits, phones and trash removal, unless otherwise noted in the individual expenditure types below. Utility allocations are based on FY 2014-15 actual expenditures and trends, unless otherwise noted. Rent allocations reflect estimated, scheduled rent.

1. Judicial Council Managed Expenditures

A total of \$79,603,116 (including reimbursements—see below) has been allocated for Judicial Council responsible expenditures. The budget includes estimated costs for new courthouses scheduled to complete and take occupancy this fiscal year. The allocation of funds for the three service providers includes a cost increase to the contracts that will occur this fiscal year and an escalation for cost plus work. In addition, the remaining regular maintenance budget is for miscellaneous expenditures. The utilities allocation reflects a 9% increase over forecasted FY 2014-15 expenditures. If actual utilities costs come in under the projected allocation, savings will be redirected for use on other needs. Budget revisions will be submitted to increase the CFTF authority by \$6,122,000 (including \$3,000,000 reimbursements) to use available resources to address cost increases.

2. Judicial Council Managed Reimbursable Expenditures

The FY 2015-16 allocation for reimbursement expenditures is \$10,000,000. Annually, the Judicial Council provides statements of estimated shared costs to counties in Judicial Council managed shared use facilities. Counties make quarterly estimate payments based on approved estimates that are then trued up to actual expenditures. The regular maintenance allocation includes the counties' share of the service provider annual contract value, miscellaneous costs, and county shared costs for facilities where regular maintenance services have been delegated to a court. A Budget Revision (BR) will be submitted to increase the reimbursement authority by \$3,000,000 to address cost increases in regular maintenance and utilities.

3. County Managed Expenditures

A total of \$44,006,979 has been allocated for County Managed Expenditures. Annually, counties provide statements of estimated shared costs in county managed shared facilities. The Judicial Council makes quarterly estimate payments on the first day of the quarter based on approved estimate statements that are then trued up to actual expenditures. The allocations for FY 2015-16 are based on FY 2014-15 expenditures, escalated 3%.

4. Insurance

The FY 2015-16 budget of \$1,000,000 remains unchanged from last fiscal year and is projected to be sufficient to support current costs. The Facility Insurance allocation will be revisited later in the fiscal year to determine whether there will be any savings that can be redirected for use on other needs.

5. Court Delegation

The FY 2015-16 facilities maintenance budget of \$4,009,491 results from the delegated contract value of \$4,422,899, based on a cost per square foot allocation of \$2.20 for Judicial Council managed facilities, and \$0.55 in county managed buildings, plus annual funding of \$52,000 to Riverside Superior Court in support of planning, less a \$465,408 redirection for county shared costs and court-funded costs. Courts bear the financial burden of costs exceeding allocated IBA funding.

Table 1 below provides a summary of the Projected Sources and Uses of funds in support of the FY 2015-16 CFTF projected budget.

**Table 1
Court Facilities Trust Fund
FY 2015-16 Projected Sources and Uses of Funds**

Excess Cash Carryover from prior year	4,715,000
--	------------------

Revenue Sources	Estimated Revenue	% of Total
County Facilities Payment	96,093,171	84.40%
Rental Revenue	7,487,184	6.60%
General Fund Transfer	8,053,000	7.10%
Night Court Fees	2,213,000	1.90%
Surplus Money Investment Fund	45,000	0.00%
Miscellaneous Revenue	10,000	0.00%
Total Revenue	113,901,355	100.00%
Total Resources Available	118,616,355	

Expenditures Categories	Estimated Expenditures	% of Total
Judicial Council Managed Exp		
Regular Maintenance	44,140,274	34.70%
Utilities	20,605,482	16.10%
Rent	13,857,360	10.80%
Insurance	1,000,000	0.80%
Total	79,603,116	62.40%
Court Delegated Exp		
Regular Maintenance	4,009,491	3.10%
Total	4,009,491	3.10%
County Managed Exp		
Regular Maintenance	7,572,253	5.90%
Utilities	33,112,830	25.90%
Rent	2,383,076	1.90%
Insurance	938,820	0.70%
Total	44,006,979	34.40%
Total Expenditures	127,619,586	100.00%
<i>Less Reimbursements</i>	<i>-10,000,000</i>	
Total Expenditures Less Reimb	117,619,586	

Resources Less Expenditures	996,769
------------------------------------	----------------

Summary:

The FY 2015-16 Budget Act provides \$121,498,000 appropriation authority for support of CFTF payables, which includes \$114,498,000 judicial branch facility program expenditures and \$7,000,000 reimbursement authority. The CFTF fund balance has sufficient reserves to support a current year augmentation to increase the current expenditure authority. This

augmentation will assist in meeting the increased costs of newly constructed and renovated courthouses scheduled to take occupancy this fiscal year as well as increased operational costs in existing court facilities. The current year augmentation request of \$3,122,000 will bring our expenditure authority to \$117,620,000, excluding reimbursements, and support the FY 2015-16 CFTF expenditure plan. Additionally, a current year augmentation to increase reimbursement authority to \$10,000,000 will meet our needs of increased reimbursement expenditures.

Until the augmentation request is approved \$6,122,000 (\$3,000,000 reimbursements) of the Judicial Council managed budget will be withheld. Upon approval of the augmentation the budget will be adjusted to reflect the additional resource and authority.

Should a determination be made that there is a need to increase the service provider annual contract value; the augmentation request will be increased up to \$4,715,000. The ability to increase our planned augmentation up to \$4,715,000 is based on projected FY 2015-16 resources less projected FY 2015-16 expenditures. The Judicial Council will continue to monitor expenditures and revenues through the close of FY 2014-15 financial reports and in FY 2015-16 to determine if changes are required to the FY 2015-16 spending plan.

Table 2 below provides the reconciliation of the FY 2015-16 CFTF appropriation authority in support of the expenditures detailed in Table 1.

Table 2
Court Facilities Trust Fund
FY 2015-16 Appropriation Reconciliation

Current Appropriation	
	121,498,000
Current Appropriation (Reimb)	
	(7,000,000)
Total	
	114,498,000
Needed Appropriation	
	127,620,000
Needed Appropriation (Reimb)	
	(10,000,000)
Total Need	
	117,620,000
Difference = Budget Revision	
Additional Appropriation	
	6,122,000
Additional Appropriation (Reimb)	
	(3,000,000)
Total	
	3,122,000



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

**Action Item 8 – (Action Required) – Quarterly Activity Report,
Quarter 4 of Fiscal Year 2014-2015**

Summary:

Review and discuss draft report *Trial Court Facility Modification Quarterly Activity Report, Quarter 4 of Fiscal Year 2014-2015*.

Supporting Documentation:

- *Trial Court Facility Modification Quarterly Activity Report, Quarter 4 of Fiscal Year 2014-2015*

Action Requested:

Provide input and additions to draft document and approve release to E&P upon revision.

This page intentionally left blank



Judicial Council of California

455 Golden Gate Avenue · San Francisco, California 94102-3688

www.courts.ca.gov

REPORT TO THE JUDICIAL COUNCIL

For business meeting on: August 20–21, 2015

Title	Agenda Item Type
Court Facilities: Trial Court Facility Modification Quarterly Activity Report for Quarter 4 of Fiscal Year 2014–2015	Information Only
Submitted by	Date of Report
Trial Court Facility Modification Advisory Committee	July 1, 2015
Hon. David Edwin Power, Chair	Contact
	Patrick McGrath, 916-643-8051 patrick.mcgrath@jud.ca.gov

Executive Summary

The Trial Court Facility Modification Advisory Committee has completed its facility modification funding for the fourth quarter of fiscal year 2014–2015. In compliance with the *Trial Court Facility Modifications Policy*, the advisory body is submitting its *Trial Court Facility Modification Quarterly Activity Report: Quarter 4, Fiscal Year 2014–2015* as information for the council. This report summarizes the activities of the TCFMAC from April 1, 2015 to June 30, 2015.

Previous Council Action

The Trial Court Facility Modification Working Group was established by Judicial Council policy in 2005. The working group first met in April 2006 and operated under the *Trial Court Facility Modifications Policy*,¹ adopted by the Judicial Council in 2005 and revised on December 12, 2014. The working group's primary oversight responsibilities included reviewing statewide facility modification requests and approving facility modification funding.

¹ As adopted in 2005, the policy was known as the *Prioritization Methodology for Modifications to Court Facilities*. When it was revised in 2012, the name also changed. See www.courts.ca.gov/documents/jc-20120727-itemG.pdf.

The working group's charge was formalized by the Judicial Council on December 14, 2012, and the working group was assigned additional oversight responsibility for the operations and maintenance of existing facilities, noncapital-related real estate transactions, energy management, and environmental management and sustainability. On April 25, 2013, the working group's status was elevated to that of advisory committee.

An updated Court-Funded Facilities Request (CFR) approval process was submitted and approved by the Judicial Council on August 23, 2013, requiring all CFRs to be reviewed and approved by the TCFMAC. These submittals may include lease-related costs (e.g., lease payments and operating costs, repairs, or modifications required by a lease); allowable court operations expenditures under rule 10.810 of the California Rules of Court (e.g., equipment, furnishings, interior painting, flooring replacement or repair, furniture repair, or records storage); and other facility improvements that are not allowable court operations expenditures under rule 10.810 (e.g., facilities operations, maintenance, repairs, and modifications, but not capital projects), if they would improve a court's functioning or reduce ongoing court operating costs.

Reports previously approved by the Judicial Council are available at www.courts.ca.gov/2567.htm under Research and Reports: Conditions in Our Courts.

Methodology and Process

Funding decisions were based on the prioritization and ranking methodologies in accordance with the *Trial Court Facility Modifications Policy*. Facility modifications are assigned one of six priority categories: Priority 1—Immediate or Potentially Critical; Priority 2—Necessary, But Not Yet Critical; Priority 3—Needed; Priority 4—Does Not Meet Current Codes or Standards; Priority 5—Beyond Rated Life, But Serviceable; and Priority 6—Hazardous Materials, Managed But Not Abated. These categories are based on methods commonly used by private-sector facility management firms. Facility modifications that are determined to be Priority 1 are to be addressed immediately and regardless of whether the court occupies a shared-use facility. With current budget constraints, the TCFMAC predominantly approves facility modification projects at the Priority 1 and Priority 2 levels. Delaying TCFMAC approval of these projects would cause continued court closures, operational failures, and undue risk to continued court operations.

Policy and Cost Implications

During the fourth quarter of fiscal year 2014–2015, the TCFMAC reviewed and approved a total of 254 facility modifications for a total projected cost of \$7,794,202. The Facility Modification Program's share of these projects totals \$6,761,502. These approved projects are limited to Priority 1 emergency projects and Priority 2 critical needs projects. One Priority 3 – Needed project was approved based on its significant energy conservation value. Among other urgently needed projects, the committee approved two building alarm system renovations for design phase work – one at Compton Courthouse in Los Angeles County and one at Central Justice Center in Orange County – in order to comply with State Fire Marshal notifications. These projects will ensure fire and life safety at two large and heavily used courthouses in the state. The

committee also ratifies emergency projects, for instance, the replacement of flush valves at the San Mateo Hall of Justice in order to prevent regular flooding requiring the replacement of ceiling tiles, sheet rock and carpet. Please see Attachment A for a detailed list of all approved projects during the fourth quarter of fiscal year 2014–2015.

During this quarter, six projects required additional funds in excess of \$50,000 from their original estimates. The Facility Modification Program’s share of these cost increases totals \$575,330. Projects that require excess costs of this magnitude are typically projects where either project managers encountered unforeseen site conditions or there existed excessive deferred maintenance.

The committee reviewed and approved one project during the fourth quarter of fiscal year 2014–2015, designed to improve the lighting energy efficiency at Gordon Schaber Courthouse in Sacramento, with a total potential cost of \$180,000, which due to a combination of rebates and energy savings has a return on investment of 13 months.

During this quarter, two Court-Funded Facilities Requests (CFRs) were reviewed and approved by the TCFMAC, from Tulare and Los Angeles Superior Courts. These CFR projects will use funding from fiscal year 2015-2016 and as such were not subject to the earlier CFR cut-off for work funded with this year moneys. As stated above, CFR submittals may include lease-related costs, allowable court operations expenditures under rule 10.810 of the California Rules of Court, and other facility improvement costs that are not allowable under rule 10.810. See Attachment B for a detailed list of CFRs approved by the TCFMAC during the fourth quarter of fiscal year 2014–2015.

Implementation Efforts

The TCFMAC conducted two in-person meetings – one in Sacramento on April 13, 2015 and one in Los Angeles at the Van Nuys Courthouse East on May 22, 2015 – to review facility modification funding requests and to discuss the topics below. The committee thanks the Los Angeles Superior Court, and especially Presiding Judge Carolyn B. Kuhl and Court Executive Officer Sherri R. Carter for the opportunity to visit the three largest courthouses in the state as well as for the use of facilities for the meeting.

- The committee conducted its regular review of facility modification projects lists: A (Emergency and Priority 1), B (FMs Under \$50K), C (Cost Increases Over \$50K), D (FMs Over \$50K Eligible for Funding), E (Funded FMs On Hold), and F (Court-Funded Facilities Requests);
- The committee toured the public and non-public areas of the Stanley Mosk Courthouse, Clara Shortridge Foltz Criminal Justice Center, and Van Nuys Courthouse East and West in Los Angeles;
- The committee received a status report on the Trial Court Facility Maintenance Pilot Program for Window Washing that ended this year;

- The committee reviewed elevator entrapment trends at two large courthouses that underwent elevator renovation projects – Compton Courthouse in Los Angeles and Gordon Schaber Courthouse in Sacramento. Both have shown significant entrapment reductions since the projects were completed;
- The committee provided support and approval for the Water Conservation Policy scheduled to be submitted to the Judicial Council for adoption;
- The committee reviewed anticipated budget allocations for operations and maintenance and facility modification funding for fiscal year 2015–2016.

Completed Courthouse Project Spotlights

Emergency Project – Flood Water Remediation (interior and exterior) at Santa Maria Courts Campus (Building G) – FM-0052984

A faulty water membrane on the north exterior wall of the facility resulted in a major leak into the building, causing significant damage in the men’s and women’s public restroom, the secured stairwell, and the surrounding exterior of the building. Microbial spores also necessitated abatement and environmental testing. Judicial Council Facilities Management staff immediately began remediation efforts, keeping the Court apprised of work progression and timelines. Work crews worked diligently to make all affected areas functional once again. Final project cost was \$214,576.



Above: the faulty membrane on the exterior of the building as it looked at time of failure (with dirt excavated).

Near Right: Repair effort on the membrane.

Far Right: The restored men’s restroom.



Priority 2 Project – Fire Pump Replacement at Wiley Manuel Courthouse, Oakland, CA – FM-0050281

During a Preventive Maintenance round, it was discovered that both fire pumps in the facility were leaking water from bad seals. Additionally, testing would require draining the entire system, causing a loss of several thousand gallons of water per test. The project manager determined that a complete replacement and installation of a closed loop metering system to save water during testing would be best. The committee approved a total estimate of \$220,000 and final costs came in under budget at \$186,086. The project satisfied the requirements of all parties involved.



Above (left): One of the old fire pumps. Notice the evidence of leaking seals just above the date stamp on the main pump shaft.
Above (right): A new fire pump, installed.

Next Steps

The *Trial Court Facility Modification Quarterly Activity Report: Quarter 1, Fiscal Year 2015–2016* will be submitted to the Judicial Council in December 2015.

Attachments

1. Attachment A: *TCFMAC Funded Project List: Quarter 4, Fiscal Year 2014–2015*
2. Attachment B: *Court-Funded Facilities Requests (CFR): Quarter 4, Fiscal Year 2014–2015*

This page intentionally left blank



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
1	FM-0017040	Los Angeles	Compton	19-AG1	2	Fire - Phase 1 - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$ 818,000	\$ 540,943	66.13
2	FM-0028322	Orange	Central Justice Center	30-A1	2	Fire - Phase 1 - Building alarm system is not code compliant and must be renovated to comply with State Fire Marshal notice to comply.	\$ 913,973	\$ 833,269	91.17
3	FM-0041559	Merced	Old Court	24-A1	2	Interior Finishes - Replace failed courtroom seats (168) and carpet as required to facilitate new seating installation. Chairs are 60 years old and replacement parts are not available. Chair failure rate is increasing and creating safety risks to the public.	\$ 105,000	\$ 105,000	100
4	FM-0047553	Los Angeles	San Fernando Courthouse	19-AC1	2	Exterior Shell - Fencing and Gates - Furnish and install new 4-foot high steel tube fence with spikes on top, attached to existing retaining wall at 2nd floor patio area to prevent access from outside and install alarmed Panic Bars at the egress gates from the patio. New fence to match existing as close as possible. Provide and install required supports and welds to fasten steel tube fence to existing retaining wall. Provide boom lift to lift and install new steel tube fence. Furnish and install new privacy screen welded to new steel tube fence. Prime and paint steel tube fence and privacy screen. Security issue in response to an incident and report.	\$ 30,944	\$ 30,944	100
5	FM-0051196	Los Angeles	Alhambra Courthouse	19-11	2	HVAC - Install new refrigerant monitoring system and modify the exhaust and supply air for chiller room, required as part of the monitoring system. There is currently no refrigerant monitoring in this room which is required by code.	\$ 28,027	\$ 24,104	86
6	FM-0051815	Merced	Old Court	24-A1	2	Roof - Renovate 1,400 sq. ft of exterior corridor roof, fascia and 200 square feet of exterior window ledge. Concrete is spalling and leaking. Work to include application of elastomeric roof coating, installation of additional pressure treated plywood and single membrane insulation, PVC patch and painting as required. Concrete spalling could fall onto passers-by below.	\$ 104,100	\$ 104,100	100
7	FM-0053006	Los Angeles	Bellflower Courthouse	19-AL1	2	Roof - Remove and replace existing roof with new PVC roof system - Due to roof currently being in poor condition, recommended removal and replacement of existing roof will bring entire system to good condition.	\$ 667,498	\$ 520,248	77.94



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
8	FM-0054053	Santa Barbara	Santa Barbara Jury Assembly Bldg.	42-G1	2	Interior Finishes - Construct three (3) Attorney/Client Meeting Rooms - Required to Facilitate move of juvenile proceedings to this location.	\$ 75,654	\$ 75,654	100
9	FM-0054490	Los Angeles	Alhambra Courthouse	19-I1	2	Fire Protection - Replace 4" Pre-Action Fire Valve assembly (UL listed). Connect to 120 volt power supply for Fire valve assembly and connect Pre-Action valve to fire panel. Correct deficiency from State Fire Marshal Report; Replace pre-action system with one that is UL listed and approved to fire department safety standards.	\$ 86,170	\$ 74,106	86
10	FM-0054578	Los Angeles	Norwalk Courthouse	19-AK1	1	Elevators, Escalators, & Hoists - Judge's Elevator #6 replaced Sheave and Bearing Assembly. Due to wear and tear and an elevator state inspector issued preliminary order to repair the sheave assembly, the sheave assembly on the judge's elevator #6 car top needs to be replaced.	\$ 40,774	\$ 34,670	85.03
11	FM-0054579	Los Angeles	Torrance Courthouse	19-C1	2	Interior Finishes - Sand & polish marble walls in elevator lobby's on floors 2, 3, 4 & 5. There is currently graffiti on multiple marble walls in elevator lobby's on multiple floors which could cause safety concerns for the public.	\$ 8,686	\$ 7,395	85.14
12	FM-0054581	Los Angeles	Alhambra Courthouse	19-I1	2	Vandalism - Sand and paint restroom walls & partitions to match existing and replace vandalized faucets. Multiple walls and partitions as well as faucets in the Women's public restrooms have been vandalized. Second and fourth floor women's public restrooms.	\$ 4,962	\$ 4,267	86
13	FM-0054583	Los Angeles	Norwalk Courthouse	19-AK1	2	Vandalism - Scrape and paint partition walls, doors and door frames inside public restrooms on multiple floors and replace broken locks on stalls. There is currently graffiti engraved into multiple door frames, doors and partition walls in public restrooms as well as multiple broken locks on the restroom stalls.	\$ 4,381	\$ 3,725	85.03
14	FM-0054584	Los Angeles	Compton Courthouse	19-AG1	2	Plumbing - Replace existing Cla-val DC 8" backflow with new Wilkins 350 DA 8" backflow assembly. Current backflow device has failed testing & is beyond repair, replacement is code required.	\$ 13,592	\$ 8,988	66.13



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
15	FM-0054585	Los Angeles	Pasadena Courthouse	19-J1	1	HVAC - Failed and Failing Valves - Remove and replace two (2) butterfly isolation valves on the AHUs hot water pipe, valve is bypassing hot water in the closed position. Remove and replace three (3) 3-way heating control valves and six (6) on bypass piping to restore heating. AHU #5 is not supplying heating to the 5th floor. Existing heating control valves of AHU #5 are non-operational, internal parts of heating control valve are seized. Body of heating control valve is leaking hot water due to deterioration.	\$ 15,076	\$ 10,455	69.35
16	FM-0054586	Los Angeles	Santa Clarita Courthouse	19-AD1	2	Interior Finishes - Replace existing door closer with new Doromatic 2520 RH Closer & adjust exit hard to work with new closer. Entrance door into Dept. 1 is not currently working properly, a new door closer must be installed to prevent security issues.	\$ 2,941	\$ 2,941	100
17	FM-0054587	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	HVAC - Replace return shaft and related components, pulleys, belts, bearings, and motor on air handler unit. The return shaft on air handler unit 4-1 is broken, shaft and multiple related components need to be replaced to make the unit operational.	\$ 46,910	\$ 32,269	68.79
18	FM-0054588	Contra Costa	Arnason Justice Center	07-E3	2	Electrical - Replace a total of 30 light bulbs with LED light bulbs; 14 have failed; lights are 25 feet off the floor and require a lift; requires off hour installation - LEDs will last longer, save energy and maintenance costs.	\$ 4,555	\$ 4,555	100
19	FM-0054589	Los Angeles	Beverly Hills Courthouse	19-AQ1	1	Electrical - Replace defective door operator and safety edge. Material Used (115 V Power master door operator with 3/4, HP motor, Drive chain, Manual Hand Chain, Safety Edge 13 10, Take up reel 16, Receiver and, Bypass pulley). Restore normal operations to Judge's roll-up gate. Judge's roll-up gate is not operating and currently in the closed position, clutch is jammed.	\$ 5,560	\$ 4,421	79.52
20	FM-0054590	Butte	Butte County Courthouse	04-A1	1	Roof - Roof Leaks - Cut back damaged roof areas and patch in the roof where the leaks are causing water intrusion in courtroom 3, Judges Chambers, main public corridor, and public transaction area.	\$ 4,072	\$ 4,072	100
21	FM-0054591	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	HVAC - Water remediation, set up containment, dry leak affected areas, replace failed pressure release piping. Water is leaking into the sheriff's locker room, coming from steamer pressure release piping.	\$ 9,550	\$ 6,569	68.79



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
22	FM-0054592	Los Angeles	Santa Monica Courthouse	19-AP1	2	Vandalism - Apply wood filler, then sand and stain wooden dividers & doors as well as replace glass and add anti-graffiti film to phone booth windows. There is currently heavy vandalism carved into the wood and glass of phone booths in public hallways on multiple floors.	\$ 13,668	\$ 10,728	78.49
23	FM-0054593	Los Angeles	Beverly Hills Courthouse	19-AQ1	2	Interior Finishes - Remove existing graffiti damaged window film, install solar window film on approx. (128) windows. There is currently graffiti on existing window film and it is also faded and cracking.	\$ 9,932	\$ 7,898	79.52
24	FM-0054595	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	1	Electrical - Replace defective 2500 AMP breaker. The 2500 AMP breaker that feeds the mechanical equipment in the building has tripped causing all HVAC equipment to be inoperable. Installed a temporary 2500 AMP breaker for 5 days until the 2500A AMP breaker arrived for install.	\$ 45,000	\$ 31,496	69.99
25	FM-0054596	Los Angeles	Whittier Courthouse	19-AO1	1	Plumbing - Set up ACM containment, create 16 SF opening in the wall, and replace copper pipe. There is currently a leak coming from a 1-1/4" domestic copper water supply line located in the pipe chase between the basement and first floor. Work also included the removal and replacement of 25 SF of wall tile.	\$ 13,637	\$ 13,637	100
26	FM-0054597	Los Angeles	Pomona Courthouse South	19-W1	1	Electrical - Restore operation to the magnetic starter. The magnetic starter coil that serves the supply fan motor VFD of AHU #4 is not energizing causing the supply fan to be inoperable.	\$ 4,963	\$ 4,523	91.14
27	FM-0054598	Los Angeles	Van Nuys Courthouse East	19-AX1	2	Vandalism - Resurface and refinish wood benches, replace (2) wood doors near jury area, and replace (2) porcelain sinks in public restroom. Currently there are multiple wood benches, wood doors, and porcelain sinks throughout the public areas of the courthouse that have been vandalized.	\$ 9,296	\$ 8,342	89.74
28	FM-0054599	Los Angeles	Van Nuys Courthouse East	19-AX1	2	Vandalism - Grounds and Parking - Remove and replace (9) exterior recessed wall light fixtures, (5) bollard light posts, and multiple missing covers for hose bibs. Currently there are multiple light posts, light fixtures, hose bibs, walls, and walkways around the exterior of the facility that have been vandalized and could become a safety issue for the public.	\$ 6,530	\$ 5,860	89.74
29	FM-0054603	San Diego	East County Regional Center	37-11	2	Interior Finishes - Leak Remediation - Replace damaged drywall and tile behind toilets, replace bottom plates and tie new partial studs into existing studs. The metal framing has been compromised due to a minor undetectable leak over several years. The leak has settled in a metal framing track and has dripped down through an enclosed plumbing shaft.	\$ 3,652	\$ 2,473	67.71



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
30	FM-0054604	Los Angeles	Parking Structure Lot 48 Van Nuys Court Complex	19-AX6	2	Electrical - Failed UPS System - Remove and replace the failed UPS System that supports the way finding and egress lighting in the parking garage. System is non-operational and is required as emergency power for egress lighting.	\$ 13,149	\$ 11,800	89.74
31	FM-0054606	San Diego	Kearny Mesa - Traffic Court KM3 Trailer	37-C2	2	HVAC - Replace Bard wall mount package unit, thermostat, electrical connections and condensate piping. Existing Bard A/C unit needs to be replaced, evaporator has deteriorated and is not working.	\$ 12,791	\$ 12,791	100
32	FM-0054608	Madera	Sierra Courthouse	20-D1	2	Exterior Shell - Spot treat infected wood and beams at the main entrance of the building for wood boring beetles and fabricate 6 copper sleeves to prevent further damage from happening - Currently the beams have been temporarily sealed and painted, with the beams being exposed to the weather year around these types of repairs will have to be done every year.	\$ 10,239	\$ 6,963	68
33	FM-0054612	Los Angeles	Torrance Courthouse	19-C1	1	Exterior Shell - Replace defective locking clips and straighten link rods. Sheriff's roll up gate was stuck in the open position.	\$ 10,467	\$ 8,912	85.14
34	FM-0054613	Los Angeles	Whittier Courthouse	19-AO1	1	Roof - Set up ACM containment, dry leak affected areas, and replace damaged roof materials. There is currently rain water leaking into the 1st floor public defenders office coming from a damaged area of the roof.	\$ 13,869	\$ 13,869	100
35	FM-0054614	Los Angeles	Pomona Courthouse South	19-W1	1	Roof - Water remediation, set up ACM containment and drying equipment to expedite the drying process. Water leaked through a section of deteriorated roof under the cooling towers. Water leaked through the ceiling tiles in the 7th floor secured hallway. No offices are affected only the 7th floor secured hallway.	\$ 12,811	\$ 12,811	100
36	FM-0054616	San Diego	Juvenile Court	37-E1	2	Fire Protection - Replace failed/obsolete server room 159 and 160 halon suppression system. The project will include new FM-200 Clean Agent system, demolition of existing piping and electrical components, connection and programming to the existing Notifier 640 fire panel, control relays, modules, fittings, PAM relay, and final testing and certification. Work will be performed after hours.	\$ 41,785	\$ 31,180	74.62



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
37	FM-0054618	Humboldt	Humboldt County Courthouse (Eureka)	12-A1	2	Electrical - Add E- power outlet in closet - install 1 - e power outlet in Telecom closet, during last earthquake power was lost to essential building equipment.	\$ 2,087	\$ 2,087	100
38	FM-0054619	Mendocino	County Courthouse	23-A1	2	Interior Finishes - Fabricate and install aluminum handrail transition pieces due to numerous trip and falls on the existing steps. One each at 68" aluminum handrail and components and one each at 15' aluminum intermediate handrail and components.	\$ 8,428	\$ 5,699	67.62
39	FM-0054620	Contra Costa	Family Law Center	07-A14	2	HVAC - IT Room's Split System is Down - Remove and replace one failed compressor and one filter dryer - Excessive heat in the IT Room will damage computer equipment causing disruption to Court activities.	\$ 3,329	\$ 3,329	100
40	FM-0054621	Los Angeles	Chatsworth Courthouse	19-AY1	2	Vandalism - Sand, scrape, prep, and paint walls & partitions; install approx. 100 sq. ft. of anti graffiti film on mirrors. There is currently graffiti on multiple walls and partitions inside the public restrooms which could cause a safety issue for the public; mirrors currently do not have anti graffiti film leaving them exposed to vandalism.	\$ 4,215	\$ 3,532	83.8
41	FM-0054624	Los Angeles	Metropolitan Courthouse	19-T1	2	HVAC - Replace existing circuit setters with new spool pieces and install (2) new Hoffmann air bleeds on suction. Current circuit setters are starving the hot water pumps, restricting water flow, which could cause the pumps to fail.	\$ 3,506	\$ 3,315	94.54
42	FM-0054625	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	2	Vandalism - Install (13) new anti-graffiti mirrors, (1) new partition door, (10) new partition stall door locks, and sand & paint multiple partitions and walls in public restrooms. There is currently graffiti on mirrors, walls, and stalls as well as vandalized fixtures in multiple public restrooms which is a safety hazard for the public.	\$ 8,143	\$ 5,699	69.99
43	FM-0054626	Santa Clara	Hall of Justice (East)	43-A1	2	Interior Door Hardware- Replace (1) failed Crash bar on the main entrance courtroom/Dept 34 - Adjust and check the operation.	\$ 2,561	\$ 2,561	100
44	FM-0054627	Sonoma	3055 Cleveland Avenue	49-B2	2	HVAC - Replace failed hot gas assembly.	\$ 4,678	\$ 4,678	100
45	FM-0054629	San Joaquin	Manteca Branch Court	39-C1	2	Plumbing - Dig up area to access valve remove failed valve with new ball valve - Old valve is leaking.	\$ 2,589	\$ 2,589	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
46	FM-0054630	San Diego	County Courthouse	37-A1	1	Elevators, Escalators, & Hoists - Replaced Run Timer Board and Predictor Board. Elevator #7 was not functioning and was caught between Lobby and second floor.	\$ 3,281	\$ 3,281	100
47	FM-0054634	Los Angeles	Torrance Courthouse	19-C1	2	Exterior Shell - Install waterproofing membrane & protection board, caulk & seal cracks, and apply urethane coating to waterproof front planter area. The front planter area is currently allowing water to penetrate into the basement hallway next to the lock up which caused a P1 water intrusion addressed by SWO 1369635 and could cause further damage.	\$ 4,263	\$ 3,630	85.14
48	FM-0054635	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Electrical - Install new conduit and controls for generator cooling system and replace (1) 225 AMP transfer control module. The cooling tower is not responding due to failed wiring.	\$ 13,825	\$ 9,510	68.79
49	FM-0054636	Los Angeles	Torrance Courthouse	19-C1	1	Elevators, Escalators, & Hoists - Replace starter coil relay. Judge's elevator #5 has a bad starter coil relay, causing elevator to not operate correctly.	\$ 8,227	\$ 7,004	85.14
50	FM-0054637	San Diego	North County Regional Center - Vista Center	37-F2	2	HVAC - Replace failed, leaking chilled water coils on AHU-4,12. Work will include, but not limited to ACM testing and abatement if required, new valves, pressure gauges, crane to remove old and place new custom coil units on roof top with after hours execution.	\$ 57,302	\$ 38,530	67.24
51	FM-0054640	Los Angeles	Metropolitan Courthouse	19-T1	2	Fire Protection - Replace Fire doors, add panic hardware, magnetic hold open, and smoke detectors with relay modules and tie into the fire alarm system to close upon activation. Fire Marshall corrections for the Fire Rated doors located on Level A, B, and C.	\$ 76,882	\$ 72,684	94.54
52	FM-0054641	Riverside	Larson Justice Center	33-C1	2	HVAC - Cooling Tower - Remove and replace the sand filtration system and the associated piping of the BAC cooling tower with a new centrifugal separator. Current system has failed and is not efficient and is costly to maintain. Each time the system is back flushed it removes the water treatment chemicals. The replacement system will save in maintenance costs, reduce health risks, maximize equipment life and minimize downtime through elimination of back flushing.	\$ 95,486	\$ 77,162	80.81
53	FM-0054646	Lassen	New Susanville Courthouse	18-C1	1	HVAC- Replace failed/faulty Leibert unit on rooftop. Isolate and remove the existing condensing unit (OM00037053) & install a new like for like model condensing unit. Unit is not in operation at this time. This unit serves to cool the court IT room.	\$ 21,257	\$ 21,257	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
54	FM-0054648	Alameda	Wiley W. Manuel Courthouse	01-B3	2	Plumbing - Replace failing institutional grade plumbing hardware in Holding cell D-106-2 - Work to be performed after hours.	\$ 4,216	\$ 4,216	100
55	FM-0054649	San Mateo	Hall of Justice	41-A1	1	Plumbing - Flush Valves - Replace 30 failed angle stops and Flush Body Valves. In the evenings the toilets continually run and overflow onto the floor flooding the court and file room damaging files, and the court space. This is to avoid another costly flood that led to remediation and replacement of ceiling tiles, sheet rock, and carpet.	\$ 38,737	\$ 38,737	100
56	FM-0054650	San Diego	Juvenile Court	37-E1	2	Electrical - Install a new electrical circuit to re-feed (6) bollard light fixtures and install a photocell on the electrical panel to operate the bollard light fixtures. Install new ballasts and lamps in these (6) bollard light fixtures. Install new underground conduit and wiring to restore power to (2) bollard light fixtures. In (1) additional bollard light fixture, replace ballast and lamp. 75% of the northwest public bollard sidewalk lights are not illuminated. This is a safety issue.	\$ 5,195	\$ 3,877	74.62
57	FM-0054651	Santa Clara	Downtown Superior Court	43-B1	1	Interior finishes - Toilet seals have failed causing extensive water damage to surrounding plaster walls - Disconnect and remove 6ea wall hung toilets and flush valves - Set up all required containment for ACM removal - Remove approx 150 sqft ACM - This includes 9 X 9 floor tiles and under laying mastic - Remove and dispose of 300 sqft of wall plaster material - Remove containment and properly dispose of. Re-install 300 SqFt of button board, lathe and plaster where removed - match existing.	\$ 63,372	\$ 63,372	100
58	FM-0054652	Santa Clara	Downtown Superior Court	43-B1	2	Plumbing - Replace 2(qty.) failed boiler #3 isolation valves - Replace 1(qty.) failed emergency pressure relief valve - Replace 1(qty.) failed bearing assembly - Restore water pressure and fill boiler system - Verify proper operation of boiler Shut down and isolate boiler system - Drain water.	\$ 4,608	\$ 4,608	100
59	FM-0054653	Lake	South Civic Center	17-B1	2	Vandalism - Remove Graffiti - Remove graffiti on exterior wallet front entrance, parking lot and utility box. Approx 250 sqft.	\$ 3,989	\$ 3,989	100
60	FM-0054654	Santa Clara	Old Courthouse	43-B2	2	Leak Damage - Replace plaster ceiling in Dept 22 conference room (10X 20 area) Ceiling has a 2' x 2' hole with plaster hanging down, and several long cracks throughout. The complete ceiling will be cleaned, patched and painted to match.	\$ 9,787	\$ 9,787	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
61	FM-0054655	Los Angeles	Metropolitan Courthouse	19-T1	1	Plumbing - Flood Remediation, Approximately 6,500 SF over four floors. Replace flush valve in restroom, contain leaking, and set up containments in Dept.72 Courtroom, Dept.68 Courtroom and Judge's Chamber Room 711C. Water extraction, clean-up, and environmental testing. Water leaked from a stuck flush valve inside a private restroom on the 8th floor. The water penetrated to the 6th floor.	\$ 13,657	\$ 13,657	100
62	FM-0054656	Los Angeles	Parking Structure-Edelman Court	19-Q2	1	Elevators, Escalators, & Hoists - Reline Elevator #1 brakes, take brakes to machine shop to be relined. Install brakes and return elevator to service. Elevator breaks are worn, causing elevator to not level properly on floors. This is a tripping hazard and safety issue.	\$ 15,883	\$ 11,117	69.99
63	FM-0054657	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	1	Electrical- Replace defective 150Hp power supply fan motor and 150Hp VFD. There is a ground fault in the electrical distribution system that supports all of the HVAC mechanical equipment that is causing circuit breakers to trip.	\$ 13,809	\$ 9,665	69.99
64	FM-0054658	Los Angeles	Compton Courthouse	19-AG1	1	Plumbing - Cracked drain line cause water fountain leak. Removed/replaced cracked 1½in P-trap and fittings to the drinking fountains drain line. Set up 10x10 containment. Environmental testing.	\$ 13,859	\$ 13,859	100
65	FM-0054659	Los Angeles	El Monte Courthouse	19-O1	1	Electrical - Install a new 400 A, Automatic Transfer Switch, 600 V to restore electrical power. The original ATS #2 failed to switch back to building power and caused a partial power outage in the building. There was no power to the elevators, stairwell lighting, and the air handler units. This issue occurred after a rain storm caused a power outage in the building.	\$ 27,498	\$ 15,982	58.12
66	FM-0054660	Los Angeles	Van Nuys Courthouse West	19-AX2	1	HVAC - Approx. 38 VAV universal volume controls for the damper actuator need to be replaced, No pneumatic control. Temperature is too hot in some areas and too cold in other areas.	\$ 11,750	\$ 11,750	100
67	FM-0054661	Los Angeles	Van Nuys Courthouse West	19-AX2	1	HVAC - 3rd flr AHU is nonoperational and there is no cold air supply, hot air supply or return air. Replace 3 VFDs - Hot deck supply 7.5hp motor drive and return 10hp drive, cold deck 30hp drive.	\$ 15,595	\$ 15,595	100
68	FM-0054662	Los Angeles	Van Nuys Courthouse East	19-AX1	2	Grounds - Broken and Missing Walkway Tiles - Provide temporary barricade, remove loose and broken tiles, prep the surface, and install new tiles. Currently the sidewalk between the East & West buildings has missing and/or damaged tiles in multiple areas totaling approx. 68 sq. ft. Loose tiles in the sidewalk are a tripping hazard for all pedestrian traffic.	\$ 4,702	\$ 4,220	89.74



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
69	FM-0054664	Los Angeles	Santa Monica Courthouse	19-AP1	2	Vandalism - Replace anti-graffiti film on (42) windows & install anti-graffiti film on restroom mirrors. There is currently graffiti scratched into the existing anti-graffiti film on the ground floor windows; mirrors in public restroom currently do not have anti-graffiti film leaving them exposed to vandalism.	\$ 4,130	\$ 3,242	78.49
70	FM-0054665	Orange	Betty Lou Lamoreaux Justice Center	30-B1	2	Electrical - Automatic Transfer Switch - Replace failed Automatic Transfer Switch - ATS02. While performing the Preventative Maintenance on ATS02, power transferred from Edison to the generator but would not transfer back to Edison. The issue is with the control cards and the cards are no longer available.	\$ 10,144	\$ 8,110	79.95
71	FM-0054667	Los Angeles	Compton Courthouse	19-AG1	2	Vandalism - Sand, scrape, prep, and paint restroom walls & replace vandalized fixtures; replace anti-graffiti film on (19) mirrors & (22) windows. There is currently graffiti on multiple walls as well as multiple vandalized fixtures inside the public restrooms.	\$ 4,907	\$ 3,245	66.13
72	FM-0054668	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	2	Grounds and Parking Lot - Install (2) new heavy duty 18 gauge hollow metal doors on trash enclosure, mounted with HD full surface hinges & panic hardware. Trash enclosure is currently missing fire rated doors and hardware which could cause a security issue.	\$ 5,604	\$ 3,855	68.79
73	FM-0054669	Santa Clara	Hall of Justice (West)	43-A2	2	HVAC - Cooling tower fan motor has failed - Replace failed #2 fan motor - Test and return unit to full service (CTW02 OM00028638).	\$ 4,179	\$ 4,179	100
74	FM-0054670	Los Angeles	Bellflower Courthouse	19-AL1	2	Vandalism - Scrape, sand & paint partition walls, install new mirrors with anti-graffiti film, install new locks on stall doors, and replace glass panels for the directories on multiple floors. There is currently graffiti engraved into mirrors & partition walls in the public restrooms as well as broken locks on the stall doors.	\$ 5,195	\$ 4,049	77.94
75	FM-0054671	Los Angeles	Compton Courthouse	19-AG1	2	Vandalism - Replace vandalized faucets, soap dispensers, toilet seat covers, re-paint walls & partitions and also install new anti-graffiti film. Inside the public restrooms many items have been vandalized and some items have been broken.	\$ 9,863	\$ 6,522	66.13
76	FM-0054672	Los Angeles	Norwalk Courthouse	19-AK1	1	Plumbing - Water remediation, contained leaking, environmental testing, dried leak affected areas and cleared drain lines in RR. A sink overflowed, flooded the deliberation room men's RR in the 4th flr Courtroom K. Water seeped thru floor and leaked into the 3rd flr Courtroom F.	\$ 9,842	\$ 8,369	85.03



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
77	FM-0054673	Contra Costa	Wakefield Taylor Courthouse	07-A2	2	Interior finishes - Earthquake - Install 20 feet ceiling grid on the second floor; Build scaffolding to reach 18 feet. Anchor support bracket to steel beam. Install 60 interlocking one foot square steel ceiling tiles; Install insulation above the ceiling. Install glass guide in room 303 - Hole in the ceiling due to the earthquake.	\$ 3,279	\$ 3,279	100
78	FM-0054674	Los Angeles	Stanley Mosk Courthouse	19-K1	1	Elevators, Escalators, & Hoists - Install new drive chain and replace damaged washer on non-reversal device in escalator 1-2. The escalator drive chain is currently stretched and is hitting the access cover which could cause the chain to come off and the escalator to stop moving.	\$ 6,616	\$ 6,616	100
79	FM-0054675	San Diego	County Courthouse	37-A1	2	Electrical - Set up full containment 30'x30'; ACM testing. Replace 200 lights and burnt ballasts. Courtroom is too dim, lights are out and need to be replaced.	\$ 7,173	\$ 7,173	100
80	FM-0054676	Los Angeles	Stanley Mosk Courthouse	19-K1	1	Elevator - Installation of two P.I. driver boards and one input/output board on the freight elevator. Failure of #1 freight elevator in-car floor indicator panel creating a safety issue.	\$ 7,166	\$ 6,970	97.26
81	FM-0054678	Los Angeles	Downey Courthouse	19-AM1	2	Electrical - Replace the fuel tank controller in the diesel tank. The existing fuel tank controller has shorted out and is no longer functional. Work is code required.	\$ 3,744	\$ 3,134	83.7
82	FM-0054679	Alameda	Hayward Hall of Justice	01-D1	1	HVAC - Replace failed gas pressure regulating valve on boiler.	\$ 8,954	\$ 8,954	100
83	FM-0054680	Los Angeles	Downey Courthouse	19-AM1	1	Elevators, Escalators, & Hoists - Replace control switch and seal for elevator #4. The control switch malfunctioned and caused the elevator to stop and not respond causing an entrapment and safety issue. Also a worn shaft seal went out causing oil to leak out onto the floor causing a slip hazard.	\$ 13,179	\$ 13,179	100
84	FM-0054681	Los Angeles	Downey Courthouse	19-AM1	2	Fire Protection - Remove existing halon tank and replace failed seals. Certify tank, recharge and reinstall per code.	\$ 3,179	\$ 2,661	83.7
85	FM-0054684	Los Angeles	Downey Courthouse	19-AM1	2	Vandalism - Sand & paint multiple walls, doors, frames, and partitions; sand and polish stainless steel; replace multiple damaged fixtures & mirrors with new anti graffiti type. Public restrooms on floors 1-4 currently have graffiti on walls, doors, frames, partitions and mirrors as well as multiple damaged fixtures.	\$ 15,083	\$ 12,624	83.7



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
86	FM-0054685	Los Angeles	Stanley Mosk Courthouse	19-K1	2	Vandalism - Scrape, sand, and paint walls in approx. (20) restrooms to match existing. Multiple public restrooms on floors 2 through 9 currently have vandalism on the walls which could be a safety concern for the public.	\$ 22,470	\$ 21,854	97.26
87	FM-0054688	Napa	Historical Courthouse	28-B1	2	HVAC - Correct oil leak on air compressor #1. - Oil leaking from compressor head causing fire and safety hazard.	\$ 2,707	\$ 2,544	93.99
88	FM-0054689	San Francisco	Civic Center Courthouse	38-A1	2	Vandalism - To remove damaged (graffiti) security film and replace with new graffiti film on 3 elevator panes in elevators 1, 3 and 4. Three panes total at 22" X 101" each.	\$ 1,297	\$ 1,297	100
89	FM-0054690	Los Angeles	East Los Angeles Courthouse	19-V1	1	Plumbing - Hot domestic water pipe leaked inside a wall in women's public RR, 2nd flr affecting (2) rooms. Water damage remediation in rm G13 & Public women's RR. Remove/replaced 180sq.ft. ceramic tile to access leak source. Replace 4ft of Copper Piping on Domestic Water Line. Environmental testing, Remediation work performed under positive ACM/Lead conditions.	\$ 35,000	\$ 27,202	77.72
90	FM-0054691	Monterey	Salinas Courthouse-North Wing	27-A1	1	Plumbing - Replace (1) failed vacuum pump.	\$ 3,051	\$ 3,051	100
91	FM-0054692	Los Angeles	Norwalk Courthouse	19-AK1	1	Plumbing - Leak Mitigation - Removed and replaced a 3' section of 2" cracked drain line, the source of the leak is a cracked drain pipe above the ceiling in Courtroom B. Water leaked through the ceiling tiles of Courtroom B. Performed water remediation in Courtroom B. Set up containment, drying equipment, and remove ACM fireproofing over spray from a drain pipe.	\$ 14,181	\$ 14,181	100
92	FM-0054693	Los Angeles	Metropolitan Courthouse	19-T1	1	Plumbing - Water remediation - Set up containments, and dry leak affected areas (approximately 2,000 SF), clean up, and restore main drain line. 5th floor Public Men's Restroom main drain line is backed up, urinals overflowed. Water went down pipe chase 3rd floor to 1st floor. Elevators #5 & #9 have water on top of cabs and in elevator pits.	\$ 13,856	\$ 13,856	100
93	FM-0054694	Orange	West Justice Center	30-D1	2	HVAC - Replace an old malfunctioning exhaust fan in the basement HVAC mechanical room. Current issues with the exhaust fan are critical including: " Failing bearings "Bent shaft " Out of balance causing excessive noise " Missing the proper motor belt adjusters " Damaged blower wheel " Parts not available due to old age.	\$ 5,294	\$ 4,801	90.68



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
94	FM-0054695	Imperial	Imperial County Courthouse	13-A1	2	Ground and Parking Lot - Remove and replace approximately 120sf of concrete sidewalk in front of the court house. Concrete is cracked, chipped, and uneven in many areas creating a trip hazard for court staff and the public. Court has reported public and staff tripping.	\$ 2,435	\$ 2,435	100
95	FM-0054697	San Mateo	Traffic/Small Claims Annex	41-A2	1	Parking lot - Remediate rain related flood damage caused by blocked sump pump drain which limited flow through system drains. Install drain screens to mitigate future issues. Areas impacted by flood water are courtroom, chambers, public lobby, file area.	\$ 14,663	\$ 14,663	100
96	FM-0054698	Los Angeles	Torrance Courthouse	19-C1	1	Elevators, Escalators, & Hoists - Install newly fabricated Selector Tape Deflector Sheaves. Elevator #5 Selector Tape Bearing worn out and requires replacement.	\$ 35,558	\$ 35,558	100
97	FM-0054699	Los Angeles	Inglewood Juvenile Court	19-E1	2	Electrical - Install 1 furniture power whip from existing receptacles. Install 10ft of conduit/Panduit for voice/data cables to the new counter location. Electrical & Data work is a necessity because the court installed 3 transaction windows.	\$ 4,500	\$ 3,635	80.78
98	FM-0054700	Alameda	Wiley W. Manuel Courthouse	01-B3	2	Fire Protection - Replace the failed main fire suppression water supply tamper switch located in the fire pump room.	\$ 2,613	\$ 2,190	83.8
99	FM-0054701	Los Angeles	Stanley Mosk Courthouse	19-K1	2	Elevator / Repair door armature and replace micro switch for Elevator #5. Doors do not properly opening resulting in 5 people being entrapped in the elevator.	\$ 3,717	\$ 3,615	97.26
100	FM-0054702	Los Angeles	Van Nuys Courthouse West	19-AX2	1	HVAC - Failing Chiller #1 - Chiller #1 requires the replacement of the failed Vane Assembly, the actuator is not functioning which is creating a very hot situation for the entire courthouse.	\$ 11,865	\$ 9,549	80.48
101	FM-0054703	Contra Costa	Wakefield Taylor Courthouse	07-A2	2	HVAC - Replace (1) failed Refrigerant Leak Detector Sensor; Replace (1) Failed Monitoring Station, and (1) CO2 Sensors; Run 30 feet or control wiring. - System failed during annual testing and could not be calibrated.	\$ 23,586	\$ 23,586	100
102	FM-0054704	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Water remediation, containments, environmental testing, emergency clean up, 4th Floor leak on 1 1/4 Black Iron Pipe Chilled Water Supply Line and a 2 1/2 cold/chilled water pipe. Water system is/was completely drained down to the 4th floor. Replacement parts included: 8 of 1 1/4 Cooper Pipe, (1) 1 1/4 MIP, (1) 1 1/4 Union, (1) 1 1/4 Coupling , (1) 1 1/4 Ball Valve.	\$ 35,000	\$ 35,000	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
103	FM-0054705	San Diego	Kearny Mesa Traffic Court	37-C1	2	HVAC - Installed new 3 ton Condensing unit. Split air conditioner is not cooling the server room and needs replacement, as the equipment may overheat and fail.	\$ 6,270	\$ 6,270	100
104	FM-0054706	Madera	Madera County Superior Court	20-A1	1	HVAC-100 ton rooftop Chiller is operating at 50% capacity due to malfunctioning solenoid valves. Chiller is currently shutting down on low pressure due to the valves not opening to allow refrigerant to flow so that the chiller can cool the courthouse. The Chillers current state does not have the capacity to cool the building in warmer temperatures 75 degrees and above. Replacement valves are essential for the chiller to reach its full operating potential.	\$ 3,000	\$ 3,000	100
105	FM-0054707	Santa Clara	Palo Alto Courthouse	43-D1	2	HVAC - Replace failed leaking hot gas isolation valve and return charge to factory specs . An active refrigerant leak has been located on circuit B - CLR02 OM00018899.	\$ 6,392	\$ 4,221	66.04
106	FM-0054708	Los Angeles	Chatsworth Courthouse	19-AY1	2	HVAC - Replace (23) burner's assemblies tubes & replace (2) surface igniters with new. Boiler #2 currently has cracked burners and malfunctioning surface igniters which will prevent proper heating to the building.	\$ 4,925	\$ 4,127	83.8
107	FM-0054709	Los Angeles	Michael D. Antonovich Antelope Valley Courthouse	19-AZ1	2	Electrical - Restore lighting to public parking lot, replace lights and ballasts. Parking lot is too dark, 50% of the lights are out (187 lights) and need to be replaced. This is a safety hazard.	\$ 4,999	\$ 3,675	73.51
108	FM-0054710	Orange	North Justice Center	30-C1	2	HVAC - Replace motor cooling solenoid valve on circuit B of Carrier Chiller #1 (model #30HXC161R-640AA/Serial # 3002Q01842). Work to include Lock out/Tag out of circuit, Recovery of Freon from circuit, Install new solenoid and valve, Charge and evacuate circuit with Freon, Start up and test operation.	\$ 2,723	\$ 2,459	90.31
109	FM-0054711	Santa Clara	Hall of Justice (East)	43-A1	2	Vandalism - Damaged Toilet Accessories - Remove graffiti from multiple toilet accessories, work will require sanding, priming and painting to remove extensive graffiti. Accessories needing replacement are a cracked vanity mirror and broken vanity faucet. Basement men's public restroom.	\$ 11,118	\$ 11,118	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
110	FM-0054713	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	2	Electrical - Re-seal water manifolds with new gaskets & seals, replace valve cover gaskets, replace coolant temp gauge & temp sender, re-seal oil reservoir with new gaskets. The emergency generator currently has multiple leaks preventing normal operation.	\$ 3,559	\$ 2,448	68.79
111	FM-0054714	Sacramento	Juvenile Courthouse	34-C2	2	HVAC - Cooling Tower - Remove failed Dolphin water treatment system and demo piping and electrical unit from cooling tower area. Remove all electrical back to panel and supporting structures and terminate for safety. Install new fabricated 5' x8" pipe in place of dolphin housing on condenser water supply line. Install new cover over chemical treatment pump and controller. Paint new piping to match existing condenser lines. Dolphin system has been abandoned on water line due to poor functionality and ineffectiveness to treat hard mineral water. Dolphin needs to be removed to prevent blockage on condenser piping.	\$ 8,213	\$ 8,213	100
112	FM-0054715	Kern	Bakersfield Juvenile Center	15-C1	2	Grounds and Parking Lot - Demo concrete and trench pipe to expose fractured line. Replace line and re-pour concrete pad adjacent to employee entrance West. Fractured 6" water line for stand pipe observed through puddling in lawn. Trench area to expose pipe and replace.	\$ 10,069	\$ 6,722	66.76
113	FM-0054716	Solano	Hall of Justice	48-A1	2	Vandalism - Interior door - Replace damaged Courtroom door and automatic flush-bolt damaged by litigant crashing through door.	\$ 6,467	\$ 6,467	100
114	FM-0054717	San Diego	County Courthouse	37-A1	1	HVAC - Replaced 4' section of galvanized steel 2.5" chilled water return line. The chilled water return line for AHU SBM-2 failed causing a leak.	\$ 6,322	\$ 4,894	77.42
115	FM-0054718	Contra Costa	George D. Carroll Courthouse	07-F1	2	Grounds and Parking lot - Replace 20' of re-enforced Sidewalk Curb and 1 Wheel Stop in the North Parking Lot that have been damaged. The broken concrete and exposed rebar are a safety hazard.	\$ 5,245	\$ 3,933	74.99
116	FM-0054719	Del Norte	Del Norte County Superior Court	08-A1	2	Electrical - Replace failed lighting to include surface ceiling mounted area fixture with LED fixture attached (4). Replace recessed can with LED equivalent (5). Recessed light will need an adapter ring to match existing hole size. Replace existing wall pack fixture with LED wall pack (6). Replace spot light fixture with LED flood light (10), per map provided. Replace 16 existing wall mounted up/down lights with LED fixture attached.	\$ 14,012	\$ 8,585	61.27
117	FM-0054720	Los Angeles	Van Nuys Courthouse West	19-AX2	1	Elevators, Escalators, & Hoists - Replaced brakes. Escalator 3-2 was tagged out by state inspector and needed brake replacement.	\$ 9,252	\$ 7,446	80.48



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
118	FM-0054721	Los Angeles	Stanley Mosk Courthouse	19-K1	1	Elevators, Escalators, & Hoists - Replaced four rail anchor bolts, realigned the rail and counterweight guides. Freight elevator #1 was out of service due to a scraping noise on the side railing when the car was traveling.	\$ 2,427	\$ 2,361	97.26
119	FM-0054722	Del Norte	Del Norte County Superior Court	08-A1	2	Plumbing - Replace 2 failing sump pumps - Replace 2 pumps with new 1/2 hp sump pumps, including main disconnect and connection to E Power Circuit in basement file storage area.	\$ 29,106	\$ 17,833	61.27
120	FM-0054724	San Bernardino	San Bernardino Courthouse - Annex	36-A2	2	COUNTY MANAGED - HVAC- Replace (1) Cooling Tower and related systems with (1) new energy efficient Cooling Tower. Scope includes Isolation valves, piping, new concrete pier extensions, electrical controls, and all structural and mechanical equipment. The existing Cooling Tower has failed and is beyond repair.	\$ 168,033	\$ 168,033	100
121	FM-0054725	Butte	Butte County Courthouse	04-A1	2	Roof - The stucco embedded metal flashing system has failed on 2 south facing parapet walls permitting water intrusion into courtroom 3 above the Judge's bench, ceiling in the Judge's Chambers, and above the restricted hallway behind courtroom 3. The work: Installation of 38 square yards of 60 mil single-ply roofing to cover and seal the affected parapet wall areas, install 450 LF of painted galvanized steel cap at the top of each parapet wall. Replace 150 LF metal roof flashing over public hall.	\$ 36,836	\$ 36,836	100
122	FM-0054726	Stanislaus	Modesto Main Courthouse	50-A1	2	HVAC - To replace failing Baltimore Aircoil Cooling Tower CTW01 (OM00003271) located in the east penthouse - The shell of Cooling Tower CTW01 has severe corrosion damage. There are several locations on the tower that have rusted through leaving too many holes to effectively repair. The base of the tower is also severally corroded and must be replaced.	\$ 280,000	\$ 217,896	77.82
123	FM-0054736	Orange	Central Justice Center	30-A1	2	HVAC - Replace hot water supply and return line to AHU-10 and 11. The project will include replacement line from butterfly valve to AHUs, check valves, unions, seismic flex, and balancing valve. Work is needed due to pipe breaking, causing a basement garage and mechanical room to flood. Currently there is no hot water being supplied to AHUs to balance cold air being supplied to the court areas.	\$ 18,528	\$ 16,892	91.17



#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
124	FM-0054737	Los Angeles	Metropolitan Courthouse	19-T1	2	Electrical - Replace 54 burnt-out exterior perimeter lamps with LED lamps (250w mercury vapor equivalent). Currently the exterior building perimeter lamps are burnt out and the insufficient lighting is creating a safety situation.	\$ 20,192	\$ 19,090	94.54
125	FM-0054738	Santa Clara	Downtown Superior Court	43-B1	1	HVAC - Isolate and drain existing condenser water valves - Replace two (2) failed condenser plates and two (2) gaskets - 80% of the condenser tubes were plugged with calcium/mineral build-up affecting the water flow, Chiller at 40% capacity and not cooling the building affecting the Courtroom Operations.	\$ 20,942	\$ 20,942	100
126	FM-0054744	Los Angeles	San Fernando Courthouse	19-AC1	2	HVAC - Replace leaking seals on condenser water pump. Currently the condenser water pump is leaking and is causing the chiller to shut down.	\$ 4,998	\$ 4,169	83.41
127	FM-0054745	Orange	Central Justice Center	30-A1	2	Electrical - Replace non-functioning FAA required rooftop aircraft warning light. The project will include specialty aerial work.	\$ 9,672	\$ 8,818	91.17
128	FM-0054746	San Bernardino	New San Bernardino Courthouse	36-R1	1	Plumbing - Replace failed No-Hub coupling. Water remediation, set up containments in S-24 and the women's public restrooms on the 6th, 7th, 8th, 9th, and 10th floors in order to expedite the drying process. Apply biocide to and extract water from approx. 100SF of carpet in S-24. Utilize approx. 16 fans and 6 dehumidifiers in affected areas to completely dry them out. Water damage caused by a leak in the 10th floor pipe chase of the women's public restroom.	\$ 11,288	\$ 11,288	100
129	FM-0054747	San Diego	County Courthouse	37-A1	2	Plumbing - Install a Pressure Regulating Valve and a Butterfly Isolation Valve to reduce the operating pressure to the Domestic Hot Water Tank (DHWT). The current DHWT has too high of water pressure and is at risk of blowing the relief valve as well as damaging plumbing fixtures.	\$ 4,984	\$ 4,984	100
130	FM-0054748	Los Angeles	Metropolitan Courthouse	19-T1	2	Electrical - Currently the lighting fixture has a short causing the light to be out in level A of the underground parking structure. Install 200 of 3/4 EMT and 1000 of #10 THHN stranded wire to replace failed wiring. Security issue.	\$ 3,737	\$ 3,533	94.54
131	FM-0054749	Solano	Hall of Justice	48-A1	2	HVAC - Air Handler - Replace failed VFD drive and control circuit board for supply fan #3. Unit is temporarily operating on manual bypass mode.	\$ 14,429	\$ 10,507	72.82
132	FM-0054750	Napa	Criminal Court Building	28-A1	2	Security - Failing Courtroom Entrance Doors - Remove doors (6 pairs, 3'0" x 9'0" x 2 3/4") at courtrooms to public halls; replace failing hinges; replace brush seals. Unable to secure doors due to failed hinges causing door sag.	\$ 9,501	\$ 9,501	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
133	FM-0054751	Humboldt	Humboldt County Courthouse (Eureka)	12-A1	2	HVAC - Make changes to air duct system to better office air balance. Switch return air and supply air register one. Remove and replace two (2) supply diffusers to better control air from blowing directly on employee desks in Court Operations.	\$ 1,078	\$ 1,078	100
134	FM-0054752	Los Angeles	Compton Courthouse	19-AG1	2	HVAC - Install pneumatic isolation valves and new Speedair electric two stage air compressor. Air compressor #1 has a failed weld on the Compressor Tank, the welds on the motor mounting bracket have come apart and is constantly leaking air at the main air tank receiver. Second stage compressor valves have failed and will not allow it to compress air into main air tank receiver.	\$ 14,211	\$ 9,398	66.13
135	FM-0054756	Napa	Criminal Court Building	28-A1	2	Electrical - Provide four (4) new lighting circuits at courtroom conference rooms (8); separate from occupancy control for courtrooms; add breakers and home run supplies to panels; label as required - Conference rooms repurposed as Court Staff offices due to functional relocations from Historic Courthouse closure (Earthquake).	\$ 7,102	\$ 7,102	100
136	FM-0054757	Alameda	Hayward Hall of Justice	01-D1	2	HVAC - Building Automation System - Replace five (5) failed controller backup batteries and re-configure and calibrate five (5) sensors for correct display values.	\$ 4,877	\$ 4,306	88.3
137	FM-0054758	Kings	Corcoran Court	16-D1	2	Roof - Prime and 3-course the sump/wall area of failed NE drain sump. Reseal the tops of all 35 roof jacks and install missing clamps. Remove all old caulking and mastic at parapet coping joints, apply new caulking, pop rivet laps together and seal the top lap with caulking. Reseal with caulking the stabilizer bar around the perimeter of the parapet and apply caulking on all the screw heads. At the five visible cuts in the roofing, secure roofing with screws and plates; 3-course the cuts and seal.	\$ 10,344	\$ 9,061	87.6
138	FM-0054760	Tulare	Tulare Division	54-B1	2	Roof - Remove loose mastic from around two leaking drains, overflows, and wall corners; prime roofing at cleaned areas (10' x 10') at each drain using Garland VOC Primer. 3-course around overflows/wall corners with flashing bond mastic and Garland GarMesh webbing. Install Energizer K Plus FR at a rate of 5 gallons per 100 square feet. Broadcast white granules into the energizer to fully cover each affected area. Caulk tops of pre-cast panel joints (6" x 4' ea) using Tuff Stuff Caulking.	\$ 4,886	\$ 3,420	70



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
139	FM-0054761	Los Angeles	Beverly Hills Courthouse	19-AQ1	2	Electrical - Remove and replace 300 amp Automatic Transfer Switch (ATS). ATS coil that transfers power from emergency to normal has failed.	\$ 25,083	\$ 19,946	79.52
140	FM-0054762	Del Norte	Del Norte County Superior Court	08-A1	2	Grounds and Parking Lot - Generator Security Fence -Remove 72 lf of old decaying wood fence and replace with new 7 foot chain link fence, installing new post where needed, work will also include a new water spigot.	\$ 10,088	\$ 6,181	61.27
141	FM-0054764	Los Angeles	West Covina Courthouse	19-X1	1	COUNTY MANAGED - Flooding occurred due to a broken water pump in the basement mechanical room. Millwrights replaced broken pump shaft assembly of the water pump.	\$ 9,713	\$ 9,713	100
142	FM-0054765	Los Angeles	Pasadena Courthouse	19-J1	2	Interior Finishes - Environmental testing, set up containment, remove & dispose of 120 sq. ft. of 12 x 12 inch VCT tiles, scrape mastic, install approx. (130) new floor tiles. Currently the vinyl floor tiles in the Department M secure hallway are delaminating which is causing a tripping hazard.	\$ 7,734	\$ 7,734	100
143	FM-0054766	Contra Costa	George D. Carroll Courthouse	07-F1	2	Vandalism - Replace 14 fixed wooden seats in the public hallway. Seats are covered with profanity and other graffiti which has been etched into the wood.	\$ 5,409	\$ 4,056	74.99
144	FM-0054767	Los Angeles	Metropolitan Courthouse	19-T1	1	Plumbing - Pinhole water leak from a 3/4" Domestic Hot Water Copper supply line penetrated 8th floor ceiling, affecting room 801A. Removed/replaced approx. 30ft of 3/4" copper pipe due to various locations for pitting and oxidation. Two (2) containments set up, 12'x10'x11' and 8'x6'x9.5' w/air machines. ACM Positive, Remediation and Environmental testing.	\$ 25,110	\$ 23,739	94.54
145	FM-0054768	Contra Costa	Wakefield Taylor Courthouse	07-A2	2	HVAC - Install vents in the bottom of four (4) IT closet doors; Install one exhaust fan with thermostat in the second floor IT Room - IT Closets. Court IT has distributed their equipment throughout the building. Cooling these closets will eliminate the need to add an expensive split system in the main IT room.	\$ 4,194	\$ 4,194	100
146	FM-0054769	Los Angeles	East Los Angeles Courthouse	19-V1	2	HVAC - Install new isolation valves on chillers #1 and #2. Chillers currently do not have isolation valves for oil return filters which are required for the recovery and changing of refrigerant.	\$ 10,284	\$ 7,993	77.72



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
147	FM-0054770	Los Angeles	East Los Angeles Courthouse	19-V1	2	HVAC - Remove and rebuild pump motor and replace main seals; re-install and provide two (2) new gaskets. Cooling tower pump motor is currently leaking from a shaft seal and needs to be rebuilt to ensure proper operation.	\$ 9,650	\$ 7,500	77.72
148	FM-0054771	Los Angeles	Santa Monica Courthouse	19-AP1	2	HVAC - Replace damaged and worn out chilled water and hot water piping insulation at the roof along with several sections of hot water piping in the air handler located on the roof. Pipes are exposed and sweating, affecting the performance and overall efficiency of the HVAC equipment at the roof.	\$ 6,640	\$ 5,212	78.49
149	FM-0054772	Los Angeles	Airport Courthouse	19-AU1	2	Elevators, Escalators, & Hoists - Install one (1) new presence sensing electronic door edge. Elevator #2 does not currently have an electronic door edge that re-opens when an obstruction is detected which is a safety hazard.	\$ 3,573	\$ 2,757	77.17
150	FM-0054774	Los Angeles	Santa Monica Courthouse	19-AP1	2	Elevators - Install new pump flange on cars #1 and #2 then return them back to service. Elevators #1 & #2 have worn out pump flanges that are currently leaking oil which is a safety hazard and could affect elevator operation.	\$ 10,069	\$ 7,903	78.49
151	FM-0054775	Los Angeles	Compton Courthouse	19-AG1	2	HVAC - Replace isolation base, springs, and utility supply fan unit #1. Supply fan unit currently has excessive vibration while running and is beyond repair. The supply fan feeds the sally port and needs to be replaced before it causes damage to surrounding area.	\$ 11,153	\$ 7,375	66.13
152	FM-0054776	Los Angeles	Torrance Courthouse	19-C1	2	Interior Finishes - Removal and disposal of loose and flaky plaster on cafeteria walls (2,600 sqft). Patch, sand, and then fully prime and apply new coat of finish. Work is needed to prevent health hazard and to eliminate potential toxic substance from public area.	\$ 4,475	\$ 3,810	85.14
153	FM-0054780	Los Angeles	Santa Monica Courthouse	19-AP1	2	HVAC - Replace fan motor, fan belt, fan shaft and bearings. Cooling Tower #2 has a bad motor, deficiencies found during PM SWO 2462088. Deficiencies need to be corrected before it affects the building HVAC system.	\$ 15,326	\$ 12,029	78.49



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
154	FM-0054781	Los Angeles	Pasadena Courthouse	19-J1	1	Plumbing - Replace approx. 10' of 3" cast iron pipe & fitting; install 2' sq. access panel in ceiling of storage room; install approx. (20) 12" x 12" new ceiling tiles; clean & disinfect leak affected areas, perform final environmental testing. A 3" main cast iron drain pipe located under the 2nd floor deputy locker room & in the ceiling of the 1st floor storage room clogged & cracked, leaking into first floor storage room causing moisture issues on walls & ceiling.	\$ 24,833	\$ 24,833	100
155	FM-0054782	Los Angeles	Pasadena Courthouse	19-J1	1	Plumbing - Set up containment & drying equipment, dry leak affected areas in chilled water pump room(180 sq. ft.), main entrance(672 sq. ft.), front of emergency generator room (125 sq. ft.), boiler room(180 sq. ft.), & South hallway (54 sq. ft.); replace approx. 5' of 1" copper pipe. There is a water leak coming from a 1" copper chill water bleed line located inside the basement mechanical room leaking into multiple areas in the basement.	\$ 15,675	\$ 15,675	100
156	FM-0054783	Los Angeles	Airport Courthouse	19-AU1	2	Graffiti Removal - Elevator#3; 3rd floor windows; Evacuation signs on all floors.	\$ 5,000	\$ 3,859	77.17
157	FM-0054785	Los Angeles	Torrance Courthouse	19-C1	1	Plumbing - Set up containment (5x5x12) and dehumidifier, dry leak affected areas using hepa vac & extractor/carpet cleaner & verify with thermal camera. Replaced 5 damaged ceiling tiles. An overflowing toilet caused by an inmate created a water leak in the 5th floor lock up flooding 2 cells and water leaked down to the 4th floor Department P courtroom.	\$ 7,033	\$ 5,988	85.14
158	FM-0054786	San Diego	East County Regional Center	37-I1	1	Plumbing - Isolate 4th, 3rd, 2nd and 1st floor sprinkler lines. Drain 2nd floor sprinkler line. Remove and replace 2' of sprinkler pipe. Fire sprinkler pipe burst above the Administrative Office Conference Room causing water to leak through to the area below.	\$ 2,431	\$ 2,431	100
159	FM-0054787	San Diego	Kearny Mesa Traffic Court	37-C1	2	Plumbing - Remove approx. 8SF of drywall immediately above a shower drain pan under full containment as the drywall joint compound contains ACM. Remove drain pan, cut out approx. 9SF of concrete and replace a failed P-trap. Re-pour concrete, install new shower insert, and rebuild wall to match existing. Environmental testing has been done. Shower and break room sink are currently unusable as the P-trap has completely failed and is blocking the drain line, need to replace P-trap.	\$ 17,778	\$ 17,778	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
160	FM-0054788	San Diego	County Courthouse	37-A1	2	Interior Finishes - Replace four damaged ceiling tiles, clean-up of ACM debris and environmental testing. Ceiling tiles are damaged and need to be replaced in Presiding Judge's chambers.	\$ 4,248	\$ 4,248	100
161	FM-0054789	Del Norte	Del Norte County Superior Court	08-A1	2	Exterior - Remove and reinstall five (5) new stainless steel attic hatch accesses. Finished and painted and sealed.	\$ 12,397	\$ 7,596	61.27
162	FM-0054790	Los Angeles	Compton Courthouse	19-AG1	2	HVAC - Replace 40hp supply fan motor with new and test for proper operation. The current supply fan motor in air handler #11 is failing.	\$ 6,888	\$ 4,555	66.13
163	FM-0054791	Los Angeles	Metropolitan Courthouse	19-T1	2	Exterior Shell - Fabricate fence to prevent homeless/public from accessing the parking alcove. This is a safety matter. Currently the homeless/public are sleeping in the employee parking alcove creating a safety issue for employees.	\$ 14,925	\$ 14,110	94.54
164	FM-0054793	Los Angeles	Pomona Courthouse South	19-W1	1	Grounds and Parking Lot - Removed old roll up door and door frame. Installed new side framing for roll up door tracks and replaced Sally Port Door. Sally Port door gate spring was broken and it would not open. The door was opened manually to allow bus access.	\$ 18,987	\$ 18,987	100
165	FM-0054794	Los Angeles	Stanley Mosk Courthouse	19-K1	1	Elevators, Escalators, & Hoists - Replaced Breaker in Electrical Room and replaced "M" Contactor and Starter Coil to Elevator #3. Public Elevator #3 was stuck on the 1st floor, a faulty contactor caused elevator to malfunction. A starter component was also damaged.	\$ 33,486	\$ 32,568	97.26
166	FM-0054795	Los Angeles	Van Nuys Courthouse West	19-AX2	1	Plumbing - Set up containment & drying equipment, perform environmental testing, dry leak affected areas in Room 10-62, replace damaged cast iron drain line. Failed cast iron drain line located above the ceiling on the 10th floor leaking into room 10-62.	\$ 15,349	\$ 15,349	100
167	FM-0054796	Los Angeles	Airport Courthouse	19-AU1	2	Electrical- Replace defective ballasts and lamps in 21 exterior bollards that are not properly illuminating the area during night hours, which is a safety hazard. Replace 20 defective wall mounted override timers, not allowing janitorial to turn on lights at night, which is also a safety hazard.	\$ 4,867	\$ 3,756	77.17
168	FM-0054799	Orange	Central Justice Center	30-A1	2	Plumbing - Replace broken copper pipe in the 3rd floor cafeteria. The leak caused damage to 2nd floor offices and waiting room. Project will include replacement of damaged wall paper, wall material, and paint.	\$ 12,481	\$ 12,481	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
169	FM-0054800	Orange	West Justice Center	30-D1	2	Plumbing - Lining of Sump Pump Station #2 pit is deteriorating and is cracked. Estimated time before reaching critical level is 4-5 months. Project to correct includes: removal of pumps, removal of any and all debris, line the pit with Zebron coating, reinstall pumps, start up and test system.	\$ 21,930	\$ 19,886	90.68
170	FM-0054802	Los Angeles	Van Nuys Courthouse West	19-AX2	2	Fire Protection - Configure wiring from stairwell doors to fire control room, make final connections, install relays to control door locks. Currently the doors in stairwells 1, 2, 3, & 4 are not locking properly; these doors are supposed to remain locked at all times and only unlock during emergencies; these doors must be fixed to eliminate public access to the secured side of the building and to make sure they work properly during an emergency.	\$ 5,516	\$ 4,439	80.48
171	FM-0054803	Los Angeles	Chatsworth Courthouse	19-AY1	2	Plumbing - Install four (4) new non-mercury, wide angle float switches and one (1) epoxy coated float anchor with stainless steel chain; clean pump pit and seal control panel. The floats in the septic tank are not currently working which could lead to tank overflow and health and safety issues.	\$ 6,219	\$ 5,212	83.8
172	FM-0054804	Los Angeles	Burbank Courthouse	19-G1	2	HVAC - Replace Electrical Expansion Valve (EXV) and thermostat on circuit A to the compressor, air cool receptacle chiller supplies cooling to west end of building. Unit is down and not cooling.	\$ 10,370	\$ 9,412	90.76
173	FM-0054805	Sacramento	Juvenile Courthouse	34-C2	2	HVAC - Cooling towers - Remove and replace existing fill material and drift eliminators. The drift eliminators for both cooling towers have filled with mineral deposits. As a result the cooling towers are struggling to maintain design load efficiency.	\$ 34,322	\$ 34,322	100
174	FM-0054806	San Joaquin	Lodi Branch - Dept. 2	39-D2	2	Security - Replace non-functioning stand-alone card-access system on vehicle and man-gate with keypad access system.	\$ 2,558	\$ 2,558	100
175	FM-0054807	Merced	Old Court	24-A1	2	Security - Set-up and install one (1) card reader programming module in the HR office and test for proper operation. Current card reader programming module has malfunctioned creating card programming problems with the access control system.	\$ 2,379	\$ 2,379	100
176	FM-0054808	Los Angeles	Chatsworth Courthouse	19-AY1	2	HVAC - Replace piping on top of cooling towers #1 and #2 with 20 feet of new 8" PVC piping per tower. The piping on cooling towers #1 and #2 is currently old and cracked which could allow a leak that would prevent proper cooling to the entire building.	\$ 14,255	\$ 11,946	83.8



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
177	FM-0054809	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	2	Electrical - Replace cracked right rear water manifold and re-seal with new gaskets and seals; re-seal three (3) other water manifolds with new gaskets and seals; replace valve cover gaskets, and replace coolant temp gauge and temp sender. Emergency generator #2 currently has a cracked water manifold and multiple other issues that could prevent normal operation and cause a safety hazard.	\$ 4,876	\$ 3,354	68.79
178	FM-0054810	Contra Costa	Arnason Justice Center	07-E3	2	Fire Protection - Replace two (2) 4" Butterfly Valves and two (2) Tamper Switches; Devices failed during the Annual Fire Panel PM.	\$ 4,700	\$ 4,700	100
179	FM-0054811	Contra Costa	Danville District Courthouse	07-C1	2	Interior Finish - Replace an 8' x 2 1/2' section of Formica countertop in the break room; Replace sink; work to be done off hours. Counter is falling apart leaving rough edges all around; employees have complained about getting splinters; This is health and safety issue.	\$ 5,313	\$ 5,313	100
180	FM-0054812	Los Angeles	San Pedro Courthouse	19-Z1	2	Plumbing - Build and install a new custom cage for backflow outside of the building. L82" x W24" x H42", and build custom footings 10x10" by 2'. Cage needed to protect backflow from vandalism.	\$ 5,000	\$ 4,758	95.15
181	FM-0054815	Solano	Solano Justice Building	48-B1	2	COUNTY MANAGED - HVAC - Chiller - Replaced aged worn-out mechanical chiller and cooling tower damaged by the August 2014 earthquake.	\$ 308,205	\$ 308,205	100
182	FM-0054819	Los Angeles	Torrance Courthouse	19-C1	1	Plumbing - Remediation, emergency clean up, extract black water and disinfect, environmental testing. An inmate inside Lock Up on the 3rd floor clogged the toilet and caused black water to penetrate multiple floors down to the basement level.	\$ 31,000	\$ 31,000	100
183	FM-0054823	Fresno	B.F. Sisk Federal Courthouse	10-O1	2	Electrical - Replace all 160 batteries in UPS01 and UPS02. Dispose of old batteries per EPA regulations. Existing batteries are now 67 months old (date code September 2009) and beginning to fail, many of the batteries are exhibiting signs of swelling and one battery has completely failed. Batteries need replacing to avoid string failure, battery leaking or exploding, fires, or equipment failure.	\$ 41,315	\$ 41,315	100
184	FM-0054825	Los Angeles	Metropolitan Courthouse	19-T1	1	Electrical - Install temporary Generator and Run 75ft of cable to tie into the Auto Transfer System (ATS) on Level B Parking. Building Emergency Generator taken off line due to metal components found inside the oil pan discovered during annual PM. Evidence that engines piston or bearings are failing & have begun to break down. Per code, Booster Fire pump system is required to be connected to E-power.	\$ 35,000	\$ 33,089	94.54



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
185	FM-0054826	Los Angeles	Santa Monica Courthouse	19-AP1	1	Grounds and Parking Lot - Replace inoperable gate operator w/ one (1) new gate operator, verify all connections & proper operation. The gate operator for the judges' parking lot exit gate is not operating and is beyond repair; operator needs to be replaced to avoid safety and security issues for judges.	\$ 10,132	\$ 7,953	78.49
186	FM-0054827	Humboldt	Humboldt County Courthouse (Eureka)	12-A1	2	Interior Finished - Encapsulation ACM flooring - Float floor where tiles are missing to the level of the remaining floor, install approx. 455 sq ft of floor covering and 80 lin ft of base to encapsulate this ACM flooring in Evidence room.	\$ 5,309	\$ 5,309	100
187	FM-0054828	Los Angeles	Santa Monica Courthouse	19-AP1	1	Plumbing - Water leaked from a galvanized domestic water supply line that runs behind the wall inside the employee men's restroom. Replaced 11 copper pipes and fittings, replaced 2x4 damaged section of wall. Set up 14x6x9 containment and 36x36x80 Decon. Set up drying equipment and performed environmental testing.	\$ 19,860	\$ 15,588	78.49
188	FM-0054829	Los Angeles	Chatsworth Courthouse	19-AY1	1	Plumbing - Dry & sanitize leak affected areas, perform environmental testing, replace approx. 10' of 3" cast iron drain line. A 3" cast iron drain line below the ceiling of the judges' enclosed parking lot has cracked causing approx. Five gallons of water to leak onto the parking structure floor.	\$ 9,850	\$ 9,850	100
189	FM-0054830	Los Angeles	Van Nuys Courthouse West	19-AX2	1	HVAC - Restore A/C to Machine Room. Rebuild the motor blower assembly and replace the shaft. The shaft broke and damaged the motor assembly. AHU 1-11 for Main Elevator Machine Room is not working and currently there is no cooling and the temperature is rising.	\$ 5,485	\$ 4,414	80.48
190	FM-0054834	Solano	Law And Justice Center	48-A2	2	HVAC - Variable Air Volume Box - Replace failed VAV for courtroom 207. Unit is temporarily operating on manual full volume setting; work to be performed during off hours on premium time.	\$ 6,592	\$ 6,592	100
191	FM-0054835	Alameda	Wiley W. Manuel Courthouse	01-B3	1	Plumbing - Water Leak - Replace failed toilet flush-o-meter components and local water supply isolation valve stem packing that were leaking in the jury deliberation room women's restroom. Extract water from floor coverings.	\$ 9,856	\$ 9,856	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
192	FM-0054838	Los Angeles	Compton Courthouse	19-AG1	2	Vandalism - Sand down 200 sq. ft. of marble stall walls and 50 sq. ft. wood entry doors to remove etched graffiti and apply sealer. Currently the stall marble walls have been vandalized by graffiti and etching. Also the entry wooden doors have etching and graffiti issues. This is safety concern since it could cause gang affiliated violence. Twelfth floor men's and women's public restrooms.	\$ 3,479	\$ 2,301	66.13
193	FM-0054839	Orange	Betty Lou Lamoreaux Justice Center	30-B1	2	HVAC - Variable Frequency Drive (VFD) - Remove and replace the existing 60 HP VFD for AHU #8 Supply Fan with a new ABB 60 HP VFD. The existing supply fan VFD caught fire and self-destructed. It is no longer functioning. The VFD controls the Supply Fan for AHU #8 and needs to be replaced to avoid disruption to operations and prolong the life of the equipment.	\$ 12,555	\$ 10,038	79.95
194	FM-0054840	Nevada	Nevada City Courthouse	29-A1	2	COUNTY MANAGED - Interior Finishes - Dividing wall between main entrance screening and exit is unstable (loose and wobbly) from patrons leaning across dividing wall. Remove existing 75"x40" dividing wall and replace with 75" x 90" wall with plexi-glass above 40" to prevent lean over going forward.	\$ 3,600	\$ 3,600	100
195	FM-0054841	Fresno	Fresno County Courthouse.	10-A1	2	Plumbing - Replace failed gaskets on the domestic hot water generator. Drain the water side of the system, shut off the steam side, disassemble the piping, remove the steam bundle, clean the flanges and install new gaskets, re-install the bundle, re-install steam piping, re-fill the tank, start and test the system for proper operation. The generator is leaking from the flanges due to failed gaskets.	\$ 2,411	\$ 2,312	95.91
196	FM-0054842	Los Angeles	Alfred J. McCourtney Juvenile Center	19-AE1	2	County Managed - Interior Finishes - Remove and replace 560 square feet of asbestos floor tiles. The floor tiles in the break room were broken and becoming a health and safety issue.	\$ 7,941	\$ 7,941	100
197	FM-0054843	Los Angeles	Pomona Courthouse South	19-W1	1	Elevators, Escalators, & Hoists - Replaced contactor on judges' elevator #6 to restore operations. Elevator was not responding and was stuck on the 4th floor with the doors closed, no entrapments.	\$ 3,693	\$ 3,366	91.14
198	FM-0054844	Los Angeles	Bellflower Courthouse	19-AL1	2	HVAC - Replace 300' of 3/0 THHN Conductor from MCC in main electrical room to Chiller #2. The main electrical conductors on Chiller #2 are currently burnt out completely and must be replaced so the chiller can operate properly.	\$ 6,517	\$ 5,079	77.94



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
199	FM-0054845	Los Angeles	Norwalk Courthouse	19-AK1	2	HVAC - Replace six (6) actuators, three (3) thermostats, three (3) reversing sensors, and 50 ft. of poly pneumatic tubing and verify operation. Currently the pneumatic VAV box controller is faulty causing inability to control temperature.	\$ 8,332	\$ 7,085	85.03
200	FM-0054846	Los Angeles	Metropolitan Courthouse	19-T1	2	Plumbing - Hydro jet 4" inch main drain to clear obstruction. This will allow waste drain water to flow freely and prevent any waste water to back-up into public sinks and urinals. 4" main drain riser has a restriction and is causing waste water to back-up into public sinks and urinals. Public health and safety issue.	\$ 4,357	\$ 4,119	94.54
201	FM-0054847	Los Angeles	Airport Courthouse	19-AU1	2	Plumbing - Remove and rebuild hot water pump #5, replace seals, clean couplings, and re-install with new fuses. Hot water pump #5 is currently leaking due to a bad seal and not running properly which is a safety hazard and a waste of energy.	\$ 3,079	\$ 2,376	77.17
202	FM-0054851	San Diego	Juvenile Court	37-E1	2	Fire Protection - Fire Safety Corrections Notice - Correct items #2, #3, & #5. Remove two (2) floor stops impeding proper operation of fire doors. Install 82 Lever Action Latch sets on doors in 1st & 2nd floors and 39 sets on doors located in 2nd floor DA Office. Install missing Smoke Seal Gaskets and Door Sweeps on 114 doors in various locations and on 10 doors in 2nd floor DA Office. Install six (6) combination security locks in specified locations. Install 22 missing Occupancy Load signs. (Ref FM ID 0054645).	\$ 105,693	\$ 78,868	74.62
203	FM-0054852	Los Angeles	Airport Courthouse	19-AU1	2	HVAC - Remove defective Variable Frequency Drive (VFD), install new VFD, and integrate the new VFD into the existing system. The VFD that controls air handler #1 motor has failed and the system will not come online unless it is in bypass mode; the VFD needs to be replaced so the motor does not run at full capacity when it doesn't need to.	\$ 18,175	\$ 14,026	77.17
204	FM-0054853	Los Angeles	Whittier Courthouse	19-AO1	2	HVAC - Rebuild Chiller Unit #1 - ACM testing required prior to rebuilding chiller unit #1. While performing the Level IV PM Chiller #1 was found to have refrigerant leaks, a defective shaft seal and the compressor windings were tripping. Work to include the replacement of the oil heater, shaft seal, condenser switch, coolant reservoir and coolant pump.	\$ 59,113	\$ 51,091	86.43
205	FM-0054855	Monterey	Salinas Courthouse-North Wing	27-A1	2	Elevator - Elevator #1 has a severely leaking oil seal and is losing hydraulic fluid. Repack the leaking seal and replace failed oil seal for hydraulic ram.	\$ 6,513	\$ 6,513	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
206	FM-0054856	Santa Clara	Downtown Superior Court	43-B1	2	HVAC - Replace two (2) failed 8" valves and bolt kits on condenser water loop that would not fully close to allow isolation.	\$ 10,404	\$ 10,404	100
207	FM-0054857	Solano	Hall of Justice	48-A1	2	Interior finishes - Cut an 18" x 36" notch in the top of the wall between the judge and the clerk in courtroom 103; The wall is 5" thick including 1/2" of Kevlar; Finish the edges of the opening with material from the cutout to assure a good match; Work to be done off-hours. Height of the bench wall between judge and clerk is too high and is causing difficulties and injuries to judge and clerk when passing/retrieving heavy case files. A work comp case has been filed.	\$ 7,536	\$ 7,536	100
208	FM-0054859	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Water remediation, environmental testing, dry leak affected area and clean up. Replace ceiling tile and replace leaking 3/4" supply line. One 1'x1' ceiling tile fell due to water damage, 3/4" supply line in ceiling is leaking and needs to be replaced. Leak damage is contained to the 18th floor secured hallway.	\$ 20,350	\$ 20,350	100
209	FM-0054860	Los Angeles	Metropolitan Courthouse	19-T1	2	Vandalism - Install new left door and rixson 27 offset arm. The existing hardware, pivots, and glass will be reused. The door was vandalized by an in-custody and must be replaced for the security of the courtroom.	\$ 4,325	\$ 4,089	94.54
210	FM-0054861	Los Angeles	Metropolitan Courthouse	19-T1	2	Grounds & Parking Lot - Install one (1) Omeron safety photo eye system and one (1) 20'L Miller electric safety edge. There are currently no safety features on the roll up gate in the employee parking lot which is a safety hazard and could cause damage to persons and property.	\$ 2,545	\$ 2,406	94.54
211	FM-0054862	San Bernardino	Barstow Courthouse	36-J1	2	HVAC - Replace leaking service port on refrigerant circuit 1A. This work is necessary as circuit 1A has lost a complete charge and has been locked-out leaving the chiller operating at 50% capacity. Deficiencies identified during the Level VIII PM for CH1 - SWO # 2462574.	\$ 3,882	\$ 3,025	77.93
212	FM-0054863	Alameda	Wiley W. Manuel Courthouse	01-B3	2	HVAC - Replace failed and leaking non-standard sized re-heat hot water coil to include ductwork transitions and heating hot water piping work.	\$ 9,625	\$ 8,066	83.8



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
213	FM-0054864	Orange	West Justice Center	30-D1	2	Plumbing - Complete remediation services required as a result of water damage in the Collections Department due to clogged drain in the 2nd floor mechanical room. Remediation effort included drying out all wet areas with fans and humidifiers, damaged wall and floor material replacement, cover base removal to ensure drywall thoroughly and professionally dried as well as ACM testing.	\$ 9,020	\$ 9,020	100
214	FM-0054865	Madera	Madera County Superior Court	20-A1	2	Security - Multiplexer-1 will be removed from the security system rack and taken into Pelco to have a new hard drive, power module, and mother board installed, once Multiplexer is back to normal operation it will be reinstalled and reprogrammed by tri-signal. Without Multiplexer-1 the security system is at 50% capability and in case of an emergency no footage can be reviewed.	\$ 5,018	\$ 5,018	100
215	FM-0054866	El Dorado	Main St. Courthouse	09-A1	2	HVAC - Restore Chiller Refrigeration system - replace hot gas bypass solenoid. Building needs cooling and chiller is main source of cooling for 09-A1 30 ton air cooled chiller. Chiller is currently shut down due to low refrigerant and off line. Chiller is used seasonally with main cooling season starting usually in May.	\$ 6,306	\$ 6,306	100
216	FM-0054868	Los Angeles	Torrance Courthouse	19-C1	2	HVAC - Replace defective 7.5HP motor (1), replace one (1) B-154 3-banded belt, replace one (1) motor pulley, and align all new parts. The cooling tower motor currently has a bad bearing causing excessive vibration and is beyond repair; if the motor goes out the cooling tower there will be only one motor to support all functions and could cause the cooling tower to malfunction.	\$ 4,708	\$ 4,008	85.14
217	FM-0054869	Solano	Hall of Justice	48-A1	2	Interior finishes - Replace failed VCT flooring in restroom to protect exposed wood subfloor from deterioration and to eliminate an unsanitary condition and an offensive odor due to exposure to liquids.	\$ 7,490	\$ 7,490	100
218	FM-0054870	Sacramento	Carol Miller Justice Center	34-D1	2	HVAC - Replace sump pump - Old sump pump stolen.	\$ 3,466	\$ 3,466	100
219	FM-0054871	Contra Costa	Arnason Justice Center	07-E3	2	Vandalism - Replace one master station, one slave station, and one power supply; Work to be done after hours. Interview phone is non functional after being vandalized.	\$ 2,196	\$ 2,196	100



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
220	FM-0054873	Los Angeles	Alhambra Courthouse	19-I1	2	HVAC - Install new refrigerant rated ball valves, remove oil line on bottom of oil separator, install new swaglock fitting and re-pipe oil line; remove, inspect, and re-attach linear float using new gaskets and O-rings; re-secure shading rings into armature with epoxy. Currently there is a leak on the bottom of the oil separator and oil is pooling up underneath the separator; also the epoxy which secures the shading rings into the stationary armature is cracked and could cause a no-start condition.	\$ 13,777	\$ 11,848	86
221	FM-0054875	Sacramento	Carol Miller Justice Center	34-D1	2	HVAC - Chiller #1 not running - Remove and replace two failed sump heaters, the chiller will not run without heaters.	\$ 2,397	\$ 2,397	100
222	FM-0054876	San Joaquin	Manteca Branch Court	39-C1	2	Interior Finishes - Replace failed flooring in main lobby (chipped epoxy over bare concrete is creating trip hazards in public lobby) with 1,300ft of rubberized floor tile.	\$ 17,963	\$ 17,963	100
223	FM-0054877	Contra Costa	George D. Carroll Courthouse	07-F1	2	Grounds and Parking Lot - Install 125 lf of 6' galvanized fencing to separate the public and court employee parking; Install two new posts with signs indicating restricted parking. The court is concerned about the existing parking. A car was stolen and a car was broken into. This is a security issue and the work is recommended by OERS.	\$ 9,321	\$ 9,321	100
224	FM-0054879	Los Angeles	Inglewood Courthouse	19-F1	2	Elevators, Escalators, & Hoists - Replace ropes on Elevator #3. Install 1,100 feet of new rope, replace five shackles. Existing elevator ropes are worn and damaged. This is a safety issue and the inspector will take elevator out of service if ropes are not replaced.	\$ 38,079	\$ 28,391	74.56
225	FM-0054881	Los Angeles	Chatsworth Courthouse	19-AY1	2	Electrical – Code required lighting - Install power and lights for twelve lighting fixtures with wire guards. Currently the lighting lumens do not meet the code requirements for file storage and puts staff at risk. Family law has relocated to Chatsworth court due to court's ongoing restructuring plan and with this comes the need to relocate the existing files as well.	\$ 20,000	\$ 20,000	100
226	FM-0054882	Los Angeles	Metropolitan Courthouse	19-T1	2	HVAC - Heating Hot Water & Chilled Water Copper pipes between Main isolation & Control valves on floors 3, 5 & 8 are corroding, leaking and deteriorating. Existing isolation valves are non-functional and the building must be drained prior to replacement. Remove/replace 300ft of copper piping, install 12 Isolation Valves, six (6) Control Valves, 12 Balancing Valves, 12 Temperature Gauges & 12 Pressure Gauges.	\$ 183,490	\$ 173,471	94.54



#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
227	FM-0054883	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	HVAC - Remediation, set up containment, environmental testing, abate ACM pipe insulation from the hot water pipe to access the leak. Replace deteriorated 1 1/4" steel pipe, restore frozen isolation valves. AHU 6-3 has a deteriorated 1 1/4" steel pipe and is leaking hot water in the 6th floor air handler room. The leak has been contained and water is being directed into the floor drain. Both 1 1/4" isolation valves are frozen and will not shut off the leak.	\$ 30,000	\$ 30,000	100
228	FM-0054884	Los Angeles	Inglewood Courthouse	19-F1	2	Elevators, Escalators, & Hoists - Replace defective selector switches and LV ring, re-wire incorrect wiring in compound on generator, and adjust selector. Elevator #3 is stuck on the 4th floor with the doors closed and is not responding; this was caused by a broken selector switch and bad wiring in compound on generator.	\$ 4,746	\$ 3,539	74.56
229	FM-0054885	Los Angeles	San Fernando Courthouse	19-AC1	2	Fire Protection - Replace all 12v failed system batteries, test multiple devices to determine cause of failure, and restore all failed system devices to return active fire monitoring to the building. The fire system is not currently functioning properly due to old batteries, outdated components, and failing devices; system needs to be restored so it can properly monitor the building for fire hazards. Deficiencies found on PM SWO# 2486061.	\$ 4,655	\$ 3,883	83.41
230	FM-0054886	San Joaquin	Lodi Branch - Dept. 2	39-D2	2	HVAC - Replace faulty components of failed Variable Frequency Drive Unit for Air Handler. Asset: OM#00028026	\$ 2,344	\$ 2,344	100
231	FM-0054887	Los Angeles	Airport Courthouse	19-AU1	2	Fire Protection - Replace one (1) 6" butterfly valve downstream of fire pump. The 6" butterfly valve that is downstream of the fire pump is leaking and needs to be replaced in order to prevent further damage and possible safety hazards.	\$ 3,777	\$ 2,915	77.17
232	FM-0054888	Orange	Central Justice Center	30-A1	2	HVAC - Replace duct work located in Sheriff Bus bay damaged by a bus. System supplies sheriff and in custody areas with air conditioning. The project will include control air to repair 8 foot length of duct and place reducing duct work to allow for buses into bus bay without compromising air flow.	\$ 5,498	\$ 5,013	91.17
233	FM-0054889	Los Angeles	Van Nuys Courthouse East	19-AX1	2	Vandalism - Install approx. 274 sq. ft. of 6 mil metal shield film over stainless steel in elevators to cover existing vandalism and prevent further damage. Public elevators 1-4 have deep scratches and scuffs on the stainless steel walls and doors which is a safety concern for the public.	\$ 4,799	\$ 4,307	89.74



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
234	FM-0054890	Orange	North Justice Center	30-C1	2	HVAC - The Magnetic Starter for Return Fan #2 for the HVAC system in Phase II is failing. Replace Magnetic Starter with a 7.5 HP ABB Variable Frequency Drive (VFD). Energy Project eligible for rebate through So Cal Edison Rebate Program.	\$ 5,277	\$ 4,766	90.31
235	FM-0054891	Orange	North Justice Center	30-C1	2	HVAC - The Magnetic Starter for Return Fan #1 for the HVAC system in Phase II is failing. Replace Magnetic Starter with a 7.5 HP ABB Variable Frequency Drive (VFD). Energy Project eligible for rebate through So Cal Edison Rebate Program.	\$ 5,210	\$ 4,705	90.31
236	FM-0054893	Contra Costa	George D. Carroll Courthouse	07-F1	2	HVAC Install two (2) Base Mounted Pumps with 2 HP, Premium Efficient, 208-230/460/3/60 Motors; Install two (2) 2" butterfly valves and new 2"x2" suction diffusers on inlet of each hot water pump; Install two (2) 1-1/2"x2" increaser and 2" triple duty valves on outlet of each hot water pump. Pump #2 has failed and the primary pump is running hot. If it fails, we will not be able to deliver hot water to the heating coils.	\$ 18,013	\$ 13,508	74.99
237	FM-0054894	Los Angeles	Stanley Mosk Courthouse	19-K1	2	Elevators, Escalators, & Hoists - Replace two steps, manufacture and install a new up-thrust track to escalator 8-7. Currently the escalator is out of service to prevent further damage and to prevent passengers from falling into the rotating machinery.	\$ 8,327	\$ 8,099	97.26
238	FM-0054895	Los Angeles	Stanley Mosk Courthouse	19-K1	2	HVAC - Replace supply fan motor with new 7.5 horsepower motor. The supply fan motor that is currently supporting AHU S-21 is not running properly and is near the end of its life cycle. if the motor fails the air handler unit will not be able to provide proper temperatures during courtroom operations.	\$ 4,555	\$ 4,430	97.26
239	FM-0054896	San Diego	East County Regional Center	37-I1	2	Elevators, Escalators, & Hoists - Replaced elevator controller module, adjusted SSDI and compounded elevator. Elevator #3 was having leveling issues on all floors, causing a tripping hazard. Elevator doors were opening too slowly for the passengers.	\$ 2,697	\$ 1,826	67.71
240	FM-0054899	Los Angeles	Airport Courthouse	19-AU1	2	Interior Finishes - Install six (6) new door magnets and holders and one (1) control relay; connect to existing circuit so doors release on alarm condition. Location: 1st floor - entering the cafeteria - two sets of doors. Basement - Corridor hallway on the north side. The doors are currently being held open manually and are not integrated with the fire system which is a safety and security issue.	\$ 11,722	\$ 9,046	77.17



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
241	FM-0054901	Los Angeles	Edmund D. Edelman Children's Court	19-Q1	2	Vandalism - Grind and polish elevator panels and doors, install 10 door alarms to prevent public access to stairwells, and install 120 corner guards on walls to prevent further damage. There is currently graffiti scratched into stainless steel elevators, vandalism in the public stairwells, and damage from carts and strollers on the corners of multiple walls in the public hallways, all of which could cause safety concerns for the public.	\$ 13,200	\$ 9,239	69.99
242	FM-0054902	Los Angeles	Airport Courthouse	19-AU1	2	HVAC - Perform modifications including: Rebuild isolation block, replace oil regulator gasket, 2 bolt flange gasket, refrigerant o-ring, rod spindle, plug pipe, screw spring plunger, purge liquid line isolation valve, two (2) 3/8 elbows, and a defective control keypad panel assembly; check all controls, settings, alignments, and restore operation. Chiller #1 currently has several leaks within the system and is taking in air and moisture which can damage components and lead to environmental hazards.	\$ 21,950	\$ 16,939	77.17
243	FM-0054903	San Bernardino	Victorville Courthouse- Dept. N-1	36-L1	2	COUNTY MANAGED - HVAC- Replace one (1) Air Handler Unit and related systems that has failed. Scope includes removal and installation of units from the roof, modifying mounting curb, electrical, new gas and condensate pipes and air balance. The existing unit is of age, parts are obsolete and are no longer available from the manufacturer.	\$ 149,703	\$ 149,703	100
244	FM-0054904	San Diego	East County Regional Center	37-I1	2	Plumbing - Replace existing domestic booster pump system with new Grundfos Domestic Water Booster Pump Package. Existing booster pump system has only two operational pumps with one pump currently inoperable due to failed controller. Existing pump system has experienced frequent failures and needs to be replaced as it is critical in providing domestic water to the upper floors.	\$ 98,201	\$ 66,492	67.71
245	FM-0054909	Los Angeles	El Monte Courthouse	19-O1	1	Elevators, Escalators, & Hoists - Replace failed brakes on judges' Elevator #5. Rebuild brake assembly with new parts at offsite facility. Return assembly to site and install in elevator. Judges' elevator was stuck in the basement with doors closed and not responding due to a faulty brake assembly.	\$ 28,555	\$ 16,596	58.12



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
246	FM-0054914	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	HVAC - Install one (1) 5" diameter x 4" long sleeve onto the shaft of the air handler unit and install one (1) new bearing. A malfunctioning bearing has cut a groove into the shaft of air handler unit #8-4 which is causing excessive vibration; the air handler unit has been placed out of service so no further damage will be caused.	\$ 6,000	\$ 4,127	68.79
247	FM-0054915	Los Angeles	Hall of Records-County Records Center	19-AV3	1	COUNTY MANAGED - Plumbing - 8" fire sprinkler supply line ruptured causing flooding in areas on the 2nd and 3rd floors. Installation of new 8" water line approx. 180 feet in length.	\$ 78,000	\$ 72,540	93
248	FM-0054916	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Floor drain in the 10th floor mechanical room - Set up containment & drying equipment, perform environmental testing, snake floor drain to remove clog, dry leak affected areas, replace approx. five (5) ceiling tiles, perform final clean & clearance testing. The floor drain in the 10th floor mechanical room is clogged causing a flood which leaked into the 9th floor court reporters office room. 9-101; multiple ceiling tiles are damaged & have collapsed to the floor, walls & floor have high moisture levels.	\$ 20,000	\$ 20,000	100
249	FM-0054917	Los Angeles	Clara Shortridge Foltz Criminal Justice Center	19-L1	1	Plumbing - Floor drain in the 8th floor mechanical room - Set up containment & drying equipment, perform environmental testing, snake floor drain to remove clog, dry leak affected areas, replace approx. three (3) 12" x 48" ceiling tiles and twelve (12) 12" x 12" ceiling tiles, perform final clean and clearance testing. The floor drain in the 8th floor mechanical room is clogged causing a flood which leaked into the 7th floor court reporters office room. 7-101; multiple ceiling tiles are damaged and have collapsed to the floor; walls have high moisture levels.	\$ 20,000	\$ 20,000	100
250	FM-0054925	Los Angeles	East Los Angeles Courthouse	19-V1	1	HVAC - Replace a faulty heating control valve (1/2 in. brass valve w/ pneumatic actuator) that leaked hot water above room #301G. The heating control valve serves a HVAC VAV box. Containment size is 7ft. W x 8ft. L x 8ft. H in room #301G. The water damaged three (3) ceiling tiles (24 in. x 24 in. x 5/8 in.). An environmental survey was performed in the leak affected area.	\$ 5,889	\$ 4,577	77.72



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment A

TCFMAC Funded Project List
Quarter 4, Fiscal Year 2014-2015

#	FM NUMBER	LOCATION	FACILITY NAME	BUILDING ID	PRIORITY	SHORT TITLE	PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE OF PRELIMINARY ESTIMATE	FACILITY MODIFICATION PROGRAM SHARE % OF COST
251	FM-0054952	Tulare	Visalia Superior Court	54-A1	2	Interior Finishes – Remove all 336 audience chairs in Depts 3, 4, 5, and 6. Remove and abate a total of 2400 sf of vinyl tile flooring and install new vinyl tile flooring. Install 48 new wooden bench seating 12 each x 13 ft long - Existing chairs are failing, beyond repair and have broken upon use. Eight chairs in Dept. 5 are unusable as are several more. This is a safety risk to the public as additional chairs can break at any time causing physical injury.	\$ 225,000	\$ 225,000	100
252	FM-0054954	Santa Cruz	Santa Cruz Jury	44-A3	2	Exterior Shell - Replace failed (2300 SF), leaking roof, (380 SF) deteriorated canopy, (50 LF) rotted gutter, (400 SF) of dry rot deck, (2800 SF) dry rot wooden exterior siding walls, (176 LF) deteriorated leaking window panes. The structure is currently leaking and several areas of the wood deck is rotted creating a structurally unsafe condition.	\$ 225,000	\$ 225,000	100
253	FM-0054955	Los Angeles	Torrance Courthouse	19-C1	2	HVAC - Perform Overhaul on Chiller #2. During Level VIII PM 2462673 on Chiller #2 several refrigerant leaks were found. Refrigerant analysis came back with "High" levels of oil in the refrigerant. Vibration analysis concluded that the chiller motor bearings are in a state of deterioration and a complete unit overhaul is needed.	\$ 116,111	\$ 98,857	85.14
254	FM-0054880	Sacramento	Gordon Schaber Sacramento Superior Court	34-A1	3	Electrical - Remove a total of 5,092 T8 fluorescent lamps and replace them with LED lamps in: (550) single lamp fixtures; (4388) dual lamp fixtures; and (153) 3 lamp fixtures. Replaces 200 aging instant start Ballast - Project will significantly reduce energy consumption and heat load throughout the facility.	\$ 180,000	\$ 180,000	100
							\$ 7,794,202	\$ 6,761,502	



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Attachment B

Court-Funded Facilities Requests (CFR)
Quarter 4, Fiscal Year 2014-2015

ITEM #	CFR NUMBER	COUNTY	BUILDING ID	FACILITY NAME	LEASE, LICENSE, OR FM	REQUEST TYPE	CFR DESCRIPTION	CFR TERM	FUND SOURCE	ESTIMATED CURRENT YEAR COSTS (Includes existing costs prior to CFR term)	ESTIMATED BUDGET YEAR COSTS	TOTAL ESTIMATED CFR COMMITMENT (CFR Term)	REVIEW NOTES - OREFM, JBCPO, & FSO
1	54-CFR009	Tulare	54-J1	Visalia Convention Center	Lease Extension	Ongoing	Lease extension 9/2/15 through 9/27/17 for Traffic Court one day a week.	Two Years	TCTF	\$ -00	\$ 10,888	\$ 21,146	Pending
2	19-CFR031	Los Angeles	TBD	312 N. Spring St. Parking Lot	New Lease	Ongoing	New five-year lease (2018-2023) for 31 parking spaces to support parking needs for Judicial Officers and Court Administration. Option for a second five-year term lease is anticipated to begin in 2023 and end in 2028. The cost also includes utilities overtime, security background checks, building access cards, and additional cameras and card readers.	Five Years	TCTF	\$ -00	\$ 109,520	\$ 547,602	Pending



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Action Item 9 – (Action Required) – Policy on Art Acquisition for Court Facilities

Summary:

Review and discuss draft *Judicial Council Policy on Art Acquisition for Court Facilities*

Supporting Documentation:

- *Judicial Council Policy on Art Acquisition for Court Facilities*

Action Requested:

Review and approve policy for adoption by Judicial Council.

This page intentionally left blank

Action Item 9
Policy on Art Acquisition for
Court Facilities

- Purpose & Scope
 - Section 1
- Art Acquisition
 - Section 4.3-4.4 & Section 4.1
- Approval of Art
 - Section 5

Action Item 9
Policy on Art Acquisition for
Court Facilities

- Reviewing Committees:
 - TCPJAC/CEAC Joint Court Facilities Advisory Committee – 7-1-15
 - CFAC – 7-16-15
 - FPWG – 7-21-15
- Targeted for Council Meeting – July 28
- Recommendation:
Approve for release to Judicial Council



Judicial Council Policy on Art Acquisition for Court Facilities

JULY 06, 2015 DRAFT

1. Purpose and Scope of the Policy

This policy is intended to guide Judicial Council of California (Judicial Council or council) staff in acquiring art on behalf of the council for the council's capital projects and for both appellate and trial court facilities that the council manages. (The council will not acquire art for county-managed court facilities or for court facilities that are leased to non-court occupants.)

This policy does not apply to art that an individual court may acquire, unless the art will be affixed to a court facility. (Only the Judicial Council may acquire art that will be affixed to a court facility because, once affixed, the art becomes part of the court facility and a council responsibility.)¹

2. Goals and Principles Guiding Acquisition of Art

Incorporating art into court facilities is intended to improve the experience of all court users and court personnel, consistent with the design excellence principles that the Judicial Council has adopted for court facilities.²

3. Definitions

- 3.1. Acquire/Acquisition: To purchase or accept as a donation works of art for court facilities.
- 3.2. Affix: To attach, add to, or fasten on permanently, as a permanent fixture.³
- 3.3. Art: A decorative or creative element to be added to the exterior or interior spaces of a newly constructed or existing court facility. (The term does not include provision for decorative or creative elements in an approved architectural design.)
- 3.4. Capital Project: New courthouse construction and major renovations or expansions to existing court facilities.
- 3.5. Court Facility: The definition provided in Government Code section 70301(d) is incorporated by reference. The term "courthouse" is an alternative and may be used interchangeably.

4. Acquisition of Art

- 4.1. Funds appropriated in the state budget act for courthouse construction, maintenance and repair may not be used to acquire art.
- 4.2. The Judicial Council may acquire art for court facilities that it manages, through private gifts (either of art or of funding for the purchase of art), provided that acceptance of such gifts and any resulting displays, will not create an appearance of impropriety.⁴

¹ Gov. Code, §§ 70301(d)(4), 70391.

² See Judicial Council of Cal., *California Trial Court Facilities Standards* (2010); Judicial Council of Cal., *Appellate Court Facilities Guidelines* (2002).

³ See Black's Law Dict. (7th ed. 1999), p. 60, col. 2 (defining "affix"); *id.*, at p. 652, col. 1 (defining "fixture").

⁴ See, e.g., *Trial Court Financial Policies and Procedures Manual* (7th ed. 2010) FIN 15.01, 6.2.2., para. 3, at p. 7 (A superior court should not accept a gift if the gift is conditioned on the court's "use or display the prospective

- 4.3. Only the Judicial Council may accept a gift of art to be affixed to a court facility. The Administrative Director may accept such gifts on behalf of the Judicial Council, as provided in rule 10.102 of the California Rules of Court, subject to paragraph 5, below.
- 4.4. Acceptance on behalf of the Judicial Council of a gift of art or funds for art from a donor who appears before or is reasonably likely to appear before the receiving court in litigation, or does or seeks to do business with the receiving court, must be conditioned on an understanding that (i) donor names and amounts will not be disclosed to the court receiving the art, and (ii) the donor's name will not be publicly displayed or otherwise publicly acknowledged.⁵

5. Approval of Art

The receiving court and the Administrative Director must both approve art that the Judicial Council acquires under this policy and any art to be affixed to a court facility.

6. Questions Regarding Acquisition, Ownership, Reproduction, or Installation of Art

Judicial Council legal staff is available to assist with any issues regarding acquisition of art (e.g. contracts to commission or purchase art) or regarding intellectual property (e.g., ownership rights and reproduction of art). Judicial Council facilities staff also is available to assist with the installation of art that is to be affixed to a court facility.

donor's name or logo"); see also Cal. Rules of Court, rule 10.102(b)(1) (Pursuant to delegation of authority from the Administrative Director of the Courts, a superior court executive officer may accept a gift for the court); Cal. Code Judicial Ethics, canon 4D(6) (limiting the ability of judges to accept gifts).

⁵ See, e.g., *Trial Court Financial Policies and Procedures Manual*, *supra*, FIN 15.01, 6.2.2, para. 4, at p. 7 (A superior court should not accept a gift if the "prospective donor currently is, or is reasonably likely to come, before the court in litigation, either as a party or attorney").



JUDICIAL COUNCIL
OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

**Action Item 10 – (Action Required) – Budget Change
Proposals for FY 2016-2017**

Summary:

Review and discuss five proposed Budget Change Proposals for FY 2016-2017

1. *Operations and Maintenance, Facility Modifications, and New Construction*
2. *Trial Court Security System Maintenance, Replacement and Improvements*
3. *Trial Court Facilities-Risk Management Program*
4. *Los Angeles Superior Court - Antelope Valley Juvenile Court Facility Modifications*
5. *Green Pilot Projects*

Supporting Documentation:

- BCP Concept documents

Action Requested:

Approve BCPs to move forward to August Judicial Council meeting.

Action Item 10-1 (BCP)

O&M, FM, New Construction

Support Function	Funding	Additional Funding Requested	Percentage of Growth	Additional FTE Required
Routine Maintenance	\$37.2M	\$27.6M	71%	4 (GF Funded)
New Facilities		\$12.4M		
Facility Modifications	\$65M	\$12M	18%	4 (GF Funded)

- Brings O&M to BOMA standard
- Brings FM to 2% Capital Reinvestment

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Pat McGrath/Angela Guzman

I. Facilities Operations Costs Adjustment

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
General Fund transfer to Court Facilities Trust Fund	4.0	\$475,000	\$27,130,000	\$27,605,000

II. Nature of Request/Problem

Senate Bill (SB) 1732 (Ch. 1082, Stats. 2002), the Trial Court Facilities Act of 2002, provided for the transfer of court facilities from the counties to the state and also stipulated that the counties provide a County Facility Payment (CFP) based on the historical costs of operating each transferred facility. The historical costs of operating each facility were based on costs for years from 1996 to 2000 inflated to the date of transfer.

Further the CFP was not intended to provide for inflationary cost increases beyond the date of transfer. SB 1732 states that “ongoing operations and maintenance of court facilities that are in excess of the county facility payment be provided by the state”. In recognition of the intent of the legislation, AB 1806, was enacted in 2006 and authorizes a cost of living increase against the CFP from the General Fund. The increase is based on the state appropriations limit (SAL) year-to-year-percentage change. Due to the State’s General Fund shortfall, the SAL adjustment was suspended for FY 2009–2010 and to date, has not been reinstated. This has required the Judicial Council to absorb facility operating costs increases through existing resources, diverting discretionary funding to address mandatory cost increases for items such as rent and utilities.

In addition, the CFPs based on the historical costs of operating each facility are not sufficient to maintain court facilities at the Building Owners and Managers Association (BOMA) industry standard. This, in addition to the continued erosion of maintenance funding to fund other cost increases, has led to increased degradation of court facilities.

CFPs are deposited into the Court Facilities Trust Fund (CFTF), and provide the major resources to fund trial court facility operations. If funding to support the inflationary cost increases and to maintain facilities at the BOMA average is not approved, non-mandatory services will continue to be reduced. Because there is little flexibility in reducing utilities or lease payments, operations and

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Pat McGrath/Angela Guzman

maintenance costs are impacted when other mandatory cost increases are incurred without concurrent funding increases.

III. Proposed Solution

Real Estate and Facilities Management (REFM) proposes an ongoing baseline adjustment of \$27.605 million from the General Fund for transfer to the CFTF, which includes \$27 million for operations and maintenance and \$605,000 to fund 4.0 positions, in order to maintain trial court facilities at industry standard levels using the Building Owners and Managers Association (BOMA) average. Based on the BOMA average cost/SF for calendar year 2013, the JC would need \$66 million annually to support the costs of maintaining the current portfolio. The current budget for routine maintenance is \$39 million which leaves a shortfall of \$27 million. The additional funds will augment the CFPs provided by the county and will provide ongoing necessary resources to maintain facility services at a recommended industry standard level of care.

IV. Alternative Solutions

Alternative #1: Provide an augmentation of \$12 million from the General Fund to support inflationary cost increases for facility operating costs, based on the total State Appropriations Limit (SAL) funding that would have been provided to the CFTF had the SAL adjustment not been suspended. This alternative was not recommended because it would not fully address the maintenance needs of the trial court facilities as it will not allow the REFM to maintain facilities to the BOMA average cost. Subsequently this will increase the existing backlog of facility modification projects and will result in continued degradation of court facilities statewide resulting in increased disruption of court services.

Alternative #2: Provide an augmentation of \$5.4 million from the General Fund to support inflationary cost increases for facility operating costs, based on the FY 2014-15 price letter adjustment. This alternative was not recommended because it would not fully address the maintenance needs of the trial court facilities as it will not allow the REFM to maintain facilities to the BOMA average cost. Subsequently this will increase the existing backlog of facility modification projects and will result in continued degradation of court facilities statewide resulting in increased disruption of court services.

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Pat McGrath/Angela Guzman

V. Other Considerations

Due to the previously known lack of inflationary cost adjustments, the Judicial Council opted to negotiate the Service Provider contracts that held the costs to a fixed price for 5 years. Since that period has ended the Judicial Council will have to reduce services to address the full inflationary adjustment and will have to absorb cost increases in the contract annually.

Government Code 70351 states that, "it is further the intent of the Legislature that funding for the ongoing operations and maintenance of court facilities that are in excess of the county facilities payments be provided by the state."

This proposal directly supports Goals II, VI and VII of the Judicial Council's Long-Range Strategic Plan, as follows:

Goal II, Independence and Accountability states, "the judicial branch must also exercise its constitutional and statutory authority and responsibility to plan for direct, monitor, and support the business of the branch and to account to the public for, the branch's performance." Securing sufficient resources to ensure accessible, safe, and efficient facilities for the public directly addresses this goal.

Goal VI, Branch-wide Infrastructure for Service Excellence states "Infrastructure improvements needed to better serve the public include (1) acquisition, construction, renovation, and maintenance of adequate facilities". This goal seeks to provide fully functional facilities that are safe and secure for conducting court business for all court users.

Goal VII, Adequate, Stable, and Predictable Funding for a Fully Functioning Branch. Consistent with the Judicial Council's legislative priority to advocate for investment in our justice system to preserve access to justice for all Californians, the branch must continue advocacy for sufficient fund balances allowing courts to manage cash flow challenges, a method for stable and reliable growth funding for courts to address annual cost increases in baseline operations, and sufficient additional resources to allow courts to (1) improve physical access to the courts by keeping courts open, (2) expand access by increasing the ability of court users to conduct branch business online, and (3) restore programs and services that were reduced or eliminated in recent years.

In addition, the CFTF funded by the CFP has not received inflationary adjustments on CFP since 2009 while costs have continued to increase, eroding the Judicial Council's ability to provide an adequate level of service to the portfolio.

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management
Contact: Patrick McGrath/Angela Guzman

I. Trial Court Facilities Modification Program Augmentation

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
General Fund	4.0	\$610,000	\$12,000,000	\$12,610,000

II. Nature of Request/Problem

Under the Lockyer-Isenberg Trial Court Funding Act of 1997, Assembly Bill (AB) 233 (Chapter 850, Statutes of 1997), funding of trial court operations became a state responsibility. AB 233 also created the Task Force on Court Facilities (Task Force) charged to review and report on the status of court facilities throughout the state, and to make recommendations as to which government entity should be responsible for funding and managing court facility construction and maintenance. The Task Force submitted its final report to the Legislature and Governor in October 2001 with the recommendation that the state assume full responsibility for all the state's court facilities.

The Task Force report identified widespread and serious problems of inadequate security, safety, and access for the disabled in the courts, and further found that a significant number of state court buildings are in need of repair, renovation, or maintenance.

Based on the most recent assessment of the trial court facilities there are a total of 2,887 deferred maintenance needs with an estimated cost of \$1.7 billion.

III. Proposed Solution

The Judicial Council proposes an ongoing appropriation from the General Fund for transfer to the State Court Facilities Construction Fund (SCFCF) in the amount of \$12.610 million, \$12.0 million for Facility Modifications and \$0.610 million to fund 4.0 positions to ensure timely facility modification project implementation. Based on the minimum industry standard for capital infrastructure reinvestment of two percent and the estimated trial court portfolio replacement cost of \$3.9 billion, there is a total reinvestment need of \$77.0 million annually (not including reimbursements). In fiscal year (FY) 2014-2015 funding for facility modifications increased \$15.0 million; resulting in a total investment in trial court modifications of \$65.0 million. Even with this increase there is a current funding shortfall of \$12.0 million. The requested funding will assist in reducing the deferred maintenance on the states facilities by addressing major repairs, system life-cycle replacements, and renovation projects in existing courthouses to provide safe and secure facilities for the benefit of all court users.

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

IV. Alternative Solutions

1. Alternative #1:

Approve augmentation from the General Fund in the amount of \$6.325 million annually, \$6.0 million for facility modification projects and \$.325 million for 2.0 positions to support project implementation and timely execution.

Pros:

- Provides some level of additional funding for the Facility Modification Program to address some of the backlog of facility assessments and projects that will assist in achieving the goals and objectives of the Judicial Council and the operations of the courts. Partially reduces the deferred maintenance on court facilities and provides additional assurance that court facilities will meet citizen and court needs.
- Less impact to General Fund
- Partially improves the organizations ability to promptly and cost effectively rectify facility security, life-safety, and accessibility problems.
- Provides a portion of the essential staff to support the increased funding for facility modifications. Provides some resources to process facility modification requests address the backlog of facility modifications and better meet the needs of the public and courts.

Cons:

- Does not allow the Judicial Council to address the full capital reinvestment need and facilities will continue to degrade impacting court operations.
- Does not fully address the unfunded backlog of facility modification projects and does not address the deferred maintenance of court facilities.

2. Alternative #2:

Approve augmentation from the General Fund in the amount of \$9.468 million annually, \$9.0 million for facility modification projects and \$0.468 million for 3.0 positions to support project implementation and timely execution.

Pros:

- Provides a higher level of additional funding for the Facility Modification Program to address more of the backlog of facility assessments and projects that will assist in achieving the goals and objectives of the Judicial Council and the operations of the courts. May allow for some priority 3 modifications to begin. Partially reduces the deferred maintenance on court facilities and provides additional assurance that court facilities will begin to meet the core element of implementing physical, remote and equal access for all Californian's.
-

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

- Less impact to General Fund
- Temporarily minimizes duration of exposure to liabilities due to existing court facilities' current state of disrepair.
- Enables the Judicial Council's ability to promptly and cost effectively address more problems related to inadequate security, lack of space for jurors, access problems for people with disabilities, structural issues, and safety.
- Provides most of the essential staff to support the increased funding for facility modifications. Provides the resources to process facility modification requests and address the backlog of facility modifications and better meet the needs of the public and courts.

Cons:

- Does not allow the Judicial Council to address the full capital reinvestment need and facilities will continue to degrade impacting court operations.
- Does not fully address the unfunded backlog of facility modification projects and does not address the deferred maintenance of court facilities.

V. Other Considerations

In order to meet the needs and ensure safety of the public and courts, it is imperative the Judicial Council have adequate funding to restore or improve the safety, security, and operations of court facilities. This proposal will continue the implementation of the mandates of the Act; to fulfill our responsibility to the state's courthouses and to have responsibility for both operations and facilities management, thus ensuring that all costs are considered when decisions are made, and further ensuring economical, efficient, and effective court operations. The proposal supports the Judicial Council's Strategic Plan.

Support of the Judicial Council's Long Range Strategic Plan

Goals I, II, VI and VII of the Judicial Council's Long-Range Strategic Plan directly support this proposal.

Goal I, Access, Fairness and Diversity states "all persons will have equal access to the court and court proceedings and programs." This proposal supports funding to ensure court users have access to the trial court facilities.

Goal II, Independence and Accountability states, "the judicial branch must also exercise its constitutional and statutory authority and responsibility to plan for, direct, monitor, and support the business of the branch and to account to the public for the branch's performance." Securing sufficient resources to ensure accessible, safe, and efficient facilities for the public directly addresses this goal.

Goal VI, Branch wide Infrastructure for Service Excellence states "Infrastructure improvements needed to better serve the public include (1) acquisition, construction, renovation, and

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

maintenance of adequate facilities.” This goal seeks to provide fully functional facilities that are safe and secure for conducting court business for all court users.

Goal VII, Consistent with the Judicial Council’s legislative priority to advocate for investment in our justice system to preserve access to justice for all Californians, the branch must make every effort to achieve greater financial independence and flexibility for funding the court system at a level of sufficiency.

Furthermore the Legislative Analyst’s Office (LAO) recently addressed deferred maintenance in its review of the FY 2015-16 Governors deferred maintenance proposal and identified the importance of the state addressing its substantial deferred maintenance backlog in its statement, “... while deferring annual maintenance lowers costs in the short run, it often results in substantial costs in the long run.”

In alignment with the LAO opinion the State-5 Year Infrastructure Plan addresses deferred maintenance stating, “Properly maintaining state facilities ensures the longest useful life of the facilities and reduces the need to build new facilities.” It goes on and says, “Deferring routine maintenance can lead to facility deterioration-and ultimately failure-and sometimes the need to replace the facility sooner than otherwise would have been required if properly maintained. Deferred maintenance can be costly and a threat to public safety if facilities become unsafe.”

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

I. Increased Operations Costs for New/Renovated Trial Court Facilities

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
General Fund transfer to Court Facilities Trust Fund			\$12,409,000	\$12,409,000
			(FY16-17)	(FY16-17)
			\$12,150,000 (FY17-18-Ongoing)	\$12,150,000 (FY17-18-Ongoing)

II. Nature of Request/Problem

Senate Bill (SB) 1732, the Trial Court Facilities Act of 2002 (Stats. 2002, Ch. 1082), provided for the transfer of court facilities from the counties to the state and requires counties to make quarterly remittance to the state, on a perpetual basis in the form of a county facility payment (CFP) based on the historical costs of operating the existing facility(ies). SB 1732 was based on findings and recommendations made by the Task Force on Court Facilities (Task Force), an 18-member task force established by the Trial Court Funding Act of 1997 (Assembly Bill 233, Chapter 850, Statutes of 1997) to identify trial and appellate court facilities needs; identify options and recommendations for funding court facility maintenance, improvements, and expansion; and recommend the division of responsibilities amongst the various government entities.

Beginning with the 2005 Budget Act the Capital Outlay projects listed below were authorized to be completed with funding from the State Court Facilities Construction Fund (SCFCF) and the Immediate and Critical Needs Account (ICNA). The projects will replace outdated, deficient, buildings and create increased square footage for crowded courts.

Existing facilities that will be vacated as a result of the construction of new facilities will contribute their CFP toward the operating expenses of the new facility. However, the CFP for those facilities is not sufficient to maintain the new facilities at a level that will allow the Judicial Council to prevent deterioration and preserve state assets.

III. Proposed Solution

The Office of Real Estate and Facilities Management proposes a transfer of \$12,409,000 in FY16-17 and ongoing transfer of \$12,150,000 from the General Fund to the Court Facilities

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

Trust Fund to address the increased facility operating costs for 22 newly constructed or renovated facilities.

The requested funding will be used to maintain the new facilities at a recommended industry standard level [Building Owners and Managers Association (BOMA)] that will prevent deterioration and preserve state assets.

If this request is not approved the Judicial Council will be required to continue to absorb these facility operating costs increases through existing resources, depleting the CFP that should have been available to fund operating expenses at other facilities.

New Courthouse Project	Project ID	Occupancy Date	Square Footage Increase	Amount Requested
Plumas-Sierra, New Portola/Loyalton Courthouse	91.32.001	Dec. 2009	6,544	\$52,940
Contra Costa, New Antioch Courthouse	91.07.001	Oct. 2010	47,069	\$293,538
Fresno, Sisk Federal Courthouse Renovation	91.10.001	Nov. 2010	174,215	\$955,933
Mono, New Mammoth Lakes Courthouse	91.26.001	Sep. 2011	11,787	-\$41,532
Lassen, New Susanville Courthouse	91.18.001	Mar. 2012	33,074	\$272,138
San Benito, New Hollister Courthouse	91.35.001	Oct. 2013 (est.)	32,841	\$214,078
Tulare, New Porterville Courthouse	91.54.001	Oct. 2013 (est.)	93,465	\$604,505
Calaveras, New San Andreas Courthouse	91.05.001	Nov. 2013 (est.)	38,502	\$273,144
Riverside, New Mid-County Courthouse	91.33.001	Mar. 2014 (est.)	52,071	\$340,600

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

San Bernardino, New San Bernardino Courthouse	91.36.001	May 2014 (est.)	291,197	\$2,388,915
Solano, Old Solano Courthouse Renovation	91.48.001	Jul. 2014	29,930	\$212,204
Butte, New North County Courthouse	91.04.001	May 2015	51,338	\$405,433
San Joaquin, Juvenile Justice Center Renovation	91.39.002	Jun. 2015	4,063	\$61,049
Madera, New Madera Courthouse	91.20.001	Sept. 2015 (est.)	74,588	\$690,007
Sutter, New Yuba Courthouse	91.51.001	Jul. 2015 (est.)	56,641	\$459,730
Yolo, New Woodland Courthouse	91.57.001	May 2015 (est.)	103,776	\$809,427
Kings, New Hanford Courthouse	91.16.001	Dec. 2015 (est.)	92,247	\$779,821
Santa Clara, New Santa Clara Family Justice Center	91.43.001	Jan. 2016 (est.)	112,900	\$0
Merced, New Los Banos Courthouse	91.24.002	Jun. 2016 (est.)	24,135	\$143,562
Tehama, New Red Bluff Courthouse	91.52.001	Oct. 2016 (est.)	32,861	\$320,200
San Joaquin, New Stockton Courthouse	91.39.001	Nov. 2016 (est.)	204,711	\$1,412,869
San Diego, New Central San Diego Courthouse	91.37.001	Dec. 2016 (est.)	396,482	\$2,028,621

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

Alameda, New East County Hall of Justice	91.01.001	Feb. 2017 (est.)	91,756	-\$268,196
Total			2,056,193	\$12,409,000

IV. Alternative Solutions

Alternative #1: 50% Augmentation - Provide an augmentation of \$6,204,000 for FY 2016-17 from the General Fund for transfer to the Court Facilities Trust Fund and an ongoing augmentation for FY 2017-18 from the General Fund for transfer to the Court Facilities Trust Fund of \$6,075,000.

Pros:

- Partially addresses cost increases anticipated in FY 2016-17 and ongoing due to the opening of 22 newly constructed or renovated court facilities.
- Reduces the number of facility repairs and interruptions to the court as some preventative maintenance efforts will resume.
- Will provide additional resources to maintain brand new infrastructure for all Californians.

Cons:

- This proposal will require a commitment of General fund resources as it will not fully fund the need.
- This alternative will continue to result in the need to reduce preventative maintenance activities as it will not fully fund the requested need.

Alternative# 2: 75% Augmentation - Provide an augmentation of \$9,306,000 for FY 2016-17 from the General Fund for transfer to the Court Facilities Trust Fund and an ongoing augmentation for FY 2017-18 from the General Fund for transfer to the Court Facilities Trust Fund of \$9,112,000.

Pros:

- Partially addresses cost increases anticipated in FY 2016-17 and ongoing due to the opening of 22 newly constructed or renovated court facilities.
 - Reduces the number of facility repairs and interruptions to the court as some preventative maintenance efforts will resume.
-

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

- Will provide additional resources to maintain brand new infrastructure for all Californians.

Cons:

- This proposal will require a commitment of General fund resources.
- This alternative will continue to result in the need to reduce preventative maintenance activities.

•

V. Other Considerations

The proposed augmentation is based on Capital Outlay projects that were approved by the State Department of Finance and the Legislature in previous Budget Acts.

Government Code 70351 states that, “it is further the intent of the Legislature that funding for the ongoing operations and maintenance of court facilities that are in excess of the county facilities payments be provided by the state.”

This proposal directly supports Goals II, VI and VII of the Judicial Council’s Long-Range Strategic Plan, as follows:

Goal II, Independence and Accountability states, “the judicial branch must also exercise its constitutional and statutory authority and responsibility to plan for direct, monitor, and support the business of the branch and to account to the public for, the branch’s performance.” Securing sufficient resources to ensure accessible, safe, and efficient facilities for the public directly addresses this goal.

Goal VI, Branch-wide Infrastructure for Service Excellence states “Infrastructure improvements needed to better serve the public include (1) acquisition, construction, renovation, and maintenance of adequate facilities”. This goal seeks to provide fully functional facilities that are safe and secure for conducting court business for all court users.

Goal VII, Adequate, Stable, and Predictable Funding for a Fully Functioning Branch. Consistent with the Judicial Council’s legislative priority to advocate for investment in our justice system to preserve access to justice for all Californians, the branch must continue advocacy for sufficient fund balances allowing courts to manage cash flow challenges, a method for stable and reliable growth funding for courts to address annual cost increases in baseline operations, and sufficient additional resources to allow courts to (1) improve physical access to the courts by keeping courts open, (2) expand access by increasing the ability of court users to conduct branch business online, and (3) restore programs and services that were reduced or eliminated in recent years.

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Patrick McGrath/Angela Guzman

In addition, the CFTF has not received inflationary adjustments on CFP's since 2009 while costs have continued to increase, eroding the Judicial Council's ability to provide an adequate level of service to the portfolio.

**Action Item 10-2 (BCP)
Trial Court Security System Maintenance,
Replacement and Improvements**

- Existing Systems
- Annual Repair & Maintenance Costs
- Annual Cost for System Replacement
- Security Grant Program
- Current Recommendations

**Action Item 10-2 (BCP)
Trial Court Security**

- Existing systems need replacement and repairs and maintenance
- Systems in new courthouses must be maintained and repaired
- Restore Trial Court Security Grant Program funding
- Add staff necessary to support these efforts

**Action Item 10-2 (BCP)
Trial Court Security -
Existing Systems**

	Cameras	Duress	Access	Intrusion
OS	80	116	27	0
REFM	15	15	25	33
Court	52	55	69	37
Total	147	186	121	70

**Action Item 10-2 (BCP)
Trial Court Security –
Annual Repair & Maintenance Costs**

• Camera Systems	\$ 497,720
• Access Systems	\$ 252,000
• Duress Systems	\$ 50,000
• Intrusion Alarms	\$ 31,351
Total	\$ 831,071

**Action Item 10-2 (BCP)
Trial Court Security –
Annual Cost for System Replacement**

• Cameras	\$ 694,988
• Access	\$ 175,528
• Duress	\$ 152,482
• Total	\$1,022,998

**Action Item 10-2 (BCP)
Trial Court Security –
Total Annual Replacement
& Repair Costs**

• Cameras	\$1,192,708
• Access	\$ 427,528
• Duress	\$ 202,482
• Intrusion	\$ 31,351
• Total	\$ 1,854,069

Action Item 10-2 (BCP)
Trial Court Security –
Trial Court Security Grant Program

- \$1.2 million in IMF
- Funding was eliminated as of FY 15/16
- Necessary to address system deficiencies (locations with no system)

Action Item 10-2 (BCP)
Trial Court Security –
Estimated Budget Change Proposal Request

• Replace & Repair	\$1,854,069
• TCSGP funding	\$1,200,000
• Additional staff (3)	\$ 390,000
• Total BCP Request	\$3,444,069

FY 2016-17 Budget Change Proposal Concept

Office: Security Operations Contact: Ed Ellestad

I. Trial Court Security System Maintenance, Replacement and Improvements

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
General Fund	3 FTE	390,000	3,054,069	3,444,069

II. Nature of Request/Problem

Describe the problem that is being addressed and provide a brief history/background of the issue. Address reasons why this activity cannot be accomplished utilizing existing base budget resources.

Security systems, which include security cameras, electronic access control, duress alarms and intrusion alarms, are vital components in ensuring the safety and security of the public, judicial officers, and court personnel. Many trial court facilities have aging or inadequate security systems that were in place when the facilities transferred from county oversight, and are in need of repair or replacement. Other facilities share systems with the county, or have no system at all. The cost of repair and replacement of these systems has been addressed in a piecemeal manner, with some systems being managed by the courts, some the Judicial Council, with many falling into disrepair due to lack of specifically directed funding.

The Judicial Council's Security Operations unit administered the Trial Court Security Grant Program for the installation and improvement of security systems in trial court facilities. The program began in fiscal year 2006-2007 and ran through the end of fiscal year 2014-2015 when the funding was eliminated. The program was funded annually from the State Trial Court Improvement and Modernization Fund (IMF), with an initial budget of \$3 million, which was reduced to \$1.2 million. The program has installed a total of 80 camera, 27 access and 116 duress alarm systems. A portion of the Trial Court Security Grant Program annual budget was also allocated for other types of security projects, such as a web-based continuity of operations planning tool, the reconfiguration of clerk's counters and the installation of ballistic glass.

The systems installed using Trial Court Security Grant Program funds have been maintained using those grant funds, as that was the only funding source available. Appropriate maintenance of the systems is critical to ensuring the safety and security of all court users. Using vital program funds to maintain these systems reduced the amount of funds available for replacement or upgrades, the actual intended use of these funds. Repair and maintenance demands have increased in proportion to the number of new systems installed, and as Capital Building Program construction projects are added to the Judicial Council portfolio.

FY 2016-17 Budget Change Proposal Concept

Office: Security Operations Contact: Ed Ellestad

The elimination of the Trial Court Security Grant Program funding has placed these systems in jeopardy as there is no other funding source available to address these costs. In addition, improvements to inadequate systems will no longer be possible, resulting in reduced safety and security in Trial Court facilities. The Trial Court Facilities Modification Advisory Committee approved allocating \$300k in one time funds for fiscal year 2015-2016 to address anticipated repairs of the existing systems installed under the grant program and systems in new courthouses with expired warranties. This will allow for the bare minimum of service and is, in no way, adequate to address the maintenance of all of the security systems in trial court facilities in the long term.

Adequate staffing is necessary in order to provide the necessary assistance and services to the trial courts. A portion of these funds will be allocated for 3 FTEs to be housed in the Security Operations unit.

III. Proposed Solution

Describe the solution (recommendation) proposed to address the problem. Discuss resources needed (funding and positions) to implement solution. Indicate if funding would need to be one-time or ongoing; and whether additional resources would be needed in future fiscal years.

Recommended Alternative: This alternative will allow existing systems to be maintained and replaced in a timely, cost effective and efficient manner. This will be achieved by continuing to maintain systems installed through the Trial Court Security Grant Program, and transferring responsibility for maintenance and replacement of the inherited security systems to the Judicial Council. This will allow the Judicial Council to assist courts, which lack the resources to adequately maintain the systems, by assuming and continuing with the responsibility for the repair, maintenance and replacement of those systems. By utilizing existing competitively bid master agreements, consistent equipment quality, pricing and service response are ensured. Improvement projects that have been delayed will be prioritized and completed, and the staff necessary to manage these projects will be added to the Security Operations unit. Funding required for this alternative is \$3.4 million.

IV. Alternative Solutions

Describe alternative solutions that were considered to address the problem, including cost estimates. Briefly discuss why these alternatives were not the recommended solutions.

FY 2016-17 Budget Change Proposal Concept

Office: Security Operations Contact: Ed Ellestad

Alternative #1: Maintenance, Repair and Replacement of Existing Systems: Under this alternative, existing systems that have been maintained by both the Judicial Council and the Trial Courts will be maintained by the Judicial Council. This will be achieved by transferring responsibility for maintenance and replacement of security systems to the Judicial Council. Two (2) FTE positions are included in this alternative. No new systems or other improvements will be completed. Funding required for this alternative is \$2,114,069.

Alternative #2: Maintenance of Existing Systems Only: Under this alternative, the existing systems will be maintained and repaired. Replacement will be a court cost and no new systems or improvements will be completed. While the maintenance costs represent lower cash outlay in the short term, failure to replace systems will result in higher costs in the long term. One (1) FTE position is included in this alternative. Funding required for this alternative is \$961,071.

V. Other Considerations

Separate funding, dedicated to security systems, projects and maintenance is vital to eliminate these efforts from competing for funding with other vital building maintenance priorities.

**Action Item 10-3 (BCP)
Trial Court Facilities –
Risk Management Program**

- Past Actions
- Recommendation
- Alternative Solutions
- Next Steps

**Action Item 10-3 (BCP)
Trial Court Facilities –
Risk Management Program:
Past Actions**

Support Function	Funding	Additional Funding Requested	Percentage of Growth	Fund Source
Risk Management Program	\$1 M	\$1.655 M	65%	General Fund

- Judicial Council approved submittal of FY 2015-16 BCP
- BCP declined by DOF

**Action Item 10-3 (BCP)
Trial Court Facilities –
Risk Management Program**

- **Recommendation:**
 - Submit concept to Judicial Council for General Fund Augmentation of \$3,931,040 to purchase facilities related insurance for effective risk management.

**Action Item 10-3 (BCP)
Trial Court Facilities –
Risk Management Program**

Alternative	Funding Requested	% of Growth	Fund Source
1	\$2.737M	273.7%	General Fund
2	\$1.343M	34.3%	General Fund
3	\$0	0%	General Fund

- Alternative 1 – Insure court buildings with title transfer or where JCC has risk of loss, FULLY allocate funds for excess liability insurance and payment of self-insured claims and lawsuit costs
- Alternative 2 – Insure all buildings where there is a contract or bond financing requirement, FULLY allocate funds for self-insured claims and lawsuit costs
- Alternative 3 – Staius quo-Insure all buildings where there is a contract or bond financing requirement, PARTIALLY allocate funds for self insured claims and lawsuit costs.

Action Item 10-3 (BCP)
Trial Court Facilities –
Risk Management Program:
Next Steps

- Step 1 – Executive and Planning Committee
- Step 2 – Judicial Council review and approval
- Step 3 – Submittal of BCP to DOF

Action Item 10-3 (BCP)
Trial Court Facilities –
Risk Management Program

- Comment and Input
- Recommendation:
Approve development and submittal of BCP
concepts to Judicial Council

This page intentionally left blank

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program Contact: Angela Guzman/Jim Mullen

I. Trial Court Facilities-Risk Management Program

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
0001-General Fund transfer to 3066-Court Facilities Trust Fund	N/A	N/A	\$3,931,040	\$3,931,040

II. Nature of Request/Problem

Senate Bill (SB) 1732, the Trial Court Facilities Act of 2002 (Ch. 1082, Stats. 2002), provided for the transfer of court facilities from the counties to the state and provided for an ongoing maintenance of effort payment, the County Facility Payment (CFP), from the County to the State. The CFP payment includes the cost of property and public liability insurance that was associated with each court building as of June 1, 2000.

The Judicial Council of California (JCC) receives \$2,934,000 in CFP payments annually for insurance costs associated with transferred court facilities. These funds were based on fiscal year (FY) 1999-2000, which was a historically low period for the cost of insurance. Property insurance costs increased dramatically after the September 11, 2001 event, and while property insurance costs have decreased over the past ten years they have remained higher than the cost basis of June 30, 2000. Public liability insurance costs have also continued to increase since June 30, 2000 due to economic and social inflation costs.

If the JCC were to pay the shared property insurance costs invoiced by the counties on jointly occupied buildings for which a county holds title, purchase property insurance on all buildings where the Judicial Council holds title, fund its annual expected paid legal defense and loss costs for public liability claims and lawsuits resulting from court facility operations, and purchase excess liability insurance to protect against catastrophic loss the expected cost would be \$6,865,040, which would exceed available CFP revenues by \$3,931,040.

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program Contact: Angela Guzman/Jim Mullen

The shortfall is calculated as follows:

Cost of County provided Shared All Risk Property Insurance:	\$556,749
Cost of County provided Shared Earthquake Property Insurance	\$991,664
Cost of All Risk Insurance on JCC owned or obligated buildings	\$1,194,274
Cost of Earthquake Property Insurance on JCC obligated buildings	\$157,263
Cost of property insurance required by bond financing and other contractual obligations	\$877,862
Annual expected legal defense and paid loss cost for Public Liability Claims and Lawsuit	\$1,693,709
Cost of Excess Liability Insurance	\$1,393,519
Total Cost of Insurance and Expected Retained Public Liability Loss	\$6,865,040
Less CFP Insurance Receipts	(\$2,934,000)
Excess Unfunded Insurance Costs	\$3,931,040

The JCC has been able to address the shortfall to date by paying the counties for the JCC's occupancy share of property insurance costs in buildings where the county retains title, by only purchasing property insurance where required to do so by contract or bond financing agreement, and by self-insuring the exposure from direct property damage, extra expense and relocation costs in those buildings where the title has been transferred to the state. Similarly, the JCC has self-insured the premise and operations exposure to public liability claims and lawsuits, without the benefit of excess self-insured retention public liability insurance for potential catastrophic events.

While this strategy has been "successful" in the past; given the current financial condition of the judicial branch, the increasing costs associated with shared and contractually required property insurance costs, and the costs associated with funding of annual legal defense and loss cost of expected public liability claims and lawsuits makes a change in strategy paramount.

Given the reduced level of discretionary funds available from the Court Facilities Trust Fund (CFTF), the Judicial Council should trade the variable, and unpredictable, cost associated with self-insurance for the fixed cost of insurance.

III. Proposed Solution

The Capital Program is proposing a General Fund augmentation of \$3,931,040 to increase its funding to pay counties for shared property insurance costs, purchase facilities related property and excess liability insurance, and to increase funding for the annual legal defense and loss cost of expected public liability claims and lawsuits.

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program Contact: Angela Guzman/Jim Mullen

The JCC recommends purchasing all risk property insurance, including coverage for the extra expense associated with a covered loss and court relocation costs incurred during the period of restoration of a damaged court building. This insurance would augment the insurance available from counties on those buildings that the county is required to insure by terms of the transfer agreements. This alternative protects the JCC from large loss, and provides for court relocation costs incurred during the period of restoration of a damaged court building. Due to the current condition of the property insurance market, where minimal premium credits are available for large deductibles or self-insured retentions, the JCC suggests a maximum deductible of \$250,000 per occurrence when soliciting insurance quotations. It may be advisable to join an established joint powers authority created for the purpose of pooling self-insured claims and purchasing reinsurance excess of predictable levels of retained loss, or explore use of the State Department of General Services, Office of Risk and Insurance Management (ORIM) programs of property insurance for state buildings under bond indebtedness.

The JCC also has significant financial exposure from public liability claims or lawsuits. Therefore, this proposal recommends fully funding the annual expected legal defense and loss cost of public liability claims and lawsuits projected for FY 2016–2017. JCC should also explore the excess insurance market for public liability insurance in excess of \$500,000, or \$1,000,000, per occurrence of self-insured retention for loss resulting from court building maintenance and operations.

IV. Alternative Solutions

Alternative #1: Insure the property insurance costs for all court buildings where title has transferred to the state, or for which the JCC has risk of loss for the consequences of a damage and destruction event, continue to fund the counties shared property insurance costs, and continue to fund the retained annual legal defense and loss cost of public liability claims and lawsuits. The estimated cost of this alternative would be \$5,670,766, which would result in a deficiency of \$2,736,766 when compared to the anticipated CFP insurance payments in FY 2016–2017 of \$2,934,000. This alternative eliminates the All Risk Insurance on JCC owned or obligated buildings. The risk with the alternative is that it does not provide for an immediate source of financing for a large loss event or a combination of loss events that exceed the financial liability of the Judicial Council to respond. Given the reduced discretionary funds available, the JCC's ability to pay retained loss has diminished significantly.

Alternative #2: Continue to fund the counties shared property insurance costs and certain property insurance costs of the JCC associated with contractual or bond obligations; and fund the retained annual legal defense and loss cost of public liability claims and lawsuits. The estimated cost of this alternative would be \$4,277,247 which would result in a deficiency of \$1,343,247 when compared to the anticipated CFP insurance payments in FY 2016–2017 of \$2,934,000. This alternative eliminates both All Risk Insurance on JCC owned or obligated buildings as well as the cost of excess liability insurance. The risk of this alternative would be that there may be insufficient resources to cover the costs incurred of a single large damage and destruction event,

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program Contact: Angela Guzman/Jim Mullen

a single public liability claim or lawsuit, or an aggregate of both. Therefore, state court facilities remain significantly underinsured.

Alternative #3: Status quo - continue to fund the counties shared property insurance cost and certain property insurance costs of the JCC associated with contractual or bond obligations in line with Alternative #2, the issue is that the anticipated CFP insurance payments for FY 2016-2017 are not sufficient to fund Alternative #2, in order to stay within the CFP revenues the JCC would only be able to fund \$350,462 for annual expected legal defense and paid loss cost for public liability claims and lawsuits. This is significantly less than the annual expected amount of \$1,693,709 needed for these costs.

V. Other Considerations

Other relevant factors related to the issue are:

1. Addresses Goal I of the Judicial Council's Long Range Strategic Plan in that "all persons will have equal access to the court and court proceedings and programs." By having adequate risk property insurance, even in the event of a loss, all people will have access to justice.
 2. Addresses Goal VI-Branchwide Infrastructure for Service Excellence established the need for a physical infrastructure that supports the needs of the judiciary and ensures continuity of operations, including a funding structure for actual disaster recovery. Acquiring sufficient resources to fund the purchase of insurance is an efficient means to ensure that money is available to fund restoration of damaged court facilities and to provide funds to relocate court operations to temporary locations during the period of restoration, directly supporting this goal.
 3. Currently, 170 of the 307 court buildings in which the JCC retains all or a portion of the risk of loss from a damage or destruction event are insured by a county, the JCC, the State Department of General Services' Office of Risk Management, or another third party. This reduces the probability by 55% of uninsured damage to a random court building within the overall portfolio.
 4. Currently, for 108 of the 307 court buildings the a county retains 100% of the risk of loss for seismic earthquake related damage or destruction because the buildings have a Level V Seismic Safety Rating.
 5. An additional 40 buildings are insured for earthquake related damage or destruction subject to a deductible of 5% of the building's replacement value.
 6. Even if funded at the requested level, there is no funding for self-insured public liability claims incurred but not paid in FY 2016-2017, or self-insured claims incurred but not reported.
 7. The cost of insurance is a fixed cost that is fully expensed in the fiscal year paid. Over the long run the cost of insurance may exceed the amount of loss dollars recovered from commercial insurers. The benefit of insurance is to trade a known cost in any fiscal period for the possible unknown cost of damage and destruction, or liability events.
-

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program Contact: Angela Guzman/Jim Mullen

8. The proposed solution does not include a recommendation to purchase insurance for earthquake related damage for every court building as such insurance is not readily available in the commercial market at an economically reasonable cost.
 9. The cost of earthquake insurance provided by the County is outside of the control of the JCC and is often a requirement of County bond indenture agreements.
 10. The JCC spent approximately \$1.1 million on insurance needs in FY 2014–2015, which is almost \$700,000 less than the CFP monies available. Providing the \$700,000 towards insurance needs will reduce funds currently spent on routine maintenance.
-

Action Item 10-4 (BCP) Antelope Valley Juvenile Court Facility Modifications

- Past Actions
- Recommendation
- Alternative Solutions
- Next Steps

Action Item 10-4 (BCP) Antelope Valley Juvenile Court Facility Modifications

Support Function	Funding	Additional Funding Requested	Percentage of Growth	Fund Source
Antelope Valley Juvenile Court Facility Modifications	\$0 M	\$3.5 M (one time)	100%	Immediate and Critical Needs Acct

- The project ranked in the Immediate Need Priority group of the Trial Court Capital-Outlay Plan.
- January 2010 submitted as an SB 1407 (ICNA) Capital Outlay project to DOF – denied and recommended to submit as an FM.
- October 2012 – JC approved referral of project to TCFMAC for consideration as an FM.

**Action Item 10-4 (BCP)
Antelope Valley Juvenile Court
Facility Modifications**

- **Recommendation:**
 - Submit concept to Judicial Council for ICNA Augmentation of \$3.5 to build out 2 shelled courtrooms and associated support spaces in the Michael D. Antonovich Courthouse and to perform minor modifications in the McCourtney Juvenile Justice Center Courthouse.

**Action Item 10-4 (BCP)
Antelope Valley Juvenile Court
Facility Modifications**

Alternative	Funding Requested	% of Growth	Fund Source
1	\$3.5M	100%	ICNA
2	\$0M	0%	ICNA

- Alternative 1 – Renovate the existing McCourtney Juvenile Justice Center Courthouse.
- Alternative 2 – Status Quo, no new funding

**Action Item 10-4 (BCP)
Antelope Valley Juvenile Court
Facility Modifications:
Next Steps**

- Step 1–Executive and Planning Committee
- Step 2–Judicial Council review and approval
- Step 3-Submittal of BCP to DOF

**Action Item 10-4 (BCP)
Antelope Valley Juvenile Court
Facility Modifications**

- Comment and Input
- Recommendation:
Approve development and submittal of BCP
concept to Judicial Council.

This page intentionally left blank

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Angela Guzman/Burt Hirschfeld

I. Los Angeles Superior Court – Antelope Valley Juvenile Court Facility Modifications

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
Immediate and Critical Needs Account			\$3,500,000 (One-time)	\$3,500,000 (One-time)

II. Nature of Request/Problem

The McCourtney Juvenile Justice Center (previously referred to as the Lancaster Juvenile Courthouse) was identified by the Judicial Council as a Senate Bill 1407 Immediate and Critical Needs Account Capital Outlay Project. This project ranked in the Immediate Need priority group of the Trial Court Capital-Outlay Plan that was adopted by the Judicial Council in October 2008. The existing courthouse contains a number of deficiencies relative to access, efficiency, security, and courtroom operations, which create impediments to the superior court's administration of justice. These conditions significantly hinder the superior court's ability to provide accessible and efficient juvenile dependency, delinquency, and informal juvenile and traffic court proceedings to its court users.

In January 2010 the Judicial Council submitted a Capital Outlay Budget Change Proposal to the state Department of Finance (DOF) to renovate the McCourtney Juvenile Justice Center Courthouse. DOF denied the request as a Capital Outlay Project and recommended submission as a Facility Modification because the project would improve a county-owned building and it was not increasing space. In October 2012, the Judicial Council referred this project to the Trial Court Facility Modification Advisory Committee for consideration as a Facility Modification. The intention was to have this project be funded separate and apart from the annual \$25 million ICNA appropriation for facility modifications.

Proposed Solution

The Real Estate and Facilities Management office, with support of the Los Angeles Superior Court, recommends an alternate solution to renovating the McCourtney Juvenile Justice Center Courthouse with the goal to improve the safety, security, and functional conditions of the

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Angela Guzman/Burt Hirschfeld

juvenile courts in the Antelope Valley. The court has plans to move the juvenile delinquency cases from the McCourtney Juvenile Justice Center Courthouse to the Michael D. Antonovich Antelope Valley Courthouse, which has security already in place (such as secure holding and separate and secure pathways from holding to the courtrooms) and thus alleviate the need to make such security modifications to the McCourtney Juvenile Justice Center Courthouse. The Board of State Community Corrections has approved the holding areas in the Antonovich Courthouse for juvenile holding. This proposed solution would make use of the final two existing shelled courtrooms at the Antonovich Antelope Valley Courthouse. The estimated project cost is \$3,244,000.

With this move of juvenile delinquency cases to the Antonovich Courthouse, both the security risks and overcrowding at the McCourtney facility will be dramatically reduced. The McCourtney facility will remain in use for juvenile dependency cases. The Judicial Council with support of the Los Angeles Court recommends minor renovations to the McCourtney Juvenile Justice Center Courthouse to improve the physical and functional conditions of this facility for the juvenile dependency calendars. The minor renovations include reconfiguration of one courtroom to accommodate its future use as a dependency court, expand public waiting areas, reconfigure floor space for additional usable space, improve temperature fluctuations, and install additional security cameras. The estimated project cost is \$256,000.

The Real Estate and Facilities Management office proposes a one-time augmentation of \$3,500,000 million from the Immediate and Critical Needs Account for facility modification projects for the Antonovich Antelope Valley Courthouse and the McCourtney Juvenile Justice Center Courthouse. The funding will provide benefits of enhanced functionality and security for the superior court and for all court users.

III. Alternative Solutions

Alternative #1: Renovate the existing McCourtney Juvenile Justice Center Courthouse. This alternative, due to deficiencies relative to size of the existing facility and lack of separate secure circulation for in-custody defendants, would be less cost effective and unlikely to solve primary overcrowding and security issues.

Alternative #2: No project, Status Quo. In this option, renovations would not occur in the Antonovich Antelope Valley Courthouse or the McCourtney Juvenile Justice Center Courthouse. Consequently, this option results in the status quo, which is the juvenile courts in

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Angela Guzman/Burt Hirschfeld

Antelope Valley remaining in existing deficient facilities and continued safety, security, overcrowding, and public service inefficiencies.

IV. Other Considerations

The proposed solution will satisfy the Los Angeles Superior Court's goal of improving the safety and service of the juvenile courts in the Antelope Valley Courthouse.

The Judicial Council has approved improving the juvenile courts in the Antelope Valley as an SB 1407 funded project, to be implemented as a Facility Modification.

This proposal supports Goal VI of the Judicial Council's Strategic Plan:

Goal VI: Branchwide Infrastructure for Service Excellence states, "Infrastructure improvements needed to better serve the public include (1) acquisition, construction, renovation, and maintenance of adequate facilities."

Action Item 10-5 (BCP)

Green Pilot Projects

- Focus on six, reasonably sized facilities
- Leverage outside resources offered by the utility companies
- Allow for a more holistic approach to conservation efforts
- Enable more aggressive energy efficiency and water conservation options
- Ensure a collaborative approach
- Highlight the Judicial Branch's leadership role in energy and water conservation efforts

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Laura Sainz

I. Augmentation to Support “Green” Pilot Projects

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
Cap and Trade	0	\$0	\$5,250,000	\$5,250,000
2017-18 Fiscal Summary:				
Cap and Trade	0	\$0	\$9,400,000	\$9,400,000

II. Nature of Request/Problem

Senate Bill (SB) 1732 (Ch. 1082, Stats. 2002), the Trial Court Facilities Act of 2002, provided for the transfer of court facilities from the counties to the state. It further stipulated that counties provide annual County Facility Payments (CFPs) based on the historic operating costs of each transferred facility, including utilities costs. However, CFPs are fixed and the Judicial Council has not received inflationary cost increases on the CFPs since FY 2009-10. To account for inflation cost increases or utility rate increases the maintenance budget is reduced as fixed costs such as lease costs and utilities must be paid.

Along with a historic rise in rates, there are other recent issues impacting utility costs. Electricity rates have risen much faster in the last two years, due to the June 2013 closure of the San Onofre Nuclear Power Plant, located in San Diego County. Tighter air quality regulations are making it difficult for utility companies to build and operate coal-fired power plants. In an effort to more closely manage the timing and distribution of power, utility companies are turning to “time-of-use” (TOU) rates. TOU rates charge a customer more for electricity used during peak times (weekdays, 12:00 p.m. – 6:00 p.m., May– October). Given the business hours of courthouse facilities, it is expected utility costs will continue to rise, and at a faster rate due to the transition to TOU rates.

Water rates are also potentially volatile. In response to the drought and mandatory reduction requirement issued by the State Water Resources Control Board, water agencies are searching for legal mechanisms to charge customers for excessive water use. In addition, financial penalties are being issued to customers who violate watering guidelines.

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Laura Sainz

Given the historic rise in utility expenses, as well as the potential for exponential increases in water and electricity costs, the Judicial Council would like to explore permanent solutions to reduce utility rates long-term, leaving more funds available for maintenance.

The Judicial Council would like to develop a leadership position on energy and water conservation issues, in an effort to further bolster the role the state has taken in engaging in energy efficiency and drought-related reporting and projects.

Proposed Solution

In the last six months, the Judicial Council has been able to leverage the outside resources of investor owned utilities, specifically Pacific Gas & Electric (PG&E) and Southern California Edison (SCE). PG&E and SCE are completing over 40 energy audits on Judicial Council facilities and have already identified a number of energy efficiency measures. In addition, the Judicial Council has engaged in an aggressive water audit program, targeting facilities with the highest water use. The water audits are provided for free by local water agencies. However, this approach leads to piecemeal solutions that do not take full advantage of a holistic approach to energy efficiency and water conservation. Many of the energy efficiency measures identified focus on minor adjustments to the heating, ventilation and air conditioning (HVAC) system versus a more integrated approach that includes the building shell, operational approaches, user considerations, and measurement and verification of actual energy savings. While the audits have identified some conservation opportunities, this approach has not allowed the Judicial Council to complete a comprehensive study of a single facility in an effort to make more effective improvements utilizing an integrated approach that includes key players in the conservation effort, such as the on-site service provider, court staff and in some cases, the county.

The Judicial Council proposes funding up to six “Green” Pilot Projects to further advance energy efficiency and water conservation efforts. The Green Pilot Projects are being proposed for the following reasons:

- The projects allow the Judicial Council to take an integrated, holistic approach to energy and water conservation efforts at a few select facilities;
- The projects will allow the Judicial Council to determine which energy efficiency and water conservation measures are most effective in a courthouse environment;
- The projects will allow the Judicial Council to engage all the necessary stakeholders, i.e., the court, the county, and the on-site service providers, required for successful long-term conservation efforts;
- The projects will allow for new technologies to be tested in a courthouse environment;

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Laura Sainz

- The projects will identify cost-effective energy efficiency and water conservation efforts that will inform future funding decisions; and
- The projects will serve as a model for other courts interested in pursuing aggressive conservation efforts.

Six courthouse facilities have been identified as potential pilot projects. These six courthouses were chosen for the following reasons:

1. The facility will be a courthouse for the next 20+ years.
2. The facility is managed by the Judicial Council.
3. The Judicial Council occupies a majority of the space.
4. The facility is on the smaller size, thereby giving us an advantage in terms of potential costs and ease of implementation.
5. There is a utility company willing to partner with us and share the cost of the pilot project.
6. The court and/or county are willing to partner with us.
7. The climate is appropriate for a potential zero net energy scenario and/or solar/photovoltaic system.
8. The pilot projects are geographically diverse and include under-represented areas.
9. There is physical space around the facility for solar, i.e. surface parking.

The six facilities are listed below:

	Facility ID	Courthouse	Region	Gross Square Feet per CAFM	Percent Court Space per CAFM
1.	27-B1	Marina Courthouse	BANCRO	15,347	100%
2.	36-J1	Barstow	SRO	35,702	78%
3.	36-P1	San Bernardino Juvenile Dependency Courthouse	SRO	28,724	55%
4.	03-C1	Amador County Courthouse	NCRO	20,346	100%
5.	34-C2	B.T. Collins Sacramento Juvenile Courthouse	NCRO	100,360	100%
6.	34-D1	Carol Miller	NCRO	98,628	98%

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Laura Sainz

Implementation of the Pilot Projects: Phase I (FY 2015-2016)

The first phase of the pilot program will be implemented in FY 2015-2016. The utility companies, including PG&E, SCE and the Sacramento Municipal Utility District (SMUD) have agreed to front the costs of the preliminary and more in-depth audits being performed at these facilities. To identify the potential improvements needed at each facility, the utility companies have preliminarily reviewed the facilities. Based on this preliminary building review and past experience with major energy efficiency projects, the utilities developed a realistic budget for the necessary energy efficiency and water conservation measures applicable to these facilities. The utility companies provided energy engineers, who reviewed energy use in the existing buildings, including peak demand and total use, lighting and the HVAC equipment in each facility.

As a follow up to this effort, the utility companies will be completing a more in-depth audit of each of these facilities. The in-depth audits allow for the direct measurement of energy and water use of specific equipment, i.e. chillers, boilers; and in the case of water, irrigation use versus interior use. The measurement and verification of energy use will allow for a more accurate payback analysis of specific measures, as well as identify any additional incentives that may be pursued. The utility companies are willing to put in this level of effort, based on a commitment by the Judicial Council to pursue the energy efficiency and/or water conservation measures that are financially feasible and provide a realistic payback.

Implementation of the Pilot Projects: Phase II (FY 2016-2017)

Based on the findings and recommendations of the in-depth, integrated audits, energy efficiency and water conservation measures will be completed during FY 2016-2017. The projected costs of these measures are as follows:

	Facility ID	Courthouse	Utility Provider	Estimated Cost
1.	27-B1	Marina Courthouse	Pacific Gas and Electric (PG&E)	\$750,000
2.	36-J1	Barstow	Southern California Edison (SCE)	\$850,000
3.	36-P1	San Bernardino Juvenile Dependency Courthouse	Southern California Edison	\$850,000
4.	03-C1	Amador County	Pacific Gas and	\$900,000

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Laura Sainz

		Courthouse	Electric (PG&E)	
5.	34-C2	B.T. Collins Sacramento Juvenile Courthouse	Sacramento Municipal Utility District (SMUD)	\$950,000
6.	34-D1	Carol Miller	Sacramento Municipal Utility District (SMUD)	\$950,000
Total				\$5,250,000

The requested funding will be used to implement energy efficiency and water conservation measures at each of the Green Pilot Projects. The variance in cost is related to size of facility, energy efficiency measures already completed, and differences in water conservation opportunities.

Implementation of the Pilot Projects: Phase III (FY 2017-2018)

The final phase of the pilot projects will be to pursue renewable energy at each of the sites in an effort to reach zero-net energy status. Zero-net energy status implies the facility is using as much energy as it is generating through on-site renewable energy. Based on future analysis either renewable energy will be purchased outright, or installed through a power purchase agreement (PPA). The final decision will be based on the final energy efficiency measures implemented at each site, the individual site variables, and the cost/benefit analysis of ownership versus “leasing” renewable energy. However, if renewable photovoltaic systems are pursued, the expected costs to purchase/own the system outright, based on projected annual energy consumption for each site are as follows:

	Facility ID	Courthouse	Estimated Cost
1.	27-B1	Marina Courthouse	\$600,000
2.	36-J1	Barstow	\$2,700,000
3.	36-P1	San Bernardino Juvenile Dependency Courthouse	\$1,100,000
4.	03-C1	Amador County Courthouse	\$1,000,000
5.	34-C2	B.T. Collins Sacramento Juvenile Courthouse	\$2,000,000

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Laura Sainz

6.	34-D1	Carol Miller	\$2,000,000
Total		Total	\$9,400,000

III. Alternative Solutions

Alternative #1: Maintain the status quo. The first alternative is to continue the status quo of funding energy efficiency and water conservation projects out of the facility modification budget. These projects are identified on a piecemeal basis, and while providing savings through reduced energy and water use, may not be the most cost effective means of implementing energy and water conservation efforts. The status quo also does not allow for the application of new technologies or operational approaches in a controlled courthouse environment. This may lead to lost opportunity costs of future projects. In addition, this reduces the funding available in the facility modification budget for other needs.

Alternative #2: Grant Funding. The second alternative is to seek grant funding for the Green Pilot Projects. Currently, there are no grant funds available for energy efficiency and water conservation projects. And, if funding does become available, the Judicial Council will be competing with numerous state agencies, schools, California State and the University of California systems.

IV. Other Considerations

- The funding request for the Green Pilot Projects is a one-time funding request. The Judicial Council will be implementing various energy efficiency and water conservation measures at these pilot sites, in an effort to identify the measures that are most effective at California courthouses.
- The pilot projects will be studied and evaluated. Successful measures will be shared with other courts, in an effort to identify appropriate facility modifications and promote operational improvements that are controlled by building occupants. Ideally, courts that might currently be hesitant to move forward with particular energy efficiency and water conservation measures will be more willing to engage based on the successful results of the pilot projects.
- The major utility companies, i.e. PG&E, SCE and SMUD, have agreed to partner with the Judicial Council. They are offering to bear a significant cost in an effort to support these pilot projects. Investing in the pilot projects will allow us to leverage resources offered by

FY 2016-17 Budget Change Proposal Concept

Office: Real Estate and Facilities Management

Contact: Laura Sainz

these companies, and ideally partner with the utility companies to continue the efforts at other courthouse facilities.

- The pilot projects could ultimately lead to the on-going reduction of utility expenses, which will have a positive impact on the O&M budget in the long-run. Without energy efficiency and water conservation measures, utility expenses will continue to increase and have a growing impact on the O&M budget, further reducing the amount available for day-to-day operations and maintenance.
- In response to Executive Orders B-18-12 and B-29-15, the Executive Branch has been proactively engaged in energy efficiency. Although the Judicial Branch is not subject to these Executive Orders, the Judicial Council would like to send the message that we are also engaged in these efforts.



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Discussion Item 3

Summary:

Discuss seismic studies performed on courthouse facilities and the possibility for a Budget Change Proposal for further seismic efforts.

Supporting Documentation:

- Slides
- List of JCC Owned Buildings with seismic ratings
- 19-K1 seismic report

This page intentionally left blank

Earthquake Peril and California Court Buildings

- California is the most seismically active state in the nation
- It has experienced some of the most destructive earthquakes in modern history
- In 1994, it experienced what was at the time the most costly natural disaster ever to strike in the United States—the Northridge Earthquake
- It is a certainty that more (some even larger) earthquakes will occur in California.
- New USGS Earthquake Study - Californians should expect a magnitude-6.7 quake to occur every 6.3 years somewhere in the state

Seismic safety ratings by Division of State Architect

- This series of definitions was developed by the California State University, the University of California, the California Department of General Services, and the Administrative Office of the Courts from 1995 through 2009
- The seismic requirements for design and assessment are based upon a prescribed Earthquake Hazard Level/Basic Safety Earthquake Levels = BSE-1, BSE-2, BSE-R or BSE-C
- Structural engineering firm of Rutherford & Chekene applied the criteria to court buildings
- Level IV - A building evaluated as meeting or exceeding the requirements of CBC Chapter 34 for Occupancy Category I-III performance criteria.
- Level V - A building evaluated as meeting or exceeding the requirements of CBC Chapter 34 for Occupancy Category I-III performance criteria only if the BSE-R and BSE-C values are reduced to 2/3 of those specified for the site
- Rutherford & Chekene continues to be engaged by the Judicial Council as its primary seismic consultant

Court Buildings

- 307 "owned" buildings
- Total SQ FT = 24,833,313
- Court Occupied SQ FT = 13,781,037
- Number with Seismic Safety Rating of V = 106
- SQ FT Seismic Safety Rating of LEVEL V = 11,832,837 (48% of Total SQ FT)

Seismic Level V

- Number with Seismic Safety Rating of V = 106 (35% of Court Buildings)
- SQ FT Seismic Safety Rating of V = 11,942,027 (48% of Total SQ FT)
- Number of Seismic Level V rated buildings for which the county retains responsibility of seismic related property damage and personal injury loss = 102
- Number of Seismic Level V rated buildings for which the JCC retains responsibility of seismic related property damage and personal injury loss = 4 (San Diego)

RISK OF LOSS

- Modeling assumption = No single loss would exceed \$50,000,000
 - the annual expected loss to all level V buildings was \$17,700,000 at a 75% confidence level
 - \$20,285,000 at a 90% confidence level
- There was a 1% chance of an annual expected loss of up to \$71,000,000
- There was a 0.1% chance of an annual expected loss of up to \$167,000,000
- An expected loss was developed for each level V court building

The 6 most exposed counties are:

- Los Angeles – 20.5% of total expected loss
- Orange – 10.4% of total expected loss
- San Bernardino – 7.62% total of expected loss
- Alameda – 7.16% of total expected loss
- San Francisco – 5.86% of total expected loss
- Ventura – 5.79% of total expected loss

At the time of the study the 5 most exposed buildings were:

- Los Angeles -Stanley Mosk Courthouse / JCC Title / Uninsured
- Los Angeles - Compton Courthouse / JCC Title / Uninsured
- Orange - Lamoreaux Justice Center / County Title / Insured
- San Bernardino - San Bernardino Courthouse Annex / County Title / Insured
- San Francisco - Hall of Justice / County Title / Uninsured

Risk Financing

- 102 Level V buildings - county financial obligation
- 4 Level V buildings – JCC financial obligation
- 40 Level IV or better buildings insured for earthquake damage
- 107 buildings insured for fire following, and sprinkler leakage following an earthquake
- Stafford Act (FEMA and California Office of Emergency Management)
 - ✓ JCC and courts can claim for cost of restoration following an earthquake for up to 75% of damage cost

Judicial Council Financial Exposure

- While third party funds may be available to make repairs in the event of an earthquake there is still substantial financial exposure to the JCC.
- For level V buildings:
 - ✓ The counties should not be considered an immediate source of funds
 - ✓ Emergency response costs must be initially absorbed by the Judicial Council with potential recovery from one of more third parties: county, insurer, FEMA
 - ✓ Both insurance and FEMA provide funds to reimburse JCC expenditures
 - ✓ Both insurance and FEMA are subject to large deductibles: a) insurance = 5% of the damaged building's replacement cost, b) FEMA = 25% of the claimed dollars

For other than level V buildings

- For other than level V buildings
 - ✓ The counties may be a source of funds depending on occupancy shares
 - ✓ Emergency response costs will be absorbed by the JCC with potential recovery for one of more third parties: county, insurer, FEMA
 - ✓ Both insurance and FEMA provide funds to reimburse expenditures made
 - ✓ Both insurance and FEMA are subject to large deductibles: a) insurance = 5% of the damages building's replacement cost, b) FEMA = 25% of the claimed dollars
 - ✓

Possible Path Forward

- Update the expected seismic loss studies completed in 2009 to provide current estimates of expected loss by building, by county, and for the court building portfolio as a whole
- Seek special appropriated funds to correct deficiencies in non-structural components that are not anchored or braced in court buildings such as mechanical, electrical and architectural elements, which can pose significant life-safety risks

Possible Path Forward

- Explore options for funding the seismic upgrading of the court buildings identified as Level V
- As building standards have improved, the risks to occupants posed by the contents of buildings, including furniture and equipment, have become more significant. Regulate and enforce securing the anchoring and bracing of court owned contents
- Establish a special, non-lapsing fund, in which to allocate funds to pay for emergency response costs, and other short-term costs necessary to maintain the basic health and safety systems of a damaged building while long-term restoration funds are obtained

Possible Path Forward

- Explore options for funding the seismic upgrading of the court buildings identified as Level V
- As building standards have improved, the risks to occupants posed by the contents of buildings, including furniture and equipment, have become more significant. Regulate and enforce securing the anchoring and bracing of court owned contents
- Establish a special, non-lapsing fund, in which to allocate funds to pay for emergency response costs, and other short-term costs necessary to maintain the basic health and safety systems of a damaged building while long-term restoration funds are obtained

FY 15-16 First Steps


- Dedicate Statewide Planning to fund a limited seismic study. (Potential \$250k)
- Seismic Study geared towards these deliverables:
 1. Develop a building cost estimate for taking the V to IV.
 2. Comparison of potential risk of damage to cost of renovation.
 3. A prioritized list based on risk and cost that has been developed.
- Review potential BCP concepts for FY 16-17 cycle

This page intentionally left blank

Judicial Council
 List of Owned Buildings
 As of 5/27/15
 By: Maria Topete




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
1	Active	Active	Alameda	BANCRO	01-A1	ABA1	Rene C. Davidson	1225 Fallon St.	Oakland	94612	Owned	Yes	County	Level V	County	
2	Active	Active	Alameda	BANCRO	01-A2	ABA2	County Administration Bldg.	1221 Oak St.	Oakland	94612	Owned	No	County	Level V	County	
3	Active	Active	Alameda	BANCRO	01-B3	ABB3	Wiley W. Manuel Courthouse	661 Washington St.	Oakland	94607	Owned	No	JCC	Acceptable	JCC	
4	Active	Active	Alameda	BANCRO	01-C1	ABC1	John George Psychiatric Pavilion	2060 Fairmont Dr.	San Leandro	94578	Owned	No	County	Not Evaluated	County	
5	Active	Active	Alameda	BANCRO	01-C3	ABC3	Juvenile Justice Center	2500 Fairmont Ave.	San Leandro		Owned	No	County		County	
6	Active	Active	Alameda	BANCRO	01-D1	ABD1	Hayward Hall of Justice	24405 Amador St.	Hayward	94544	Owned	No	JCC	Acceptable	JCC	
7	Active	Active	Alameda	BANCRO	01-D2	ABD2	Winton Bldg.	224 W. Winton Ave.	Hayward	94544	Owned	No	County	Not Evaluated	County	
8	Active	Active	Alameda	BANCRO	01-F1	ABF1	George E. McDonald Hall of Justice	2233 Shoreline Drive	Alameda	94501	Owned	No	JCC	Level V	County	
9	Active	Active	Alameda	BANCRO	01-H1	ABH1	Fremont Hall of Justice	39439 Paseo Padre Pkwy.	Fremont	94538	Owned	No	JCC	Level V	JCC	
10	Active	Active	Alameda	BANCRO	01-I1	ABI1	Edgewater	7751 Edgewater Drive	Oakland	94621	Owned		County		County	
11	Active	Inactive	Alpine	NCRO	02-A1	ACA1	Alpine County Courthouse	14777 State Route 89	Markleeville	96120	Owned	Yes	County	Level V	County	
12	Active	Active	Amador	NCRO	03-C1	ADC1	New Amador County Courthouse	500 Argonaut Lane	Jackson		Owned		JCC	Acceptable	JCC	
13	Active	Active	Butte	NCRO	04-A1	AEA1	Butte County Courthouse	1 Court St.	Oroville	95965	Owned	No	JCC	Acceptable	County	
14	Active	Active	Butte	NCRO	04-A3	AEA3	Juvenile Hall	41 County Center Dr.	Oroville	95965	Owned	No	County	Not Evaluated	County	
15	Active	Active	Butte	NCRO	04-D1	AED1	Chico Courthouse	655 Oleander Ave.	Chico	95926	Owned	No	JCC	Level V	JCC	
16	Active	Active	Butte	NCRO	04-E1	AEE1	Paradise Courthouse	747 Elliot Rd.	Paradise	95969	Owned	No	County	Level V	County	
17	Active	Active	Butte	NCRO	04-F1	AEF1	New North Butte County Courthouse	1775 Concord Avenue	Chico		Owned		JCC		JCC	
18	Active	Active	Calaveras	NCRO	05-C1	AFC1	New San Andreas Courthouse	400 Government Center Drive	San Andreas	95249	Owned	No	JCC	Acceptable	JCC	
19	Active	Inactive	Colusa	NCRO	06-A1	AGA1	Historic Courthouse	547 Market St.	Colusa	95932	Owned	Yes	County	Not Evaluated	County	
20	Active	Active	Colusa	NCRO	06-A2	AGA2	Courthouse Annex	532 Oak St.	Colusa	95932	Owned	No	County	Not Evaluated	County	
21	Active	Active	Colusa	NCRO	06-A3	AGA3	Family Law (the Bunker)	547 Market Street	Colusa		Owned	No	County	Not Evaluated	County	
22	Active	Active	Contra Costa	BANCRO	07-A10	AHAA	File Unit	1111 Ward Street	Martinez	94553	Owned	No	County	Not Evaluated	County	
23	Active	Active	Contra Costa	BANCRO	07-A14	AHAE	Family Law Center	751 Pine Street	Martinez	94553	Owned		JCC	Not Evaluated	County	
24	Active	Active	Contra Costa	BANCRO	07-A2	AHA2	Wakefield Taylor Courthouse	725 Court St.	Martinez	94553	Owned	Yes	JCC	Level V	JCC	
25	Active	Active	Contra Costa	BANCRO	07-A3	AHA3	Bray Courts	1020 Ward St.	Martinez	94553	Owned	No	JCC	Acceptable	County	
26	Active	Active	Contra Costa	BANCRO	07-A4	AHA4	Jail Annex	1010 Ward St.	Martinez	94553	Owned	No	County	Acceptable	County	
27	Active	Active	Contra Costa	BANCRO	07-B1	AHB1	Juvenile Hall	202 Glacier Dr.	Martinez	94553	Owned	No	County	Not Evaluated	County	
28	Active	Active	Contra Costa	BANCRO	07-C1	AHC1	Danville District Courthouse	640 Ygnacio Valley Rd.	Walnut Creek	94596	Owned	No	JCC	Level V	JCC	
29	Active	Active	Contra Costa	BANCRO	07-C3	AHC3	2020 North Broadway	2020 North Broadway	Walnut Creek	94596	Owned		County	Not Evaluated	County	
30	Active	Active	Contra Costa	BANCRO	07-D1	AHD1	Concord-Mt. Diablo District	2970 Willow Pass Rd.	Concord	94519	Owned	No	JCC	Acceptable	JCC	
31	Active	Active	Contra Costa	BANCRO	07-E3	AHE3	Richard E. Arnason Justice Center	1000 Center Drive	Pittsburg	94565	Owned		JCC		JCC	
32	Active	Active	Contra Costa	BANCRO	07-F1	AHF1	George D. Carroll Courthouse	100 37th St.	Richmond	94805	Owned	Yes	JCC	Level V	JCC	
33	Active	Active	Contra Costa	BANCRO	07-F2	AHF2	Archival Storage	100 38th St.	Richmond	94805	Owned	No	JCC Delegated to County	Not Evaluated	County	
34	Active	Active	Del Norte	BANCRO	08-A1	AIA1	Del Norte County Superior Court	450 'H' St.	Crescent City	95531	Owned	No	JCC	Acceptable	County	
35	Active	Active	Del Norte	BANCRO	08-A2	AIA2	Del Norte County Sheriff's Building	650 5th St.	Crescent City	95531	Owned	No	County	Not Evaluated	County	
36	Active	Active	El Dorado	NCRO	09-A1	AJA1	Main St. Courthouse	495 Main St.	Placerville	95667	Owned	Yes	JCC	Level V	County	




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
37	Active	Active	El Dorado	NCRO	09-B1	AJB1	Bldg. C	2850 Fairlane Court	Placerville	95667	Owned	No	County	Not Evaluated	County	
38	Active	Active	El Dorado	NCRO	09-C1	AJC1	Cameron Park	3321 Cameron Park Dr.	Cameron Park	95682	Owned	No	JCC	Acceptable	JCC	
39	Active	Active	El Dorado	NCRO	09-E1	AJE1	Johnson Bldg.	1354 Johnson Blvd.	South Lake Tahoe	96150	Owned	No	JCC	Level V	County	
40	Active	Active	El Dorado	NCRO	09-G1	AJG1	Juvenile Hall	295 Fair Lane	Placerville	95667	Owned	No	County		County	
41	Active	Active	Fresno	NCRO	10-A1	BAA1	Fresno County Courthouse	1100 Van Ness Ave.	Fresno	93724	Owned	No	JCC	Level V	County	
42	Active	Active	Fresno	NCRO	10-B1	BAB1	North Annex Jail	1255 M St.	Fresno	93721	Owned	No	JCC Delegated to County	Acceptable	County	
43	Active	Active	Fresno	NCRO	10-F1	BAF1	Reedley Court	815 G St.	Reedley	93654	Owned	No	JCC	Acceptable	JCC	Closed or Vacant
44	Active	Active	Fresno	NCRO	10-G1	BAG1	Clovis Court	1011 5th St.	Clovis	93612	Owned	No	JCC	Not Evaluated	JCC	Closed or Vacant
45	Active	Active	Fresno	NCRO	10-K1	BAK1	Firebaugh Court	1325 O St.	Firebaugh	93622	Owned	No	JCC	Not Evaluated	JCC	Closed or Vacant
46	Active	Active	Fresno	NCRO	10-O1	BAO1	B.F. Sisk Federal Courthouse	1130 O Street	Fresno		Owned	No	JCC	Not Evaluated	JCC	
47	Active	Active	Glenn	NCRO	11-A1	BBA1	Historic Courthouse	526 West Sycamore St.	Willows	95988	Owned	Yes	JCC	Level V	JCC	
48	Active	Active	Glenn	NCRO	11-A4	BBA4	Historic Courthouse Addition	526 West Sycamore Street	Willows	95988	Owned		JCC		JCC	Closed or Vacant
49	Active	Active	Glenn	NCRO	11-B1	BBB1	Orland Superior Court	821 E. South St.	Orland	95963	Owned	No	County	Acceptable	County	
50	Active	Active	Humboldt	BANCRO	12-A1	BCA1	Humboldt County Courthouse (Eureka)	825 Fifth St.	Eureka	95501	Owned	No	County	Not Evaluated	County	
51	Active	Active	Humboldt	BANCRO	12-B1	BCB1	John Hayes Memorial Veterans Hall	483 Conger St.	Garberville	95542	Owned	Yes	County	Not Evaluated	County	
52	Active	Active	Humboldt	BANCRO	12-D1	BCD1	Juvenile Courtroom	2002 Harrison Ave.	Eureka	95501	Owned	No	County	Not Evaluated	County	
53	Active	Active	Humboldt	BANCRO	12-E1	BCE1	Hoopa Courthouse	Highway 96	Hoopa	95546	Owned	Yes	County	Not Evaluated	County	
54	Active	Active	Imperial	SRO	13-A1	BDA1	Imperial County Courthouse	939 W. Main St.	El Centro	92243	Owned	No	JCC	Level V	County	
55	Active	Active	Imperial	SRO	13-D1	BDD1	Winterhaven Court	2124 Winterhaven Dr.	Winterhaven	92283	Owned	No	JCC	Not Evaluated	JCC	
56	Active	Active	Imperial	SRO	13-E2	BDE2	Brawley Court	220 E. Main St.	Brawley		Owned		County	Not Evaluated	County	
57	Active	Active	Inyo	NCRO	14-A1	BEA1	Inyo Historic Courthouse	168 N. Edwards St.	Independence	93526	Owned	Yes	County	Level V	County	
58	Active	Active	Kern	SRO	15-A1	BFA1	Bakersfield Superior Court	1415 Truxtun Ave, 1315 Truxtun Ave, 1661 L Street	Bakersfield	93301	Owned	No	JCC	Level V	County	
59	Active	Active	Kern	SRO	15-B1	BFB1	Bakersfield Justice Bldg.	1215 Truxtun Ave.	Bakersfield	93301	Owned	No	County	Level V	County	
60	Active	Active	Kern	SRO	15-C1	BFC1	Bakersfield Juvenile Center	2100 College Ave.	Bakersfield	93305	Owned	No	JCC	Acceptable	County	
61	Active	Active	Kern	SRO	15-D1	BFD1	Delano/North Kern Court	1122 Jefferson St.	Delano	93215	Owned	No	JCC	Acceptable	JCC	
62	Active	Active	Kern	SRO	15-E1	BFE1	Shafter/Wasco Courts Bldg.	325 Central Valley Hwy	Shafter	93263	Owned	No	JCC	Acceptable	JCC	
63	Active	Active	Kern	SRO	15-F1	BFF1	Taft Courts Bldg.	311 N Lincoln St.	Taft	93268	Owned	No	JCC	Acceptable	JCC	
64	Active	Active	Kern	SRO	15-H1	BFH1	Arvin/ Lamont Branch	12022 Main St.	Lamont	93241	Owned	No	JCC	Level V	County	
65	Active	Active	Kern	SRO	15-I1	BFI1	Mojave-Main Court Facility	1773 Hwy. 58	Mojave	93501	Owned	No	County	Acceptable	County	
66	Active	Active	Kern	SRO	15-I2	BFI2	Mojave-County Administration Bldg.	1775 Hwy. 58	Mojave	93501	Owned	No	County	Acceptable	County	
67	Active	Active	Kern	SRO	15-J1	BFJ1	Ridgecrest-Main Facility	132 East Coso St.	Ridgecrest	93555	Owned	No	County	Acceptable	County	
68	Active	Active	Kern	SRO	15-J2	BFJ2	Ridgecrest - Division B Courtroom	420 N China Lake Blvd.	Ridgecrest	93555	Owned	No	JCC	Not Evaluated	JCC	
69	Active	Active	Kings	NCRO	16-A1	BGA1	Hanford Building A	1426 South Drive	Hanford	93230	Owned	No	JCC	Level V	County	
70	Active	Active	Kings	NCRO	16-A2	BGA2	Hanford Building B	1426 South Drive	Hanford	93230	Owned	No	JCC	Acceptable	County	
71	Active	Active	Kings	NCRO	16-A3	BGA3	Hanford Building C	1426 South Drive	Hanford	93230	Owned	No	JCC	Acceptable	County	

Judicial Council
List of Owned Buildings
As of 5/27/15
By: Maria Topete




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
72	Active	Active	Kings	NCRO	16-A4	BGA4	Probation Building	1424 Forum Dr. Dept 8	Hanford	93230	Owned	No	JCC	Acceptable	County	
73	Active	Active	Kings	NCRO	16-C1	BGC1	Avenal Court	501 E. Kings St..	Avenal	93204	Owned	No	JCC	Acceptable	JCC	
74	Active	Active	Kings	NCRO	16-D1	BGD1	Corcoran Court	1000 Chittenden Ave.	Corcoran	93212	Owned	No	JCC	Acceptable	JCC	
75	Active	Active	Lake	BANCRO	17-A3	BHA3	Lakeport Court Facility	255 N. Forbes St.	Lakeport	95453	Owned	No	County	Level V	County	
76	Active	Active	Lake	BANCRO	17-B1	BHB1	South Civic Center	7000A S. Center Dr.	Clearlake	95422	Owned	No	JCC	Level V	JCC	
77	Active	Active	Lassen	NCRO	18-C1	BIC1	New Susanville Courthouse	2610 Riverside Drive	Susanville	96130	Owned	No	JCC	Acceptable	JCC	
78	Active	Active	Los Angeles	SRO	19-AC1	BKA1	San Fernando Courthouse	900 Third Street	San Fernando	91340	Owned	No	JCC	Acceptable	County	
79	Active	Active	Los Angeles	SRO	19-AD1	BKA7	Santa Clarita Courthouse	23747 West Valencia Boulevard	Santa Clarita	91355	Owned	No	County	Level V	County	
80	Active	Active	Los Angeles	SRO	19-AD2	BKA8	Santa Clarita Administrative Center	23757 West Valencia Boulevard	Santa Clarita	91355	Owned	No	County	Not Evaluated	County	
81	Active	Active	Los Angeles	SRO	19-AE1	BKA9	Alfred J. McCourtney Juvenile Justice Center	1040 West Avenue J	Lancaster	93534	Owned	No	County	Level V	County	
82	Active	Active	Los Angeles	SRO	19-AF1	BKAG	Sylmar Juvenile Court	16350 Filbert Street	Sylmar	91342	Owned	No	County	Level V	County	
83	Active	Active	Los Angeles	SRO	19-AG1	BLA6	Compton Courthouse	200 West Compton Boulevard	Compton	90220	Owned	No	JCC	Level V	JCC	
84	Active	Active	Los Angeles	SRO	19-AI1	BLAH	Los Padrinos Juvenile Court	7281 East Quill Drive	Downey	90242	Owned	No	County	Acceptable	County	
85	Active	Active	Los Angeles	SRO	19-AK1	BLAI	Norwalk Courthouse	12720 Norwalk Boulevard	Norwalk	90650	Owned	No	JCC	Level V	County	
86	Active	Active	Los Angeles	SRO	19-AL1	BLAK	Bellflower Courthouse	10025 East Flower Street	Bellflower	90706	Owned	No	JCC	Not Evaluated	County	
87	Active	Active	Los Angeles	SRO	19-AM1	BLAL	Downey Courthouse	7500 East Imperial Highway	Downey	90242	Owned	No	JCC	Level V	County	
88	Active	Active	Los Angeles	SRO	19-AN1	BJA1	David V. Kenyon Juvenile Justice Center	7625 South Central Avenue	Los Angeles	90001	Owned	No	County	Not Evaluated	County	
89	Active	Active	Los Angeles	SRO	19-AO1	BLAN	Whittier Courthouse	7339 Painter Avenue	Whittier	90602	Owned	No	JCC	Level V	County	
90	Active	Active	Los Angeles	SRO	19-AP1	BLAR	Santa Monica Courthouse	1725 Main Street	Santa Monica	90401	Owned	No	JCC	Level V	JCC	
91	Active	Active	Los Angeles	SRO	19-AP3	BLAY	Santa Monica Court Annex	1725 Main St.	Santa Monica		Owned		JCC	Not Evaluated	JCC	
92	Active	Active	Los Angeles	SRO	19-AQ1	BKAI	Beverly Hills Courthouse	9355 Burton Way	Beverly Hills	90210	Owned	No	JCC	Level V	JCC	
93	Active	Active	Los Angeles	SRO	19-AR1	BJA2	West Los Angeles Courthouse	1633 Purdue Avenue	Los Angeles	90025	Owned	No	JCC	Level V	JCC	
94	Active	Active	Los Angeles	SRO	19-AR2	BJA5	Jury Assembly Trailer	1633 Purdue Ave.	Los Angeles	90025	Owned	No	JCC	Not Evaluated	JCC	
95	Active	Active	Los Angeles	SRO	19-AR3	BJA6	Former Jury Assembly Trailer	1633 Purdue Ave.	Los Angeles	90025	Owned	No	JCC	Not Evaluated	JCC	
96	Active	Active	Los Angeles	SRO	19-AR4	BJA7	Small Claims Court - 99A	1633 Purdue Ave.	Los Angeles	90025	Owned	No	JCC	Not Evaluated	JCC	
97	Active	Active	Los Angeles	SRO	19-AR6	BJA3	Parking Lot West Los Angeles Courthouse	1633 Purdue Avenue	Los Angeles		Owned		JCC		JCC	
98	Active	Active	Los Angeles	SRO	19-AS1	BKAK	Malibu Courthouse	23525 Civic Center Way	Malibu	90265	Owned	No	County	Level V	County	
99	Active	Active	Los Angeles	SRO	19-AU1	BJA9	Airport Courthouse	11701 South La Cienega Boulevard	Los Angeles	90045	Owned	No	JCC	Not Evaluated	County	
100	Active	Active	Los Angeles	SRO	19-AV1	BJAB	Hall of Records	320 West Temple Street	Los Angeles	90012	Owned	No	County	Level V	County	
101	Active	Active	Los Angeles	SRO	19-AV3	BJAC	County Records Center	222 North Hill Street	Los Angeles	90012	Owned		County		County	
102	Active	Active	Los Angeles	SRO	19-AX1	BKAN	Van Nuys Courthouse East	6230 Sylmar Avenue	Van Nuys	91401	Owned	No	JCC	Acceptable	JCC	
103	Active	Active	Los Angeles	SRO	19-AX2	BKAR	Van Nuys Courthouse West	14400 Erwin Street Mall	Van Nuys	91401	Owned	No	JCC	Level V	JCC	
104	Active	Active	Los Angeles	SRO	19-AY1	BKAU	Chatsworth Courthouse	9425 Penfield Avenue	Chatsworth	91311	Owned	No	JCC	Not Evaluated	County	

Judicial Council
 List of Owned Buildings
 As of 5/27/15
 By: Maria Topete




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
105	Active	Active	Los Angeles	SRO	19-AZ1	BKAW	Michael D. Antonovich Antelope Valley Courthouse	42011 4th Street West	Lancaster	93534	Owned	No	JCC	Not Evaluated	County	
106	Active	Active	Los Angeles	SRO	19-C1	BLC1	Torrance Courthouse	825 Maple Avenue	Torrance	90503	Owned	No	JCC	Level V	JCC	
107	Active	Active	Los Angeles	SRO	19-C2	BLC2	Torrance Annex	3221 Torrance Boulevard	Torrance	90503	Owned	No	JCC	Level V	JCC	
108	Active	Active	Los Angeles	SRO	19-C3	BLC3	S. Bay Muni Court Jury Assembly Trailer	825 Maple Dr.	Torrance	90503	Owned	No	JCC	Not Evaluated	JCC	
109	Active	Active	Los Angeles	SRO	19-C4	BLC4	S. Bay Municipal Traffic Court Trailer	825 Maple Dr.	Torrance	90503	Owned	No	JCC	Not Evaluated	JCC	
110	Active	Active	Los Angeles	SRO	19-E1	BLE1	Inglewood Juvenile Court	110 Regent Street	Inglewood	90301	Owned	No	JCC	Level V	JCC	
111	Active	Active	Los Angeles	SRO	19-F1	BLF1	Inglewood Courthouse	One Regent Street	Inglewood	90301	Owned	No	JCC	Level V	JCC	
112	Active	Active	Los Angeles	SRO	19-F2	BLF2	East Parking Structure	One E. Regent Street	Inglewood	90301	Owned	No	JCC		JCC	
113	Active	Active	Los Angeles	SRO	19-F3	BLF3	West Parking Structure	One W. Regent Street	Inglewood	90301	Owned	No	JCC		JCC	
114	Active	Active	Los Angeles	SRO	19-G1	BKG1	Burbank Courthouse	300 East Olive	Burbank	91502	Owned	No	JCC	Level V	County	
115	Active	Active	Los Angeles	SRO	19-H1	BKH1	Glendale Courthouse	600 East Broadway	Glendale	91206	Owned	No	JCC	Level V	JCC	
116	Active	Active	Los Angeles	SRO	19-I1	BKI1	Alhambra Courthouse	150 West Commonwealth Avenue	Alhambra	91801	Owned	No	JCC	Level V	County	
117	Active	Active	Los Angeles	SRO	19-J1	BKJ1	Pasadena Courthouse	300 East Walnut Street	Pasadena	91101	Owned	No	JCC	Level V	County	
118	Active	Active	Los Angeles	SRO	19-K1	BJK1	Stanley Mosk Courthouse	111 North Hill Street	Los Angeles	90012	Owned	No	JCC	Level V	JCC	
119	Active	Active	Los Angeles	SRO	19-L1	BJL1	Clara Shortridge Foltz Criminal Justice Center	210 West Temple Street	Los Angeles	90012	Owned	No	JCC	Level V	JCC	
120	Active	Active	Los Angeles	SRO	19-N1	BLN1	Monrovia Training Center	300 W. Maple Ave.	Monrovia	91016	Owned	No	JCC	Acceptable	JCC	
121	Active	Active	Los Angeles	SRO	19-O1	BKO1	El Monte Courthouse	11234 East Valley Boulevard	El Monte	91731	Owned	No	JCC	Level V	JCC	
122	Active	Active	Los Angeles	SRO	19-O2	BKO2	Parking Structure-El Monte Courthouse-	11228 E. Valley Blvd	El Monte	91731	Owned		JCC		JCC	
123	Active	Active	Los Angeles	SRO	19-P1	BLP1	Mental Health Court	1150 North San Fernando Road	Los Angeles	90065	Owned	No	JCC	Level V	JCC	
124	Active	Active	Los Angeles	SRO	19-Q1	BKQ1	Edmund D. Edelman Children's Court	201 Centre Plaza Drive	Monterey Park	91754	Owned	No	JCC	Acceptable	JCC	
125	Active	Active	Los Angeles	SRO	19-Q2	BKQ2	Parking Structure-Edelman Court	201 Centre Plaza Drive	Monterey Park		Owned		JCC		JCC	
126	Active	Active	Los Angeles	SRO	19-R1	BLR1	Eastlake Juvenile Court	1601 Eastlake Avenue	Los Angeles	90033	Owned	No	County	Level V	County	
127	Active	Active	Los Angeles	SRO	19-S1	BLS1	Hollywood Courthouse	5925 Hollywood Boulevard	Los Angeles	90028	Owned	No	JCC	Level V	JCC	
128	Active	Active	Los Angeles	SRO	19-T1	BLT1	Metropolitan Courthouse	1945 South Hill Street	Los Angeles	90007	Owned	No	JCC	Level V	JCC	
129	Active	Active	Los Angeles	SRO	19-U1	BLU1	Central Arraignment Courts	429 Bauchet Street	Los Angeles	90012	Owned	No	County	Level V	County	
130	Active	Active	Los Angeles	SRO	19-V1	BLV1	East Los Angeles Courthouse	4848 E. Civic Center Way	East Los Angeles	90022	Owned	No	JCC	Level V	County	
131	Active	Active	Los Angeles	SRO	19-W1	BLW1	Pomona Courthouse South	400 Civic Center Plaza	Pomona	91766	Owned	No	JCC	Level V	JCC	
132	Active	Active	Los Angeles	SRO	19-W2	BLW4	Pomona Courthouse North	350 West Mission Boulevard	Pomona	91766	Owned	No	JCC	Level V	JCC	
133	Active	Active	Los Angeles	SRO	19-W3	BLW2	Parking Lot 78-Pomona Court Public Parking	350 W. 7th St.	Pomona		Owned		JCC		JCC	
134	Active	Active	Los Angeles	SRO	19-X1	BKX1	West Covina Courthouse	1427 West Covina Parkway	West Covina	91790	Owned	No	County	Level V	County	

Judicial Council
List of Owned Buildings
As of 5/27/15
By: Maria Topete




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
135	Active	Active	Los Angeles	SRO	19-Y2	BLY2	Parking Structure Lot 67 Long Beach	101 Magnolia Ave	Long Beach		Owned		JCC		JCC	
136	Active	Active	Los Angeles	SRO	19-Y3	BJY3	Long Beach Courthouse Modular	415 W. Ocean Blvd.	Long Beach	90802	Owned	No	JCC		JCC	
137	Active	Active	Los Angeles	SRO	19-Y5	BJY5	Governor George Deukmejian Courthouse	275 Magnolia Ave.	Long Beach	90802	Owned	No	Landlord	Acceptable	JCC	
138	Active	Active	Los Angeles	SRO	19-Z1	BLZ1	San Pedro Courthouse	505 South Centre Street	San Pedro	90731	Owned	No	JCC	Level V	JCC	
139	Active	Active	Madera	NCRO	20-A1	CAA1	Madera County Superior Court	209 W. Yosemite Ave.	Madera	93637	Owned	Yes	JCC	Level V	County	
140	Active	Active	Madera	NCRO	20-D1	CAD1	Sierra Courthouse	40601 Road 274	Bass Lake	93604	Owned	No	JCC	Acceptable	County	
141	Active	Active	Madera	NCRO	20-F1	CAF1	New Madera Courthouse	200 South G Street	Madera	93637	Owned		JCC		JCC	
142	Active	Active	Madera	NCRO	20-F2		New Madera Courthouse Parking Garage	220-224 South G Street	Madera	93637	Owned		JCC		JCC	
143	Active	Inactive	Marin	BANCRO	21-A1	CBA1	Civic Center Courthouse	3501 Civic Center Dr.	San Rafael	94903	Owned	Yes	County	Not Evaluated	County	
144	Active	Active	Marin	BANCRO	21-B1	CBB1	Juvenile Detention	16 Jeanette Prandi Way	San Rafael	94903	Owned	No	County	Not Evaluated	County	
145	Active	Inactive	Mariposa	NCRO	22-A1	CCA1	Mariposa County Courthouse	5088 Bullion St.	Mariposa	95338	Owned	Yes	County	Acceptable	County	
146	Active	Active	Mendocino	BANCRO	23-A1	CDA1	County Courthouse	100 N. State St.	Ukiah	95482	Owned	No	JCC	Level V	County	
147	Active	Active	Mendocino	BANCRO	23-B1	CDB1	Ft. Bragg Justice Center	700 S. Franklin St.	Fort Bragg	95437	Owned	No	County	Acceptable	County	
148	Active	Active	Merced	NCRO	24-A1	CEA1	Old Court	627 W. 21st Street	Merced	95340	Owned	Yes	JCC	Acceptable	JCC	
149	Active	Active	Merced	NCRO	24-A8	CEA8	New Downtown Merced Courthouse	2260 N Street	Merced	95340	Owned	No	JCC	Not Evaluated	County	
150	Active	Active	Merced	NCRO	24-D1	CED1	Los Banos Courtroom	445 I Street	Los Banos	93635	Owned	No	County	Level V	County	
151	Active	Active	Merced	NCRO	24-E1	CEE1	Iris Garrett Juvenile Justice Correctional Complex	2840 W. Sandy Mush Road	Merced	95340	Owned		County	Not Evaluated	County	
152	Active	Active	Modoc	NCRO	25-A1	CFA1	Barclay Justice Center	205 S. East Street	Alturas	96101	Owned	No	JCC	Level V	JCC	
153	Active	Inactive	Modoc	NCRO	25-A2	CFA2	Modoc County Courthouse	204 S. Court St.	Alturas	96101	Owned	Yes	County	Level V	County	
154	Active	Active	Mono	NCRO	26-B2	CGB2	New Mammoth Lakes Courthouse	100 Thompsons Way	Mammoth Lakes	93546	Owned	No	JCC		JCC	
155	Active	Active	Monterey	BANCRO	27-A1	CHA1	Salinas Courthouse- North Wing	240 Church St.	Salinas	93901	Owned	No	JCC	Level V	County	
156	Active	Active	Monterey	BANCRO	27-B1	CHB1	Marina Courthouse	3180 Del Monte Blvd.	Marina	93933	Owned	No	JCC	Not Evaluated	JCC	
157	Active	Active	Monterey	BANCRO	27-C1	CHC1	Monterey Courthouse	1200 Aguajito Rd.	Monterey	93940	Owned	No	County	Level V	County	
158	Active	Active	Monterey	BANCRO	27-D1	CHD1	King City Courthouse	250 Franciscan Way	King City	93930	Owned	No	County	Level V	County	
159	Active	Active	Monterey	BANCRO	27-E1	CHE1	Juvenile Courthouse	1422 Natividad Rd.	Salinas	93906	Owned	No	County	Not Evaluated	County	
160	Active	Active	Napa	BANCRO	28-A1	CIA1	Criminal Court Building	1111 Third St.	Napa	94559	Owned	No	JCC	Not Evaluated	County	
161	Active	Active	Napa	BANCRO	28-B1	CIB1	Historic Courthouse	825 Brown St.	Napa	94559	Owned	Yes	JCC	Level V	County	
162	Active	Active	Napa	BANCRO	28-C1	CIC1	Napa Juvenile Court	2350 Old Sonoma Rd.	Napa	94559	Owned	No	JCC	Not Evaluated	County	
163	Active	Active	Nevada	NCRO	29-A1	CJA1	Nevada City Courthouse	201 Church St.	Nevada City	95959	Owned	Yes	County	Level V	County	
164	Active	Active	Nevada	NCRO	29-A2	CJA2	Nevada City Courthouse Annex	201 Church St.	Nevada City	95959	Owned	No	County	Level V	County	
165	Active	Active	Nevada	NCRO	29-B1	CJB1	Joseph Center	10075 Levon Ave	Truckee	96160	Owned	No	County	Acceptable	County	
166	Active	Active	Orange	SRO	30-A1	DAA1	Central Justice Center	700 Civic Center Dr W.	Santa Ana	92701	Owned	No	JCC	Acceptable	JCC	
167	Active	Active	Orange	SRO	30-A2	DAA2	Central Justice Center Annex	909 North Main St.	Santa Ana	92701	Owned	No	County	Not Evaluated	County	
168	Active	Active	Orange	SRO	30-A3	DAA3	Civil Complex Center ("CXC")	751 W. Santa Ana Blvd.	Santa Ana	92701	Owned	No	JCC	Not Evaluated	JCC	
169	Active	Active	Orange	SRO	30-A5	DAA5	Flower Street Parking Lot	Southeast corner of Flower Street and Civic Center	Santa Ana	92701	Owned	No	JCC Delegated to County	Not Evaluated	JCC	

Judicial Council
List of Owned Buildings
As of 5/27/15
By: Maria Topete




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
170	Active	Active	Orange	SRO	30-B1	DAB1	Betty Lou Lamoreaux Justice Center	341 The City Dr.	Orange	92868	Owned	No	JCC	Level V	County	
171	Active	Active	Orange	SRO	30-B2	DAB2	Computer Systems Trailer	331 The City Drive South	Orange	92868	Owned	No	County	Not Evaluated	County	
172	Active	Active	Orange	SRO	30-C1	DAC1	North Justice Center	1275 N. Berkeley Ave.	Fullerton	92832	Owned	No	JCC	Level V	County	
173	Active	Active	Orange	SRO	30-D1	DAD1	West Justice Center	8141-8144 13th St.	Westminster	92683	Owned	No	JCC	Level V	County	
174	Active	Active	Orange	SRO	30-E1	DAE1	Harbor Justice Center-Newport Beach Facility	4601 Jamboree Road	Newport Beach	92660	Owned	No	JCC	Level V	County	
175	Active	Active	Placer	NCRO	31-A1	DBA1	Historic Courthouse	101 Maple Ave	Auburn	95603	Owned	Yes	County	Acceptable	County	
176	Active	Active	Placer	NCRO	31-B2	DBB2	County Jail	2775 Richardson Dr	Auburn	95603	Owned	No	County	Not Evaluated	County	
177	Active	Active	Placer	NCRO	31-B3	DBB3	Juvenile Hall	11270 'B' Ave	Auburn	95603	Owned	No	County	Not Evaluated	County	
178	Active	Active	Placer	NCRO	31-F1	DBF1	Tahoe City Courthouse	2501 North Lake Blvd.	Tahoe City	96145	Owned	No	JCC Delegated to County	Not Evaluated	County	
179	Active	Active	Placer	NCRO	31-H1	DBH1	Bill Santucci Justice Center	10820 Justice Center Dr	Roseville	95678	Owned	No	JCC	Not Evaluated	County	
180	Active	Inactive	Plumas	NCRO	32-A1	DCA1	Quincy Courthouse	520 Main St.	Quincy	95971	Owned	Yes	County	Level V	County	
181	Active	Active	Plumas	NCRO	32-B2	DCB2	Plumas/Sierra Regional Courthouse	600 South Gulling Street	Portola	96122	Owned	No	JCC		JCC	
182	Active	Active	Plumas	NCRO	32-C1	DCC1	Chester Civic Complex	222 First St.	Chester	96020	Owned	No	County	Not Evaluated	County	
183	Active	Active	Plumas	NCRO	32-D1	DCD1	Greenville Justice Court	115 Hwy 89	Greenville	95947	Owned	No	County	Not Evaluated	County	
184	Active	Active	Riverside	SRO	33-A1	DDA1	Family Law Court	4175 Main St.	Riverside	92501	Owned	No	JCC	Not Evaluated	County	
185	Active	Inactive	Riverside	SRO	33-A2	DDA2	1903/1933 Courthouse	4050 Main St.	Riverside	92501	Owned	Yes	County	Level V	County	
186	Active	Active	Riverside	SRO	33-A3	DDA3	Hall of Justice	4100 Main St.	Riverside	92501	Owned	No	JCC	Acceptable	County	
187	Active	Active	Riverside	SRO	33-C1	DDC1	Larson Justice Center	46-200 Oasis Street	Indio	92201	Owned	No	JCC	Not Evaluated	County	
188	Active	Active	Riverside	SRO	33-C3	DDC3	Indio Juvenile Court	47-671 Oasis St.	Indio		Owned	No	County	Not Evaluated	County	
189	Active	Active	Riverside	SRO	33-D1	DDD1	Blythe Courthouse - Superior Court	265 N. Broadway	Blythe	92225	Owned	No	JCC	Not Evaluated	County	
190	Active	Active	Riverside	SRO	33-E1	DDE1	Palm Springs Courts	3255 E. Tahquitz Canyon Way	Palm Springs	92262	Owned	No	County	Level V	County	
191	Active	Active	Riverside	SRO	33-F1	DDF1	Hemet	880 N. State St.	Hemet	92343	Owned	No	JCC	Level V	County	
192	Active	Active	Riverside	SRO	33-G4	DDG4	New Riverside Mid-County Courthouse.	311 East Ramsey	Banning	92220	Owned		JCC		JCC	
193	Active	Active	Riverside	SRO	33-H1	DDH1	Temecula	41002 County Center Dr.	Temecula	92591	Owned	No	County	Acceptable	County	
194	Active	Active	Riverside	SRO	33-J1	DDJ1	Corona	505 S. Buena Vista	Corona	92882	Owned	No	County	Level V	County	
195	Active	Active	Riverside	SRO	33-M1	DDM1	Southwest Justice Center	30755 Auld Road	Murrieta		Owned	No	JCC	Not Evaluated	County	
196	Active	Active	Riverside	SRO	33-N1	DDN1	Riverside Juvenile Court	9991 County Farm Rd.	Riverside	92503	Owned	No	JCC	Level V	County	
197	Active	Active	Sacramento	NCRO	34-A1	DEA1	Gordon Schaber Sacramento Superior Court	720 Ninth St.	Sacramento	95814	Owned	No	JCC	Level V	JCC	
198	Active	Active	Sacramento	NCRO	34-A5	DEA5	Lorenzo E. Patino Hall of Justice	651 I St.	Sacramento	95814	Owned	No	County	Not Evaluated	County	
199	Active	Active	Sacramento	NCRO	34-A7	DEA7	OCIT	799 G Street. Sacramento	Sacramento	95814	Owned		County	Not Evaluated	County	
200	Active	Active	Sacramento	NCRO	34-C2	DEC2	Juvenile Courthouse	9605 Kiefer Road	Sacramento	95827	Owned		JCC		County	
201	Active	Active	Sacramento	NCRO	34-D1	DED1	Carol Miller Justice Center Court Facility	301 Bicentennial Circle	Sacramento	95826	Owned	No	JCC	Level V	JCC	
202	Active	Active	San Benito	BANCRO	35-B1	DFB1	Juvenile Courtroom	708 Flynn Rd.	Hollister	95023	Owned	No	County	Not Evaluated	County	

Judicial Council
List of Owned Buildings
As of 5/27/15
By: Maria Topete




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
203	Active	Active	San Benito	BANCRO	35-C1	DFC1	New Hollister Courthouse	450 Fourth Street	Hollister	95023	Owned	No	JCC		JCC	
204	Active	Active	San Bernardino	SRO	36-A1	DGA1	San Bernardino Courthouse	351 N. Arrowhead Ave	San Bernardino	92415	Owned	Yes	JCC	Level V	County	
205	Active	Active	San Bernardino	SRO	36-A2	DGA2	San Bernardino Courthouse - Annex	351 N. Arrowhead Ave	San Bernardino	92415	Owned	No	JCC	Level V	County	
206	Active	Active	San Bernardino	SRO	36-C1	DGC1	Fontana Courthouse	17780 Arrow Blvd.	Fontana	92335	Owned	No	JCC	Level V	County	
207	Active	Active	San Bernardino	SRO	36-C2	DGC2	Fontana Jury Assembly Room	17830 Arrow Blvd.	Fontana	92335	Owned	No	County	Not Evaluated	County	
208	Active	Active	San Bernardino	SRO	36-C3	DGC3	Fontana Jury Assembly Building	17782 Arrow Blvd.	Fontana	92335	Owned	No	JCC		JCC	Closed or Vacant
209	Active	Active	San Bernardino	SRO	36-E1	DGE1	Joshua Tree Courthouse	6527 White Feather Rd.	Joshua Tree	92252	Owned	No	County	Level V	County	
210	Active	Active	San Bernardino	SRO	36-E2	DGE2	Joshua Tree Modular	6525 White Feather Rd.	Joshua Tree	92252	Owned/Leased	No	JCC		JCC	
211	Active	Active	San Bernardino	SRO	36-F1	DGF1	Rancho Cucamonga Courthouse	8303 Haven Ave.	Rancho Cucamonga	91730	Owned	No	County	Acceptable	County	
212	Active	Active	San Bernardino	SRO	36-G1	DGG1	Chino Courthouse	13260 Central Ave.	Chino	91710	Owned	No	County	Acceptable	County	
213	Active	Active	San Bernardino	SRO	36-I1	DGI1	Big Bear Courthouse	477 Summit Blvd.	Big Bear Lake	92315	Owned	No	County	Not Evaluated	County	
214	Active	Active	San Bernardino	SRO	36-J1	DGJ1	Barstow Courthouse	235 East Mountain View Street	Barstow	92311	Owned	No	JCC	Acceptable	County	
215	Active	Active	San Bernardino	SRO	36-K1	DGK1	Needles Courthouse/Clerk's Office	1111 Bailey St., Civic Center Complex	Needles	92363	Owned	No	County	Acceptable	County	
216	Active	Active	San Bernardino	SRO	36-K2	DGK2	Needles Courthouse-Dept. N-1	1111 Bailey St., Civic Center Complex	Needles	92363	Owned		County	Not Evaluated	County	
217	Active	Active	San Bernardino	SRO	36-L1	DGL1	Victorville Courthouse-Dept. N-1	14455 Civic Dr.	Victorville	92392	Owned	No	County	Level V	County	
218	Active	Active	San Bernardino	SRO	36-M1	DGM1	Mental Health Office and Courtroom	400 N. Pepper Ave.	Colton	92324	Owned	No	County	Not Evaluated	County	
219	Active	Active	San Bernardino	SRO	36-O2	DG02	E. Gilbert Campus-Juvenile Court	790 E. Gilbert St., Building 9	San Bernardino	92415	Owned	No	County	Not Evaluated	County	
220	Active	Active	San Bernardino	SRO	36-O3	DG03	E. Gilbert Campus-Court Technology	790 E. Gilbert St., Building 11	San Bernardino	92415	Owned	No	County	Not Evaluated	County	
221	Active	Active	San Bernardino	SRO	36-P1	DGP1	Juvenile Dependency Courthouse	860 E. Gilbert St.	San Bernardino	92415	Owned		JCC	Not Evaluated	County	
222	Active	Active	San Bernardino	SRO	36-R1	DGR1	San Bernardino Justice Center	247 West Third Street	San Bernardino	92401	Owned	No	JCC	Acceptable	JCC	
223	Active	Active	San Diego	SRO	37-A1	DHA1	County Courthouse	220 West Broadway	San Diego	92101	Owned	No	JCC	Level V	JCC	
224	Active	Active	San Diego	SRO	37-A2	DHA2	Hall of Justice	330 West Broadway	San Diego	92101	Owned	No	County	Not Evaluated	County	
225	Active	Active	San Diego	SRO	37-A3	DHA3	Old Jail	220 West "C" Street	San Diego	92101	Owned		JCC		JCC	Closed or Vacant
226	Active	Active	San Diego	SRO	37-B1	DHB1	Madge Bradley Bldg.	1409 Fourth Ave	San Diego	92101	Owned	No	JCC Delegated to County	Not Evaluated	County	
227	Active	Active	San Diego	SRO	37-C1	DHC1	Kearny Mesa Court	8950 Clairemont Mesa Blvd.	San Diego	92123	Owned	No	JCC	Level V	JCC	

Judicial Council
List of Owned Buildings
As of 5/27/15
By: Maria Topete




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
228	Active	Active	San Diego	SRO	37-C2	DHC2	Kearny Mesa Traffic Court KM3 Trailer	8950 Clairemont Mesa Blvd.	San Diego	92123	Owned	No	JCC	Not Evaluated	JCC	
229	Active	Active	San Diego	SRO	37-C3	DHC3	Kearny Mesa Traffic Court KM4 Trailer	8950 Clairemont Mesa Blvd.	San Diego	92123	Owned	No	JCC	Not Evaluated	JCC	
230	Active	Active	San Diego	SRO	37-C4	DHC4	Kearny Mesa Traffic Court KM5 & KM6 Trailer	8950 Clairemont Mesa Blvd.	San Diego	92123	Owned		JCC		JCC	
231	Active	Active	San Diego	SRO	37-D1	DHD1	Family Court	1501-1555 Sixth Ave	San Diego	92101	Owned		County	Level V	County	
232	Active	Active	San Diego	SRO	37-E1	DHE1	Juvenile Court	2851 Meadow Lark Dr.	San Diego	92123	Owned	No	JCC	Acceptable	JCC	
233	Active	Active	San Diego	SRO	37-E2	DHE2	Department 11	2901 Meadow Lark Dr.	San Diego	92123	Owned	No	County	Not Evaluated	County	
234	Active	Active	San Diego	SRO	37-E3	DHE3	Department 9 Trailer	2851 Meadow Lark Dr.	San Diego	92123	Owned	No	JCC	Not Evaluated	JCC	
235	Active	Active	San Diego	SRO	37-E4	DHE4	Department 10 Trailer	2851 Meadow Lark Dr.	San Diego	92123	Owned	No	JCC	Not Evaluated	JCC	
236	Active	Active	San Diego	SRO	37-F1	DHF1	North County Regional Center - South	325 South Melrose Drive	Vista	92081	Owned	No	County	Not Evaluated	County	
237	Active	Active	San Diego	SRO	37-F2	DHF2	North County Regional Center - North	325 South Melrose Drive	Vista	92081	Owned	No	JCC	Level V	JCC	
238	Active	Active	San Diego	SRO	37-F3	DHF3	North County Regional Center - Annex	325 South Melrose Drive	Vista	92081	Owned	No	JCC	Level V	JCC	
239	Active	Active	San Diego	SRO	37-F4	DHF4	Trailer - Dept 34	325 South Melrose Drive	Vista	92081	Owned	No	JCC	Not Evaluated	JCC	
240	Active	Active	San Diego	SRO	37-F5	DHF5	Trailer - Dept 35	325 South Melrose Drive	Vista	92081	Owned	No	JCC	Not Evaluated	JCC	
241	Active	Active	San Diego	SRO	37-F6	DHF6	Trailer - Storage A	325 South Melrose Drive	Vista	92081	Owned	No	JCC	Not Evaluated	JCC	
242	Active	Active	San Diego	SRO	37-F7	DHF7	Trailer - Family Support	325 South Melrose Drive	Vista	92081	Owned	No	JCC	Not Evaluated	JCC	
243	Active	Active	San Diego	SRO	37-H1	DHH1	South County Regional Center	500 Third Ave.	Chula Vista	91910	Owned	No	County	Level V	County	
244	Active	Active	San Diego	SRO	37-I1	DHI1	East County Regional Center	250 E. Main St.	El Cajon	92020	Owned	No	JCC	Level V	JCC	
245	Active	Active	San Francisco	BANCRO	38-A1	DIA1	Civic Center Courthouse	400 McAllister St.	San Francisco	94102	Owned	No	JCC	Not Evaluated	County	
246	Active	Active	San Francisco	BANCRO	38-B1	DIB1	Hall of Justice	850 Bryant St.	San Francisco	94103	Owned	No	County	Level V	County	
247	Active	Active	San Francisco	BANCRO	38-C1	DIC1	Youth Guidance Center	375 Woodside Ave.	San Francisco	94127	Owned	No	JCC	Not Evaluated	County	
248	Active	Active	San Francisco	BANCRO	38-C3	DIC3	Family Justice Center Site - Bldg 1	375 Woodside Avenue	San Francisco	94127	Owned		County		County	
249	Active	Active	San Francisco	BANCRO	38-C4	DIC4	Family Justice Center Site - Bldg 2	375 Woodside Avenue	San Francisco	94127	Owned		County		County	
250	Active	Active	San Francisco	BANCRO	38-C5	DIC5	Family Justice Center Site - Bldg 3	375 Woodside Avenue	San Francisco	94127	Owned		County		County	
251	Active	Active	San Joaquin	NCRO	39-A1	DJA1	Stockton Courthouse	222 E. Weber Ave.	Stockton	95202	Owned	No	County	Level V	County	
252	Active	Active	San Joaquin	NCRO	39-B1	DJB1	French Camp Juvenile Justice Center	535 W. Mathews Rd.	French Camp	95231	Owned	No	County	Acceptable	County	
253	Active	Active	San Joaquin	NCRO	39-C1	DJC1	Manteca Branch Court	315 E. Center St.	Manteca	95336	Owned	No	JCC	Acceptable	JCC	
254	Active	Active	San Joaquin	NCRO	39-D2	DJD2	Lodi Branch- Dept. 2	315 W. Elm St.	Lodi	95240	Owned	No	JCC	Acceptable	JCC	
255	Active	Active	San Joaquin	NCRO	39-E1	DJE1	Tracy Branch Courthouse	475 E. 10th St.	Tracy	95376	Owned	No	JCC	Acceptable	JCC	
256	Active	Active	San Joaquin	NCRO	39-E2	DJE2	Tracy Modular 1: Support	475 East Tenth St.	Tracy	95376	Owned	No	JCC	Not Evaluated	JCC	
257	Active	Active	San Joaquin	NCRO	39-E3	DJE3	Tracy Modular 2: Courtroom	475 East Tenth St.	Tracy	95376	Owned	No	JCC	Not Evaluated	JCC	
258	Active	Active	San Joaquin	NCRO	39-E4	DJE4	Tracy Agriculture Building	503 East Tenth St.	Tracy	95376	Owned	No	JCC	Not Evaluated	JCC	
259	Active	Active	San Luis Obispo	SRO	40-A1	EAA1	Courthouse Annex	1035 Palm St.	San Luis Obispo	93408	Owned	No	County	Level V	County	




	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
260	Active	Active	San Luis Obispo	SRO	40-B1	EAB1	Veterans Memorial Bldg.	801 Grand Ave.	San Luis Obispo	93401	Owned	No	County	Not Evaluated	County	
261	Active	Active	San Luis Obispo	SRO	40-C1	EAC1	Juvenile Services Center	1065 Kansas Ave.	San Luis Obispo	93408	Owned	No	JCC Delegated to County	Not Evaluated	County	
262	Active	Active	San Luis Obispo	SRO	40-E1	EAE1	Grover Beach Branch	214 S 16th St.	Grover Beach	93433	Owned	No	JCC	Not Evaluated	County	
263	Active	Active	San Luis Obispo	SRO	40-G1	EAG1	Records Storage	1144 Monterey St.	San Luis Obispo	93408	Owned		County		County	
264	Active	Active	San Luis Obispo	SRO	40-H1	EAH1	1070 Palm St.	1070 Palm St.	San Luis Obispo	93408	Owned		JCC		JCC	
265	Active	Active	San Luis Obispo	SRO	40-I1	EAI1	Camp Storage	1475 Kansas Avenue	San Luis Obispo		Owned		County		County	
266	Active	Active	San Luis Obispo	SRO	40-J1	EAJ1	Paso Robles Courthouse	901 Park Street	Paso Robles	93446	Owned		JCC		County	
267	Active	Active	San Mateo	BANCRO	41-A1	EBA1	Hall of Justice	400 County Center	Redwood City	94063	Owned		County	Acceptable	County	
268	Active	Active	San Mateo	BANCRO	41-A2	EBA2	Traffic/ Small Claims Annex	500 County Center	Redwood City	94063	Owned	No	JCC	Level V	County	
269	Active	Active	San Mateo	BANCRO	41-B1	EBB1	Central Branch	800 North Humboldt St.	San Mateo	94401	Owned	No	JCC	Level V	County	
270	Active	Active	San Mateo	BANCRO	41-C1	EBC1	Northern Branch Courthouse	1050 Mission Rd.	South San Francisco	94080	Owned	No	JCC	Level V	JCC	
271	Active	Active	San Mateo	BANCRO	41-C2	EBC2	Northern Branch Jail Annex	1050 Mission Rd.	South San Francisco	94080	Owned	No	JCC Delegated to County	Not Evaluated	County	
272	Active	Active	San Mateo	BANCRO	41-F1	EBF1	Juvenile Branch, Paul Scannell Drive	222 Paul Scannell Drive	San Mateo	94402	Owned	No	County		County	
273	Active	Inactive	Santa Barbara	SRO	42-A1	ECA1	Santa Barbara County Courthouse	1100 Anacapa St.	Santa Barbara	93101	Owned	Yes	N/A	Level V	County	
274	Active	Active	Santa Barbara	SRO	42-B1	ECB1	Figueroa Division	118 E. Figueroa St.	Santa Barbara	93101	Owned	No	JCC	Level V	JCC	
275	Active	Active	Santa Barbara	SRO	42-B2	ECB2	Santa Barbara Court Trailer	118 E. Figueroa St.	Santa Barbara	93101	Owned	No	County	Not Evaluated	County	
276	Active	Active	Santa Barbara	SRO	42-C1	ECC1	Santa Barbara Juvenile Court	4500 Hollister Ave.	Santa Barbara	93110	Owned	No	JCC	Not Evaluated	County	
277	Active	Active	Santa Barbara	SRO	42-D1	ECD1	Lompoc Division	115 Civic Center Plaza	Lompoc	93436	Owned	No	County	Level V	County	
278	Active	Active	Santa Barbara	SRO	42-E1	ECE1	Solvang Superior Court	1745 Mission Drive	Solvang	93463	Owned	No	County	Not Evaluated	County	
279	Active	Active	Santa Barbara	SRO	42-F1	ECF1	Santa Maria Courts Bldgs C + D	312 E. Cook St.	Santa Maria	99454	Owned	No	JCC	Level V	County	
280	Active	Active	Santa Barbara	SRO	42-F3	ECF3	Santa Maria Courts, Bldgs. A + B	312 E. Cook St.	Santa Maria		Owned	No	JCC	Level V	County	
281	Active	Active	Santa Barbara	SRO	42-F4	ECF4	Santa Maria Courts, Bldg F	312 E. Cook St.	Santa Maria		Owned	No	JCC	Not Evaluated	County	

Judicial Council
 List of Owned Buildings
 As of 5/27/15
 By: Maria Topete



	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
282	Active	Active	Santa Barbara	SRO	42-F5	ECF5	Santa Maria Courts, Bldg G	312 E. Cook St.	Santa Maria		Owned	No	JCC	Not Evaluated	County	
283	Active	Active	Santa Barbara	SRO	42-G1	ECG1	Santa Barbara Jury Assembly Bldg.	1108 Santa Barbara	Santa Barbara	93101	Owned	No	JCC	Not Evaluated	JCC	
284	Active	Active	Santa Barbara	SRO	42-H1	ECH1	Santa Maria Juvenile Court (new)	4285 California Blvd.	Santa Maria	93455	Owned	No	JCC	Not Evaluated	County	
285	Active	Active	Santa Clara	BANCRO	43-A1	EDA1	Hall of Justice (East)	190 W. Hedding	San Jose	95110	Owned	No	JCC	Acceptable	County	
286	Active	Active	Santa Clara	BANCRO	43-A2	EDA2	Hall of Justice (West)	200 W. Hedding	San Jose	95110	Owned	No	JCC	Acceptable	County	
287	Active	Active	Santa Clara	BANCRO	43-A3	EDA3	Juvenile Delinquency Court	840 Guadalupe Pkwy.	San Jose	95110	Owned	No	JCC Delegated to County	Not Evaluated	County	
288	Active	Active	Santa Clara	BANCRO	43-B1	EDB1	Downtown Superior Court	191 N. First St.	San Jose	95113	Owned	No	JCC	Acceptable	JCC	
289	Active	Active	Santa Clara	BANCRO	43-B2	EDB2	Historic Courthouse	161 N. First St.	San Jose	95113	Owned	Yes	JCC	Acceptable	JCC	
290	Active	Active	Santa Clara	BANCRO	43-D1	EDD1	Palo Alto Courthouse	270 Grant St.	Palo Alto	94306	Owned	No	JCC	Acceptable	County	
291	Active	Active	Santa Clara	BANCRO	43-F1	EDF1	Sunnyvale Courthouse	605 W. El Camino Real	Sunnyvale	94087	Owned	No	JCC	Acceptable	JCC	
292	Active	Active	Santa Clara	BANCRO	43-G1	EDG1	Santa Clara Courthouse	1095 Homestead Rd.	Santa Clara	95050	Owned	No	JCC	Acceptable	JCC	
293	Active	Active	Santa Clara	BANCRO	43-N1	EDN1	Morgan Hill Courthouse	301 Diana Avenue	Morgan Hill		Owned	No	JCC	Not Evaluated	County	
294	Active	Active	Santa Cruz	BANCRO	44-A1	EEA1	Main Courthouse	701 Ocean St.	Santa Cruz	95060	Owned	No	JCC	Level V	County	
295	Active	Active	Santa Cruz	BANCRO	44-A2	EEA2	County Administration Bldg.	701 Ocean St.	Santa Cruz	95060	Owned	No	County	Level V	County	
296	Active	Active	Santa Cruz	BANCRO	44-A3	EEA3	Jury Assembly Room	701 Ocean Street	Santa Cruz	95060	Owned	No	JCC	Not Evaluated	County	
297	Active	Active	Santa Cruz	BANCRO	44-C1	EEC1	Jail Courtroom	259 Water St.	Santa Cruz	95060	Owned	No	JCC Delegated to County	Not Evaluated	County	
298	Active	Active	Santa Cruz	North America	44-D1	EED1	Juvenile Court	3650 Graham Hill Rd.	Felton	95018	Owned	No	County	Not Evaluated	County	
299	Active	Active	Shasta	NCRO	45-A1	EFA1	Main Courthouse	1500 Court St.	Redding	96001	Owned		JCC	Level V	County	
300	Active	Active	Shasta	NCRO	45-A2	EFA2	Justice Center	1655 West St.	Redding	96001	Owned	No	County	Not Evaluated	County	
301	Active	Active	Shasta	NCRO	45-A7	EFA7	Courthouse Annex	1500 Court St.	Redding	96001	Owned	No	JCC	Level V	County	
302	Active	Active	Shasta	NCRO	45-B1	EFB1	Shasta County Superior Court/Sheriff's Station	20509-C Shasta St.	Burney	96013	Owned	No	County	Level V	County	
303	Active	Active	Shasta	NCRO	45-C1	EFC1	Juvenile Hall	2680 Radio Lane	Redding	96001	Owned	No	County	Not Evaluated	County	
304	Active	Inactive	Shasta	NCRO	45-E2	EFE2	1505 Court Street	1505 Court Street	Redding		Owned		JCC		JCC	
305	Active	Active	Sierra	NCRO	46-A1	EGA1	Courthouse/Sheriff Station-Jail	100 Courthouse Square	Downieville	95936	Owned	Yes	County	Level V	County	
306	Active	Active	Siskiyou	NCRO	47-A1	EHA1	Siskiyou County Courthouse	311 Fourth St.	Yreka	96097	Owned	Yes	County	Level V	County	
307	Active	Active	Siskiyou	NCRO	47-B1	EHB1	Dorris	324 N. Pine St.	Dorris	96023	Owned	No	JCC	Acceptable	JCC	
308	Active	Active	Solano	BANCRO	48-A1	EIA1	Hall of Justice	600 Union Ave.	Fairfield	94533	Owned	Yes	JCC	Level V	County	
309	Active	Active	Solano	BANCRO	48-A2	EIA2	Law and Justice Center	530 Union Ave.	Fairfield	94533	Owned		County	Acceptable	County	
310	Active	Active	Solano	BANCRO	48-A3	EIA3	Old Solano Courthouse	580 Texas Street	Fairfield		Owned		JCC	Not Evaluated	JCC	
311	Active	Active	Solano	BANCRO	48-B1	EIB1	Solano Justice Building	321 Tuolumne St.	Vallejo	94590	Owned		County	Level V	County	
312	Active	Active	Sonoma	BANCRO	49-A1	EJA1	Hall of Justice	600 Administration Dr.	Santa Rosa	95403	Owned	No	County	Level V	County	
313	Active	Active	Sonoma	BANCRO	49-A2	EJA2	Main Adult Detention Facility	2777 Ventura Avenue	Santa Rosa	95403	Owned		County		County	
314	Active	Active	Sonoma	BANCRO	49-D2	EJD2	Juvenile Justice Center	7425 Rancho Los Guilicos Rd.	Santa Rosa	95409	Owned		County		County	
315	Active	Active	Stanislaus	NCRO	50-A1	FAA1	Modesto Main Courthouse	800 11th Street	Modesto	95354	Owned	Yes	JCC	Acceptable	JCC	
316	Active	Active	Stanislaus	NCRO	50-A2	FAA2	Hall of Records	1100 I Street	Modesto	95353	Owned		JCC	Level V	JCC	

Judicial Council
 List of Owned Buildings
 As of 5/27/15
 By: Maria Topete



	Building Record Status	Building Status	County	Region	Building ID	Oracle ID	Building Name	Address	City	Zip Code	Owned/Leased	Historic	Managing Party	Siesmic Status	Title Holder	Comments
317	Active	Active	Stanislaus	NCRO	50-B1	FAB1	Modesto Juvenile Court	2215 Blue Gum Avenue	Modesto	95358	Owned	No	JCC Delegated to County	Acceptable	County	
318	Active	Active	Stanislaus	NCRO	50-C1	FAC1	Ceres Superior Court	2744 Second St.	Ceres	95307	Owned	No	JCC	Level V	JCC	
319	Active	Active	Stanislaus	NCRO	50-D1	FAD1	Turlock Superior Court	300 Starr Ave.	Turlock	95380	Owned	No	JCC	Acceptable	County	
320	Active	Active	Sutter	NCRO	51-A1	FBA1	Courthouse West	446 Second St.	Yuba City	95991	Owned	Yes	JCC	Level V	County	
321	Active	Active	Sutter	NCRO	51-A2	FBA2	Courthouse East	463 Second St.	Yuba City	95991	Owned	No	JCC	Level V	County	
322	Active	Active	Tehama	NCRO	52-A3	FCA3	Annex No. 2	445 Pine Street	Red Bluff	96080	Owned	No	JCC	Acceptable	County	
323	Active	Active	Tehama	NCRO	52-B1	FCB1	Superior Court at Corning	720 Hoag St.	Corning	96021	Owned	No	JCC	Acceptable	JCC	
324	Active	Inactive	Trinity	NCRO	53-A1	FDA1	Trinity County Courthouse	11 Court Street	Weaverville	96093	Owned	Yes	County	Level V	County	
325	Active	Active	Trinity	NCRO	53-E1	FDE1	Hayfork Courthouse	6641 B State Hwy 3	Hayfork	96041	Owned		County	Not Evaluated	County	
326	Active	Active	Tulare	NCRO	54-A1	FEA1	Visalia Superior Court	221 South Mooney Blvd.	Visalia	93291	Owned	No	County	Level V	County	
327	Active	Active	Tulare	NCRO	54-B1	1-Feb	Tulare Division	425 E. Kern St.	Tulare	93274	Owned		JCC	Acceptable	County	
328	Active	Active	Tulare	NCRO	54-C1	FEC1	Porterville Courthouse	87 E. Morton Ave.	Porterville	93257	Owned		County	Level V	County	
329	Active	Active	Tulare	NCRO	54-D1	FED1	William Silveria Jr. Juvenile Justice Center	11200 Ave. 368	Visalia	93291	Owned	No	County	Not Evaluated	County	
330	Active	Active	Tulare	NCRO	54-E1	FEE1	Dinuba Division of the Tulare Superior Court	640 South Alta Ave.	Dinuba	93618	Owned	No	JCC	Not Evaluated	County	
331	Active	Active	Tulare	NCRO	54-F1	FEF1	Adult Pre-Trial Court	36650 Road 112	Visalia	93291	Owned	No	County	Not Evaluated	County	
332	Active	Active	Tulare	NCRO	54-I1	FEI1	South County Justice Center	300 East Olive Avenue	Porterville	93257	Owned	No	JCC	Acceptable	JCC	
333	Active	Inactive	Tuolumne	NCRO	55-A1	FFA1	Historic Courthouse	41 W. Yaney	Sonora	95370	Owned	Yes	County	Level V	County	
334	Active	Inactive	Tuolumne	NCRO	55-B1	FFB1	Washington St. Branch	60 North Washington St.	Sonora	95370	Owned	No	County	Not Evaluated	County	
335	Active	Active	Tuolumne	NCRO	55-D1	FFD1	New Sonora Courthouse		Sonora		Owned		JCC		JCC	
336	Active	Active	Ventura	SRO	56-B1	FGB1	East County Courthouse	3855 Alamo Street	Simi Valley	93062	Owned	No	County	Level V	County	
337	Active	Active	Ventura	SRO	56-F1	FGF1	Juvenile Courthouse	4353 Vineyard Ave.	Oxnard		Owned		County	Not Evaluated	County	
338	Active	Inactive	Yolo	NCRO	57-A1	FHA1	Historic Courthouse	725 Court St.	Woodland	95695	Owned	Yes	County	Level V	County	
339	Active	Active	Yolo	NCRO	57-A10	FHAA	New Woodland Courthouse	1000 Main Street	Woodland	95695	Owned		JCC		JCC	
340	Active	Active	Yolo	NCRO	57-A11	FHAB	New Woodland Courthouse Parking	525 & 625 Sixth Street	Woodland	95695	Owned		JCC		JCC	
341	Active	Active	Yolo	NCRO	57-A2	FHA2	Old Jail (Department 9)	213 Third Street	Woodland	95695	Owned	No	County	Acceptable	County	
342	Active	Active	Yolo	NCRO	57-A5	FHA5	Family Support	238 West Beamer Street	Woodland		Owned	No	County	Not Evaluated	County	
343	Active	Active	Yolo	NCRO	57-A8	FHA8	Traffic Court - Modular	275 First Street / 601 Court Street	Woodland		Owned		JCC		JCC	
344	Active	Active	Yuba	NCRO	58-A1	FIA1	Yuba County Courthouse	215 Fifth St.	Marysville	95901	Owned	No	County	Level V	County	
345	Active	Active	Orange	SRO	64-E1	GEE1	601 W. Santa Ana Blvd - 4 DCA 3	601 W. Santa Ana Blvd	Santa Ana	92701	Owned	No	JCC		JCC	
346	Active	Active	Fresno	NCRO	65-A2	GFA2	2424 Ventura Street - 5 DCA	2424 Ventura Street	Fresno	93721	Owned	No	JCC		JCC	
347	Active	Active	Fresno	NCRO	65-A3	GFA3	5th DCA, Fresno, Parking		Fresno		Owned		JCC		JCC	

19-K1-Stanley Mosk



California Court Building Seismic Assessment Program

Building Information Sheet

BLDG. ID 19-K1

Sheet: 1 of

County: Los Angeles County No. 19 Site ID. K Bldg. No. 1
Bldg. Name: Los Angeles County Superior/Municipal Court
Address: 110 N. Grand Avenue City: Los Angeles


Total Area (ft²): 736,200 500 Yr USGS Liquefaction Potential: 0
Level of Seismicity: high S_{a03} 1.52 g S_{a10} 0.50 g Alquist/Priolo: N Site Class: B

Building Photo:



19K01B2.jpg

Site Location Map:





California Court Building Seismic Assessment Program
Initial Screening

Seismic Evaluation Sheet

BLDG. ID 19-K1

Sheet: 2 of

Drawing Title: LA County Courthouse Sheets: 1-535 Date: 5/17/55
(Add'l Dwgs.) _____ Sheets: _____ Date: _____

Supplemental Information: _____ Date: _____
(e.g. Reports/ Previous Evaluations)

Design Code/Date: LA city Code 53 No of Stories: 6 St. + P.H. Ht. Above Grade: 120' ft +
Bsmt Grade change

Single, stand-alone building: Yes No (If No, complete Special Conditions Supplemental sheet)

Additional Comments:

Building Sub-Types	BM Yr.	Story Limit		DSA V+ ¹	TBE	DSA IV- ²
		Moderate	High			
W1 Wood light frame < 3000 ft ²	1976	4	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
W1A Wood light frame > 3000 ft ²	1997	4	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
W2 Commercial/Industrial Wood > 5000 ft ²	1976	4	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
S1 Steel Moment Frame - Rigid Diaphragm	1994	6	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
S1A Steel Moment Frame - Flexible Diaphragm	1994	6	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
S2 Steel Braced Frame - Rigid Diaphragm	1988	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
S2A Steel Braced Frame - Flexible Diaphragm	1988	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
S3 Pre-engineered Steel Light Frame	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="radio"/> S4 Steel Frame with Concrete Shear Walls	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Steel Moment Frame	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
➔ Steel Gravity Frame	1976	6	6	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
S5 Steel Frame with Masonry Infill - Rigid Diaphragm	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
S5A Steel Frame with Masonry Infill - Flexible Diaphragm	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
C1 Concrete Moment Frames	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Beams & Columns	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Slabs & Columns	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pier & Spandrel	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
C2 Concrete Shear Walls	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Concrete Bearing/Shear Walls	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Concrete Gravity Frame w/ Shear Walls	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Exterior Punched Shear Wall	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
C2A C2 with Flexible Diaphragm	1976	6	6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
C3 Concrete Frame with Masonry Infill - Rigid Diaphragm	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
C3A Concrete Frame with Masonry Infill - Flexible Diaphragm	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PC1 Precast/ Tilt-up walls - Flexible Diaphragm	1997	2	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PC1A PC1 with Rigid Diaphragm	1997	2	2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PC2 Precast Frames and Shear Walls	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PC2A PC2 with no walls	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
RM1 R/F Masonry Bearing Wall - Flexible Diaphragm	1997	6	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
RM2 R/F Masonry Bearing Wall - Rigid Diaphragm	1976	6	3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
URM Unreinforced Masonry Bearing Wall - Flexible Diaphragm UCBC 1991	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
URMA Unreinforced Masonry Bearing Wall - Rigid Diaphragm	--	--	--	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

¹ Potentially unable to meet DSA IV or better; complete DSA V+ Supplemental Sheet

² Potentially qualifying for exemption due to benchmark status; complete DSA IV- Supplemental Sheet

Reviewed by: Nabih Joussef Date: 4/23/03
BIU WALLACE



California Court Building Seismic Assessment Program
 Tier 1 Evaluation
 Cover Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/R&C Reviewed By: PCR/HF
 Bldg. Name: Stanley Mosk Courthouse Date: 12/15/03
 Bldg. Address: 111 North Hill St. Los Angeles Page: 1 of 18


Bldg. Ids Included in this report

19-K1-A (West Wing)
 19-K1-B (East Wing)

Document Availability (Drawings, reports, etc.)

Partial set of Architectural and Structural drawings available
 Partial set of Architectural and Structural drawings available

KEY PLAN



BUILDING PHOTOS



West Wing Elevation



Seismic joint viewed from the south courtyard



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Table of Contents

Building ID: 19-K1 By/Firm: Walterio A. López/R&C Reviewed By: PCR/HF
Bldg. Name: Stanley Mosk Courthouse Date: 12/15/03
Bldg. Address: 111 North Hill St. Los Angeles Page: 2 of 18

TABLE OF CONTENTS

ITEM	PAGE
Cover Sheet	1
Table of Contents	2
Summary Sheet	3
Retrofit Concept Sheet	5
Deficiency List	6
Documentation Sheet	7
Data Summary Sheet	8
3.7.6 Basic Structural Checklist For Building Type S4	9
3.7.6S Supplemental Structural Checklist for Building Type S4	12
3.8 Geologic Site Hazard and Foundation Checklist	14
3.9 (Modified) Nonstructural Component Checklist	16
Appendix A – Workshop Results	19



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Summary Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C Date: 12/15/03
Bldg. Name: Stanley Mosk Courthouse Page: 3 of 18

BUILDING DESCRIPTION

Site and Building Configuration

This report has been written to include both the West Wing (19-K1-A) and the East Wing (19-K1-B) structures; the conclusions herein apply to both structures except where noted.

The building was constructed in 1957 on a site sloping from east to west. A seismic joint separates the two wings. The entrance to the East Wing is located on the first floor on 111 North Hill Street while the entrance to the West Wing is located on the fourth floor on 110 North Grand Avenue. A crawl space about 4' high covers the entire East Wing and about 2 bays beyond the seismic joint. The site and foundation are stepped west of the seismic joint. The building is rectangular in plan with the building transitioning into a tower through a setback at the third floor at the East Wing and a similar setback at the sixth floor at the West Wing

Structural System

The building has a concrete slab and structural steel beams and columns system for gravity loads and a combination of cast-in-place concrete shear wall and pier and spandrel lateral-load resisting system. The building consists of an East and a West Wing separated by a 5" wide seismic joint. The building is 7 stories tall in the East Wing and 9 stories tall in the West Wing. The pier and spandrel systems are lightly reinforced and many lines of resistance are not continuous to the foundation. The building skin consists of stone panels attached to the concrete shear walls. Concrete shear walls and individual steel columns rest on continuous and isolated spread footings.

	<u>Original</u>	<u>Addition</u>
Building Condition:	<u>Good overall, wall cracks visible at penthouse levels</u>	
Date of Construction:	<u>May 17, 1955</u>	
Year/Design Code:	<u>1952 UBC</u>	
ASCE 31 Bldg. Type:	<u>S4, Steel frames with concrete shear walls</u>	

SITE DATA

Site Class: B S_{DS}: 1.52 g S_{D1}: 0.53 g
Geologic Hazard(s): **Fault Rupture:** No **Liquefaction:** No **Landslide:** No

OVERALL SEISMIC DEFICIENCIES & EXPECTED SEISMIC PERFORMANCE

The major structural deficiencies can be summarized as weak story, soft story, geometry, vertical discontinuities, existing wall cracks, shear stress check, reinforcing steel, and overturning.

It can be expected that this building will perform poorly during strong ground shaking. It can be expected that the building would exhibit substantial structural damage and possible partial localized collapse of areas where shear walls become discontinuous at the lower levels. During strong ground shaking extensive damage to non-structural components and buildings systems can be expected. Post-earthquake repair may not be cost-effective.

DSA Seismic Risk Level (Tier 1): I II III IV V VI VII

- RECOMMENDATION**
- No Further Study, Assign Risk Level From Tier 1
 - Perform Tier 2 Evaluation (Check applicable box below)
 - Risk Level Can Be Refined
 - Retrofit Concept Can be Refined
 - Field Exploration Required
 - Other (Explain) _____



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Summary Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 4 of 18

Explanation of Tier 2 Objective:

By performing an evaluation using Tier 1 methodology this building is classified as Level V at best. By performing a Tier 2 evaluation, a clearer assessment of the seismic risk classification can be made and retrofit schemes can be studied.



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Retrofit Concept Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 5 of 18

PRELIMINARY RETROFIT CONCEPT

Add full-height interior concrete shear walls to reduce the load demand in the existing brittle, limited-capacity, discontinuous shear walls. Adding new shear walls and strengthening columns supporting discontinuous shear walls would be the minimum retrofit required to mitigate the seismic deficiencies. However, such mitigation would be accompanied by disruption to occupants and therefore may have to be accomplished in phases.

Provide lateral bracing for suspended lath and plaster ceiling in areas of public assembly for more than 50 occupants. Please note that the space above the ceiling was not accessible to verify the method of attachment of the lath and plaster ceiling. Most likely, buildings of this vintage will lack the required bracing for lateral forces. Should future destructive exploration demonstrate the presence of adequate lateral bracing, the above retrofit requirements can be waived.



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Deficiency List

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 6 of 18

DEFICIENCY LIST (Listed in order of importance)

Non-Conforming Checklist Item	Justification to Waive Non-Compliance
Vertical Discontinuities	<u>Do not waive.</u> Shear walls along the longitudinal axis of the building in both wings are discontinuous and so are walls along lines B and Y and over the loading dock.
Weak Story	<u>Do not waive.</u> Because the major shear walls along the longitudinal axis of the building in both wings are discontinuous, the story strength below the discontinuous walls is reduced significantly. The following columns supporting discontinuous shear walls have been identified as presenting life-safety concerns: D/12, K/12, D/1, K/1, Y/4, Y/9, W/4, L/4.
Soft Story	<u>Do not waive.</u> Because the major shear walls along the longitudinal axis of the building in both wings are discontinuous, the story stiffness below the discontinuous walls is reduced significantly
Geometry	<u>Do not waive.</u> The discontinuous shear walls mentioned above create a change in the horizontal dimension of the lateral-load-resisting system of more than 30% from the story where the discontinuity occurs to the level below.
Existing Wall Cracks	<u>Do not waive.</u> Significant wall cracking was reported and mapped in the structural engineering reports cited on page 7. Many of those cracks have since been repaired, with the most visible ones being at penthouse levels.
Reinforcing Steel	<u>Do not waive.</u> $\rho=0.0020$ at many wall locations
Shear Stress Check	<u>Do not waive.</u> The shear demand on many wall elements exceeded their capacities by a factor of at least 2 and at locations as high as 4.
Overturning	<u>Do not waive.</u> Both wings of this building have shear walls in both directions with base/height ratios that are about 60% smaller than what would be required not to trigger the deficiency.
Non-Structural Components	There is a potential to waive this presumed non-compliance. During the site visit, it was not possible to visually confirm attachment of non-structural but they are presumed to be deficient. However, this non-conformance may be waived if visual inspection confirms that non-structural components are adequately attached.



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Documentation Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C Date: 12/15/03
Bldg. Name: Stanley Mosk Courthouse Page: 7 of 18

DOCUMENTATION

Architectural Drawings: Sheets 1 through 21, 21A, 22 through 27 by Stanton, Williams, Austin, Field & Fry Architects dated May 17, 1955.

Structural Drawings: Sheets S1 through S10, S10A, S11 through S35, and S1A through S1C by Brandow & Johnston Structural Engineers dated May 17, 1955.

Other Drawings

Reports: Structural Evaluation Reports 19K1-K1 through 19K1-K3 (Modified Phase 1A Reports) by Rachlin & Rachlin Architects dated February 28, 1996.
Structural Evaluation Report 19K1-K5 (Modified Phase 1B Report) by Rachlin & Rachlin Architects dated April 2, 1996.

Limitations of available documents: No limitations

WALK-THROUGH SITE VISIT

Date of visit: May 20, 2003

Limitation of walk-through: Support of non structural components such as ceilings was not determined.



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Data Summary Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C Date: 12/15/03
Bldg. Name: Stanley Mosk Courthouse Page: 8 of 18

DATA SUMMARY SHEET

BUILDING DATA

Year Built: 1955 Year Remodeled: 2002 Design Code: 1952 UBC
Area (sf): 736,200 Length (ft): 700 Width (ft): 300
No. Stories: 7 East Wing / 9 West Wing Story Height: 16 Total Height: 168

SITE DATA Site Class B F_a 1.0 F_v 1.0 S_1 0.795 S_s 2.278 Level of Seismicity: High

CONSTRUCTION DATA

Gravity Load Structural System: Cast-in-place concrete slab over structural steel beams and columns
Exterior Transverse Walls: Cast-in place concrete walls Opening(s)? No
Exterior Longitudinal Walls: Cast-in place concrete walls Opening(s)? Yes. Punched walls
Roof Materials/Framing: Concrete slab over structural steel beams
Intermediate Floors/Framing: Concrete slab over structural steel beams
Ground Floor: Concrete slab on grade at West Wing, concrete slab over structural steel beams over crawl space at East Wing.
Columns: Structural steel Foundation: _____
General Condition of Structure: Good
Evidence of Settling? No
Special Features and Comments: Seismic joint separating

LATERAL FORCE RESISTING SYSTEM

	<u>Longitudinal</u>	<u>Transverse</u>
ASCE 31-02 Building Type:	<u>S4- steel frame with concrete shear walls</u>	<u>Same</u>
Diaphragms:	<u>Formed concrete slab</u>	
Vertical Elements:	<u>Concrete shear walls and spandrel and piers.</u>	
Connections:	<u>Reinforcing steel for concrete elements; plates, angles, and rivets for steel elements</u>	
Details:		
Building Period, T (sec):	<u>0.72</u>	
Modification Factor, C:	<u>1.0</u>	
Response Spectral Acceleration, S_a :	<u>0.736g</u>	
Seismic Base Shear, V (kips):	<u>58559</u>	
Component Modification Factor, m:	<u>2.5</u>	

CHECKLIST REQUIRED FOR EVALUATION:

Level of Seismicity	Basic Structural (Sec. 3.7)	Supplemental Structural (Sec. 3.7)	Geologic Site Hazard and Foundation (Sec. 3.8)	Nonstructural
Moderate	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
High	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 9 of 18

**3.7.6 BASIC STRUCTURAL CHECKLIST FOR BUILDING TYPE S4:
STEEL FRAMES WITH CONCRETE SHEAR WALLS**

This Basic Structural Checklist shall be completed when required by Table 3-2.

Each of the evaluation statements on this checklist shall be marked compliant (C), non-compliant (NC), or not applicable (N/A) for a Tier 1 Evaluation. Compliant statements identify issues that are acceptable according to the criteria of this standard, while non-compliant statements identify issues that require further investigation. Certain statements may not apply to the buildings being evaluated. For non-compliant evaluation statements, the design professional may choose to conduct further investigation using the corresponding Tier 2 evaluation procedure; the section numbers in parentheses following each evaluation statement correspond to Tier 2 evaluation procedures.

C3.7.6 Basic Structural Checklist for Building Type S4

These buildings consist of a frame assembly of steel beams and steel columns. The floors and roof diaphragms consist of cast-in-place concrete slabs or metal deck with or without concrete fill. Framing consists of steel beams, open web joists or steel trusses. Lateral forces are resisted by cast-in-place concrete shear walls. These walls are bearing walls where the steel frame does not provide a complete vertical support system. In older construction the steel frame is designed for vertical loads only. In modern dual systems, the steel moment frames are designed to work together with the concrete shear walls in proportion to their relative rigidity. In the case of a dual system, the walls shall be evaluated under this building type and the frames shall be evaluated under S1 or S1A, Steel Moment Frames. The steel frame may provide a secondary lateral-force-resisting system depending on the stiffness of the frame and the moment capacity of the beam-column connections.

C	NC	N/A	COMMENT
BUILDING SYSTEM			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	LOAD PATH: The structure shall contain a minimum of one complete load path for Life Safety and Immediate Occupancy for seismic force effects from any horizontal direction that serves to transfer the inertial forces from the mass to the foundation. (Tier 2: Sec. 4.3.1.1)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	MEZZANINES: Interior mezzanine levels shall be braced independently from the main structure, or shall be anchored to the lateral-force-resisting elements of the main structure. (Tier 2: Sec. 4.3.1.3)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	WEAK STORY: The strength of the lateral-force-resisting system in any story shall not be less than 80% of the strength in an adjacent story, above or below, for Life-Safety and Immediate Occupancy. (Tier 2: Sec. 4.3.2.1)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	SOFT STORY: The stiffness of the lateral-force-resisting system in any story shall not be less than 70% of the lateral-force-resisting system stiffness in an adjacent story above or below, or less than 80% of the average lateral-force-resisting system stiffness off the three stories above or below for Life Safety and Immediate Occupancy. (Tier 2: Sec. 4.3.2.2)
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	GEOMETRY: There shall be no changes in horizontal dimension of the lateral-force-resisting system of more than 30% in a story relative to



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 10 of 18

**3.7.6 BASIC STRUCTURAL CHECKLIST FOR BUILDING TYPE S4:
STEEL FRAMES WITH CONCRETE SHEAR WALLS**

C	NC	N/A	COMMENT	
			adjacent stories for Life Safety and Immediate Occupancy, excluding one-story penthouses and mezzanines. (Tier 2: Sec. 4.3.2.3)	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	VERTICAL DISCONTINUITIES: All vertical elements in the lateral-force-resisting system shall be continuous to the foundation. (Tier 2: Sec. 4.3.2.4)	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	MASS: There shall be no change in effective mass more than 50% from one story to the next for Life Safety and Immediate Occupancy. Light roofs, penthouses and mezzanines need not be considered. (Tier 2: Sec. 4.3.2.5)	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	TORSION: The estimated distance between the story center of mass and the story center of rigidity shall be less than 20% of the building width in either plan dimension for Life Safety and Immediate Occupancy. (Tier 2: Sec. 4.3.2.6)	West Wing does not comply. East Wing complies.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DETERIORATION OF STEEL: There shall be no visible rusting, corrosion, cracking or other deterioration in any of the steel elements or connections in the vertical- or lateral-force-resisting systems. (Tier 2: Sec. 4.3.3.3)	Based on existing reports
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DETERIORATION OF CONCRETE: There shall be no visible deterioration of concrete or reinforcing steel in any of the vertical- or lateral-force-resisting elements. (Tier 2: Sec. 4.3.3.4)	Based on existing reports
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	CONCRETE WALL CRACKS: All existing diagonal cracks in wall elements shall be less than 1/8" for Life Safety and 1/16" for Immediate Occupancy, shall not be concentrated in one location, and shall not form an X pattern. (Tier 2: Sec. 4.3.3.9)	Based on existing reports
LATERAL FORCE RESISTING SYSTEM				
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COMPLETE FRAMES: Steel or concrete frames classified as secondary components shall form a complete vertical load carrying system. (Tier 2: Sec. 4.4.1.6.1)	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	REDUNDANCY: The number of lines of shear walls in each principal direction shall be greater than or equal to 2 for Life Safety and Immediate Occupancy. (Tier 2: Sec. 4.4.2.1.1)	



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 11 of 18

**3.7.6 BASIC STRUCTURAL CHECKLIST FOR BUILDING TYPE S4:
STEEL FRAMES WITH CONCRETE SHEAR WALLS**

C	NC	N/A	COMMENT
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>SHEAR STRESS CHECK: The shear stress in the concrete shear walls, calculated using the Quick Check procedure of Section 3.5.3.3, shall be less than the greater of 100 psi or $2 \sqrt{f'c}$ for Life Safety and Immediate Occupancy. (Tier 2: Sec. 4.4.2.2.1)</p> <p>Detailed shear stress checks were performed instead of the quick stress check. In almost all cases, the demand on the wall exceeded the wall capacity by a multiple.</p>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>REINFORCING STEEL: The ratio of reinforcing steel area to gross concrete area shall be not less than 0.0015 in the vertical direction and 0.0025 in the horizontal direction for Life Safety and Immediate Occupancy. The spacing of reinforcing steel shall be equal to or less than 18" for Life Safety and Immediate Occupancy. (Tier 2: Sec. 4.4.2.2.2)</p> <p>$\rho=0.0020$ at many wall locations</p>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<p>COLUMN SPLICES: Steel columns encased in shear wall boundary elements shall have splices that develop the tensile strength of the column. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.4.2.2.9)</p>
CONNECTIONS			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>TRANSFER TO SHEAR WALLS: Diaphragms shall be connected for transfer of loads to the shear walls for Life Safety and the connections shall be able to develop the lesser of the shear strength of the walls for Immediate Occupancy. (Tier 2: Sec. 4.6.2.1)</p>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>FOUNDATION DOWELS: Wall reinforcement shall be doweled into the foundation for Life Safety and the dowels shall be able to develop the lesser of the strength of the walls or the uplift capacity of the foundation for Immediate Occupancy. (Tier 2: Sec. 4.6.3.5)</p>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>SHEAR-WALL-BOUNDARY COLUMNS: The shear wall boundary columns shall be anchored to the building foundation for Life Safety and the anchorage shall be able to develop the tensile capacity of the column for Immediate Occupancy. (Tier 2: Sec. 4.6.3.6)</p>



California Court Building Seismic Assessment Program
 Tier 1 Evaluation
 Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
 Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
 Page: 12 of 18

**3.7.6S SUPPLEMENTAL STRUCTURAL CHECKLIST FOR BUILDING TYPE S4
 STEEL FRAMES WITH CONCRETE SHEAR WALLS**

This Supplemental Structural Checklist shall be completed when required by Table 3-2. The Basic Structural Checklist shall be completed prior to completing this Supplemental Structural Checklist.

C	NC	N/A	COMMENT
LATERAL FORCE RESISTING SYSTEM			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	COUPLING BEAMS: The stirrups in coupling beams over means of egress shall be spaced at or less than $d/2$ and shall be anchored into the confined core of the beam with hooks of 135° or more for Life Safety. All coupling beams shall comply with the requirements above and shall have the capacity in shear to develop the uplift capacity of the adjacent wall for Immediate Occupancy. (Tier 2: Sec. 4.4.2.2.3)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	OVERTURNING: All shear walls shall have aspect ratios less than 4 to 1. Wall piers need not be considered. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.4.2.2.4)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CONFINEMENT REINFORCING: For shear walls with aspect ratios greater than 2 to 1, the boundary elements shall be confined with spirals or ties with spacing less than $8d_b$. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.4.2.2.5)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	REINFORCING AT OPENINGS: There shall be added trim reinforcement around all wall openings with a dimension greater than three times the thickness of the wall. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.4.2.2.6)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	WALL THICKNESS: Thickness of bearing walls shall not be less than $1/25$ the unsupported height or length, whichever is shorter, nor less than 4". This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.4.2.2.7)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	WALL CONNECTIONS: There shall be a positive connection between the shear walls and the steel beams and columns for Life Safety and the connection shall be able to develop the strength of the walls for Immediate Occupancy. (Tier 2: Sec. 4.4.2.2.8)



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 13 of 18

**3.7.6S SUPPLEMENTAL STRUCTURAL CHECKLIST FOR BUILDING TYPE S4
STEEL FRAMES WITH CONCRETE SHEAR WALLS**

C	NC	N/A	COMMENT
DIAPHRAGMS			
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<p>OPENINGS AT SHEAR WALLS: Diaphragm openings immediately adjacent to the shear walls shall be less than 25% of the wall length for Life Safety and 15% of the wall length for Immediate Occupancy. (Tier 2: Sec. 4.5.1.4)</p> <p>At lines B and Y.</p>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<p>PLAN IRREGULARITIES: There shall be tensile capacity to develop the strength of the diaphragm at re-entrant corners or other locations of plan irregularities. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.5.1.7)</p>
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<p>DIAPHRAGM REINFORCEMENT AT OPENINGS: There shall be reinforcing around all diaphragm openings larger than 50% of the building width in either major plan dimension. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.5.1.8)</p>
CONNECTIONS			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>UPLIFT AT PILE CAPS: Pile caps shall have top reinforcement and piles shall be anchored to the pile caps for Life Safety, and the pile cap reinforcement and pile anchorage shall be able to develop the tensile capacity of the piles for Immediate Occupancy. (Tier 2: Sec. 4.6.3.10)</p> <p>West Wing complies based on information shown on S23, S24. N/A at East Wing.</p>



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 14 of 18

3.8 GEOLOGIC SITE HAZARDS AND FOUNDATIONS CHECKLIST

This Geologic Site Hazards and Foundations Checklist shall be completed when required by Table 3-2.

Each of the evaluation statements on this checklist shall be marked compliant (C), non-compliant (NC), or not applicable (N/A) for a Tier 1 Evaluation. Compliant statements identify issues that are acceptable according to the criteria of this standard, while non-compliant statements identify issues that require further investigation. Certain statements may not apply to the buildings being evaluated. For non-compliant evaluation statements, the design professional may choose to conduct further investigation using the corresponding Tier 2 evaluation procedure; the section numbers in parentheses following each evaluation statement correspond to Tier 2 evaluation procedures.

C	NC	N/A	COMMENT
---	----	-----	---------

GEOLOGIC SITE HAZARDS

The following statements shall be completed for buildings in levels of high or moderate seismicity.

- | | | | |
|-------------------------------------|--------------------------|--------------------------|---|
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | LIQUEFACTION: Liquefaction susceptible, saturated, loose granular soils that could jeopardize the building's seismic performance shall not exist in the foundation soils at depths within 50 feet. under the building for Life Safety and Immediate Occupancy. (Tier 2: Sec. 4.7.1.1) |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | SLOPE FAILURE: The building site shall be sufficiently remote from potential earthquake-induced slope failures or rockfalls to be unaffected by such failures or shall be capable of accommodating any predicted movements without failure. (Tier 2: Sec. 4.7.1.2) |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | SURFACE FAULT RUPTURE: Surface fault rupture and surface displacement at the building site is not anticipated. (Tier 2: Sec. 4.7.1.3) |

CONDITION OF FOUNDATIONS

The following statement shall be completed for all Tier 1 building evaluations.

- | | | | | |
|-------------------------------------|--------------------------|--------------------------|--|----------------------------|
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | FOUNDATION PERFORMANCE: There shall be no evidence of excessive foundation movement such as settlement or heave that would affect the integrity or strength of the structure. (Tier 2: Sec. 4.7.2.1) | Based on existing reports. |
|-------------------------------------|--------------------------|--------------------------|--|----------------------------|

The following statement shall be completed for buildings in levels of high or moderate seismicity being evaluated to the Immediate Occupancy Performance Level.

- | | | | | |
|--------------------------|--------------------------|-------------------------------------|---|----------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | DETERIORATION: There shall not be evidence that foundation elements have deteriorated due to corrosion, sulfate attack, material breakdown, or other reasons in a manner that would affect the integrity or strength of the structure. (Tier 2: Sec. 4.7.2.2) | Based on existing reports. |
|--------------------------|--------------------------|-------------------------------------|---|----------------------------|



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 15 of 18

3.8 GEOLOGIC SITE HAZARDS AND FOUNDATIONS CHECKLIST

CAPACITY OF FOUNDATIONS

The following statement shall be completed for all Tier 1 building evaluations.

- POLE FOUNDATIONS:** Pole foundations shall have a minimum embedment depth of 4 ft. for Life Safety and Immediate Occupancy. (Tier 2: Sec. 4.7.3.1)

The following statements shall be completed for buildings in levels of moderate seismicity being evaluated to the Immediate Occupancy Performance Level and for buildings in levels of high seismicity.

- OVERTURNING:** The ratio of the effective horizontal dimension of the lateral-force-resisting system at the foundation level to the building height (base/height) shall be greater than 0.6Sa. (Tier 2: Sec. 4.7.3.2)
- TIES BETWEEN FOUNDATION ELEMENTS:** The foundation shall have ties adequate to resist seismic forces where footings, piles, and piers are not restrained by beams, slabs, or soils classified as Class A, B, or C. (Tier 2: Sec. 4.7.3.3)
- DEEP FOUNDATIONS:** Piles and piers shall be capable of transferring the lateral forces between the structure and the soil. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.7.3.4)
- SLOPING SITES:** The difference in foundation embedment depth from one side of the building to another shall not exceed one story in height. This statement shall apply to the Immediate Occupancy Performance Level only. (Tier 2: Sec. 4.7.3.5)



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 16 of 18

3.9 (Modified) NONSTRUCTURAL COMPONENT CHECKLIST

C	NC	N/A	COMMENT
URM PARTITIONS			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	UNREINFORCED MASONRY: Unreinforced masonry or hollow clay tile partitions shall be adequately braced at a spacing of equal to or less than 10 ft in levels of low and moderate seismicity and 6 ft. in regions of high seismicity or shall be installed tight from floor to floor. Such walls shall not have a height to thickness ratio of greater than 15:1. (Tier 2: Sec. 4.8.1.1)
CLADDING AND GLAZING			
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	SUSPENDED LATH AND PLASTER: Ceilings over assembly areas for more than 50 occupants consisting of suspended lath and plaster or gypsum board shall be attached to resist seismic forces for every 12 square feet of area. (Tier 2: Sec. 4.8.2.4) Presumed to be non-compliant. Visual confirmation could not take place during site visit.
CLADDING AND GLAZING			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CLADDING ANCHORS: Cladding components weighing more than 10 psf shall be mechanically anchored to the exterior wall framing at a spacing equal to or less than 4 ft. A spacing of up to 6 ft is permitted where only the Basic Nonstructural Checklist is required by Table 3-2. (Tier 2: Sec. 4.8.4.1)
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	DETERIORATION: There shall be no evidence of deterioration, damage or corrosion in any of the connection elements. (Tier 2: Sec. 4.8.4.2) Presumed to be compliant. Visual confirmation could not take place during site visit.
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CLADDING ISOLATION: For moment frame buildings of steel or concrete, panel connections shall be detailed to accommodate a story drift ratio of 0.02. Panel connection detailing for a story drift ration of 0.01 is permitted where only the Basic Nonstructural Checklist is required by Table 3-2. (Tier 2: Sec. 4.8.4.3)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	MULTISTORY PANELS: For multistory panels attached at each floor level, panel connections shall be detailed to accommodate a drift ratio of 0.02. Panel connection detailing for a story drift ration of 0.01 is permitted where only the Basic Nonstructural Checklist is required by Table 3-2. (Tier 2: Sec. 4.8.4.4)
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	BEARING CONNECTIONS: Where bearing connections are required, there shall be a minimum of two bearing connections for each wall panel. (Tier 2: Sec. 4.8.4.5)



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 17 of 18

3.9 (Modified) NONSTRUCTURAL COMPONENT CHECKLIST

C	NC	N/A	COMMENT
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<p>INSERTS: Where inserts are used in concrete connections, the inserts shall be anchored to reinforcing steel or other positive anchorage. (Tier 2: Sec. 4.8.4.6)</p>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>PANEL CONNECTIONS: Exterior cladding panels shall be anchored out-of-plane with a minimum of 4 connections for each wall panel. Two connections per wall panel are permitted where only the Basic Nonstructural Checklist is required by Table 3-2. (Tier 2: Sec. 4.8.4.7)</p> <p>Presumed to be compliant, the spirit of the check at the very least. Presumption cannot be verified either through available plans or during site visit. Cladding underwent minor ground shaking during the Northridge Earthquake without out-of-plane failures.</p>
MASONRY VENEER			
<p>Note: Masonry veneer components shall only be considered over points of egress or over outdoor public assembly areas.</p>			
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<p>SHELF ANGLES: Masonry veneer shall be supported by shelf angles or other elements at each floor 30 feet or more above ground for Life Safety and at each floor above the first floor for Immediate Occupancy. (Tier 2: Sec. 4.8.5.1)</p> <p>Although N/A supports for granite veneer are provide in the form of shelves created by the concrete wall spandrels or angles in limited number of cases. See S17-S21.</p>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>TIES: Masonry veneer shall be connected to the back-up with corrosion-resistant ties. The ties shall have a spacing of equal to or less than 24" with a minimum of one tie for every 2-2/3 square feet. A spacing of up to 36" is permitted where only the Basic Nonstructural Checklists is required by Table 3-2. (Tier 2: Sec. 4.8.5.2)</p> <p>Presumed to be compliant, the spirit of the check at the very least. Presumption cannot be verified either through available plans or during site visit. Cladding underwent minor ground shaking during the Northridge Earthquake without out-of-plane failures.</p>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>WEAKENED PLANES: Masonry veneer shall be anchored to the back-up adjacent to weakened planes such as at the locations of flashing. (Tier 2: Sec. 4.8.5.3)</p> <p>Presumed to be compliant, the spirit of the check at the very least. Presumption cannot be verified either through available plans or during site visit. Cladding underwent minor ground shaking during the Northridge Earthquake without out-of-plane failures.</p>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>DETERIORATION: There shall be no evidence of deterioration, damage or corrosion in any of the connection elements. (Tier 2: Sec. 4.8.5.4)</p> <p>Presumed to be compliant. Visual confirmation could not take place during site visit</p>
PARAPETS, CORNICES, ORNAMENTATION AND APPENDAGES			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<p>URM PARAPETS: There shall be no laterally unsupported unreinforced masonry parapets or cornices with height-to-thickness ratios greater than 1.5. A height-to-thickness ration of up to 2.5 is permitted where only the Basic Nonstructural Checklists is required by Table 3-2. (Tier 2: Sec. 4.8.8.1)</p>



California Court Building Seismic Assessment Program
Tier 1 Evaluation
Checklist

Building ID: 19-K1 By/Firm: Walterio A. López/R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 18 of 18

3.9 (Modified) NONSTRUCTURAL COMPONENT CHECKLIST

C	NC	N/A	COMMENT
<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	CANOPIES: Canopies located at building exits shall be anchored at a spacing of 6 feet or less. An anchorage spacing of up to 10 feet 5 is permitted where only the Basic Nonstructural Checklists is required by Table 3-2. (Tier 2: Sec. 4.8.8.2)



California Court Building Seismic Assessment Program
 Tier 2 Evaluation
 Cover Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/R&C Reviewed By: PCR/HF
 Bldg. Name: Stanley Mosk Courthouse Date: 12/15/03
 Bldg. Address: 111 North Hill St. Los Angeles Page: 1 of 8


Bldg. Ids Included in this report

19-K1-A (West Wing)
 19-K1-B (East Wing)

Document Availability (Drawings, reports, etc.)

Partial set of Architectural and Structural drawings available
 Partial set of Architectural and Structural drawings available

KEY PLAN



BUILDING PHOTOS



West Wing Elevation



Seismic joint viewed from the south courtyard



California Court Building Seismic Assessment Program
Tier 2 Evaluation
Table of Contents

Building ID: 19-K1 By/Firm: Walterio A. López/R&C Reviewed By: PCR/HF
Bldg. Name: Stanley Mosk Courthouse Date: 12/15/03
Bldg. Address: 111 North Hill St. Los Angeles Page: 2 of 8

TABLE OF CONTENTS

ITEM	PAGE
Cover Sheet	1
Table of Contents	2
Summary Sheet	3
Retrofit Concept Sheet	4
Deficiency List	5
Analysis Methods	6
Documentation Sheet	7
Appendix A – Workshop Results	
Appendix B – Tier 1 Evaluation Report	
Appendix C – Tier 2 Calculations	



California Court Building Seismic Assessment Program
Tier 2 Evaluation
Summary Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C Date: 12/15/03
Bldg. Name: Stanley Mosk Courthouse Page: 3 of 8

BUILDING DESCRIPTION

Site and Building Configuration

This report has been written to include both the West Wing (19-K1-A) and the East Wing (19-K1-B) structures; the conclusions herein apply to both structures except where noted.

The building was constructed in 1957 on a site sloping from east to west. A seismic joint separates the two wings. The entrance to the East Wing is located on the first floor on 111 North Hill Street while the entrance to the West Wing is located on the fourth floor on 110 North Grand Avenue. A crawl space about 4' high covers the entire East Wing and about 2 bays beyond the seismic joint. The site and foundation are stepped west of the seismic joint. The building is rectangular in plan with the building transitioning into a tower through a setback at the third floor at the East Wing and a similar setback at the sixth floor at the West Wing

Structural System

The building has a concrete slab and structural steel beams and columns system for gravity loads and a combination of cast-in-place concrete shear wall and pier and spandrel lateral-load resisting system. The building consists of an East and a West Wing separated by a 5" wide seismic joint. The building is 7 stories tall in the East Wing and 9 stories tall in the West Wing. The pier and spandrel systems are lightly reinforced and many lines of resistance are not continuous to the foundation. The building skin consists of stone panels attached to the concrete shear walls. Concrete shear walls and individual steel columns rest on continuous and isolated spread footings.

	<u>Original</u>	<u>Addition</u>
Building Condition:	<u>Good, some cracks visible, especially at penthouse levels</u>	
Date of Construction:	<u>May 17, 1955</u>	
Year/Design Code:	<u>1952 UBC</u>	
ASCE 31 Bldg. Type:	<u>Steel frames with concrete shear walls</u>	

SITE DATA

Site Class: B S_{DS}: 1.52 g S_{D1}: 0.53 g
Geologic Hazard(s): **Fault Rupture:** No **Liquefaction:** No **Landslide:** No

OVERALL SEISMIC DEFICIENCIES & EXPECTED SEISMIC PERFORMANCE

The major structural deficiencies can be summarized as weak story, soft story, geometry, vertical discontinuities, existing wall cracks, shear stress check, reinforcing steel, and overturning.

It can be expected that this building will perform poorly during strong ground shaking. It can be expected that the building would exhibit substantial structural damage and possible partial localized collapse of areas where shear walls become discontinuous at the lower levels. During strong ground shaking extensive damage to non-structural components and buildings systems can be expected. Post-earthquake repair may not be cost-effective.

DSA SEISMIC RISK LEVEL (Tier 2): I II III IV V VI VII



California Court Building Seismic Assessment Program
Tier 2 Evaluation
Summary Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 4 of 8

Further Study (Beyond Tier 2):

No Further Study, Assign Risk Level From Tier 2

Further Study Recommended (Explain below)

Tier 2 evaluation validates the risk level assigned in Tier 1. However, the seriousness of the deficiencies associated with discontinuous shear walls, weak stories, and soft stories, (i.e., the possibility of partial localized collapse at columns located at entrances and loading dock areas) are such that further analyses would probably illustrate better the problem areas and contribute to a more efficient retrofit scheme.



California Court Building Seismic Assessment Program
Tier 2 Evaluation
Retrofit Concept Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 5 of 8

RETROFIT CONCEPTS

Several retrofit concepts could be applied to this building to mitigate the seismic deficiencies. They are:

- Strengthening existing concrete shear walls by increasing their thickness and/or their lengths.
- Adding full-height new interior concrete shear walls
- Adding new exterior steel bracing
- Adding new exterior concrete shear wall towers
- Adding base isolation in two different planes; namely, below the first floor from lines J through Z at the East Wing and from lines A through J below the fourth floor at the West Wing.



California Court Building Seismic Assessment Program
 Tier 2 Evaluation
 Deficiency List

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C
 Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
 Page: 6 of 8

DEFICIENCY LIST (Listed in order of importance)

Non-Conforming Checklist Item	Comment on Tier 2 Evaluation Results
Vertical Discontinuities	<u>Do not waive.</u> Shear walls along the longitudinal axis of the building in both wings are discontinuous and so are walls along lines B and Y and over the loading dock.
Weak Story	<u>Do not waive.</u> Because the major shear walls along the longitudinal axis of the building in both wings are discontinuous, the story strength below the discontinuous walls is reduced significantly. Tier 2 analyses confirm that columns D/12, K/12, D/1, K/1, Y/4, Y/9, W/4, L/4 withstand very high demands because of their supporting discontinuous shear walls and therefore present life-safety concerns.
Soft Story	<u>Do not waive.</u> Because the major shear walls along the longitudinal axis of the building in both wings are discontinuous, the story stiffness below the discontinuous walls is reduced significantly
Geometry	<u>Do not waive.</u> The discontinuous shear walls mentioned above create a change in the horizontal dimension of the lateral-load-resisting system of more than 30% from the story where the discontinuity occurs to the level below.
Existing Wall Cracks	<u>Do not waive.</u> Significant wall cracking was reported and mapped in the structural engineering reports cited on page 7. Many of those cracks have since been repaired, with the most visible ones being at penthouse levels.
Reinforcing Steel	<u>Do not waive.</u> $\rho=0.0020$ at many wall locations
Shear Stress Check	<u>Do not waive.</u> The shear demand on many wall elements exceeded their capacities by a factor of at least 2 and at locations as high as 4.
Overturning	<u>Do not waive.</u> Both wings of this building have shear walls in both directions with base/height ratios that are about 60% smaller than what would be required not to trigger the deficiency.
Non-Structural Components	There is a potential to waive this presumed non-compliance. During the site visit, it was not possible to visually confirm attachment of non-structural but they are presumed to be deficient. However, this non-conformance may be waived if visual inspection confirms that non-structural components are adequately attached.



California Court Building Seismic Assessment Program
Tier 2 Evaluation
Analysis Methods

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C
Bldg. Name: Stanley Mosk Courthouse

Date: 12/15/03
Page: 7 of 8

ANALYSIS METHODS

- The crawl space under the East Wing and portion of the West Wing was not included in the model. The base of the computer model was assumed to be at the first floor.
- The soil at the site was assumed to be a firm shale.
- Materials:
 - Concrete: $f_c = 3,000$ psi
 - Reinforcing steel: ASTM A-15 & A-305 with $f_y = 33$ ksi
 - Structural steel: ASTM A-7 weldable with "A" series connectors with $F_y = 33$ ksi
- Where a discrepancy exists between the existing wall elevations and the existing framing plans, the information shown on the elevations was assumed to be correct.
- A three-dimensional elastic model utilizing ETABS version 8.2.6 was created for each wing of the building.
- All concrete shear walls, wall piers, and spandrel beams were modeled using the following cracked section properties:
 - Flexural Rigidity: $0.5E_cI_g$
 - Shear Rigidity: $0.4E_cA_w$
 - Axial Rigidity: E_cA_g
- The linear dynamic procedure (LDP) was used to compute demands.
- The demands obtained from the results of the LDP were compared to the capacities of the existing wall elements using a factor $m = 2.5$.
- Conclusions:
 - Existing concrete shear walls and pier and spandrel systems are not Tier 2 compliant.
 - Columns supporting discontinuous shear walls withstand high axial loads that exceed their buckling capacities.
 - Demands at existing diaphragms spreading the load of discontinuous shear walls exceed their capacities.



California Court Building Seismic Assessment Program
Tier 2 Evaluation
Documentation Sheet

Building ID: 19-K1 By/Firm: Walterio A. López/ R&C Date: 12/15/03
Bldg. Name: Stanley Mosk Courthouse Page: 8 of 8

DOCUMENTATION

Architectural Drawings: Sheets 1 through 21, 21A, 22 through 27 by Stanton, Williams, Austin, Field & Fry Architects dated May 17, 1955.

Structural Drawings: Sheets S1 through S10, S10A, S11 through S35, and S1A through S1C by Brandow & Johnston Structural Engineers dated May 17, 1955.

Other Drawings

Reports: Structural Evaluation Reports 19K1-K1 through 19K1-K3 (Modified Phase 1A Reports) by Rachlin & Rachlin Architects dated February 28, 1996.
Structural Evaluation Report 19K1-K5 (Modified Phase 1B Report) by Rachlin & Rachlin Architects dated April 2, 1996.

Limitations of available documents: No limitations

WALK-THROUGH SITE VISIT

Date of visit: May 20, 2003

Limitation of walk-through: Support of non structural components such as ceilings was not determined.



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Discussion Item 4

Summary:

Discuss Santa Barbara Superior Court's transition of juvenile proceedings to the Jury Assembly Building.

Supporting Documentation:

- Slide

This page intentionally left blank

Discussion Item 4

Santa Barbara Area Court Improvement Status Update

- Project assigned to Peggy Symons
- DOF concurs keeping Jury Assembly makes sense
- Disposition process for trailer engaged
- Real Estate approaching county to determine interest.



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Discussion Item 5

Summary:

Update on status of *Trial Court Methodology for Prioritizing and Ranking Facility Modifications*

Supporting Documentation:

- Slide

This page intentionally left blank

Discussion Item 5

Prioritization Methodology

Status Update

- Goal – Align Methodology with FM Policy
- Review in progress w/ REFM & Legal
- Structure may change
- Bright lines identified
- Grey areas under review and discussion
- Potential Committee Review – 9-15



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Information Only Item 1

Summary:

Informational Budget Change Proposal for Funds Transfer to Complete Funding Plan for the Alameda Courthouse Project.

Supporting Documentation:

- BCP Concept document

This page intentionally left blank

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program Contact: Angela Guzman

I. Transfer of Funding to Support the Alameda Capital Outlay Project

2016-17 Fiscal Summary:

Fund Source	# Positions	Personal Services \$	Operating Expense & Equipment \$	Total Estimated Cost
Court Facilities Trust Transfer to Immediate and Critical Need Account			\$903,000	\$903,000

II. Nature of Request/Problem

The Alameda County –New East County Hall of Justice is currently under construction after approval of the funding plan through the Judicial Council, the Department of Finance (DOF), and the Legislature. The new courthouse will provide permanent replacement facilities for the Alameda Superior Court to consolidate from four facilities that have significant security problems, severe accessibility deficiencies, are overcrowded, and have many physical problems which prevent the court from providing safe and efficient service to the public.

The FY 2014-15 Budget Act, Senate Bill 852, Chapter 25, Statutes of 2014, authorized the loan of \$39.113 million from the Immediate and Critical Needs Account (ICNA) to cash fund the project in lieu of using county-issued bonds, which results in the savings of approximately \$20 million due to avoiding the cost of financing the project. Within the 2014-15 Budget Act, Provision 1 of Item 0250-301-3138 states,

- 1. The funds appropriated in Schedule (.5) of this item shall be a loan, as described in subdivision (a) of the Section 70301 of the Government Code, from the Immediate and Critical Needs Account to finance a portion of the cost of acquiring the Alameda County New East County Courthouse to be repaid without interest and on such other terms as established by the Judicial Council from state and county revenues available for the repayment of this loan, including the county's local courthouse construction funds.*

As a part of the funding plan, approved by the Judicial Council, DOF and the Legislature \$903,000 from the Court Facilities Trust Fund (CFTF) was committed as a resource to repay the loan from the ICNA to fund the project.

In August 2008, the Judicial Council authorized the submittal of a Budget Change Proposal to the State Department of Finance in the amount of \$903,000 to utilize funding from the Court Facilities Trust Fund for the Alameda – East County Hall of Justice. Prior to this approval the

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program Contact: Angela Guzman

court and the county were actively involved in developing a funding strategy to move the project forward.

The project has significant economic opportunities associated with it, including the following:

- donation of land from the County of Alameda,
- commitment of Court Civil Assessment revenue from the Alameda Superior Court - \$20.8 million upfront and annual contributions of \$2 million until the ICNA loan is paid off,
- commitment of Court Civil Assessment revenue from the Alameda Superior Court - \$20.8 million upfront and annual contributions of \$2 million until the ICNA loan is paid off,
- commitment of Local Courthouse Construction Fund from the County of Alameda - \$12.7 million upfront and annual contributions of an estimated \$2.5 million until the ICNA loan is paid off.

III. Proposed Solution

The Judicial Council requests a budget line item to transfer \$903,000 in funds from the CFTF to the ICNA to support the financial plan for the construction of the Alameda County – new East County Hall of Justice. The transfer would be in place until the loan from the ICNA is fully paid off, which is estimated to occur in 7-8 years, and would not begin until the Gale Schenone lease is terminated.

IV. Alternative Solutions

Alternative #1: Status quo, do not transfer CFTF funding in support of the funding plan for this project. This alternative is not recommended as the ICNA resources are proposed to fund other commitments. The funding plan which included the use of the CFTF funding has been approved by DOF and the legislature.

Alternative #2: Defer \$903,000 in Facility Modification commitments from the ICNA annually for the period of the loan repayment to facilitate the payback of the loan from the ICNA. This option is not recommended as the original commitment by the Judicial Council included the use of \$903,000 in CFTF funding for this purpose and DOF and the Legislature have approved this plan. Utilizing this option would require the concurrence of the DOF and subsequently the Legislature.

FY 2016-17 Budget Change Proposal Concept

Office: Capital Program

Contact: Angela Guzman

V. Other Considerations

Although the proposal recommends the redirection of CFP funding related to the Gale Schenone lease it is only a portion of the CFP revenue related to this facility. The CFP revenue related to the Gale Schenone lease is approximately \$1.6 million the balance of the CFP would offset the operating costs in the new facility.

The construction of the New East County Courthouse began in February 2015 and is expected to reach completion in February 2017.

The Judicial Council and the County have entered into a Project Development Agreement that was approved by the State Public Works Board which contained provisions regarding the setting and modification of the project budget.



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: 7/17/2015

Information Only Item 2

Summary:

Informational report on FY 15-16 budget reconciliation and spending plan, as well as completed and canceled facility modifications during the reporting period.

Supporting Documentation:

- Budget reconciliation document

This page intentionally left blank



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION
ADVISORY COMMITTEE

Meeting Date: July 17, 2015

Facility Modifications Completed and Canceled

During the July reporting period, 234 facility modifications were completed, coming in nearly 10% under budget of expected expenditures. Along with the 17 funded, canceled facility modifications, there was a total cost savings of \$758,990 to the FM program budget.

Status	Quantity	Estimated Cost of FM Program Budget Share	Actual Cost of FM Program Budget Share	% of Estimated Cost
Completed	234	\$4,779,602	\$4,308,950	90.15%
Funded FMs Canceled	17	\$130,360	N/A	N/A
Non-Funded FMs Canceled	17	N/A	N/A	N/A

Status	Quantity	Cost Adjustment to FM Program Budget
Completed	234	\$628,630
Canceled	17	\$130,360
TOTAL COST ADJUSTMENT		\$758,990

FY 2015-2016 FM Budget YTD Reconciliation

As no funds have yet been expended this fiscal year, the full budget of \$65M remains available.

FY 2015-2016 (\$1,000s)			
Description	Budget Amount	Reconciled Expenditure	Funds Available
Statewide FM Planning Allocation	\$4,000	\$0	\$4,000
Priority 1 FM Allocation	\$10,000	\$0	\$10,000
FMs Less Than \$50K Allocation	\$8,000	\$0	\$8,000
Planned FMs Allocation	\$2,900	\$0	\$3,000
Priority 2-6 FMs Allocation	\$40,100	\$0	\$40,000
TOTALS:	\$65,000	\$0	\$65,000



JUDICIAL COUNCIL OF CALIFORNIA

TRIAL COURT FACILITY MODIFICATION ADVISORY COMMITTEE

Meeting Date: July 17, 2015

FY 2015-2016 FM Budget Spending Plan

There is an anticipated spend of \$32,430 at this meeting, which encompasses all initial budget allocations aside from Priority 2-6 FMs over \$50K. The projections below also account for energy efficiency projects and FMs that are approved by the committee but remain unfunded due to lack of county shared funding commitments.

FY 2015-2016 Spending Plan (\$1,000s)	
Month/Item	Spending
JUL 2015	\$32,430
AUG 2015	\$3,000
OCT 2015	\$7,000
DEC 2015	\$3,000
JAN 2016	\$7,010
MAR 2016	\$4,000
APR 2016	\$3,000
MAY 2016	\$3,000
Energy Efficiency – OCT 2015	\$1,000
Energy Efficiency – JAN 2016	\$1,000
Approved Projects Pending County Funds	\$560
TOTAL	\$65,000